



CITY OF THE DALLES, OREGON
CONTRACT DOCUMENTS FOR:

CONTRACT NO. 2023-003 2023 ADA IMPROVEMENT PROJECT

CONTRACT DOCUMENTS
VOLUME 1 - BIDDING REQUIREMENTS, CONTRACT FORMS,
CONDITIONS OF THE CONTRACT,
TECHNICAL SPECIFICATIONS, DRAWINGS

Project Manager:
Todd Stephens, P.E.
City Engineer
1215 West First Street
The Dalles, OR 97058
Telephone: (541) 296-5401



EXPIRES: 6/30/24

Bids must be submitted via email to thedallesbids@ci.the-dalles.or.us no later than 2:00 p.m. Pacific Standard Time on January 26, 2023. Note: Immediately following the electronic submission of a bid, bidders will receive confirmation that the bidder's email has been received. **THE DUTY IS ON THE BIDDER TO ENSURE THAT THE REQUIRED BID DOCUMENTS ARE ATTACHED TO ANY EMAIL BEING SENT TO THE CITY IN RESPONSE TO THIS ADVERTISEMENT FOR BIDS.**

Bid Opening will be via Zoom meeting. The meeting ID is 858 0212 1281. The Passcode is 068006.

TABLE OF CONTENTS

VOLUME 1

PART 1 - BID BOOKLET

Bidder Checklist
Invitation to Bidders
Advertisement for Bids
Conflict of Interest Guidelines
Prequalification Form
Conflict of Interest Disclosure
Proposal
Bid Bond
Subcontractor Disclosure Form
Non-Collusion Affidavit
Responsibility Determination Form
Notice of Award
BOLI Prevailing Wage Rates Cover

PART 2 - CONTRACT BOOKLET

Contract
Performance Bond
Payment Bond
Notice to Proceed
Certification of Workers' Compensation Coverage

PART 3 – PART 00100 OF 2022 CITY OF THE DALLES STANDARD SPECIFICATIONS FOR CONSTRUCTIONS

PART 4 – SPECIAL PROVISIONS

PART 5 – DRAWINGS

DESCRIPTIONS OF PARTS OF CONTRACT WHICH ARE NOT BOUND HEREIN

(1) Standard Specifications

The “2022 City of The Dalles Standard Specifications for Construction”.

Copies of the 2022 City of The Dalles Standard Specifications for Construction may be obtained by contacting City of The Dalles Public Works Department (541) 296-5401 or downloaded at: www.ci.the-dalles.or.us/engineering

(2) Prevailing Wage Rates

The current “Prevailing Wage Rates for Public Works Contracts in Oregon” published by the Oregon Bureau of Labor and Industries.

Current copies of the “Prevailing Wage Rates for Public Works Contracts in Oregon” may be obtained by contacting Oregon Bureau of Labor and Industries (971) 673-0761 or downloaded at: www.oregon.gov/boli/WHI/PWR/Pages/pwr_state.aspx



PART 1

BID BOOKLET

2023 ADA IMPROVEMENT PROJECT
CONTRACT NO. 2023-003

BIDDER'S CHECKLIST

- ___ Completed Prequalification Form and submit as directed in the Invitation to Bidders, by **January 19, 2023 at 4:00 p.m.**

ITEMS TO BE INCLUDED IN BID SUBMITTAL:

- ___ Completed Bid Proposal
- ___ Completed Affidavit of Noncollusion
- ___ Completed Bidder's Bond
- ___ Signed addenda as may be issued during the bidding period
- ___ Completed Disclosure of First-Tier Subcontractors Form per Section 00120.40(f)- Submitted within two hours of Bid Opening via email to **thedallesbids@ci.the-dalles.or.us.**
- ___ Submit bid documents via email only to **thedallesbids@ci.the-dalles.or.us** by **January 26, 2023 at 2:00 p.m.**



City of The Dalles
Department of Public Works
1215 West 1st Street
The Dalles, OR 97058

December 28, 2022

INVITATION TO BIDDERS
RE: 2023 ADA IMPROVEMENT PROJECT
CONTRACT NO. 2023 – 003

Dear Contractor,

The City of The Dalles, Department of Public Works, is requesting a bid from your firm to furnish all materials, labor and equipment necessary to complete the concrete work for 40 curb ramps including concrete curb and gutter, concrete curb, and concrete sidewalk. All work will be conducted in accordance with the contract documents. If your price proposal is the lowest, you are judged a responsible and responsive bidder, the cost of the project is within budget limitations for each bid schedule, and award is authorized by the City Council you will receive a Notice of Award.

Electronic copies of the contract documents can be downloaded from the city's website at <http://www.thedalles.org/bids>. Bidder will be responsible for checking the website regularly for addendums and additional information for the project.

Bids shall be submitted no later than **January 26, 2023 at 2:00 p.m. Pacific Standard Time via email to: thedallesbids@ci.the-dalles.or.us**, at which time the email account designated for bid receipt will be accessed. Bids shall not be sent to any other email addresses. Bid responses will be read aloud via a Zoom meeting. Zoom Meeting ID is 858 0212 1281 and use Passcode 068006. **Note:** Immediately following the electronic submission of a bid, bidders will receive confirmation that the bidder's email has been received. **THE DUTY IS ON THE BIDDER TO ENSURE THAT THE REQUIRED BID DOCUMENTS ARE ATTACHED TO ANY EMAIL BEING SENT TO THE CITY IN RESPONSE TO THIS ADVERTISEMENT FOR BIDS.**

Bidders must be prequalified in accordance with the laws of the State of Oregon. Prequalification forms shall be sent via email to tstephens@ci.the-dalles.or.us and must be received by **January 19, 2023 at 4:00 p.m. Pacific Standard Time.**

Questions, objections or comments regarding the project specifications must be submitted by email directed to Todd Stephens, PE, Project Manager at tstephens@ci.the-dalles.or.us. They must be received no later than five (5) calendar days before the bid opening date.

Sincerely,

CITY OF THE DALLES, OR

Todd Stephens,
Project Engineer
City of The Dalles

ADVERTISEMENT FOR BIDS

Contract No. 2023 – 003

The City of The Dalles (“City”) is soliciting bids for the **2023 ADA Improvement Project**. Bids must be submitted no later than **January 26, 2023 at 2:00 p.m. Pacific Standard Time via email to: thedallesbids@ci.the-dalles.or.us**, at which time the email account designated for bid receipt will be accessed. Bids shall not be sent to any other email addresses. Bid responses will be read aloud via a Zoom meeting. The Zoom Meeting ID is 858 0212 1281 and use Passcode 068006. Note: Immediately following the electronic submission of a bid, bidders will receive confirmation that the bidder’s email has been received. **THE DUTY IS ON THE BIDDER TO ENSURE THAT THE REQUIRED BID DOCUMENTS ARE ATTACHED TO ANY EMAIL BEING SENT TO THE CITY IN RESPONSE TO THIS ADVERTISEMENT FOR BIDS.**

The work to be performed shall consist of furnishing all materials, labor and equipment necessary to complete the concrete work for 40 curb ramps including concrete curb and gutter, concrete curb, and concrete sidewalk. All work will be conducted in accordance with the contract documents. Bids must be submitted on the proposal form furnished by the City of The Dalles and shall bear the signature of the Bidder.

The Invitation to Bidders, Proposal Form, Contract, Specifications, Drawings and other Contract Documents will be posted to the City’s website at **<http://www.thedalles.org/bids>**. Bidder will be responsible for checking the website regularly for addendums and additional information for the project. Questions regarding contract documents should be directed to Todd Stephens, Project Manager via email at: **tstephens@ci.the-dalles.or.us**

The City may reject any bid not in compliance with all prescribed public bidding procedures and requirements, and may reject for good cause any or all bids or bid schedules upon a finding of the City it is in the public interest to do so in accordance with ORS 279B.100. The City also reserves the right to waive any informality in connection with said bid or to postpone the award of the contract for sixty days. Each proposal must contain a statement as to whether the bidder is a resident bidder as defined by ORS 279A.120.

Bidders must be prequalified in accordance with the laws of the State of Oregon. Prequalification forms shall be sent via email to **tstephens@ci.the-dalles.or.us** and must be received by **January 19, 2023 at 4:00 p.m. Pacific Standard Time.**

Attention is particularly called to the requirements as to conditions of employment to be observed and minimum wage rates to be paid under the contract. No bid will be received or considered by the City of The Dalles unless the bid contains a statement by the Bidder as part of their bid that provisions of ORS 279C.830 will be complied with.

No bid shall be considered by the public contracting agency unless the bidder is registered with the Construction Contractors Board or licensed by the State Landscape Contractors Board as required by ORS 671.530.

No bid may be withdrawn after the time set for the bid opening, or before the award of the Contract, unless award is delayed for a period exceeding 60 days.

CITY OF THE DALLES, OREGON
Izetta Grossman, CMC, City Clerk

PUBLISHING DATE: December 28, 2022

**CITY OF THE DALLES CONFLICT OF
INTEREST GUIDELINES (COI GUIDELINES)
City of The Dalles (Agency)**

A Firm shall follow these COI Guidelines when submitting any Proposal in response to an Agency Procurement or when entering into any Contract with Agency, and throughout the period during which the Proposal/Bid is open or the Contract is in effect. A Firm shall provide the COI Guidelines and associated COI Disclosure Form to all of its Subconsultants and Subcontractors at any tier of a Proposal or Contract and shall ensure that the Firm and each of its Subconsultants or Subcontractors make any disclosures required by these guidelines or as required by a specific Procurement or Contract. The Agency will follow and apply these COI Guidelines when conducting Agency procurements.

1. Definitions

The [definitions](#) that apply to these COI Guidelines and the Agency's COI Disclosure Form are at the end of this document.

2. Required Disclosures

Submittal of a Correct and signed COI Disclosure Form is required if any of the following apply (note that "Public Official" includes all Agency employees):

- a Firm or any of its Associates have any Apparent, Potential or Actual Conflicts Of Interest per these COI guidelines or per the criteria of any COI Form included as part of a Procurement or Contract;
- a Procurement or Contract document specifically requires submittal of a COI Disclosure Form (e.g., if the prospective Project includes preparation of an Environmental Impact Statement or Environmental Assessment, submittal of COI Disclosure Forms is always required.);
- a Firm has any changes to its staffing or organization (whether before or after entering into a Contract) that result in an Apparent, Potential or Actual Conflict Of Interest per these guidelines or per the criteria of any COI form associated with a particular Procurement or Contract. Any such changes shall be disclosed within 10 business days via submittal of a complete and signed COI Disclosure Form.
- The response to any of the following questions is "yes" (with respect to a Procurement or current Contract with Agency):
 1. Is any Associate of the Firm a former employee of Agency (within the last year)?
 2. Is any Associate of the Firm a Relative or Member of the Household of a current employee of Agency who had or may have a role in this Procurement, Authorization of the Contract, Contract administration, or oversight of the Contractor's performance?
 3. Does the Firm or any Associate of the Firm have an Actual, Apparent or Potential Conflict Of Interest ("Individual" or "Organizational") with regard to any member of an Agency Procurement evaluation or selection team?
 4. Did the Firm or any Associate of the Firm conduct prior work on the Project described in the Procurement, or participate in preparing any part of the Procurement or any documents or reports related to the Procurement or to which the Procurement refers?
 5. Does the Firm or any Associate of the Firm have any past, present or currently planned interests which are an Actual, Apparent or Potential Conflict of Interest ("Individual" or "Organizational") with respect to performing the work for Agency?
 6. Has the Firm or an Associate of the Firm offered to a Public Official, or is the Firm aware of

any Public Official that has solicited or received, directly or indirectly, any pledge or promise of employment or other benefit based on the understanding that the Public Official's vote, official action or judgment would be influenced thereby?

7. Has (or will) the Firm or an Associate of the Firm provided a direct beneficial financial interest to any person within two years after the person ceased to hold a position as a Public Official who was involved in the Procurement or Authorization for the Contract, or is the Firm aware of any such person or Public Official who has or will receive a direct beneficial financial interest within the two year period?
8. Is the Firm aware of any current or former Public Official that has an Actual, Apparent or Potential Conflict Of Interest with respect to the Procurement or award of this Contract or performing the work for Agency?
9. Does the prospective Contract include development of an environmental assessment (EA) or environmental impact statement (EIS)?
10. If a Procurement is to obtain personal services for the purpose of administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing a public contract, is the Firm or an Associate or an Affiliate of the Firm a party to the subject public contract?
11. Has the Firm or any Associate of the Firm entered into personal services contract(s) with Agency for the purpose of advising or assisting in developing specifications, a scope or statement of work, an invitation to bid, a request for proposals or other solicitation documents and materials related to this procurement?

If none of the foregoing apply, a Firm shall provide a written and signed certification (specified by Agency) that the Firm has read and complied with these COI Guidelines and the COI Disclosure Form and did not answer Yes to any of the questions, or, if required by the Agency, the Firm shall complete and submit a Correct and signed COI Disclosure Form.

A Firm shall incorporate in each required COI Disclosure Form any COI disclosure information provided by its staff and attach COI Disclosure Forms from each of its Subcontractors (that have required disclosures of conflicts or potential conflicts of interest), prior to such Firm performing any services under a Contract.

Agency's COI Disclosure Form is available on the Internet at the following Intranet site: www.ci.the-dalles.or.us/engineering . Some Procurements may require submittal of a COI Disclosure Form (other than the standard form) that is specific to the Procurement.

3. Governing Standards

Both Oregon and federal laws govern disclosure and management of conflicts of interest in transportation contracting processes. The disclosure requirements of these COI Guidelines apply to all Agency contracting activities {Architectural and Engineering (A&E) and non-A&E, public improvements, goods, and trade services} without regard to which particular federal or Oregon laws govern the activity. Agency also has a Code of Conduct Policy for conflicts of interest regarding the employment of former Agency employees, which is explained below.

Agency Code of Conduct Policy Regarding Former Agency Employees

When employees of firms which compete for or have Contracts with the Agency come to work for the Agency, and when Agency employees go to work for firms which compete for or have Contracts with the Agency, a Potential Conflict of Interest may exist.

Use of a former Agency employee by a Firm on the same, or substantially similar Procurement, for which the employee performed a role or function for the Agency, unless mitigated to the satisfaction of the Agency, is prohibited for a period of one year following separation of employment with the Agency. Roles and functions of particular concern include drafting specifications or statements of work, reviewing or scoring a bid or proposal, authorizing service or assigning work, awarding a Contract, administering a Contract, or overseeing Contractor's performance. The Agency may determine that the role or Procurement is not substantially similar because of differences in location of the Project or work, because of the type and method of Procurement, or because the role performed was minor in nature such as a technical sufficiency review. Examples of mitigation that may, in appropriate situations, be acceptable to the Agency include separation of certain decision-making functions concerning the Project, not using the employee in preparation of proposals but allowing them to perform work on the Project, and not having the employee have direct contact with Agency staff formerly under their supervision.

For each Procurement, Firms shall disclose to Agency the identification of any employee(s) that had been employed by Agency within the last one-year period. Each Firm's disclosure shall include a signed statement by the former Agency employee of their proposed role for the Firm in the particular Procurement and any resulting Contract. Failure of a Firm to disclose such relationship or to remedy such potential violation will result in the rejection of the Firm's bid or cancellation of the Contract with the Agency as well as being grounds for cancellation of a Firm's prequalification or designation of a Firm as ineligible for future Procurements as not being a responsible bidder. (Also see below regarding the ORS 244.047 two-year ban on any direct beneficial interest.)

Oregon State Standards

The current Oregon statutory framework, as generally applied, addresses conflicts of interest in public contracting by emphasizing the need for open and impartial Procurement methods and by prohibiting certain conflicts of interest involving public officials. The following statutes and administrative rules establish Oregon's general policies and the restrictions and prohibitions regarding conflicts of interest for public contracts and Public Officials:

- The policies of the Public Contracting Code (ORS 279A.015) encourage public contracting competition that supports openness and impartiality to the maximum extent possible, while recognizing that the nature of effective and meaningful competition depends upon the service being procured.
- According to ORS 279A.015(2) a sound and responsive public contracting system should instill public confidence through ethical and fair dealing, honesty and good faith on the part of government officials and those who do business with the government.
- ORS Chapter 244 prohibits conflicts of interest of Public Officials. Among the prohibitions are offering a public employee a pledge of future employment based on an understanding that the offer would influence the public employee's official action or judgment.
- ORS 244.047(2) and (3) provide the following:
 - (2) "Except as provided in subsection (3) of this section, a person may not, for two years after the person ceases to hold a position as a public official, have a direct beneficial financial interest in a public contract that was authorized by:
 - (a) The person acting in the capacity of a public official; or
 - (b) A board, commission, council, bureau, committee or other governing body of a public body of which the person was a member when the contract was authorized.

- (3) Subsection (2) of this section does not apply to a person who was a member of a board, commission, council, bureau, committee or other governing body of a public body when the contract was authorized, but who did not participate in the authorization of the contract.”

Agency’s administrative rules in OAR 731 Division 70 establish conflict of interest rules for the Oregon Innovative Partnership Program. The Oregon Government Ethics Commission also has administrative rules for public officials in OAR 199 Division 5.

- ORS 279.C.307 includes the following:

- (1) “Except as provided in subsection (2) of this section, a contracting agency that procures personal services for the purpose of administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing a public contract that is subject to this chapter may not:

(a) Procure the personal services from a contractor or an affiliate of a contractor who is a party to the public contract that is subject to administration, management, monitoring, inspection, evaluation or oversight by means of the personal services; or

(b) Procure the personal services through the public contract that is subject to administration, management, monitoring, inspection, evaluation or oversight by means of the personal services.

- (2) Subsection (1) of this section does not apply to a procurement that qualifies as a Construction Manager/General Contractor procurement or a Design-Build procurement, both as defined in OAR 125-249-0610 or 137-049-0610.

- (3) As used in this section, “affiliate” means a person that, directly or indirectly through one or more intermediaries, controls, is controlled by or is under common control with the contractor described in subsection (1)(a) of this section.”

- ORS 279B includes the following per 2012 Senate Bill 1518, Section 2 (Oregon Laws 2012, Chapter 53):

- (1) Except as provided in subsection (2) of this section, a state contracting agency that procures personal services for the purpose of advising or assisting the state contracting agency in developing specifications, a scope or statement of work, an invitation to bid, a request for proposals or other solicitation documents and materials related to a procurement may not accept from the contractor, or an affiliate of the contractor, that advised or assisted the state contracting agency a bid or proposal for the goods or services described, specified or identified in the solicitation documents or materials if a reasonable person would believe that, by giving the advice or assistance, the contractor or affiliate would have or would appear to have an advantage in obtaining the public contract that is the subject of the solicitation.

- (2)(a) If a state contracting agency anticipates that the state contracting agency will or must seek advice or assistance of the type described in subsection (1) of this section from a contractor that is also engaged in providing goods or services that will be described or identified in the solicitation documents and materials that result from the advice or assistance, and the state contracting agency wishes to accept a bid or proposal from the contractor, the state contracting agency, before awarding a contract for the advice or

assistance, shall apply to the Director of the Oregon Department of Administrative Services for an exception to the prohibition set forth in subsection (1) of this section.

(b) The state contracting agency in the application for the exception shall include findings and justifications, along with sufficient facts to support the findings and justifications, that will enable the director to make an independent judgment as to whether:

(A) The state contracting agency needs advice or assistance from a contractor to develop the solicitation documents and materials described in subsection (1) of this section;

(B) Accepting a bid or proposal from the contractor that gives the advice or assistance is the only practicable way in which the state contracting agency can conduct the procurement successfully; and

(C) Approving the exception:

(i) Is unlikely to encourage favoritism in awarding public contracts or to substantially diminish competition for public contracts; and

(ii)(I) Is reasonably expected to result in substantial cost savings to the state contracting agency or the public; or

(II) Otherwise substantially promotes the public interest in a manner that could not be practicably realized by complying with the prohibition described in subsection (1) of this section.

(c)(A) If the director approves the state contracting agency's application, the director shall prepare written findings and justifications for the approval. The state contracting agency's findings, justifications and facts and the director's findings, justifications and approval are public records that are subject to disclosure as provided in ORS 192.410 to 192.505.

(B) If the director disapproves the state contracting agency's application, the director shall state the director's reasons for the disapproval in a written notice to the state contracting agency and shall indicate whether the disapproval extends only to the state contracting agency's acceptance of a bid or proposal from a contractor that gives advice or assistance in preparing solicitation documents and other materials or whether the director also disagrees with the state contracting agency's stated need for advice or assistance from a contractor.

(C) The director's approval or disapproval is final.

(3) As used in this section, "affiliate" means a person that, directly or indirectly through one or more intermediaries, controls, is controlled by or is under common control with a contractor described in this section.

(4) This section does not apply to the Secretary of State or the State Treasurer.

- [OAR 137-048-0130](#)(8), (9) and (10) provides:

"(8) As required by ORS 279C.307, pertaining to requirements to ensure the objectivity and independence of providers of certain Personal Services which are procured under ORS chapter 279C, Contracting Agencies may not:

(a) Procure the Personal Services identified in ORS 279C.307 from a Contractor or an affiliate of a Contractor who is a party to the Public Contract that is subject to administration, management, monitoring, inspection, evaluation or oversight by means of the Personal

Services; or

(b) Procure the Personal Services identified in ORS 279C.307 through the Public Contract that is subject to administration, management, monitoring, inspection, evaluation or oversight by means of the Personal Services.

(9) The requirements of ORS 279C.307 and section (8) of this rule apply in the following circumstances, except as provided in section (10) of this rule:

(a) A Contracting Agency requires the Procurement of Personal Services for the purpose of administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing a Public Contract or performance under a Public Contract that is subject to ORS chapter 279C. A Public Contract that is “subject to ORS chapter 279C” includes a Public Contract for Architectural, Engineering, Photogrammetric Mapping, Transportation Planning or Land Surveying Services, a Public Contract for Related Services or a Public Contract for construction services under ORS chapter 279C.

(b) The Procurements of Personal Services subject to the restrictions of ORS 279C.307 include, but are not limited to, the following:

(A) Procurements for Architectural, Engineering, Photogrammetric Mapping, Transportation Planning or Land Surveying Services, which involve overseeing or monitoring the performance of a construction Contractor under a Public Contract for construction services subject to ORS chapter 279C;

(B) Procurements for commissioning services, which involve monitoring, inspecting, evaluating or otherwise overseeing the performance of a Contractor providing Architectural, Engineering, Photogrammetric Mapping, Transportation Planning or Land Surveying Services or the performance of a construction Contractor under a Public Contract for construction services subject to ORS chapter 279C;

(C) Procurements for project management services, which involve administration, management, monitoring, inspecting, evaluating compliance with or otherwise overseeing the performance of a Contractor providing Architectural, Engineering, Photogrammetric Mapping, Transportation Planning or Land Surveying Services, construction services subject to ORS chapter 279C, commissioning services or other Related Services for a Project;

(D) Procurements for special inspections and testing services, which involve inspecting, testing or otherwise overseeing the performance of a construction Contractor under a Public Contract for construction services subject to ORS chapter 279C; and

(E) Procurements for other Related Services or Personal Services, which involve administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing the Public Contracts described in Section (9)(a) of this rule.

(10) The restrictions of ORS 279C.307 do not apply in the following circumstances, except as further specified below:

(a) To a Contracting Agency’s Procurement of both design services and construction services through a single “Design-Build” Procurement, as that term is defined in OAR 137-049-0610. Such a Design-Build Procurement includes a Procurement under an Energy Savings Performance Contract, as defined in ORS 279A.010. Provided, however, the restrictions of ORS 279C.307 do apply to a Contracting Agency’s Procurement of Personal Services for the

purpose of administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing a Design-Build Contract or performance under such a Contract resulting from a Design-Build Procurement; and

(b) To a Contracting Agency's Procurement of both pre-construction services and construction services through a single "Construction Manager/General Contractor" Procurement, as defined in OAR 137-049-0610. Provided, however, the restrictions of ORS 279C.307 do apply to a Contracting Agency's Procurement of Personal Services for the purpose of administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing a Construction Manager/General Contractor Contract or performance under such a Contract resulting from a Construction Manager/General Contractor Procurement."

Agency's COI Guidelines embody the intent of encouraging competition through openness, impartiality, and public disclosure of relevant information (and the avoidance of conflicts of interest) as described in ORS 279A.015, ORS Chapter 244, and Agency's Code of Conduct Policy.

The two-year prohibition against a Public Official having a direct beneficial financial interest in a public contract as provided in ORS 244.047 would generally preclude the person from working under the public contract and from representing the Firm in dealings with the public agency for whom the person had worked. Sharing in the general profits of the Firm (such as a year-end bonus for overall corporate profits) is likely not a direct beneficial financial interest, however, a bonus or other compensation paid just on the basis of the public contract would be subject to the prohibition.

Federal Standards— Procurements Related To Design-Build and Design-Bid-Build

Pursuant to 23 USC § 112(b)(3), the FHWA has promulgated administrative rules that affect federally funded Design-Build procurements and related procurements. These rules, which are in Chapter 23 of the CFR Part 636, are used as the basis for Agency's guidelines on the subject and specifically regulate both Organizational and Individual Conflicts Of Interest. Agency's COI Guidelines incorporate a number of concepts from these federal provisions.

The main rule on Organizational Conflicts Of Interest in Design-Build transactions is 23 CFR §636.116. This rule affects not only Design-Build procurements, but also "any contract for engineering services, inspection or technical support in the administration of the Design-Build contract." Following is a summary of this federal rule (Agency's COI Guidelines apply this rule to design-bid-build and non-A&E activities as well):

Generally, a consultant who assists the state in preparing a Request for Proposals (RFP) document may not, subsequently, propose in response to the RFP. However, the state may determine that the consultant does not have a conflict of interest for a subsequent Procurement, if the consultant furnished only "low-level" documents that were incorporated into the RFP and made available to all offerors, and did not assist the state in the development of instructions to offerors or evaluation criteria for the RFP.

These Design-Build regulations also apply to "improper business practices and personal conflicts of interest" of the Agency's selection team members. 23 CFR § 636.117 indicates that Federal Acquisition Regulations ("FARs"---specifically 48 CFR Part 3, Improper Business Practices and Personal Conflicts of Interest) will apply to the state's selection team members in the absence of relevant state laws and procedures. These regulations require government business to be "above reproach," conducted "with complete impartiality and with preferential treatment for none" and with "the highest degree of public trust and an impeccable standard of conduct" to avoid "even the appearance of a conflict of interest."

In design-bid-build transactions, where engineering services are procured separately from the construction services, ordinarily the consulting Firm providing the engineering services is not eligible to bid on the construction work for the Project.

No Firm or any Associate of a Firm in connection with a Transportation Project shall have, directly or indirectly, any interest, other than their employment or retention by a State or other governmental instrumentality, in any Contract in connection with such Project. No firm or an Associate of a Firm shall have, directly or indirectly, any interest in any real property acquired or to be acquired for a Project unless such interest is openly disclosed upon the records of Agency and such Firm or Associate has not participated and will not participate in such acquisition for and in behalf of Agency (see 23 CFR § 1.33).

Federal Standards - National Environmental Policy Act (NEPA)

No Firm preparing or providing environmental analysis or impact documents relating to a Project, including draft and final Environmental Assessments (EA) or Environmental Impact Statements (EIS) may have a financial or other interest in the outcome of the Project. A financial or other interest in the outcome of the Project includes any known benefits other than general enhancement of professional reputation, and includes any agreement, enforceable promise, guarantee or expectation of future work on the Project as well as any indirect benefit the Firm is aware of such as if the Project would aid proposals sponsored by the Firm's other clients. Compliance with [40 C.F.R. 1506.5\(c\)](#) is required, which includes the requirement for a conflict of interest disclosure statement from each Firm establishing that the Firm does not have a financial or other interest in the Project.

4. COI Considerations Related to Previous Work on Projects

No Firm that has previously performed services on behalf of Agency for a Project may be a Proposer or participate as an equity owner, team member, Subcontractor of or to a Proposer on the Project, or have a financial interest in any of the foregoing entities with respect to the Project, unless Agency is satisfied in its sole discretion that:

- (a) such services were completed prior to initiation of the Procurement for the Project (exceptions may apply for NEPA services on a case-by-case evaluation of the project specifics against the applicable CFRs),
- (b) such services included only Low Level Documents and did not include development of instructions to offerors or evaluation criteria for the RFP,
- (c) such services did not provide the Firm with access to or knowledge of Agency confidential or inside information that could provide an unfair competitive advantage with respect to the Procurement,
- (d) the prior Contract and information provided to the Firm in the performance of its services are either irrelevant to the Procurement or are available on an equal and timely basis to all Proposers,
- (e) the work product from the Firm incorporated into or relevant to the Procurement is available through Public Disclosure on an equal and timely basis to all Proposers, and
- (f) any environmental documents prepared by the Firm have been determined to be objective, and that the Agency demonstrated independent decision-making authority during the environmental process.

In such instances where Agency is satisfied in the manner described above, Agency may still, in its sole discretion, restrict the scope of Procurement services for which the Firm shall be eligible

to perform in order to further the intent and goals of these COI Guidelines.

Public Disclosure of services or products is an important consideration in determining if an Organizational Conflict Of Interest exists. All COI Disclosure Forms will be considered public records.

5. COI Disclosure Process

A Firm shall certify its conformance with these COI Guidelines at the time of submitting a proposal to Agency or entering into a Contract with Agency. If submittal of COI Disclosure Form(s) is required per these COI Guidelines or a specific Procurement or Contract, a Firm shall represent the correctness of a completed COI Disclosure Form. If a Firm has any changes to its staffing or organization (whether before or after entering a Contract) that result in an Actual, Apparent or Potential Conflict Of Interest (Individual or Organizational) per these COI Guidelines or per the criteria of any COI form associated with a particular Procurement or Contract, any such changes shall be disclosed within 10 business days via submittal of a Correct and signed COI Disclosure Form.

A Firm shall assure that any COI Disclosure Form it submits includes any information required to be disclosed by its Subcontractors and other Associates, on behalf of the Firm. A Firm may submit either the Subcontractors' separate COI Disclosure Forms or incorporate Subcontractor information into its own COI Disclosure Form. The disclosure required with the proposal applies to the prime and all proposed Subcontractors that are identified or anticipated at the time of proposal submission.

The identification, assessment, and management of Actual or Potential Conflicts Of Interest are joint tasks among Agency, the Firm and the Firm's team. A Firm must work together with Agency in an atmosphere of candor and accountability during the period of negotiation or performance of the Contract with Agency. Agency makes the final determination as to the adequacy of any COI disclosures or COI management plan offered by the Firm.

Agency's COI determination is based on a number of factors such as:

- ✓ Situational Facts – description of the situation and all known facts specific to the actual or perceived COI
- ✓ Type of Work - specific product or service and Contract(s) involved
- ✓ Relationship to Management - specific interactions with Agency decision-makers
- ✓ Public Disclosure - timing and availability of product or service

The specific facts disclosed in any COI situation will be unique to that situation. Therefore, the decisions and conclusions reached in one situation may or may not be directly applicable to another. For example, the definition of "low-level" documents does not isolate a Firm producing them from a potential COI situation. The ultimate determination will take into account the other factors described above.

6. Examples of Conflict of Interest Situations

Agency offers the following examples to better illustrate conflict of interest situations that may arise during the course of the performance of a Personal Services Contract or a Price Agreement and any WOC entered into between Agency and a Firm, or during any Agency Procurement process, in order to provide guidance to Firms as they determine if their specific situations warrant disclosure, evaluation, and management.

1. A Design-Build solicitation requires the responding teams to propose how to manage site features that were uncovered by a geotechnical engineering Firm. The Firm's reports to

Agency on the Project are available to the public. A multi-specialty engineering Firm that is the parent company of the geotechnical engineering Firm submits a proposal to design the overall Project. Depending on the particular mitigating facts, Agency might determine in writing that the multi-specialty engineering Firm is eligible to propose.

2. Agency seeks comprehensive project management services for a series of Transportation Projects. One of the proposing Firms employed a senior official from Agency who played a significant role in providing direction for the solicitation, six months ago. Agency initially assesses this situation as a potential Organizational Conflict Of Interest and provides information to potential Proposers of this assessment through an addendum to the RFP. In its proposal, the Proposer provides mitigating information and written assurances that this individual works in an area of the company that will not be working on their program management proposal and that the individual will be isolated inside the company from any information associated with the program, will not be lobbying Agency, will not engage in any activities that would violate the Agency Code of Conduct Policy for the prescribed one year period, and for a period of two years will not have a direct beneficial interest in the contract. Depending on the particular facts, Agency might determine that, while the proposing Firm has a potential Organizational Conflict Of Interest, that conflict has been adequately mitigated and the Firm will not be disqualified from submitting a proposal.
3. Agency issues an RFP for design and oversight of an intelligent system to collect bridge tolls. The RFP provides that companies having a financial interest in the relevant telecommunications hardware will be excluded from bidding. A company under common ownership with a major electronics manufacturer desires to bid. Agency initially assesses this situation as an Organizational Conflict Of Interest, because it cannot know in advance whether the hardware products of this electronics manufacturer would be used in the Project, and Agency informs potential Proposers of its concern related to this type of conflict via addendum to the RFP. In its proposal, the company offers no mitigating facts or organizational plans that address Agency's concerns about the conflict. Depending on the particular facts, Agency determines that the company has an actual conflict of interest.
4. Agency seeks advice of an industry advisory committee to formulate the specifications for an information technology (IT) RFP. An IT Firm that participated in the advisory committee wishes to submit a proposal in response to the RFP. Depending on the particular facts, Agency might determine that the role of the Firm was to represent the industry in the context of a public meeting where other Firms were invited to submit comments, and that the Firm therefore does not have an Organizational Conflict Of Interest.
5. Agency contracts with an A&E Firm to develop "low-level" documents prior to establishing a schedule for a RFP in which the "low level" documents, still under development, will be used by prospective Proposers. The A&E Firm has attended the pre-proposal meeting and wishes to propose on the RFP. Agency determines that the company has a potential Organizational Conflict Of Interest because of the fact that the low-level documents have not been made public and the Firm will still be developing the documents during the solicitation. The company then mitigates the potential conflict of interest by suspending development of new reports during the open period of the solicitation and making all data and information sources available on an Agency website prior to the RFP release. Agency determines that the potential conflict has been adequately managed and the Firm will not be disqualified from submitting a proposal or being part of the proposing team.
6. Agency contracts with a consulting Firm to assist Agency in the development of an RFP and sample Contract for a Design-Build Procurement for construction of certain Transportation Projects. The Firm has close contact with Agency decision-makers in the development of the evaluation criteria for the RFP and the proposed Contract terms, and that information is shared throughout the Firm with all management and technical personnel. The Firm will not be able to submit a proposal in the design-build Procurement, or participate as a team member with a Firm submitting a proposal in

response to the RFP.

7. Agency seeks comprehensive program management services for a series of Transportation Projects. Prior to release of the RFP, Agency shared its interpretation of the applicable conflict of interest requirements with the industry. One of the proposing Firms has a related entity with a planned interest in future design-build construction work related to the transportation program. The COI Disclosure Form does not clearly state whether the related entity is a subsidiary, major partner, Subcontractor, or affiliate of a Subcontractor. The proposing Firm describes its intent to restrict the flow of information concerning construction Projects to the related entity and thereby to its affiliate construction company but does not clarify how much information will be shared between the principal and its Subcontractors and affiliates or the controls placed on the principal-Subcontractor-affiliate relationship. Furthermore, the proposing Firm has provided mitigation information, indicating that the related entity will not participate in providing services under the program management Contract (i.e., design, source selection, award of Contract, etc.). Agency may conclude the proposing Firm does not have a conflict of interest that detracts from its eligibility for the program management award. Agency may determine that the related entity has a conflict of interest in future design-build construction work related to the bridge repair and replacement program that has not been adequately mitigated by the measures and information provided by the proposing Firm. As a result, if the proposing Firm is awarded the program management Contract, the related construction company will be ineligible for construction work under the program. This determination will depend upon the precise relationship between the related entity and the Proposer.
8. Completion of a project may encourage construction of a shopping center or industrial park from which a Firm stands to benefit. If a Firm is aware that it has such an interest in the decision on the proposal, it will be disqualified from preparing an EIS to preserve the objectivity and integrity of the NEPA process.
9. Agency issues an RFP for A&E services to prepare plans, specifications, and estimate (PS&E) to replace a bridge. The PS&E will be completed as part of a design-bid-build process. One of the A&E firms proposing on the design services owns XYZ Inc., a subsidiary that provides program management services to Agency under a separate contract. Agency's intent, as advertised in the RFP, is to use XYZ Inc. for administration and oversight of the A&E design services for the bridge replacement project. The A&E firm that is the parent of XYZ Inc. would be ineligible for award of the A&E design contract.
10. Agency issues an ITB for construction services to replace a bridge. The replacement is being done using the design-bid-build process. One of the construction firms bidding on the public improvement project owns XYZ Inc., a subsidiary that provides construction contract administration and inspection services to Agency under a separate contract. Agency's intent, as advertised in the ITB, is to use XYZ Inc. for administration and inspection of the bridge replacement project. The construction firm that is the parent of XYZ Inc. would be ineligible for award of the construction contract.

Definitions

The following definitions apply to these COI Guidelines and the Agency's COI Disclosure Form:

“Actual Conflict Of Interest” means that an individual or Firm is unable to render impartial assistance or advice to Agency, has impaired objectivity in performing the Project work, or has an unfair competitive advantage. For purposes of ORS Chapter 244, and as defined in ORS 244.020(1), “Actual Conflict of Interest” means any action or any decision or recommendation by a person acting in a capacity as a public official, the effect of which *would be* to the private pecuniary benefit or detriment of the person or the person's relative or any business with which the person or a relative of the person is associated unless the pecuniary benefit or detriment arises out of the circumstances described in the ORS Chapter 244 definition for “Potential Conflict

of Interest” (see definition below).

“**Affiliate**” (of the Firm) means a person or entity that, directly or indirectly through one or more intermediaries, controls, is controlled by or is under common control of the Firm.

“**Apparent Conflict Of Interest**” means that an individual or Firm may reasonably be perceived to have an Actual Conflict of Interest or a Potential Conflict Of Interest.

“**Associate**” (of the Firm) means an employee, executive, director, key project personnel, consultant, contractor or Subcontractor, or any immediate family member of the foregoing.

“**Authorization**” (of the Contract). A public contract is authorized by a Public Official if the Public Official performed a significant role in the selection of a Firm or the execution of the Contract. A *significant role includes* recommending approval or signing of the Contract, including serving as a reference, recommending selection or serving on a selection committee or team, or having the final authorizing authority for the Contract.

“**Bidder**” means a legally operating business entity submitting a bid in response to a Procurement.

“**Conflict Of Interest**” or “**COI**” means an Individual Conflict Of Interest or Organizational Conflict Of Interest and includes an Actual, Potential, or Apparent Conflict Of Interest.

“**COI Disclosure Form**” means a manually signed disclosure of any Actual Conflict Of Interest, Apparent Conflict Of Interest or Potential Conflict Of Interest documented in the form of Agency’s COI Disclosure Form.

“**Correct**” means, in the context of determining the accuracy of a COI Disclosure Form, that the form, in all material respects, is complete, accurate, not misleading, and does not omit any material information.

“**Contract**” means an Agreement to Agree (ATA), Price Agreement (PA), Work Order Contract (WOC), Purchase Order (PO), or any other contract with Agency.

“**Firm**” means a Proposer or Bidder under a Procurement, a consultant or contractor under a Contract, or a Subcontractor at any tier of a Proposer, consultant, or contractor, and any partner or member of any of the foregoing. A Firm includes all persons, individual or corporate, without regard to form of legal entity, and any partner or member of any of the foregoing.

“**Member of the Household**” (of the Public Official) means any person who resides with the Public Official.

“**Individual Conflict Of Interest**” means that an individual has a conflict of interest because of a financial interest, gift, or other activities or relationships with other persons including but not limited to individuals with whom the individual has business, familial or household relationships.

“**Interest**” (in the context of a conflict of interest) means a direct or indirect interest and includes a personal as well as financial interest.

“**Low-Level Document**” means A&E, non-A&E and IT program or Project related documents which provide a basic understanding of a specific aspect of the program or Project. As referred to in 23CFR 636.116 with regard to A&E and related services, “the role of the consultant or subconsultant was limited to provision of preliminary design, reports, or similar “low-level” documents that will be incorporated into the RFP, and did not include assistance in development of instructions to offerors or evaluation criteria”.

"Organizational Conflict Of Interest" means that a relationship or situation exists whereby a Firm or any of its Associates has past, present, or currently planned interests or activities that either directly or indirectly (through a client, contractual, financial, organizational or other relationship) may relate to the work to be performed under the proposed Contract with Agency and which (a) diminish the Firm's or an Associate's capacity to give impartial, technically sound, objective assistance or advice, (b) may impair the Firm's or an Associate's objectivity in performing the Contract, (c) may impair Agency's objectivity in oversight of the Contractor's performance, or (d) may result in an unfair competitive advantage. It does not include the normal flow of benefits from the performance of the Contract.

"Potential Conflict Of Interest" means that an individual or Firm, as a result of current plans, may reasonably be expected to have an actual conflict of interest. For purposes of ORS Chapter 244, and as defined in ORS 244.020(11), "Potential Conflict of Interest" means any action or any decision or recommendation by a person acting in a capacity as a public official, the effect of which *could be* to the private pecuniary benefit or detriment of the person or the person's relative, or a business with which the person or the person's relative is associated, unless the pecuniary benefit or detriment arises out of the following: (a) an interest or membership in a particular business, industry, occupation or other class required by law as a prerequisite to the holding by the person of the office or position.; (b) any action in the person's official capacity which would affect, to the same degree, a class consisting of all inhabitants of the state or a smaller class consisting of an industry, occupation or other group including one of which or in which the person, or the person's relative or business with which the person or the person's relative is associated, is a member or is engaged; or (c) membership in or membership on the board of directors of a nonprofit corporation that is tax-exempt under section 501(c) of the Internal Revenue Code.

"COI Guidelines" refers to this document and all references herein.

"Procurement" means a Request for Proposals (RFP), Request for Qualifications (RFQ), Request for Information (RFI), Invitation to Bid (ITB), or any other form of solicitation or Procurement by Agency.

"Proposal" means a bid, proposal, or other submission appropriate to a Procurement.

"Proposer" means a legally operating business entity submitting a Proposal in response to a Procurement.

"Public Disclosure" means the work product or service (in connection with the preparation of a Procurement) is available for public review and analysis for a reasonable amount of time, typically at least thirty (30) calendar days.

"Public Official" means any person who is serving the State of Oregon or any of its political subdivisions or any other public body as defined in ORS 174.109 as an elected official, appointed official, employee, agent or otherwise, irrespective of whether the person is compensated for the services. (All Agency employees are Public Officials.)

"Relative" (of a Public Official) means:

- the Public Official's spouse or domestic partner;
- the children, siblings, spouses of siblings or parents of the Public Official or the Public Official's spouse; or
- any individual for whom the Public Official has a legal support obligation or for whom the Public Official provides benefits arising from the Public Official's public employment or from whom the Public Official receives benefits arising from that individual's employment.

"Subcontractor" means a subcontractor or subconsultant at any tier.

“Transportation Project” or **“Project”** means any proposed or existing undertaking pertaining to highways, bridges, motor carriers, motor vehicles, public transit, rail, transportation safety, information systems, and such other programs related to transportation that are assigned to Agency under applicable law.

PREQUALIFICATION FORM

**2023 ADA IMPROVEMENT PROJECT
CONTRACT No. 2023-003**

1) BIDDER'S GENERAL INFORMATION

Contractor's Name: _____

Doing business as: _____
(An Individual, Partnership, Corporation, LLC)

Oregon Secretary of State Corp. Div. Registry No. _____

Address 1: _____

Address 2: _____

Phone: _____ Fax: _____

Application prepared by: _____

Preparer's Email: _____

Oregon Construction Contractors Board No. (CCB) _____

Other State License No. _____

2) BONDING

Surety Company: _____

Agent Name: _____

Address 1: _____

Address 2: _____

Phone: _____ Fax: _____

Bonding Capacity: Per Project \$ _____ Aggregate \$ _____

3) **WORK EXPERIENCE**

A. How many years has your firm been in business under its present name?

As a prime contractor? _____ As a subcontractor? _____

B. How many years' experience in construction work has your firm had?

As a prime contractor? _____ As a subcontractor? _____

C. **ATTACH TO THIS FORM** the experience resume of the person who will be designated on-site construction manager. On-site manager shall have ODOT ADA Certification for Contractors or approved equal. Provide copy of certifications with resume.

D. List three (3) projects completed as of recent date involving work of a similar type and complexity (attach sheets as needed):

PROJECT #1

Owner Name, Project Name	Contract Price	Date of Completion
Contact Name, Address and Phone of Owner	Describe Work Performed	

PROJECT #2

Owner Name, Project Name	Contract Price	Date of Completion
Contact Name, Address and Phone of Owner	Describe Work Performed	

PROJECT #3

Owner Name, Project Name	Contract Price	Date of Completion
Contact Name, Address and Phone of Owner	Describe Work Performed	

4) SUPPLEMENTAL QUESTIONS – Attach written explanations as appropriate

A. Has your company changed its name during the past 5 years? Yes ____ No ____
If yes, provide your company's former name: _____

B. Has your company ever been denied prequalification by any state, local or federal agency in this or any other state?

Yes ____ No ____ **if yes, please attach an explanation**

C. Has your company ever failed to complete a state, local or federal public improvement contract?

Yes ____ No ____ **if yes, please attach an explanation**

D. Has your company had any claims placed against one of your payment bonds or performance bonds in the past 5 years?

Yes ____ No ____ **if yes, please attach an explanation**

E. Have you or your company ever been debarred from bidding on contracts by any state, local or federal agency in this or any other state?

Yes ____ No ____ **if yes, please attach an explanation**

F. Has your company filed for bankruptcy in the past 5 years?

Yes ____ No ____ **if yes, please attach an explanation**

G. Has your company had any willful OSHA violations in the past 5 years?

Yes ____ No ____ **if yes, please attach an explanation**

H. Within the last 5 years has the applicant, or any parent, subsidiary or affiliate, failed to complete a state, local or federal public improvement (works) contract?

Yes ____ No ____ **if yes, please attach an explanation**

I. Within the last 5 years has the applicant, or any parent, subsidiary or affiliate, been found in breach of a local, state or federal contract?

Yes ____ No ____ **if yes, please attach an explanation**

- J.** Within the last 5 years have you, your company or any officers, agents or employees of your company been found to have violated any State or Federal prevailing wage statute, regulation (including the federal Davis-Bacon and Related Acts and ORS 279C.830 et. seq.) in any Final Order of the Oregon Bureau of Labor and Industries or the US Department of Labor, or by any court of competent jurisdiction?

Yes ____ No ____

If yes, provide copies of the final order or judgment and explain in detail the following:

- the circumstances behind any violation, including the amount not paid
- whether the amounts have now been paid
- the reasons for the violation
- all efforts undertaken to ensure that future violations will not occur

- K.** Does your firm have available the appropriate financial, material, equipment, facility and personnel resources and expertise, or ability to obtain the resources and expertise, necessary to demonstrate the capability of the firm to meet all contractual responsibilities?

Yes ____ No ____ **if yes, please provide supporting documentation**

- L.** Is your firm experiencing financial distress or having difficulty securing financing?

Yes ____ No ____

- M.** Does your firm have sufficient cash flow to fund day-to-day operations throughout the proposed contract period?

Yes ____ No ____

- N.** Within the last 5 years, has your firm completed previous contracts of a similar nature with a satisfactory record of performance? [For purposes of this question, a satisfactory record of performance means that to the extent that the costs associated with and time available to perform a previous contract remained within your firm's control, your firm stayed within the time and budget allotted for the procurement and otherwise performed the contract in a satisfactory manner.]

Yes ____ No ____ **if no, please attach an explanation**

- O.** Does your firm have all required licenses, insurance and/or registrations, if any, and is the firm legally authorized to do business in the State of Oregon?

Yes ____ No ____ **if no, please attach an explanation**

- P.** Is your firm covered by liability insurance and other insurance in amounts required in the contract specifications or have the ability to obtain the required insurance in the amounts required in the specifications after notice of award?

Yes ____ No ____

- Q.** Does your firm qualify as a carrier-insured employer or a self-insured employer under ORS 656.407 or has elected coverage under ORS 656.128?

Yes ____ No ____

- R.** Has your firm complied with the tax laws of the State or a political subdivision of the State, including ORS 305.620 and ORS Chapters 316, 317 and 318?

Yes ____ No ____

5) CERTIFICATION STATEMENT

I certify that the foregoing statements and information provided in all sections of this application are correct and true as of the date of this application and that I am authorized to bind this company contractually. I further certify that any additional information requested by the City to process this application will be true and correct.

Name

Title

Signature

Date

Company Name

CONFLICT OF INTEREST (COI) DISCLOSURE FORM

Firms under Contract or proposing to enter into a Contract with Agency must be in conformance with the "City of The Dalles (COTD) Conflict of Interest Guidelines" available on the Internet at: www.ci.thedalles.or.us/engineering. The definitions of terms used in this COI Disclosure Form shall be those provided in the City of The Dalles Conflict Of Interest Guidelines (note that "Public Official" includes all Agency employees).

This COI Disclosure Form is submitted in response to (check only one):

- ☐ **Agency RFP# _____ [or] ITB# _____**
- ☐ **Contract # _____**
- ☐ **Price Agreement # _____ WOC# _____ [or] PO# _____**
- ☐ **Changes to COI Disclosure Form previously submitted for (RFP # _____, ITB # _____, Price Agreement # _____, WOC # _____, Contract # _____)**

This COI Disclosure Form must be signed in ink by a principal of the Firm to certify that it is correct. A Firm's certification that its disclosure form is correct includes the disclosure by its Associates and Subcontractors.

My signature certifies that as disclosed on or attached to the present form:

- (a) the Firm's disclosures are complete, accurate, and not misleading.
- (b) the Firm has provided the City of The Dalles COI Guidelines to all Associates and Subcontractors (if any) and the present form includes or has attached any required COI disclosures from those sources.

I hereby certify that I am authorized to sign this COI Disclosure Form as a Representative for the Firm identified below:

Complete Legal Name of Firm: _____

Address: _____

Telephone: _____

Fax No: _____

Signature: _____ **Date:** _____

Please answer all questions "Yes", "No" or "N/A" (if uncertain answer "Yes.") If the answer to any of the questions is "Yes," then use the applicable "Comments" fields to:

(a) furnish all relevant facts that are necessary to make the response complete, accurate, and not misleading; and

(b) identify any actions that must be taken to avoid, neutralize, or mitigate such conflict of interest (e.g. communications barriers, restraint or restriction upon future contracting activities, or other precaution)

1. a) Is any Associate of the Firm a former employee of Agency within the last year? **No** ☐ **Yes** ☐
- b) Is any Associate of the Firm a Relative or Member of the Household of a current Agency employee that had or will have any involvement with this Procurement or Contract Authorization? **No** ☐ **Yes** ☐

If the answer to either of the above questions is "Yes", complete the attached "Relatives and Former Agency Employees -Roles and Signatures" table (Part A and/or Part B, as applicable).

2. Does the Firm or any Associate of the Firm have an Actual, Apparent or Potential Conflict Of Interest ("Individual" or "Organizational") with regard to any known member of an Agency Procurement evaluation or selection team? **No** ☐ **Yes** ☐ **Comments:**

3. Did the Firm or any Associate of the Firm conduct prior work on the Project described in the Procurement, or participate in preparing any part of the Procurement or any documents or reports related to the Procurement or to which the Procurement refers? **No** ☐ **Yes** ☐ **Comments:**
4. Does the Firm or any Associate of the Firm have any past, present or currently planned personal or financial interests which are an Actual, Apparent or Potential Conflict of Interest ("Individual" or "Organizational"), with respect to the Procurement or award of this Contract or performing the work for Agency or acquisition of any real property for the Project? **No** ☐ **Yes** ☐ **Comments:**
5. Has the Firm or an Associate of the Firm offered to a Public Official, or is the Firm aware of any Public Official that has solicited or received, directly or indirectly, any pledge or promise of employment or other benefit based on the understanding that the Public Official's vote, official action or judgment would be influenced thereby? **No** ☐ **Yes** ☐ **Comments:**
6. Has (or will) the Firm or an Associate of the Firm provided a direct beneficial financial interest to any person within two years after the person ceased to hold a position as a Public Official who was involved in the Procurement or Authorization for the Contract, or is the Firm aware of any such person or Public Official who has or will receive a direct beneficial financial interest within the two year period? **No** ☐ **Yes** ☐ **Comments:**
7. Is the Firm aware of any current or former Public Official that has an Actual, Apparent or Potential Conflict Of Interest with respect to the Procurement or award of this Contract or performing the work for Agency? **No** ☐ **Yes** ☐ **Comments:**
8. Does the prospective Contract/WOC include development of an Environmental Assessment (EA) or Environmental Impact Statement (EIS)? **No** ☐ **Yes** ☐
- If yes**, in accordance with the disclosure statement requirements of Council on Environmental Quality Regulation, 40 C.F.R 1506.5(c), does the Firm have any financial or other interest in the outcome of this Project; and/or does the Firm have any agreement, enforceable promise, or guarantee to provide any future work on this Project? **No** ☐ **Yes** ☐ **Comments:**
9. Have Subcontractors or other Associates furnished COI Disclosure Forms, separate from the present form, which included conflicts or potential conflicts of interest? (If yes, attach the disclosures.) **No** ☐ **Yes** ☐ **N/A** ☐ **Comments:**
10. If the prospective Contract/WOC includes personal services for the purpose of administering, managing, monitoring, inspecting, evaluating compliance with or otherwise overseeing a public contract, is the Firm or an Associate or an Affiliate of the Firm a party to the subject public contract? **No** ☐ **Yes** ☐ **N/A** ☐ **Comments:**
11. Has the Firm or any Associate of the Firm entered into personal services contract(s) with Agency for the purpose of advising or assisting in developing specifications, a scope or statement of work, an invitation to bid, a request for proposals or other solicitation documents and materials related to this procurement? **No** ☐ **Yes** ☐ **Comments:**

Relatives and Former Agency Employees - Roles and Signatures

For each employee of the Firm that was employed by Agency within the last year, state the job the employee performed for Agency, the role the employee now serves for the Firm and the date the employee left Agency. Use Part B for Firm Associates with Relatives or Members of the Household working for Agency that had or will have involvement with this Procurement or Contract.

Part A: Employees that left Agency in the last year.			
Employee Name/Signature	Job Performed for Agency	Current Role with Firm	Date left Agency
Name: _____ Sign: _____ <ul style="list-style-type: none"> Involved with this Procurement on behalf of COTD? No <input type="checkbox"/> Yes <input type="checkbox"/> Involved with Proposal development for this Procurement? No <input type="checkbox"/> Yes <input type="checkbox"/> 			
Name: _____ Sign: _____ <ul style="list-style-type: none"> Involved with this Procurement on behalf of COTD? No <input type="checkbox"/> Yes <input type="checkbox"/> Involved with Proposal development for this Procurement? No <input type="checkbox"/> Yes <input type="checkbox"/> 			
Name: _____ Sign: _____ <ul style="list-style-type: none"> Involved with this Procurement on behalf of COTD? No <input type="checkbox"/> Yes <input type="checkbox"/> Involved with Proposal development for this Procurement? No <input type="checkbox"/> Yes <input type="checkbox"/> 			
Part B: Identify Associates of the Firm that are Relatives or Members of the Household of Agency employees currently working for Agency, if the Agency employee had or will have any involvement with this Procurement or Contract.			
Firm Associate's Name	Name and Relationship of Relative or Member of Household Employed at Agency	Role at Agency	Agency employee's Role with this Procurement

(Make copies of this form as needed to list additional employees.)

PROPOSAL

Proposal of _____ (hereinafter called BIDDER),
organized and existing under the laws of the State of _____, doing business as _____*
to the CITY OF THE DALLES, OREGON, (hereinafter called OWNER).

In compliance with your Advertisement for Bids, BIDDER hereby proposes to perform all work necessary for

CONTRACT NO. 2023-003 2023 ADA IMPROVEMENT PROJECT

in strict accordance with the contract documents, within the time set forth herein, and at the prices stated below.

By submission of this Proposal, each BIDDER certifies, and in the case of a joint Proposal each party certifies as to their own organization, that this Proposal has been arrived at independently, without consultation, communication or agreement as to any matter relating to this Proposal with any other BIDDER or with any competitor.

BIDDER hereby agrees to commence work under this contract on or before a date to be specified in the Notice to Proceed and to fully complete the project by **June 2, 2023**. BIDDER further agrees to pay liquidated damages, the sum calculated at the per diem rate set forth in Section 00180.85(b) for each consecutive calendar day thereafter for which the Contractor is in breach of the Contract.

BIDDER further states that provisions of ORS 279C.830 will be complied with.

BIDDER in supplying this proposal acknowledges the receipt of the Contract Document package.

BIDDER further acknowledges receipt of the following Addenda:

No. 1 _____ Date

No. 2 _____ Date

No. 3 _____ Date

*Insert "a corporation", "a partnership", or "an individual", as applicable.

BIDDER agrees to perform all the work described in the contract documents for the following unit prices or lump sum.

Item Number	Approximate Quantity	Units	Description & Unit Price	Extended Amount
#1	1	LS	MOBILIZATION	\$ _____
#2	1	LS	TEMPORARY WORK ZONE TRAFFIC CONTROL AND PEDESTRIAN ROUTING	\$ _____
#3	1	LS	CONSTRUCTION SURVEYING AND MONUMENT REINSTATEMENT	\$ _____
#4	1	LS	EROSION AND POLLUTION CONTROL	\$ _____
#5	868	LF	REMOVE EXISTING CONCRETE CURB @ _____	\$ _____
#6	593	SY	REMOVE EXISTING CONCRETE SIDEWALK @ _____	\$ _____
#7	585	SY	REMOVE EXISTING ASPHALT @ _____	\$ _____
#8	114	CY	GENERAL EXCAVATION @ _____	\$ _____
#9	57	CY	3/4 INCH MINUS ROCK BASE @ _____	\$ _____
#10	692	SY	CONCRETE SIDEWALK @ _____	\$ _____

#11	395	LF	CONCRETE CURB @ _____	\$ _____
#12	697	LF	CONCRETE CURB AND GUTTER @ _____	\$ _____
#13	40	EA	EXTRA FOR NEW CURB RAMPS @ _____	\$ _____
#14	40	EA	TRUNCATED DOMES ON NEW SURFACES @ _____	\$ _____
#15	1	LS	REINSTATE FENCE	\$ _____

TOTAL BID AMOUNT

\$_____

BIDDER acknowledges through the submission of this Proposal that the work to be performed in this project shall require close coordination with the Owner.

Respectfully submitted,

(Contractor)

By _____ Date _____

Address _____

License Number (if applicable) _____

SEAL (if Bid is by a Corporation)

ATTEST:

RESIDENT BIDDER: _____ YES _____ NO

BID BOND

(SEE SECTION 00120.40(E) - 10%)

KNOW ALL MEN BY THESE PRESENTS, that we, the undersigned

_____ as Principal, and
_____ as Surety, are

hereby held and firmly bound unto **CITY OF THE DALLES** in the penal sum of
\$ _____ for the payment of which, well and truly to be made, we hereby jointly and
severally bind ourselves, our successors, and assigns.

Signed, this ____ day of _____, 2023.

The Condition of the above obligation is such that whereas the Principal has submitted to **CITY
OF THE DALLES** a certain **PROPOSAL**, attached hereto and hereby made a part hereof to
enter into a contract in writing, for
CONTRACT NO. 2023-003, 2023 ADA IMPROVEMENT PROJECT

NOW, THEREFORE

(a) If said **PROPOSAL** shall be rejected, or
(b) If said **PROPOSAL** shall be accepted and the Principal shall execute and deliver a
contract in the Form of Contract attached hereto (properly completed in accordance with said
PROPOSAL) and shall furnish a **BOND** for their faithful performance of said contract, and for
the payment of all persons performing labor or furnishing materials in connection therewith, and
shall in all other respects perform the agreement created by the acceptance of said **PROPOSAL**,
then this obligation shall be void, otherwise the same shall remain in force and effect; it being
expressly understood and agreed that the liability of the Surety for any and all claims hereunder
shall, in no event, exceed the penal amount of this obligation as herein stated.

The surety, for value received, hereby stipulates and agrees that the obligations of said Surety
and its **BOND** shall be in no way impaired or affected by any extension of the time within which
the **CITY** may accept such **PROPOSAL**; and said Surety does hereby waive notice of any such
extension.

IN WITNESS WHEREOF, the Principal and the Surety have hereunto set their hands and
seals, and such of them as are corporations have caused their corporate seals to be hereto affixed
and these presents to be signed by their proper officers, the day and year first set forth above.

_____(L.S.)
(Principal)

By _____
(Title)

(Surety)

By _____
(Title)

IMPORTANT - Surety companies executing **BONDS** must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the State where the project is located.

DISCLOSURE OF FIRST-TIER SUBCONTRACTORS

PROJECT NAME: 2023 ADA IMPROVEMENT PROJECT

CONTRACT NUMBER: 2023-003

BID CLOSING: Date: January 26, 2023 Time: 2:00 P.M.

This form must be submitted at the location specified in the Invitation to Bid on the advertised bid closing date and within two working hours after the advertised bid closing time. List below the name of each subcontractor that will be furnishing labor or materials and that is required to be disclosed, the category of work that the subcontractor will be performing and the dollar value of the subcontract. Enter "NONE" if there are no subcontractors that need to be disclosed.
ATTACH ADDITIONAL SHEETS IF NEEDED.

<u>NAME</u>	<u>DOLLAR VALUE</u>	<u>CATEGORY OF WORK</u>
1) _____	_____	_____
_____	_____	_____
_____	_____	_____
2) _____	_____	_____
_____	_____	_____
_____	_____	_____
3) _____	_____	_____
_____	_____	_____
_____	_____	_____
4) _____	_____	_____
_____	_____	_____
_____	_____	_____

Failure to submit this form by the disclosure deadline will result in a nonresponsive bid. A nonresponsive bid will not be considered for award.

Form submitted by (bidder name): _____

Contact name: _____ Phone No. _____

Submit this form via email to thedallesbids@ci.the-dalles.or.us by 4:00 p.m. on January 26, 2023

NON-COLLUSION AFFIDAVIT

Contract Bid No. 2023-003

2023 ADA IMPROVEMENT PROJECT

State of _____

County of _____

I state that I am (title) _____ of (name of firm) _____ and that I am authorized to make this affidavit on behalf of my firm, and its owners, directors, and officers. I am the person responsible in my firm for the price(s) and the amount of this bid.

I state that:

A. The price(s) and amount of this bid have been arrived at independently and without consultation, communication or agreement with any other contractor, bidder or potential bidder, except as disclosed on the attached appendix.

B. That neither the price(s) nor the amount of this bid, and neither the approximate prices(s) nor approximate amount of this bid, have been disclosed to any other firm or person who is a bidder or potential bidder, and they will not be disclosed before bid opening.

C. No attempt has been made or will be made to induce any firm or person to refrain from bidding on this contract, or to submit a bid higher than this bid, or to submit any intentionally high or noncompetitive bid or other form of complementary bid.

D. The bid of my firm is made in good faith and not pursuant to any agreement or discussion with, or inducement from, any firm or person to submit a complementary or other noncompetitive bid.

E. (name of firm) _____, its affiliates, subsidiaries, officers, directors and employees are not currently under investigation by any governmental City and have not in the last four years been convicted of or found liable for any act prohibited by State of Federal law in any jurisdiction, involving conspiracy or collusion with respect to bidding on any public contract, except as described on the attached appendix.

I state that (name of firm) _____ understands and acknowledges that the above representations are material and important, and will be relied on by City of The Dalles, Oregon in awarding the contract(s) for which this bid is submitted. I understand and my firm understands that any misstatement in this affidavit is and shall be treated as fraudulent concealment from City of The Dalles, Oregon of the true facts relating to the submission of bids for this contract.

(Name of Company/Position)

Sworn to and subscribed before me this ____ day of _____, 2023.

NOTARY PUBLIC FOR OREGON

My Commission expires: _____

RESPONSIBILITY DETERMINATION FORM

Project Name: **2023 ADA IMPROVEMENT PROJECT**

Contract Number: 2023-003

Business Entity Name: _____

CCB License Number: _____

Form Submitted By: City of The Dalles, Oregon

City's Representative: Name: _____
Title: _____
Date: _____

The City of The Dalles has done all of the following:

- ☐ Checked the list created by the Construction Contractors Board under ORS 701.227 for bidders who are not qualified to hold a public improvement contract.
- ☐ Determined whether the bidder has met the standards of responsibility. In so doing, the City has considered whether the bidder:
 - ☐ Has available the appropriate financial, material, equipment, facility and personnel resources and expertise, or the ability to obtain the resources and expertise, necessary to meet all contractual responsibilities.
 - ☐ Holds current licenses that businesses or service professionals operating in this state must hold in order to undertake or perform the work specified in the contract.
 - ☐ Is covered by liability insurance and other insurance in amounts required in the solicitation documents.
 - ☐ Qualifies as a carrier-insured employer or a self-insured employer under ORS 656.407 or has elected coverage under ORS 656.128.
 - ☐ Has disclosed the bidder's first-tier subcontractors in accordance with ORS 279C.370.

- ☐ Has a satisfactory record of performance.
- ☐ Has a satisfactory record of integrity.
- ☐ Is qualified legally to contract with the City.
- ☐ Has supplied all necessary information in connection with the inquiry concerning responsibility.
- ☐ Has complied with the tax laws of the State or a political subdivision of the State, including ORS 305.620 and ORS Chapters 316, 317, and 318.

- ☐ Determined the bidder to be one of the following:
 - ☐ Responsible under ORS 279C.375(2)(a) and (b).
 - ☐ Not responsible under ORS 279C.375(2)(a) and (b)

NOTICE OF AWARD

TO: _____

PROJECT DESCRIPTION: **CONTRACT NO. 2023-003**
 2023 ADA IMPROVEMENT PROJECT

The City has considered the **BID** submitted by you for the above described work in response to its Advertisement for Bids dated **December 28**, 2022.

You are hereby notified that your **BID** has been accepted for the amount \$ _____

You are required by the General Conditions to execute the Contract and furnish the required **Contractor's Performance Bond, Payment Bond, and Original Certificates of Insurance** within ten (10) calendar days from the date of receipt of this notice.

If you fail to execute said Contract and to furnish said **BONDS** and original certificates of insurance within ten (10) days from the date of this Notice, the **CITY** will be entitled to consider all of your rights arising out of the **CITY'S** acceptance of your **BID** as abandoned and forfeit your **BID BOND**. The City will be entitled to such other rights as may be granted by law.

You are required to return an acknowledged copy of this **NOTICE OF AWARD** to the **CITY**.

Dated this _____ day of _____, 2023.

CITY OF THE DALLES, OREGON

By _____
Todd Stephens

Title Project Engineer

ACCEPTANCE OF NOTICE

Receipt of the above **NOTICE OF AWARD** is hereby acknowledged

By _____
(Company Name)

this the _____ day of _____, 2023.

By _____ Title _____



City of The Dalles

Department of Public Works
1215 West 1st Street
The Dalles, OR 97058

PREVAILING WAGE NOTE

This project is subject to Oregon prevailing wage law. All workers shall be paid no less than the applicable prevailing wage rate for the type of work being performed. The current “Prevailing Wage Rates for Public Works Contracts in Oregon” published by the Oregon Bureau of Labor and Industries shall apply to this contract. Current copies of the “Prevailing Wage Rates for Public Works Contracts in Oregon” may be obtained by contacting Oregon Bureau of Labor and Industries at (971) 673-0761 or by downloading a copy at: www.oregon.gov/boli/WHI/PWR/Pages/pwr_state.aspx

Current Prevailing Wage Rates for this project are the July 1, 2022 published rates and

July 1, 2022 Prevailing Wage Rates as amended on August 1, 2022:

July 1, 2022 published rates:

<https://www.oregon.gov/boli/workers/Prevailing%20Wage%20Rate%20Books/July%201,%202022%20PWR%20Rate%20Book.pdf>

August 1, 2022 amendments:

<https://www.oregon.gov/boli/workers/Prevailing%20Wage%20Rate%20Books/October%201%202022%20Amendment.pdf>

Oregon Bureau of Labor and Industries

Prevailing Wage Rates for Public Works Contracts

Val Hoyle
Labor Commissioner
Rates Effective July 1, 2022



**AMENDMENTS TO OREGON DETERMINATION 2022-02
EFFECTIVE OCTOBER 1, 2022**

Occupation and Premium/Differential Pay

Base Rate / Fringe Rate

GLAZIER

44.43

25.29

Add \$1.00 to base rate when employee works from a swing stage, scaffold, suspended contrivance or mechanical apparatus from the third floor up or thirty feet of free fall (whichever is less), and employee is required to wear a safety belt.

Add twenty percent (20%) to base rate when employee works from a bosun chair (non-motorized single-man apparatus), regardless of height.

Certified welders shall receive twenty percent (20%) above the base rate for actual time spent performing welding duties.

IRONWORKER

41.62

31.72

Zone Differential for Ironworker

(Add to Basic Hourly Rate)

Zone 2 **5.63/hr.** or \$45.00 maximum per day

Zone 3 **8.75/hr.** or \$70.00 maximum per day

Zone 4 **11.25/hr.** or \$90.00 maximum per day

Zone 1: Projects located within 45 miles of city hall in the reference cities listed below.

Zone 2: More than 46 miles, but less than 60 miles.

Zone 3: More than 61 miles, but less than 100 miles.

Zone 4: More than 100 miles.

Note: Zone pay for Ironworkers shall be determined using the quickest route per Google Maps and computed from the city hall or dispatch center of the reference cities listed below **or** the residence of the employee, whichever is nearer to the project.

Reference Cities and Dispatch Center

Medford

Portland

LIMITED ENERGY ELECTRICIAN

Area 2 (Regions 12 and 13)

34.51

16.04

Reference Counties

Baker

Grant

Umatilla

Wallowa

Gilliam

Morrow

Union

Wheeler



PART 2

CONTRACT BOOKLET

2023 ADA IMPROVEMENT PROJECT
CONTRACT NO. 2023-003

CONTRACT

THIS AGREEMENT, made this _____ day of _____, **2023** by and between the CITY OF THE DALLES, Oregon, hereinafter called "**CITY**", acting through its City Council or designee, and _____ doing business as _____ *
*(an individual),(a partnership),(a corporation)
located in the City of _____, County of _____, and State of _____, hereinafter called "**CONTRACTOR**".

WITNESSETH: That, for and in consideration of the payments and agreements hereinafter mentioned to be made and performed by the **CITY**, the **CONTRACTOR** hereby agrees with the **CITY** to commence and complete the work described in the **CONTRACT DOCUMENTS** and comply with the terms in the **CONTRACT DOCUMENTS** for **CONTRACT NO. 2023-003 2023 ADA IMPROVEMENT PROJECT** for the sum of \$ _____ dollars or as shown in the Proposal.

CONTRACTOR will furnish all of the material, supplies, tools, equipment, labor, expertise, bonds, insurance, licenses, permits, and other services, including subcontractors approved under this agreement, necessary for the completion of the project.

CONTRACTOR will furnish proper and adequate Workers' Compensation coverage. In the event the **CONTRACTOR'S** insurance does not cover each and every subcontractor, certificates of insurance issued on policies by companies that are acceptable to the **CITY** covering each and every subcontractor must be filed with the **CITY** prior to the commencement of such subcontract operations. Before commencing work under this agreement, **CONTRACTOR** will provide the **CITY** with evidence that it is either a "self-insured employer" or a "carrier insured employer" for Workers' Compensation as required by ORS Chapter 656.

CONTRACTOR hereby agrees to commence work under this contract on or before the date specified in the **CITY'S** written "Notice to Proceed" and to fully complete the project by **June 2, 2023**. The **CONTRACTOR** further agrees to pay liquidated damages for each consecutive day thereafter for which the contractor is in breach of the contract as provided in Section 00180.85 of the Standard Specifications.

The provisions and requirements of Chapter 279(A),(B), and (C) Oregon Revised Statutes and the rules of the local Contract Review Board are hereby referred to and incorporated herein as a part of this contract and the **CONTRACTOR'S** obligations under the terms of this contract.

The term "**CONTRACT DOCUMENTS**" means and includes the following:

Advertisement for Bids	Invitation to Bidders
Proposal	Subcontractors Disclosure Form
Bid Bond	Notice of Award
Prevailing Wage Rates	Contract
Performance Bond	Payment Bond
Notice to Proceed	Non-Collusion Affidavit
Drawings	Prequalification Form
Technical Specifications	Special Provisions
Responsibility Determination Form	City of The Dalles Standard Specifications for Construction

The **CITY** will pay to the **CONTRACTOR** in the manner and at such times as set forth in the "General Conditions" such amounts as required by the Contract Documents.

This agreement shall be binding upon all parties hereto and their respective heirs, executors, administrators, successors, and assigns.

IN WITNESS THEREOF, the parties hereto have executed, or caused to be executed by their duly authorized officials, the agreement in duplicate, each of which shall be deemed an original, on the date first written above.

CITY : **CITY OF THE DALLES**

BY: _____
City Manager

NAME: _____

Approved as to Form:

SEAL:

City Attorney

ATTEST: _____
City Clerk

CONTRACTOR: _____

BY: _____
(Title)

NAME: _____
(Please type)

SEAL:

ATTEST: _____
(Title)

ADDRESS: _____

PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS THAT:

(Name of Contractor)

(Address of Contractor)

a _____, hereinafter called
(Corporation, Partnership, Individual)

Principal, and _____
(Name of Surety)

(Address of Surety)

hereinafter called Surety, are held and firmly bound unto:

CITY OF THE DALLES

(Name of Owner)

313 Court Street, The Dalles, Oregon 97058

(Address of Owner)

hereinafter called **CITY**, in the penal sum of \$ _____ in lawful money of the United States, for the payment of which sum well and truly to be made, we bind ourselves, successors, and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF OBLIGATION is such that whereas, the Principal entered into a certain contract with the **CITY** dated the _____ day of _____, 2023, a copy of which is hereto attached and made a part hereof for:

CONTRACT NO. 2023-003
2023 ADA IMPROVEMENT PROJECT

NOW, THEREFORE, if the Principal shall well, truly, and faithfully perform its duties, all the undertakings, covenants, terms, conditions, and agreements of said contract during the original term thereof, and any extensions thereof which may be granted by the **CITY**, with or without notice to the Surety and during the one year guaranty period, and if they shall satisfy all claims and demands incurred under such contact, and shall fully indemnify and save harmless the **CITY** from all costs and damages which it may suffer by reason of failure to do so, and shall reimburse and repay the **CITY** all outlay and expense which the **CITY** may incur in making good any default, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the contract or to the **WORK** to be performed thereunder or the **SPECIFICATIONS** accompanying the same shall in any way affect its obligation on this **BOND**, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the contract or to the **WORK** or to the **SPECIFICATIONS**.

PROVIDED FURTHER, that no final settlement between the **CITY** and the **CONTRACTOR** shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

IN WITNESS WHEREOF, this instrument is executed in three (3) counterparts, each one of which shall be deemed an original, this the _____ day of _____, 2023.

ATTEST:

Secretary
(Principal)

Principal

(SEAL)

BY _____

Witness as to Principal

(Address)

Surety

ATTEST:

BY _____

Attorney-in-Fact

Witness as to Surety

(Address)

(Address)

Phone: _____

NOTE: Date of **BOND** must not be prior to date of **CONTRACT**. If **CONTRACTOR** is a Partnership, all partners should execute **BOND**.

IMPORTANT: Surety companies executing **BONDS** must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the State where the **PROJECT** is located.

PAYMENT BOND

KNOW ALL MEN BY THESE PRESENTS THAT:

(Name of Contractor)

(Address of Contractor)

a _____, hereinafter called
(Corporation, Partnership, Individual)

Principal, and _____
(Name of Surety)

(Address of Surety)

hereinafter called Surety, are held and firmly bound unto:

CITY OF THE DALLES

(Name of Owner)

313 Court Street, The Dalles, Oregon 97058

(Address of Owner)

hereinafter called **CITY**, in the penal sum of \$ _____ in lawful money of the United States, for the payment of which sum well and truly to be made, we bind ourselves, successors, and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF OBLIGATION is such that whereas, the Principal entered into a certain contract with the **CITY** dated the _____ day of _____, 2023, a copy of which is hereto attached and made a part hereof for

CONTRACT NO. 2023-003
2023 ADA IMPROVEMENT PROJECT

NOW, THEREFORE, if Principal shall promptly make payment to all persons, firms, **SUBCONTRACTORS**, and corporations furnishing materials for or performing labor in the prosecution of the **WORK** provided for in such contract, and any authorized extension or modification thereof, including all insurance premiums on said **WORK**, and for all labor, performed in such **WORK**, whether by **SUBCONTRACTOR** or otherwise, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the contract or to the **WORK** to be performed there under or the **SPECIFICATIONS** accompanying the same shall

in any way affect its obligation on this **BOND**, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the contract or to the **WORK** or to the **SPECIFICATIONS**.

PROVIDED FURTHER, that no final settlement between the **CITY** and the **CONTRACTOR** shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

IN WITNESS WHEREOF, this instrument is executed in three (3) counterparts, each one of which shall be deemed an original, this the _____ day of _____, 2023.

ATTEST:

Secretary
(Principal)

(SEAL)

Principal

BY _____

Witness as to Principal

(Address)

ATTEST:

Surety

BY _____

Attorney-in-Fact

Witness as to Surety

(Address)

(Address)

Phone: _____

NOTE: Date of **BOND** must not be prior to date of **CONTRACT**. If **CONTRACTOR** is a Partnership, all partners should execute **BOND**.

IMPORTANT: Surety companies executing **BONDS** must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the State where the **PROJECT** is located.

NOTICE TO PROCEED

To:

Date:

**PROJECT: CONTRACT NO. 2023-003
2023 ADA IMPROVEMENT PROJECT**

The City of The Dalles has executed the contract documents for the above mentioned project. You are hereby notified to commence **WORK** in accordance with the **CONTRACT** dated _____, on or before _____.

BEFORE ON-SITE WORK CAN COMMENCE, the following items below need to be completed (00180.40(b)):

- **Return an acknowledged copy of Notice to Proceed to City (00130.90)**
- **Contract Submittals – Submitted 5 days prior to a preconstruction meeting**
 - Project Work Schedule (00180.41)
 - Traffic Control Plan (00225.05)
 - Pollution Control Plan (00290.30)
 - Erosion and Sediment Control Plan (00280.04)
 - Trucking Service Agreement (if any) (00180.20(e)(1) and 00180(e)(3))
 - Curb Ramp Plan (00759.02)
- **Schedule and attend the Preconstruction Meeting with representatives of City of The Dalles Public Works.**

Only after the preconstruction meeting is held and project submittals are reviewed and approved, can On-site Work for the project begin.

**CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT**

BY **Todd Stephens**
TITLE **Project Engineer**

ACCEPTANCE OF NOTICE

Receipt of the above **NOTICE TO PROCEED** is hereby acknowledged by

_____, this ____ day of _____, 2023.
(Company Name)

BY _____ TITLE _____

CERTIFICATION OF WORKERS' COMPENSATION COVERAGE

The Contractor, for the purposes of this contract, hereby certifies that it is currently providing Oregon Workers' Compensation coverage for all its employees and will maintain coverage throughout the course of the project through one of the following methods:

1. ☐ "Carrier-Insured Employer" (State Accident Insurance Fund corp. or other authorized insurer)

Insurance Company Name _____

ID/Policy Number _____

2. ☐ "Self-Insured Employer" (Certified by the Workers' Compensation Division)

ID number as assigned by the
Workers' Compensation Division _____

3. ☐ I am an independent contractor and will perform all work under this contract without the assistance of others.

In the event of cancellation or change in the information above, Contractor certifies that it will immediately notify the Department of said cancellation or change and will obtain alternate coverage.

Dated _____ 2023

(Contractor's Signature)

REMINDER – ADDITIONAL INFORMATION NEEDED

Has your insurance carrier filed with Oregon Workers' Compensation Division a guaranty contract as proof of coverage for your employees working in Oregon?

For filing information, contact the Workers' Compensation Division at Labor and Industries Building: Salem, OR 97301; Phone (503) 947-7810



PART 3

PART 00100 OF 2022 CITY OF THE DALLES STANDARD SPECIFICATIONS FOR CONSTRUCTION - GENERAL CONDITIONS

2023 ADA IMPROVEMENT PROJECT
CONTRACT NO. 2023-003

PART 00100 - GENERAL CONDITIONS

Section 00110 - Organization, Conventions, Abbreviations, and Definitions

Organization

00110.00 Organization of Specifications - The Specifications comprise the following:

- The "2022 Oregon Standard Specifications for Construction", which contain Part 00100 "General Conditions", addressing the solicitation process and contractual relationships and Parts 00200 through 03000 containing the detailed "Technical Specifications" involved in prosecution of the Work, organized by subject matter; and
- The Special Provisions.

In addition, throughout the Specifications:

- Each Part is divided into Sections and Subsections.
- Reference to a Section includes all applicable requirements of the Section.
- When referring to a Subsection, only the number of the Subsection is used; the word "Subsection" is implied.
- Where Section and Subsection numbers are not consecutive, the interval has been reserved for use in the Special Provisions or future expansion of the Standard Specifications.

Conventions

00110.05 Conventions Used throughout the Specifications Include:

(a) Grammar - The "2022 Oregon Standard Specifications for Construction", Part 00100 "General Conditions", is written in the indicative mood, in which the subject is expressed. Parts 00200 through 03000, the detailed "Technical Specifications", are generally written in the imperative mood, in which the subject is implied. Therefore, throughout Parts 00200 through 03000, and on the Plans:

- The subject, "the Contractor", is implied.
- "Shall" refers to action required of the Contractor, and is implied.
- "Will" refers to decisions or actions of the Agency and/or the Engineer.
- The following words, or words of equivalent meaning, refer to the actions of the Agency and/or the Engineer, unless otherwise stated: "allowed", "directed", "established", "permitted", "ordered", "designated", "prescribed", "required", "determined".
- The words "approved", "acceptable", "authorized", "satisfactory", "suitable", "considered", and "rejected", "denied", "disapproved", or words of equivalent meaning, mean by or to the Agency and/or the Engineer, subject in each case to Section 00150 of the General Conditions.
- The words "as shown", "shown", "as indicated", or "indicated" mean "as indicated on the Plans".
- Certain Subsections labeled "Payment" contain statements to the effect that the accepted quantities "will be paid for at the Contract unit price, per unit of measurement, for the following items" (followed by a list of items). In such cases, the Agency will pay for only those Pay Items listed in the Schedule of Items.

(b) Capitalization of Terms - Capitalized terms, other than titles, abbreviations, and grammatical usage, indicate that they have been given a defined meaning in the Standard Specifications. Refer to Section 00110.20 "Definitions". Defined terms will always be capitalized in Part 00100; in Parts 00200 through 03000, defined terms will generally not be capitalized, with the notable exception of "the Contractor", "the Agency", and "the Engineer".

(c) Punctuation - In this publication the "outside method" of punctuation is employed for placement of the comma and the period with respect to quotation marks. Only punctuation that is part of the quoted matter is placed within quotation marks.

(d) References to Laws, Acts, Regulations, Rules, Ordinances, Statutes, Orders, and Permits - References are made in the text of the Specifications to "laws", "acts", "rules", "statutes", "regulations", "ordinances", etc. (collectively referred to for purposes of this Subsection as "Law"), and to "orders" and "permits" (issued by a governmental authority, whether local, state, or federal, and collectively referred to for purposes of this Subsection as "Permits"). Reference is also made to "applicable laws and regulations". The following conventions apply in interpreting these terms, as used in the Specifications.

- **Statutes and Rules** - Oregon Revised Statutes (ORS) and Oregon Administrative Rules (OAR) referenced in the Specifications are accessible on line, including through the Oregon Legislative Counsel Committee website (see 00110.05(e)) and through the Oregon Secretary of State Archives Division website (see 00110.05(e)).
- **Law** - In each case, unless otherwise expressly stated therein, the Law is to be understood to be the current version in effect. This also applies where a specific Law is referenced or cited, regardless of whether the text of the Law has been included in the Specifications or not, and regardless of whether the text of the Law has been summarized or paraphrased. In each case, the current version of the Law is applicable under any contract. The reader is therefore cautioned to check the actual text of the Law to confirm that the text included in the Specifications has not been modified or superseded.
- **Permits** - Orders and permits issued by a government agency may be modified during the course of performing the work under a contract. Therefore, wherever the term "order" or "permit" is used in the Specifications, it is intended to refer to the then-current version. That version may be embodied in a modified, superseding order or permit, or it may consist of all terms and conditions of prior orders or permits that have not been superseded, as well as the additional terms added by amendment or supplement. In certain cases, the orders and/or permits are identified by name in the Specifications; in other cases the terms are used in the generic sense. The reader is cautioned to check the text(s) of each order and permit identified either by name or by generic reference.
- **Applicable Laws and Regulations** - Where phrases such as "applicable law", "applicable laws and regulations", "applicable legal requirements" or similar phrases appear, they are to be understood as including all applicable laws, acts, regulations, administrative rules, ordinances, statutes, and orders and permits issued by a governmental or regulatory authority without limitation. The words "law" or "laws" may or may not be capitalized in such phrases.

(e) Reference to Websites - For Specifications that reference this Subsection, the Agency will identify the website addresses in the Special Provisions.

Abbreviations

00110.10 Abbreviations - Following are meanings of abbreviations used in the Standard Specifications, in the Special Provisions, on the Plans, and in other Contract Documents. Other

abbreviations and meanings of abbreviations may be used in the individual Sections of the Standard Specifications to which they apply, in the Special Provisions, and in OAR 731-005 and OAR 731-007.

AAR	- Association of American Railroads
AASHTO	- American Association of State Highway and Transportation Officials
ABC	- Associated Builders and Contractors, Inc.
AC	- Asphalt Concrete
ACI	- American Concrete Institute
ACP	- Asphalt Concrete Pavement
ACWS	- Asphalt Concrete Wearing Surface
ADA	- Americans with Disabilities Act
AGC	- Associated General Contractors of America
AIA	- American Institute of Architects
AISC	- American Institute of Steel Construction
AISI	- American Iron and Steel Institute
AITC	- American Institute of Timber Construction
ANSI	- American National Standards Institute
APA	- Engineered Wood Association
APWA	- American Public Works Association
AREMA	- American Railway Engineering and Maintenance of Right-of-Way Association
ASCE	- American Society of Civil Engineers
ASME	- American Society of Mechanical Engineers
ASTM	- American Society for Testing and Materials
ATPB	- Asphalt Treated Permeable Base
ASTV	- Actual Strength Test Value
AWG	- American Wire Gauge
AWPA	- American Wood Protection Association
AWS	- American Welding Society
AWWA	- American Water Works Association
CAGT	- Certified Aggregate Technician
CAT-I	- Certified Asphalt Technician I
CAT-II	- Certified Asphalt Technician II
CBM	- Certified Ballast Manufacturers
CCO	- Contract Change Order
CCT	- Concrete Control Technician
CDT	- Certified Density Technician
CEBT	- Certified Embankment and Base Technician
CFR	- Code of Federal Regulations
CMDT	- Certified Mixture Design Technician
CPF	- Composite Pay Factor
CRSI	- Concrete Reinforcing Steel Institute
CS	- Commercial Standard, Commodity Standards Division, U.S. Department of Commerce
CSTT	- Concrete Strength Testing Technician
D1.1	- Structural Welding Code - Steel, American Welding Society, current edition
D1.5	- Bridge Welding Code, American Welding Society, current edition
DBE	- Disadvantaged Business Enterprise
DEQ	- Department of Environmental Quality, State of Oregon
DOGAMI	- Department of Geology and Mineral Industries, State of Oregon
DSL	- Department of State Lands, State of Oregon
EAC	- Emulsified Asphalt Concrete

EPA	- U.S. Environmental Protection Agency
ESCP	- Erosion and Sediment Control Plan
FHWA	- Federal Highway Administration, U.S. Department of Transportation
FSS	- Federal Specifications and Standards, General Services Administration
GSA	- General Services Administration
ICEA	- Insulated Cable Engineers Association (formerly IPCEA)
IES	- Illuminating Engineering Society
IMSA	- International Municipal Signal Association
ISO	- International Standards Organization
ISSA	- International Slurry Surfacing Association
ITE	- Institute of Transportation Engineers
JMF	- Job Mix Formula
MFTP	- Manual of Field Test Procedures (ODOT)
MIL	- Military Specifications
MSC	- Minor Structure Concrete
MUTCD	- Manual on Uniform Traffic Control Devices for Streets and Highways, FHWA, U.S. Department of Transportation
NEC	- National Electrical Code
NEMA	- National Electrical Manufacturer's Association
NESC	- National Electrical Safety Code
NIST	- National Institute of Standards and Technology
NPDES	- National Pollutant Discharge Elimination System
NPS	- Nominal Pipe Size (dimensionless)
OAR	- Oregon Administrative Rules
ODA	- Oregon Department of Agriculture
ODOT	- Oregon Department of Transportation
ORS	- Oregon Revised Statutes
OR-OSHA	- Oregon Occupational Safety and Health Division of the Department of Consumer and Business Services
OSHA	- Occupational Safety and Health Administration, U.S. Department of Labor
PCA	- Portland Cement Association
PCC	- Portland Cement Concrete
PCI	- Precast/Prestressed Concrete Institute
PCP	- Pollution Control Plan
PF	- Pay Factor of a constituent
PLS	- Professional Land Surveyor
PMBB	- Plant Mixed Bituminous Base
PTI	- Post-Tensioning Institute
PUC	- Public Utility Commission, State of Oregon
QA	- Quality Assurance
QC	- Quality Control
QCT	- Quality Control Technician
QL	- Quality Level
QPL	- Qualified Products List
RAP	- Reclaimed Asphalt Pavement
REA	- Rural Electrification Administration, U.S. Department of Agriculture
RMA	- Radio Manufacturers Association or Rubber Manufacturers Association
SAE	- Society of Automotive Engineers
SI	- International System of Units (Système Internationale)
SRCM	- Soil and Rock Classification Manual (ODOT)
SSPC	- Society for Protective Coatings

T	- Tolerances, AASHTO Test Method
TM	- Test Method (ODOT)
TV	- Target Value
UBC	- Uniform Building Code (as adopted by the State of Oregon)
UL	- Underwriters Laboratory, Inc.
UPC	- Uniform Plumbing Code (as adopted by the State of Oregon)
USC	- United States Code
WAQTC	- Western Alliance for Quality Transportation Construction
WCLIB	- West Coast Lumber Inspection Bureau
WWPA	- Western Wood Products Association

Definitions

00110.20 Definitions – The following are definitions of words and phrases used in the Standard Specifications, in the Special Provisions, on the Plans, and in other Contract Documents. Other definitions may be in the individual Sections of the Standard Specifications to which they apply, in the Special Provisions, and in OAR 731-005 and OAR 731-007.

3D Engineered Model - The Agency-prepared electronic file(s) that identify northing, easting, and elevation to represent the Work to be performed. The 3D Engineered Model may include the surface model(s) or other designed Work elements and is an electronic representation of the line, grade, and Cross Section applicable to the Project.

3D Construction Model - Supplemental unstamped 3D model, not furnished by the Agency, that the Contractor is required to submit to the Engineer.

Act of God or Nature - A natural phenomenon of such catastrophic proportions or intensity as would reasonably prevent performance.

Actual Strength Test Value (ASTV) - The ASTV at 28 Days is the average compressive strength of the three cylinders tested. All specimens that show definite evidence, other than low strength, of improper sampling, molding, handling, curing, or testing shall be discarded. The average strength of the remaining cylinders shall then be considered the test result.

Addendum - A written or graphic modification, issued before the opening of Bids, which revises, adds to, or deletes information in the Solicitation Documents or previously issued Addenda.

Additional Work - Increased quantities of any Pay Item, within the scope of the Contract, for which a unit price has been established.

Advertisement - The public announcement (Notice to Contractors) inviting Bids for Work to be performed or Materials to be furnished.

Agency - The City of The Dalles, which has entered into a Contract with the Contractor.

Agency-Controlled Lands - Lands owned by the Agency, or controlled by the Agency under lease or agreement, or under the jurisdiction and control of the Agency for the purposes of the Contract.

Aggregate - Rock of specified quality and gradation.

Attorney-in-Fact - An Entity appointed by another to act in its place, either for some particular purpose, or for the transaction of business in general.

Award - Written notification to the Bidder that the Bidder has been awarded a Contract.

Base - A Course of specified material of specified thickness placed below the Pavement.

Bid - A competitive offer, binding on the Bidder and submitted in response to an invitation to bid.

Bid Bond - The Surety bond for Bid guaranty

Bid Booklet - The version that can be accessed and printed from the Agency website, which contains the information identified in 00120..

Bid Closing - The date and time after which Bids, Bid modifications, and Bid withdrawals will no longer be accepted.

Bid Documents - See under Solicitation Document.

Bid Opening - The date and time Bids are opened.

Bid Schedule - The list of Pay Items, their units of measurement, and estimated quantities. (When a Contract is awarded, the Bid Schedule becomes the Schedule of Items.)

Bid Section - The portion of the Bid Booklet containing all pages after the Bidder's checklist and before the appendix.

Bidder - An Entity that submits a Bid in response to an invitation to bid.

Bike Lane - A lane in the Traveled Way, designated by striping and Pavement markings for the preferential or exclusive use of bicyclists.

Borrow - Material lying outside of planned or required Roadbed excavation used to complete Project earthwork.

Boulders - Particles of Rock that will not pass a 12-inch square opening.

Bridge - A single or multiple span Structure, including supports, that carries motorized and non-motorized vehicles, pedestrians, or utilities on a Roadway, walk, or track over a watercourse, Highway, Railroad, or other feature.

Buttress - A Rock fill placed at the toe of a landslide or potential landslide in order to resist slide movement.

Calendar Day - Any Day shown on the calendar, beginning and ending at midnight.

Camber - A slight arch in a surface or Structure to compensate for loading.

Change Order - A written order issued by the Engineer to the Contractor modifying Work required by the Contract, or adding Work within the scope of the Contract, and, if applicable, establishing the basis of payment for the modified Work, or otherwise modifying the Contract.

Changed Work - Work included in a Pay Item and within the scope of the Contract that is different from that reflected in the Contract Documents. (See 00140.30.)

Class of Project - A designation based on a Project's funding source, (i.e., State or Federal-aid).

Class of Work - A designation referring to the type of Work in which Bidders must be prequalified. Classes of Work are limited to those listed in ODOT's Contractor's Prequalification Application.

Clay - Soil passing a No. 200 sieve that can be made to exhibit plasticity (putty-like properties) within a range of water contents.

Clear Zone - The total roadside border area, starting at the edge of the Traveled Way, available for safe use by errant vehicles. This area may consist of a shoulder, a recoverable slope, a non-recoverable slope, and/or a clear run-out area. The desired width is dependent upon the traffic volumes and speeds and on the roadside geometry.

Close Conformance - Where working tolerances are given on the Plans or in the Specifications, Close Conformance means compliance with those tolerances. Where working tolerances are not given, Close Conformance means compliance, in the Engineer's judgment, with reasonable and customary manufacturing and construction tolerances.

Coarse Aggregate - Crushed Rock or crushed Gravel retained on a 1/4-inch sieve, with allowable undersize.

Cobbles - Particles of Rock, rounded or not, that will pass a 12-inch square opening and be retained on a 3-inch sieve.

Commercial Grade Concrete - Concrete furnished according to Contractor proportioning, placed in minor Structures and finished as specified.

Contract - The written agreement between the Agency and the Contractor, including, without limitation, all Contract Documents, describing the Work to be completed and defining the rights and obligations of the Agency and the Contractor.

Contract Administration Engineer - The Agency representative presiding over Agency-level claims review under 00199.40.

Contract Amount - Sum of the Pay Item amounts computed by multiplying the Pay Item quantities by the unit prices in the Schedule of Items.

Contract Documents - Solicitation Documents, Specifications, Plans, Contract booklet, Change Orders, Force Account Work orders, pay documents issued by the Agency, Materials certifications, Project Work schedules, final estimate, written orders and authorizations issued by the Agency, Material source development and reclamation plans, and permits, orders and authorizations obtained by the Contractor or Agency applicable to the Project, as well as all documents incorporated by reference therein.

Contract Time - The amount of time allowed to complete the Work under the Contract.

Contractor - The Entity awarded the Contract according to the solicitation.

Course - A specified Surfacing Material placed in one or more Lifts to a specified thickness.

Coverage - One Pass by a piece of Equipment over an entire designated area.

Cross Section - The exact image formed by a plane cutting through an object, usually at right angles to a central axis, to determine area.

Day - A Calendar Day including weekdays, weekends, and holidays, unless otherwise specified.

Durable Rock - Rock that has a slake durability index of at least 90% based on a two-cycle slake durability test, according to ASTM D4644. In the absence of test results, the Engineer may evaluate the durability visually.

Emulsified Asphalt - Emulsified asphalt cement.

Emulsified Asphalt Concrete - A mixture of Emulsified Asphalt and graded Aggregate.

Engineer - The City Engineer acting either directly or through authorized representatives.

Entity - A natural person capable of being legally bound, sole proprietorship, limited liability company, corporation, partnership, limited liability partnership, limited partnership, for-profit or nonprofit unincorporated association, business trust, two or more persons having a joint or common economic interest, or any other person with legal capacity to contract, or a government or governmental subdivision.

Equipment - All machinery, tools, manufactured products, and fabricated items needed to complete the Contract or specified for incorporation into the Work.

Establishment Period - The time specified to assure satisfactory establishment and growth of planted Materials.

Existing Surfacing - Pavements, slabs, curbs, gutters, walks, driveways, and similar constructions of bricks, blocks, portland cement concrete, bituminous treated materials, and granular Surfacing materials on existing Highways.

Extra Work - Work not included in the Contract, but deemed by the Engineer to be necessary to complete the Project.

Final Acceptance - Written confirmation by the Agency that the Project has been completed according to the Contract, with the exception of latent defects and Warranty obligations, if any, and has been accepted.

Final Inspection - The inspection conducted by the Engineer to determine that the Project has been completed according to the Contract.

Fine Aggregate - Crushed Rock, crushed Gravel, or Sand that passes a 1/4-inch sieve, with allowable oversize.

First Notification - Written acknowledgment by the Engineer of the date on which workers employed by the Contractor or a Subcontractor have begun performance of the Contract, including Aggregate source development or erection of a plant, but not including installation of covered temporary signs according to Section 00222.

Force Account Work - Items of Extra Work ordered by the Engineer that are to be paid according to Section 00197.

Granular Material - Graded and selected free-draining material composed of particles of Rock, Sand, and Gravel.

Gravel - Particles of Rock, rounded or not, that will pass a 3-inch sieve and be retained on a No. 4 sieve.

Highway - Every road, street, thoroughfare and place, including Bridges, viaducts and other Structures within the boundaries of the State, open, used or intended for use by vehicular traffic.

Incidental - A term identifying those acts, services, transactions, property, Equipment, labor, Materials, or other items for which the Agency will make no separate or additional payment.

Inspector - The representative of the Engineer authorized to inspect and report on Contract performance.

Leveling - Placing a variable-thickness Course of Materials to restore horizontal and vertical uniformity to existing Pavements, normally continuous throughout the Project.

Lift - The compacted thickness of material placed by Equipment in a single Pass.

Mandatory Source - A material source provided by the Agency from which the Contractor is required to obtain Materials. (See 00160.00(b) and 00160.40.)

Materials - Any natural or manmade substance specified for use in the construction of the Project or for incorporation into the Work.

Median - The portion of a divided Highway separating traffic traveling in opposite directions.

Multiple Course Construction - Two or more Courses, exclusive of Patching or Leveling, placed over the entire Roadway width.

Multi-Use Path - That portion of the Highway Right-of-Way or a separate Right-of-Way, physically separated from motor vehicle traffic and designated for use by pedestrians, bicyclists and other non-motorized users.

Neat Line - Theoretical lines specified or indicated on the Plans for measurement of quantities.

Nondurable Rock - Rock that has a slake durability index of less than 90% based on a two-cycle slake durability test, as tested by ASTM D4644, or Rock that is observed to readily degrade by air, water, and mechanical influence.

Notice to Contractors - The public announcement inviting Bids for Work to be performed or Materials to be provided.

Notice to Proceed - Written notice authorizing the Contractor to begin performance of the Work.

On-Site Work - Any Work taking place on the Project Site, including designated staging areas adjacent to the Project Site, except for installation of covered temporary signs according to Section 00222.

Organic Soil - A Soil with sufficient organic content to influence the Soil properties.

Panel - The width of specified Material being placed by Equipment in a single Pass.

Pass - One movement of a piece of Equipment over a particular location.

Patching - Placing a variable-thickness Course of Materials to correct sags, dips, and/or bumps to the existing grade and Cross Section, normally intermittent throughout the Project.

Pavement - Asphalt concrete or portland cement concrete placed for the use of motor vehicles, bicycles, or pedestrians on Roadways, Shoulders, Multi-Use Paths and parking areas.

Pay Item (Contract Item) - A specific unit of Work for which a price is provided in the Contract.

Payment Bond - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of its obligation to pay promptly in full all sums due for Materials, Equipment, and labor furnished to complete the Work.

Peat - A Soil composed primarily of vegetative matter in various stages of decomposition, usually with an organic odor, dark brown to black color, and a spongy consistency.

Performance Bond - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of the Contract.

Plans - Standard and Supplemental Drawings, and approved unstamped and reviewed stamped Working Drawings. (See 00150.10 and 00150.35.)

Project - The sum of all Work to be performed under the Contract.

Project Manager - The Engineer's representative who directly supervises the engineering and administration of a Contract.

Project Site - The geographical dimensions of the real property on which the Work is to be performed, including designated contiguous staging areas.

Prospective Source - A Material source provided by the Agency, from which the Contractor has the option of obtaining Materials. (See 00160.00(a) and 00160.40.)

Publicly-Owned Equipment - Equipment acquired by a state, county, municipality or political subdivision primarily for use in its own operations.

Public Traffic - Vehicular or pedestrian movement, not associated with the Contract Work, on a public way.

Railroad - Publicly or privately owned rail carriers, including passenger, freight, and commuter rail carriers, their tenants, and licensees. Also, Utilities that jointly own or use such facilities.

Right-of-Way - Land, property, or property interest, usually in a strip, acquired for or devoted to transportation or other public works purposes.

Roadbed - Completed excavations and embankments for the Subgrade, including ditches, side slopes, and slope rounding, if any.

Roadside - The area between the outside edges of the Shoulders and the Right-of-Way boundaries. Unpaved Median areas between inside Shoulders of divided Highways and infield areas of interchanges are included.

Roadway - That portion of a Highway improved, designed, or ordinarily used for vehicular travel, exclusive of the berm or Shoulder. If a Highway includes two or more separate Roadways, the term "Roadway" refers to any such Roadway separately, but not to all such Roadways collectively. (See Traveled Way.)

Rock - Natural deposit of solid material composed of one or more minerals occurring in large masses or fragments.

Sand - Particles of Rock that will pass a No. 4 sieve and be retained on a No. 200 sieve.

Schedule of Items - The list of Pay Items, their units of measurement, estimated quantities, and prices.

Schedule of Values - The breakdown of the values of the component elements comprising a lump sum Pay Item.

Second Notification - Written acknowledgment by the Engineer of the end of Contract Time according to 00180.50(g).

Shoulder - The part of a Roadbed contiguous to the Traveled Way or Roadway, whether paved or unpaved, for accommodating stopped vehicles, for emergency use and for lateral support of Base and surface Courses.

Silt - Soil passing a No. 200 sieve that is nonplastic or exhibits very low plasticity.

Single Course Construction - A wearing Course only, not including patching or Leveling Courses or partial width Base Course.

Slope - Vertical distance to horizontal distance, unless otherwise specified.

Soil - Accumulations of particles produced by the disintegration of Rock, which sometimes contains organic matter. Particles may vary in size from Clay to Boulders.

Solicitation Document - Documents which define the procurement of a public improvement Project, including, but not limited to, the Bid Booklet, Agency-provided Plans, Standard Specifications, Special Provisions, Addenda, and which includes all documents incorporated by reference. May also be called Bid Documents.

Special Provisions - The special directions, provisions, and requirements specific to a Project that supplement or modify the Standard Specifications. Permits and orders governing the Project that are issued directly to the Agency by a governmental or regulatory authority are considered to be part of the Special Provisions, to the extent and under the conditions stipulated in the Special Provisions. This includes any amended or supplemental permits or orders issued during the course of performing the Work under a Contract.

Special Services - Work services that the Contractor and Engineer agree cannot be satisfactorily performed by the Contractor's and Subcontractors' forces, (e.g., fabrication and machining work that is most effectively performed away from the Project Site, or rental of operated Equipment as defined in 00180.20(c)).

Specifications - The Standard Specifications and Special Provisions, together with all provisions of other documents incorporated therein by reference.

Standard Drawings - The Agency-prepared detailed drawings for Work or methods of construction that normally do not change from project to project.

Standard Specifications - "City of The Dalles Standard Specifications for Construction", current edition.

State - The State of Oregon.

Structures - Bridges, retaining walls, endwalls, cribbing, buildings, culverts, manholes, catch basins, drop inlets, sewers, service pipes, underdrains, foundation drains, and other similar features which may be encountered in the Work.

Subbase - A Course of specified material of specified thickness between the Subgrade and a Base.

Subcontractor - An Entity having a direct contract with the Contractor or another Subcontractor, at any tier, to perform a portion of the Work.

Subgrade - The top surface of completed earthwork on which Subbase, Base, Surfacing, Pavement, or a Course of other Material is to be placed.

Substructure - Those parts of a Structure which support the Superstructure, including bents, piers, abutments, and integrally built wing walls, up to the surfaces on which bearing devices rest. Substructure also includes portions above bearing surfaces when those portions are built integrally with a Substructure unit (e.g., backwalls of abutments). When Substructure and Superstructure elements are built integrally, the division between Substructure and Superstructure is considered to be at the bottom soffit of the longitudinal or transverse beam, whichever is lower. Culverts and rigid frames are considered to be entirely Substructure.

Superstructure - Those parts of a Structure above the Substructure, including bearing devices.

Supplemental Drawings - The Agency-prepared detailed drawings for Work or methods of construction that are Project specific, and are denoted by title in the Project title block.

Supplier - The Entity that furnishes goods to be incorporated into the Work.

Surety - The Entity that issues the bond.

Surfacing - The Course or Courses of Material on the Traveled Way, auxiliary lanes, Shoulder, or parking areas for pedestrian, bicycle or vehicle use.

Third Notification - Written acknowledgment by the Engineer, subject to Final Acceptance, that as of the date of the notification the Contractor has completed the Project according to the Contract, including, without limitation, completion of all minor corrective work, Equipment and plant removal, site clean-up, and submittal of all certifications, bills, forms and documents required under the Contract.

Ton - One short ton of 2,000 pounds (Ton, ton, Tn, or T).

Topsoil - Soil ready for use in a planting bed.

Traffic Lane - That part of the Traveled Way marked for moving a single line of vehicles.

Traveled Way - That part of the Highway for moving vehicles, exclusive of berms and Shoulders.

Typical Section - That Cross Section established by the Plans or the 3D Engineered Model which represents in general the lines to which the Contractor shall work in the performance of the Contract.

Unsuitable Material - Frozen material, or material that contains organic matter, muck, humus, Peat, sticks, debris, chemicals, toxic matter, or other deleterious materials not normally suitable for use in earthwork.

Utility - A line, facility, or system for producing, transmitting, or distributing communications, power, electricity, heat, gas, oil, water, steam, waste, stormwater not connected with highway drainage, or

any other similar commodity which directly or indirectly serves the public. The term may also mean the utility company, district, or cooperative owning and operating such facilities, including any wholly-owned or controlled subsidiary.

Warranty Bond - The approved security furnished by the Contractor's, Subcontractor's, or Supplier's Surety as a guaranty of the Contractor's performance of its warranty obligations.

Wetlands - Areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, vegetation typically adapted for life in saturated Soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas.

Work - The furnishing of all Materials, Equipment, labor, and Incidentals necessary to successfully complete any individual Pay Item or the entire Contract, and the discharge of duties and obligations imposed by the Contract.

Working Drawings - Supplemental Plans, not furnished by the Agency, that the Contractor is required to submit to the Engineer. (See 00150.35.)

Section 00120 - Bidding Requirements and Procedures

00120.00 Prequalification of Bidders -

- (1) **Prequalification.** Pursuant to ORS 279C.430 and Local Contract Review Board Rule 04-0220, two types of prequalification are authorized:
 - a. **Mandatory Prequalification.** The Agency may, by rule, resolution, ordinance or other law or regulation, require mandatory prequalification of Offerors on forms prescribed by the Agency's Contract Review Authority. The Agency must indicate in the Solicitation Document if it will require mandatory prequalification. Mandatory prequalification is when the Agency conditions an Entity's submission of an Offer upon the Entity's prequalification. The Agency shall not consider an offer from an Entity that is not prequalified if the Agency required prequalification.
 - b. **Permissive Prequalification.** The Agency may prequalify an Entity of the Agency's Solicitation list on forms prescribed by the Agency's Contract Review Authority, but in permissive prequalification the Agency shall not limit distribution of a Solicitation to that list. The Agency's determination of prequalification shall be valid for a period of three years.
- (2) **Prequalification Presumed.** If an Entity is currently prequalified by either the Oregon Department of Transportation or the Oregon Department of Administrative Services to perform Contracts, the Entity shall be rebuttably presumed qualified to perform similar Work for the Agency.
- (3) **Standards for Prequalification.** An Entity may prequalify by demonstrating to the Agency's satisfaction:
 - a. That the Entity's financial, material, equipment, facility and personnel resources and expertise, or ability to obtain such resources and expertise, indicate that the Entity is capable of meeting all contractual responsibilities;
 - b. The Entity's record of performance;
 - c. The Entity's record of integrity;
 - d. The Entity is qualified to contract with the Agency (See Local Contract Review Board Rule 04-0370(2) regarding standards of responsibility.)
- (4) **Notice of Denial.** If an Entity fails to prequalify for a mandatory prequalification, the Agency shall notify the Entity, specify the reasons under Section (3) of Local Contract Review Board Rule 04-0220 and inform the Entity of the Entity's right to a hearing under ORS 279C.445 and 279C.450."

00120.01 General Bidding Requirements - Bidders may obtain and submit Bids by paper.

The standard prequalification forms furnished by the Agency shall be used by the Bidder to file authorized signatures with the Agency. Signatures are of personnel authorized to submit Bids, modify Bids, or withdraw Bids. As and when applicable, the Contractor shall maintain the certifications required by ORS 279A.107.

00120.05 Request for Plans, Special Provisions, and Bid Booklets:

Bidders must obtain Solicitation Documents from the **City of The Dalles City Clerk, City Hall, 313 Court Street, The Dalles, OR 97058; phone (541) 296-5481 ext. 1120**. Each request must include both the name of the person ordering or obtaining the Solicitation Documents, and the name of the Entity intending to use them. (The Agency will add the name of the Entity intending to use the Solicitation Documents to the list of Holders of Bidding Plans.)

Copies of the current City of The Dalles Standard Specifications for Construction and Standard Drawings may be downloaded from www.ci.the-dalles.or.us/engineering.

00120.10 Bid Booklet - The Bid Booklet may include, but is not limited to:

- Bidder's checklist
- Bid Section
- Appendix, which includes required time-sensitive forms, DBE information, sample forms, and other informational pages

The Bid Section includes all pages after the Bidder's checklist and before the appendix. The Bid Section may include, but is not limited to:

- Invitation to Bidders
- Advertisement for Bids
- Prequalification Form
- Conflict of Interest Disclosure Form
- Proposal (Bid Schedule)
- Bid Bond
- First-tier Subcontractor Disclosure Form
- Non-Collusion Affidavit
- Responsibility Determination Form
- Notice of Award
- Prevailing Wage Rates Cover Sheet
- Part 00100 of the General Conditions of the City of The Dalles Standard Specifications for Construction

- Special Provisions

00120.15 Examination of Work Site and Solicitation Documents; Consideration of Conditions to be Encountered - Before submitting a Bid, Bidders shall carefully examine the site of the proposed Work, the Bid Booklet, Plans, and Specifications. Bidders shall also contact Utility owners to verify all Utilities' anticipated involvement on the Project Site. Bidders are also encouraged to review any subsurface investigation material referenced in 00120.25 that may be available. Submission of a Bid will constitute confirmation that the Bidder has examined the Project Site and Solicitation Documents, finds the Plans and Specifications to be sufficiently detailed and accurate to enable Bidder to properly perform the Work, and understands the conditions to be encountered in performing the Work and all requirements of the Contract.

The Bidder is responsible for loss or unanticipated costs suffered by the Bidder because of the Bidder's failure to fully examine the site and become fully informed about all conditions of the Work, or failure to request clarification of Plans and Specifications Bidder believes to be erroneous or incomplete.

Any clarification of Plans and Specifications needed by the Bidder shall be requested in writing through the Engineer. Requests shall be made in sufficient time for the Agency's reply to reach all Bidders before Bid Closing. Oral explanations or interpretations given before receiving Bids for a Project will not be binding. To be binding, interpretation of the Plans and Specifications by the Agency must be made by written Addendum furnished to all Holders of Bidding Plans according to 00120.30. Notification of erroneous or incomplete Plans or Specifications shall also be submitted to the Engineer. Such notification shall also be made in sufficient time for the Agency to make any necessary modifications and issue Addenda to Bidders prior to Bid Closing.

00120.16 Material, Equipment, and Method Substitutions - When the Contract specifies certain Materials, Equipment, products, and/or methods, the Bidder shall include those Materials, Equipment, products, and/or methods in the Bid unless the Engineer has issued an Addendum granting approval to substitute. Unless the Engineer has approved substitutions of Materials, Equipment, products, and/or methods prior to opening of Bids, the Bidder shall furnish the items specified in the Contract. Substitution after Award is specified in 00180.31(b), 00180.31(c), and 00180.31(d). The procedure for requesting approval is as follows:

- (a) **Written Request** - Unless specified as the subject of an exemption per ORS 279C.345, if a Bidder proposes to use Materials, Equipment, products, and/or methods other than those specified, the Bidder shall send a written request to the Engineer, at least seven (7) Calendar Days prior to Bid Opening, including complete descriptive and technical information on the proposed Materials, Equipment, products, and/or methods.

(b) Functional Similarity - Materials, products, and Equipment proposed for substitution shall be similar in design, and equal or better in quality and function to those specified.

(c) Manufacturer's Information - If manufacturers' brochures or information is needed, the Bidder shall submit three copies of each with all pertinent information clearly marked.

(d) Differences - The Bidder shall specifically note all differences between the specified Materials, Equipment, products, and/or methods and the proposed substitutes.

(e) Cost - Where a substitute will result in alteration of the design or space requirements, or any other modifications to the Plans, the Bidder shall include in the substitution request all items of cost for the revised design and construction.

(f) Notification of Holders of Bidding Plans - If the Engineer approves any proposed substitution, such approval, and any modifications necessitated to the design and construction by the substitution, will be acknowledged by Addenda.

00120.17 Use of Agency-Owned Land for Staging or Storage Areas - The Contractor may use Agency-owned property for staging or storage areas, subject to the following limitations:

(a) Within Normal Right-of-Way Limits - If approved by the Engineer, the Contractor may use available property within the normal Right-of-Way limits for the purpose of constructing improvements under the Contract. Where the Agency owns, or has rights to, other adjacent properties in the Project area, "normal Right-of-Way" is limited to a line drawn across that property connecting the normal Right-of-Way limits on either side of the property.

(b) Outside Normal Right-of-Way Limits - The Contractor may not use Agency-owned property outside of normal Right-of-Way limits for the Project without the approval of the Engineer.

If a Bidder obtains approval before submitting a Bid, use of the property will be at no cost to the Contractor, or at a cost stated by the Engineer upon granting approval, as confirmed by Addendum.

If approval is not obtained before submitting a Bid, and the Contractor proposes to use Agency-owned property outside the normal Right-of-Way limits, then use of the property may be approved by the Engineer, but the Contractor will be assessed fair market value, as determined by the Engineer, for use of the property.

(c) Restrictions on Use - Contractors shall comply with all applicable laws, ordinances, and regulations pertaining to use of Agency-owned property, and shall:

- Not cause unreasonable impacts on traffic and other facility users.
- Clean up all hazardous materials deposited by, or resulting from, Contractor operations.
- Be responsible for all costs associated with use of the property.

00120.20 Interpretation of Quantities in Bid Schedule - Quantities appearing in the Bid Schedule are approximate and are provided only for comparison of Bids. The Agency does not warrant that the actual individual items, amount of Work, or quantities will correspond to those shown in the Bid Schedule. Payment to the Contractor will be made only for actual quantities of Work performed and accepted or Materials furnished and accepted, as required by the Contract. Quantities of Work to be performed and Materials to be furnished may each be increased, decreased, or omitted as provided in 00120.30 and 00140.30.

00120.25 Subsurface Investigations - If the Agency or its consultant has conducted subsurface or geologic investigations of the proposed Project Site, the results of the investigations may be included

in written reports. If reports have been prepared, copies will be available at the Engineer's office. If the Agency has retained subsurface samples, they will also be available for inspection. Bidders and the Contractor may make arrangements for viewing the samples through the Engineer's office.

The availability of subsurface information from the Agency is solely for the convenience of the Bidder and shall not relieve the Bidder or the Contractor of any risk, duty to make examinations and investigations as required by 00120.15, or other responsibility under the Contract Documents. It is mutually agreed to by all parties that:

- The written report(s) are reference documents and not part of the Contract Documents.
- The subsurface investigations made by the Agency are for the purpose of obtaining data for planning and design of the Project.
- The data for individual test boring logs apply only to that particular boring and is not intended to be conclusive as to the character of any material between or around test borings.
- If Bidders use this information in preparing a Bid, it is used at their own risk, and Bidders are responsible for all conclusions, deductions, and inferences drawn from this information.

00120.30 Changes to Plans, Specifications, or Quantities before Opening of Bids - The Agency reserves the right to issue Addenda making changes or corrections to the Plans, Specifications, or quantities. Only holders of the Solicitation Documents obtained from the Agency who have been identified by the Agency as Holders of Bidding Plans, as required by 00120.05, will be notified of these Addenda by mail or delivery service. The Agency will not be responsible for failure of Bidders to receive Addenda sent as described in the preceding paragraph. Bids may be rejected if opened and found by Agency not to be based on Addenda issued before Bids were opened.

00120.40 Preparation of Bids - Bids not in compliance with the requirements of this Subsection will be considered non-responsive.

(a) General:

Bids - Bidders shall not alter, in any manner, the paper documents within the Bid. Bidders shall complete the certifications and statements included in the Bid Section of the Bid Booklet according to the instructions. Signature of the Bidder's authorized representative thereon constitutes the Bidder's confirmation of and agreement to all certifications and statements contained in the Bid Booklet. Entries on paper documents in the Bid Section shall be in ink or typed. Signatures and initials shall be in ink.

The Bidder shall properly complete and bind all the paper documents in the Bid Section, as specified in 00120.10, together with all other required documents that are part of the Bid Booklet, between the front and back covers of the Bid Booklet, except that the Bid Bond is not required if another permissible type of Bid guaranty is provided. (See 00120.40(e).)

(b) Bidding Considerations - Bidders may refer to the following Subsections for requirements that may affect bidding considerations:

Subsection	Requirements
00120.80	Reciprocal Preference for Oregon Resident Bidders
00130.80	Project Site Restrictions
00150.55	Cooperation with Other Contractors
00150.75	Protection and Maintenance of Work during Construction
00160.20(a)	Buy America
00160.20(b)	Buy Oregon
00170.07	Record Requirements
00180.20	Subcontracting Limitations
00180.21	Subcontracting
00195.00(a)	Cost of Insurance and Bonds
00195.50(a)(1)	Progress Estimates
00199.30	Claims Procedure

(c) Bid Schedule Entries: Using figures, Bidders shall fill in all blank spaces in the paper Bid Schedule. For each item in the paper Bid Schedule, Bidders shall enter the unit price and the product of the unit price multiplied by the quantity given. The unit price shall be greater than zero, shall contain no more than two decimal places to the right of the decimal point, and shall be expressed in U.S. dollars and cents (for example, \$150.25 or \$0.37). Bidders shall also enter the total amount of the Bid obtained by adding amounts for all items in the paper Bid Schedule. Corrections or changes of item entries shall be in ink, with incorrect entry lined out and correct entry entered and initialed.

(d) Bidder's Address and Signature Pages - Bidders shall include in the Bid the address to which all communications concerning the Bid and Contract should be sent. The Bid must be signed by a duly authorized representative of the Bidder

(e) Bid Guaranty - All Bids shall be accompanied by a Bid guaranty in the amount of 10% of the total amount of the Bid. Acceptable Surety companies are limited to those authorized to do business in the State of Oregon. Forfeiture of Bid guaranties is covered by 00130.60, and return of guaranties is covered by 00130.70.

The Bid guaranty shall be either a Surety bond, irrevocable letter of credit issued by an insured institution as defined in ORS 706.008, or security in the form of a cashier's check or certified check made payable to the Agency. (See ORS 279C.365(4).)

If a Surety bond is submitted, Bidders shall use the Agency's standard Bid Bond form included with the paper Bid Booklet. Bidders shall submit the bond with original signatures and the Surety's seal affixed. The Bid guaranty shall be submitted by mail, delivery service, or hand delivered to the offices and addresses, and at the times given in the Bid Booklet

(f) Disclosure of First-Tier Subcontractors - Without regard to the amount of a Bidder's Bid, if the Agency's cost range for a public improvement Project in the "Notice to Contractors", or in other advertisements or Solicitation Documents, exceeds \$100,000, the Bidder shall, within two (2) working hours of the time Bids are due to be submitted, submit to the Agency, on a form provided by the Agency, a disclosure identifying any first-tier Subcontractors that will furnish labor or labor and Materials, and whose subcontract value would be equal to or greater than:

- Five percent (5%) of the total Project Bid, but at least \$15,000; or
- \$350,000, regardless of the percentage of the total Project Bid.

For each Subcontractor listed, Bidders shall state:

- The name of the anticipated Subcontractor;
- The dollar amount of the anticipated subcontract; and
- The category of Work that the Subcontractor is anticipated to perform.

If no subcontracts subject to the above disclosure requirements are anticipated, a Bidder shall so indicate by entering "NONE" or by filling in the appropriate check box. For each Subcontractor listed, Bidders shall provide all requested information. Failure to submit a form or submission of a form that does not include the information required by ORS 279C.370 for each Subcontractor listed, specifically the name of each anticipated Subcontractor, the dollar amount of each anticipated subcontract and the category of Work each Subcontractor is anticipated to perform, will result in the rejection of the Bid. The Agency is not required to determine the accuracy or the completeness of the Subcontractor disclosure. See ORS 279C.370 and OAR 731-007-0260.

The Subcontractor Disclosure Form may be submitted for a paper Bid (see 00120.05(b)(1)) by filling out the Subcontractor Disclosure Form from the Bid Booklet included in the Bid Booklet and submitting it together with the Bid at the time and place designated for receipt of Bids;

Subcontractor Disclosure Forms submitted by any method will be considered late if not received by the Agency within two (2) working hours of the time designated for receiving Bids.

The Agency is not responsible for partial, failed, illegible or partially legible email transmissions or submittals, and such forms may be rejected as incomplete.

In the event that multiple Subcontractor Disclosure Forms are submitted, the last version received prior to the deadline will be considered to be the intended version.

(g) Disclosure of Conflict of Interest - Bidders shall review the Agency's Conflict of Interest Guidelines, and if any disclosures are required (with the exception of any required disclosures for Subcontractors, which are addressed under 00180.21), Bidders shall complete the Conflict of Interest Disclosure Form(s) and submit, before the time Bids are due to be submitted, according to 00120.45(a). The City of The Dalles Conflict of Interest Guidelines and Conflict of Interest Disclosure Form are available from the City of The Dalles Public Works Department, 1215 West First Street, The Dalles, OR 97058 or at www.ci.the-dalles.or.us/engineering.

00120.45 Submittal of Bids: Bids may be submitted by mail, parcel delivery service, or hand delivery to the offices and addresses, and at the times, given in the Bid Booklet. Bidders shall submit Bids in a sealed envelope marked with the word "Bid", the name of the Project, and the words "To Be Opened Only by Authorized Personnel" on the outside. If submitting Bids by mail or by parcel delivery service, the Bidder shall place the sealed envelope containing the paper Bid inside a separate sealed envelope or package.

Paper Bids submitted after the time set for receiving paper Bids will not be opened or considered. The Agency assumes no responsibility for the receipt and return of late paper Bids.

00120.50 Submitting Bids for More than One Contract - A Bidder who desires to submit either paper Bids or electronic Bids for more than one Contract at a single opening of multiple Bids may submit one of the "Limiting Statements" in the Bid as follows:

- If the volume of Work to be awarded is to be limited by the number of Contracts, fill in Limiting Statement No. 1 in the Bid.
- If the volume of Work to be awarded is to be limited by the total of the Contract Amounts, fill in Limiting Statement No. 2 in the Bid Booklet.

If a Bidder makes a limiting statement on any Bid, the statement will apply to all Bids submitted by the Bidder at that opening. Should limiting statements be made on more than one Bid, and the statements differ, the lower limiting number or amount shall govern.

Bidders shall make no qualifications of the Bids that attempt to reserve the right to choose, from among two or more Contracts, the Contract or Contracts that the Bidder will accept. Selection of Contracts will be made by the Agency.

00120.60 Revision or Withdrawal of Bids: All pre-closing modifications or withdrawals of bids shall be comport with Rule 04-0300 of the Local Contract Review Board Rules. **At** any time prior to the scheduled time for opening and reading of bids, any Bidder may withdraw its proposal, either personally or by written request to the office indicated in the Bid Booklet. If the withdrawal is made personally, proper receipt shall be given therefore. Withdrawal of a bid shall not disqualify the Bidder from submitting another proposal provided the time for receipt of bid has not expired. After the time scheduled for opening and reading the bids, no Bidder shall be permitted to withdraw its bid unless acceptance is delayed by the Agency for a period exceeding sixty (60) days. Negligence on the part of the Bidder in preparing the bid confers no right to withdraw its bid after said scheduled time.

00120.65 Opening and Comparing Bids - Bids will be opened and the total price for each Bid will be read publicly at the time and place specified in the Notice to Contractors and the Bid Booklet. Bidders and other interested parties are invited to be present.

Bids for each Project will be compared on the basis of the total amount of each Bid. The total amount of the Bid will be the total sum computed from quantities listed in the Bid Schedule and unit prices entered by the Bidder.

In case of conflict between the unit price and the corresponding extended amount, the unit price shall govern, and the Agency may make arithmetic corrections on extension amounts.

00120.70 Rejection of Non-responsive Bids - A Bid will be considered irregular and will be rejected if the irregularity is deemed by the Agency to render the Bid non-responsive. Examples of irregularities include, without limitation:

- The Bid Section documents provided are not properly used or contain unauthorized alterations.
- The Bid is incomplete or incorrectly completed.
- The Bid contains improper additions, deletions, alternate Bids, or conditions.
- The Bid or Bid modifications are not signed by a person authorized to submit Bids or modify Bids, as required by 00120.01.
- The Bid is submitted on documents not obtained directly from the Agency, or is submitted by a Bidder who is not registered on Agency's "Holders of Bidding Plans" list, as required by 00120.05.
- A member of a joint venture and the joint venture submit Bids for the same Project. Both Bids may be rejected.
- The Bid has entries not typed or in ink, or has signatures or initials not in ink (save for changes received by email as provided by 00120.60).
- Each change or correction is not individually initialed.
- White-out tape or white-out liquid is used to correct item entries.
- The price per unit cannot be determined.
- The Bid guaranty is insufficient or improper.

- The original Bid Bond form is not used or is altered.
- The Oregon Construction Contractors Board registration number and expiration date are not shown on the Bid if required in the Solicitation Document. This requirement applies to State-funded Projects, with the exception of Aggregate production and landscape Projects. (Not required on Federal-aid Projects.)
- A disclosure of first-tier Subcontractors, if required under 00120.40(f), is not received within 2 working hours of the time Bids are due to be submitted, or the disclosure form is not complete.
- The Bidder has not complied with the DBE requirements of the solicitation.
- The Bid does not acknowledge all issued Addenda.
- The Bid contains entries that are not greater than zero.
- The Bid contains entries with more than two decimals to the right of the decimal point.
- The Bid entries are not expressed in U.S. dollars and cents.
- The Bidder has not submitted required Conflict of Interest Disclosure Form(s), if any. (See 00120.40(g).)
- The Bidder has liquidated and delinquent debt owed to the Agency or any department or agency of the Agency.

00120.80 Reciprocal Preference for Oregon Resident Bidders - This Subsection applies only to Contracts for Projects financed without federal funds.

Bidders shall complete the certificate of residency provided by the Agency in the Bid Booklet. Failure to properly complete the form will be cause to reject the Bid.

As used in the certificate of residency and this Subsection, "Resident Bidder" means a Bidder who has:

- Paid unemployment taxes or income taxes in the State of Oregon during any of the 12 calendar months immediately preceding submission of the Bid;
- A business address in the State of Oregon; and
- Certified in the Bid that the Bidder qualifies as a Resident Bidder.

"Nonresident Bidder" means a Bidder who is not a Resident Bidder as defined above.

In determining the lowest Bid, the Agency will, for the purpose of awarding the Contract, add a percentage increase to the Bid of a Nonresident Bidder equal to the percentage, if any, of the preference given to that Bidder in the state in which the Bidder resides (ORS 279A.120). The percentage preference applied in each state will be published on or before January 1 of each year by the Oregon Department of Administrative Services. The Agency may rely on these percentages without incurring liability to any Bidder (ORS 279A.120).

This increase will only be applied to determine the lowest Bid, and will not cause an increase in payment to the Contractor after Award of the Contract.

00120.90 Disqualification of Bidders - The Bid(s) of a disqualified Bidder will be rejected. Any of the following reasons is sufficient to disqualify a Bidder:

- More than one Bid is submitted for the same Work by an Entity under the same or different name(s).

- Evidence of collusion among Bidders. Participants in collusion will be found not responsible, and may be subject to criminal prosecution.
- Any of the grounds for disqualification cited in ORS 279C.440.

A Bidder will be disqualified if the Bidder has:

- Not been prequalified as required by 00120.00;
- Been declared ineligible by the Commissioner of the Bureau of Labor and Industries under ORS 279C.860;
- Not been registered (licensed) by the Oregon Construction Contractors Board (CCB) or has not been licensed by the State Landscape Contractors Board before submitting a Bid (ORS 279C.365(1)(k), ORS 701.021, ORS 701.026, and ORS 671.530). The Bidder's registration number and expiration date shall be shown in the Bid form, if requested. Failure to furnish the registration number, if requested, will render the Bid non-responsive and subject to rejection. (Not required on Federal-aid projects.); or
- Been determined by the CCB under ORS 701.227 not to be qualified to hold or participate in a public contract for a public improvement.

00120.91 Rejection of Bid on Grounds of Nonresponsibility of Bidder - The Bid of a Bidder who is found to be nonresponsible according to the criteria listed in 00130.10, the Local Contract Review Board Rules, or ORS 279C.375(3) will be rejected.

Section 00130 - Award and Execution of Contract

00130.00 Consideration of Bids - After opening and reading Bids, the Agency will check them for correct extensions of unit prices and totals. (See 00120.65.) The total of extensions, corrected where necessary, will be used by the Agency for Award purposes.

The Agency reserves the right to waive minor informalities and irregularities, seek clarification of any Bid or response that, in its sole discretion, it deems necessary or advisable, and to reject any or all Bids for irregularities under 00120.70 or for good cause after finding that it is in the public interest to do so (ORS 279C.395). An example of good cause for rejection in the public interest is the Agency's determination that any of the unit Bid prices are significantly unbalanced to the Agency's potential detriment. The Agency may correct obvious clerical errors, when the correct information can be determined from the face of the documents, if it finds that the best interest of the Agency and the public will be served thereby.

Bids will be considered and a Contract awarded, if at all, within 30 Calendar Days from the date of Bid Opening, unless an extension beyond that time is agreed to by both parties and acknowledged in writing by the Bidder.

00130.10 Award of Contract - After the Bids are opened and a determination is made that a Contract is to be awarded, the Contract will be awarded to the lowest responsible Bidder. For the purposes of this Section, "lowest responsible Bidder" means the responsible Bidder who submitted the lowest responsive Bid, who is not on the list created by the Construction Contractors Board according to ORS Chapter 701, and who has:

- Substantially complied with all prescribed public bidding procedures and requirements.
- Available the appropriate financial, Materials, Equipment, facility and personnel resources and expertise, or ability to obtain the resources and expertise, necessary to indicate the capability of the prospective Bidder to meet all contractual responsibilities.
- A satisfactory record of performance. In evaluating a Bidder's record of performance, the Agency may consider, among other things, whether the Bidder completed previous contracts of a similar nature with a satisfactory record of performance. For purposes of evaluating a Bidder's performance on previous contracts of a similar nature, a satisfactory record of performance means that to the extent that the costs associated with and time available to perform a previous contract remained within the Bidder's control, the Bidder stayed within the time and budget allotted for the procurement and otherwise performed the contract in a satisfactory manner. Satisfactory performance of the Contract also includes compliance with the requirements for records in 00170.07 for Contracts with the Agency.
- A satisfactory record of integrity. In evaluating a Bidder's record of integrity, the Agency may consider, among other things, whether the Bidder has previous criminal convictions for offenses related to obtaining or attempting to obtain a contract or subcontract or in connection with the Bidder's performance of a contract or subcontract.
- Qualified legally to contract with the Agency.
- Supplied all necessary information in connection with the inquiry concerning responsibility. If a prospective Bidder fails to promptly supply information requested by the Agency concerning responsibility, the Agency will base the determination of responsibility upon any available information, or may find the prospective Bidder not to be responsible.
- Not been disqualified by the public contracting agency under ORS 279C.440.
- An unexpired certificate issued by the Oregon Department of Administrative Services (under ORS 279A.167) upon completion of the curriculum and assessment that the Bidder understands the prohibitions set forth in ORS 652.220 and in other laws or rules that prohibit discrimination in compensation or wage payment. The certificate is only required if the Bidder employs 50 or

more full-time workers and submitted a Bid for a procurement with an estimated contract price that exceeds \$500,000.

If the Bidder is found not to have a satisfactory record of performance or integrity, the Agency will document the record and the reasons for the unsatisfactory finding.

In determining whether the Bidder is responsible, the Agency may also consider whether the Bidder has liquidated and delinquent debt owed to the State of Oregon or any department or agency of the State.

The Agency will provide Notice of Intent to Award to all Bidders.

The Award will not be final until the later of the following:

- Three (3) working days after the Notice of Intent to Award has been sent to each Bidder; or
- The Agency has provided a written response to each timely protest, denying the protest and affirming the Award.

If the Agency accepts a Bid and awards a Contract, the Agency will send the successful Bidder written notice of acceptance and Award.

Notice of Award and Contract booklets ready for execution will be sent within 30 Calendar Days of the opening of Bids or within the number of Calendar Days specified in the Special Provisions or a written mutual agreement.

00130.15 Right to Protest Award - Adversely affected or aggrieved Bidders, limited to the three apparent lowest Bidders and any other Bidder directly in line for Contract Award, may submit to the Agency a written protest of the Agency's intent to Award within 3 working days following posting of the Notice of Intent to Award to all Bidders. The protest shall specify the grounds upon which it is based.

The Agency will not consider late protests.

00130.20 Cancellation of Award - Without liability to the Agency, the Agency may for good cause cancel Award at any time before the Contract is executed by all parties to the Contract, as provided by ORS 279C.395 for rejection of Bids, upon finding it is in the public interest to do so.

00130.30 Contract Booklet - The Contract booklet may include, but is not limited to:

- Addenda
- Contract
- Performance Bond
- Payment Bond
- Certification of workers' compensation coverage

00130.40 Contract Submittals - Before the Agency will execute the Contract, the successful Bidder shall furnish the following:

(a) Performance and Payment Bonds - When Awarded the Contract, the successful Bidder shall furnish a Performance Bond and a Payment Bond of a Surety authorized to do business in the State of Oregon.

The successful Bidder shall submit the standard bond forms, which are bound in the Contract booklet. Faxed or photocopied bond forms will not be accepted. The amount of each bond shall be equal to the Contract Amount. The Performance Bond and the Payment Bond must be signed by the Surety's authorized Attorney-in-Fact, and the Surety's seal must be affixed to each bond. A power of attorney for the Attorney-in-Fact shall be attached to the bonds in the Contract booklet, which must include bond numbers, and the Surety's original seal must be affixed to the power of attorney. Bonds shall not be canceled without the Agency's consent, nor will the Agency normally release them, prior to Contract completion.

When a coating system warranty is required by 00594.75, the Contractor shall also furnish a supplemental warranty performance bond as and when described in 00594.75.

(b) Certificates of Insurance - The successful Bidder shall furnish the Agency certificates of insurance applicable to the Project, according to 00170.70. The insurance coverages shall remain in force throughout the performance of the Contract and shall not be allowed to lapse without prior written approval of the Agency. Bidders may refer to 00170.70 for minimum coverage limits and other requirements.

For specified Contracts, certified copies, and in some instances the original, of insurance policies may be required by the Special Provisions.

(c) Workers' Compensation - To certify compliance with the workers' compensation insurance coverage required by 00170.61(a) and 00170.70(d), the successful Bidder shall complete and sign the "Certification of Workers' Compensation Coverage" form bound in the Contract booklet.

(d) Registration Requirements:

(1) ORS 701.021, ORS 701.026, and ORS 671.530 require that Bidders be registered with the Oregon Construction Contractors Board or licensed by the State Landscape Contractors Board prior to submission of a Bid on a Project not involving federal funds. Registration with the Construction Contractors Board or licensing by the State Landscape Contractors Board is not a prerequisite to bidding on Federal-aid Projects; however, the Agency will not execute a Contract until the Contractor is so registered or licensed.

(2) Bidders must be registered with the Corporation Division, Oregon Secretary of State, if bidding as a corporation, limited liability company, joint venture, or limited liability partnership, or if operating under an assumed business name and the legal name of each person carrying on the business is not included in the business name.

(3) A Contractor registered under ORS Chapter 701 may bid on a landscaping project or perform a construction project that includes landscape contracting as a portion of the project if the landscape contracting is subcontracted to a licensed landscaping business as defined in ORS 671.520.

(4) A landscaping business may bid on a Project or perform a Contract that includes the phase of landscape contracting for which it is not licensed if it employs a landscape contractor, or subcontracts with another licensed landscaping business, licensed for that phase.

(e) Tax Identification Number - The successful Bidder shall furnish the Agency the Bidder's Federal Tax Identification Number.

00130.50 Execution of Contract and Bonds:

(a) By the Bidder - The successful Bidder shall deliver the required number of Contract booklets with the properly executed Contract, Performance Bond, Payment Bond, certification of workers' compensation coverage, and the required certificates of insurance, to the Agency within 10 Calendar Days after the date on which the Contract booklets are sent or otherwise conveyed to the Bidder under 00130.10. The Bidder shall return the originals of all documents received from the Agency and named in this Subsection, with original signatures. Certificates of insurance shall also be originals. Certificates of insurance for coverages that are permitted by the Agency under 00170.70(a) to be obtained by appropriate Subcontractors shall be delivered by the Contractor to the Agency together with the Contractor's request under 00180.21 for approval of the subcontract with that Subcontractor. No copies of these documents will be accepted by the Agency.

Proper execution requires that:

- If the Contractor is a partnership, limited liability partnership, joint venture, or limited liability company, an authorized representative of each Entity comprising it shall sign the Contract, Performance Bond, and Payment Bond, and an authorization to sign shall be attached.
- If the Contractor is a corporation, the President and the Secretary of that corporation shall sign the Contract, Performance Bond, and Payment Bond. However, if other corporate officers are authorized to execute contracts and bonds, the successful Bidder shall furnish with those documents a certified, true and correct copy of the corporate bylaws or minutes stating that authority. If only one officer is signing, then the bylaws or minutes must include the authority to sign without the signature of others. The successful Bidder shall also include the title(s) or corporate office(s) held by the signer(s).

(b) By the Agency - Within seven (7) Calendar Days after the Agency has received and verified the properly executed documents specified in 00130.50(a), and received legal sufficiency approval from the Agency Attorney (if required), the Agency will execute the Contract. The Agency will then send a fully-executed original Contract booklet to the successful Bidder, who then officially becomes the Contractor.

00130.60 Failure to Execute Contract and Bonds - Failure of the successful Bidder to execute the Contract and provide the required certificates, certifications, and bonds may be cause for cancellation of the Award, and may be cause for forfeiture of the Bid guaranty under ORS 279C.385.

Award may then be made to the next lowest responsible Bidder, the Project may be re-advertised, or the Work may be performed otherwise as the Agency decides.

The forfeited Bid guaranty will become the Agency's property, not as a penalty but as liquidation of damages resulting from the Bidder's failure to execute the Contract and provide the certificates, certifications, and bonds as required by these Specifications.

00130.70 Release of Bid Guaranties - Bid guaranties will be released and checks returned 7 Calendar Days after Bids are opened, except for those of the three apparent lowest Bidders on each Project. The guaranties of the three apparent lowest Bidders will be released and checks returned to unsuccessful Bidders within 7 Days of the Agency's execution of the Contract.

00130.80 Project Site Restriction - Until the Agency sends the Contractor written Notice to Proceed with the Work, and the Contractor has filed the public works bonds required in 00170.20, the Contractor shall not go onto the Project Site on which the Work is to be done, nor move Materials, Equipment, or workers onto that Project Site.

The Contractor will not automatically be entitled to extra compensation because the commencement of Work is delayed by failure of the Agency to send the Contract for execution. However, if more than 30 Calendar Days elapse between the date the Bid is opened and the date the Agency sends the Contract to be executed, the Agency will consider granting an adjustment of time for completion of the Work to offset any actual delay to Contract completion resulting directly from delay in commencement.

00130.90 Notice to Proceed - Notice to Proceed will be issued within 5 Calendar Days after the Contract is executed by the Agency.

Should the Agency fail to issue the Notice to Proceed within 5 Calendar Days of Contract execution, the Contractor may apply for an adjustment of Contract Time according to 00180.80(c).

The Engineer will issue a First Notification recording the date the performance of the Contract has begun.

Section 00140 - Scope of Work

00140.00 Purpose of Contract - The purpose of the Contract is to set forth the rights and obligations of the parties and the terms and conditions governing completion of the Work. The Contractor's obligations shall include without limitation the following:

- The Contractor shall furnish all Materials, Equipment, labor, transportation, and Incidentals required to complete the Work according to Plans, Specifications, and terms of the Contract.
- The Contractor shall perform the Work according to the lines, grades, Cross Section data, Typical Sections, dimensions, and other details shown on the Plans or in the 3D Engineered Model, as modified by written order, or as directed by the Engineer.
- The Contractor shall perform all Work determined by the Engineer to be necessary to complete the Project.
- The Contractor shall contact the Engineer for any necessary clarification or interpretation of the Contract.

00140.10 Typical Sections - The Typical Sections are intended to apply in general. At other locations where the Typical Section is not appropriate, the Contractor shall perform construction to the identified alignment as directed by the Engineer.

00140.20 Thickness - The thickness of Courses of Materials shown on the Plans, given in the Specifications, or established by the Engineer is considered to be the compacted thickness. Minor variations are acceptable when within tolerances specified in the Specifications or Plans, or when approved by the Engineer.

00140.30 Agency-Required Changes in the Work - Changes to the Plans, quantities, or details of construction are inherent in the nature of construction and may be necessary or desirable during the course of Project construction.

Without impairing the Contract, the Agency reserves the right to require changes it deems necessary or desirable within the scope, which in the Specifications means general scope, of the Project. These changes may modify, without limitation:

- Specifications and design
- Grade and alignment
- Cross Sections and thicknesses of Courses of Materials
- 3D Engineered Model
- Method or manner of performance of Work
- Project Limits

or may result in:

- Increases and decreases in quantities
- Additional Work
- Elimination of any Contract item of Work
- Acceleration or delay in performance of Work

Upon receipt of a Change Order, the Contractor shall perform the Work as modified by the Change Order. If the Change Order increases the Contract Amount, the Contractor shall notify its Surety of the increase and shall provide the Agency with a copy of any resulting modification to bond documents. The Contractor's performance of Work according to Change Orders shall neither

invalidate the Contract nor release the Surety. Payment for changes in the Work will be made according to 00195.20. Contract Time adjustments, if any, will be made according to 00180.80.

00140.40 Differing Site Conditions - The following constitute differing Project Site conditions provided such conditions are discovered at the Project Site after commencement of the Work:

- **Type 1** - Subsurface or latent physical conditions that differ materially from those indicated in the Contract Documents; or
- **Type 2** - Unknown physical conditions of unusual nature that differ materially from those ordinarily encountered and generally recognized as inherent in the Work provided for in the Contract.

The party discovering such a condition shall promptly notify the other party, in writing, of the specific differing conditions before they are disturbed and before the affected Work is performed. The Contractor shall not continue Work in the affected area until the Engineer has inspected such condition according to 00195.30 to determine whether an adjustment to Contract Amount or Contract Time is required.

Payment adjustments due to differing Project Site conditions, if any, will be made according to 00195.30. Contract Time adjustments, if any, will be made according to 00180.80.

00140.50 Environmental Pollution Changes - ORS 279C.525 will apply to any increases in the scope of the Work required as a result of environmental or natural resources laws enacted or amended after the submission of Bids for the Contract. The Contractor shall comply with the applicable notice and other requirements of ORS 279C.525. The applicable rights and remedies of that statute will also apply.

In addition to ORS 279C.525, the Agency has compiled a list at 00170.01 of those federal, State, and local agencies, of which the Agency has knowledge, that have enacted ordinances, rules, or regulations dealing with the prevention of environmental pollution and the preservation of natural resources that may affect the performance of Agency contracts.

00140.60 Extra Work - If directed by the Engineer's written order, the Contractor shall perform work not included in the Contract. The Contractor shall perform this work according to:

- Standard Specifications
- Other Plans and Specifications issued by the Engineer

Payment for Extra Work will be made according to Section 00196. Contract Time adjustments, if any, will be made according to 00180.80.

00140.65 Disputed Work - The Contractor may dispute any part of a Change Order, written order, or an oral order from the Engineer by the procedures specified in Section 00199.

00140.70 Cost Reduction Proposals - The Contractor may submit written proposals to the Engineer that modify Plans, Specifications, or other Contract Documents for the sole purpose of reducing the total cost of construction. Unless otherwise agreed to in writing by the Agency, a proposal that is solely or primarily a proposal to reduce estimated quantities or delete Work, as determined by the Engineer, is not eligible for consideration as a cost reduction proposal and will instead be addressed under 00140.30, whether proposed or suggested by the Agency or the Contractor.

- (a) **Proposal Requirements** - The Agency will not adopt a cost reduction proposal that impairs essential functions or characteristics of the Project, including, but not limited to, service life,

economy of operation, ease of maintenance, designed appearance, or design and safety standards.

To conserve time and funds, the Contractor may first submit a written request for a feasibility review by the Engineer. The request should contain a description of the proposal together with a rough estimate of anticipated dollar and time savings. The Engineer will, within a reasonable time, advise the Contractor in writing whether or not the proposal would be considered by the Agency, should the Contractor elect to submit a detailed cost reduction proposal.

A detailed cost reduction proposal shall include without limitation the following information:

- A description of existing Contract requirements for performing the Work and the proposed change;
- The Contract items of Work affected by the proposed change, including any quantity variation caused by the proposed change;
- Pay Items affected by the proposed change including any quantity variations;
- A detailed cost estimate for performing the Work under the existing Contract and under the proposed change. Cost estimates shall be made according to Section 00197. Costs of re-design, which are incurred after the Agency has accepted the proposal, shall be included in the cost of proposed work; and
- A date by which the Engineer must accept the proposal in order to accept the proposed change without impacting the Contract Time or cost reduction amount.

(b) Continuing to Perform Work - The Contractor shall continue to perform the Work according to Contract requirements until the Engineer issues a Change Order incorporating the cost reduction proposal. If the Engineer fails to issue a Change Order by the date specified in the proposal, the proposal shall be deemed rejected.

(c) Consideration of Proposal - The Engineer is not obligated to consider any cost reduction proposal. The Agency will not be liable to the Contractor for failure to accept or act upon any cost reduction proposal submitted.

The Engineer will determine in its sole discretion whether to accept a cost reduction proposal as well as the estimated net savings in construction costs from the adoption of all or any part of the proposal. In determining the estimated net savings, the Engineer may disregard the Schedule of Items. The Engineer will establish prices that represent a fair measure of the value of Work to be performed or to be deleted as a result of the cost reduction proposal.

(d) Sharing Investigation Costs - As a condition for considering a Contractor's cost reduction proposal, the Agency reserves the right to require the Contractor to share in the Agency's costs of investigating the proposal. If the Agency exercises this right, the Contractor shall provide written acceptance of the condition to the Engineer. Such acceptance will authorize the Agency to deduct its share of investigation costs from payments due or that may become due to the Contractor under the Contract.

(e) Acceptance of Proposal Requirements - If the Contractor's cost reduction proposal is accepted in whole or in part, acceptance will be made by a Change Order that will include without limitation the following:

- Statement that the Change Order is made according to 00140.70;
- Revised Contract Documents that reflect all modifications necessary to implement the approved cost reduction measures;
- Any conditions to which the Agency's approval is subject;

- Estimated net savings in construction costs attributable to the approved cost reduction measures; and
- A payment provision according to which the Contractor will be paid 50% of the estimated net savings amount as full and adequate consideration for performance of the Work of the Change Order.

The Contractor's cost of preparing the cost reduction proposal and the Agency's costs of investigating the proposal, including any portion paid by the Contractor, will be excluded from determination of the estimated net savings in construction costs. Costs of re-design, which are incurred after the Agency has accepted the proposal, will be included in the cost of the Work attributable to cost reduction measures.

If the Agency accepts the cost reduction proposal, the Change Order that authorizes the cost reduction measures will also address any Contract Time adjustment.

(f) Right to General Use - Once submitted, the cost reduction proposal becomes the property of the Agency. The Agency reserves the right to adopt the cost reduction proposal for general use without additional compensation to the Contractor when it determines that a proposal is suitable for application to other contracts.

00140.80 Use of Publicly Owned Equipment - The Contractor is prohibited from using publicly-owned Equipment except in the case of emergency. In an emergency, the Contractor may rent publicly-owned Equipment provided that:

- The Engineer provides written approval that states that such rental is in the public interest; and
- Rental does not increase the Project cost.

00140.90 Final Trimming and Cleanup - Before Final Inspection as described in 00150.90, the Contractor shall neatly trim and finish the Project and remove all remaining unincorporated Materials and debris. Final trimming and cleanup shall include without limitation the following:

- The Contractor shall retrim and reshape earthwork, and shall repair deteriorated portions of the Project Site.
- Where the Work has impacted existing facilities or devices, the Contractor shall restore or replace those facilities to their pre-existing condition.
- The Contractor shall clean all drainage facilities and sanitary sewers of excess Materials or debris resulting from the Work.
- The Contractor shall clean up and leave in a neat, orderly condition, Rights-of-Way, Materials sites, and other property occupied in connection with performance of the Work.
- The Contractor shall remove temporary buildings, construction plants, forms, falsework and scaffolding, surplus and discarded Materials, and rubbish.
- The Contractor shall dispose of Materials and debris, including, without limitation, forms, falsework, scaffolding, and rubbish resulting from clearing, grubbing, trimming, clean-up, removal, and other Work. These Materials and debris become the property of the Contractor. The Contractor shall dispose of these Materials and debris immediately.

Unless the Contract specifically provides for payment for this item, the Agency will make no separate or additional payment for final trimming and cleanup.

Section 00150 - Control of Work

00150.00 Authority of the Engineer - The Engineer has full authority over the Work and its suspension. (See Section 00180.) The Contractor shall perform all Work to the complete satisfaction of the Engineer. The Engineer's determination shall be final on all matters, including, but not limited to, the following:

- Quality and acceptability of Materials and workmanship
- Measurement of unit price Work
- Timely and proper prosecution of the Work
- Interpretation of Contract Documents
- Payments due under the Contract

The Engineer's decision is final and, except as provided in 00180.80 for adjustments of Contract Time and Section 00199 for claims for additional compensation, may be challenged only through litigation.

Work performed under the Contract will not be considered complete until it has passed Final Inspection by the Engineer and has been accepted in writing by the Agency.

Interim approvals issued by the Engineer, including, but not limited to, Third Notification, will not discharge the Contractor from responsibility for errors in prosecution of the Work, for improper fabrication, for failure to comply with Contract requirements, or for other deficiencies, the nature of which are within the Contractor's control.

00150.01 Project Manager's Authority and Duties - The Engineer may designate a Project Manager as its representative on the Project with authority to enforce the provisions of the Contract.

When the Engineer has designated a Project Manager, the Contractor should direct all requests for clarification or interpretation of the Contract, in writing, to the Project Manager. The Project Manager will respond within a reasonable time. Contract clarification or interpretation obtained from persons other than the Project Manager will not be binding on the Agency.

The Project Manager shall have the authority to appoint Inspectors and other personnel as required to assist in the administration of the Contract.

00150.02 Inspector's Authority and Duties - To the extent delegated under 00150.01, Inspectors are authorized to represent the Engineer and Project Manager to perform the following:

- Inspect Work performed and Materials furnished, including, without limitation, the preparation, fabrication, or manufacture of Materials to be used;
- Orally reject defective Materials and to confirm such rejection in writing;
- By oral order, temporarily suspend the Work for improper prosecution pending the Engineer's decision; and
- Exercise additional delegated authority.

Inspectors are not authorized to:

- Accept Work or Materials.
- Alter or waive provisions of the Contract.
- Give instructions or advice inconsistent with the Contract Documents.

00150.10 Coordination of Contract Documents - The Contract Documents, including, but not limited to, Contract Change Orders, the Special Provisions, the Plans, and the Standard Specifications are intended to collectively describe all of the items of Work necessary to complete the Project.

(a) Order of Precedence - The Engineer will resolve any discrepancies between these documents in the following order of precedence:

- Contract Change Orders;
- Special Provisions;
- Stamped Agency-prepared drawings specifically applicable to the Project and bearing the Project title;
- Reviewed and accepted, stamped Working Drawings;
- 3D Engineered Models and supplemental Agency-prepared line, grade and Cross Section data applicable to the Project;
- Standard Drawings;
- Approved unstamped Working Drawings and 3D Construction Models;
- Standard Specifications; and
- All other Contract Documents not listed above.

Notes on a drawing shall take precedence over drawing details.

Dimensions shown on the drawings, or that can be computed, shall take precedence over scaled dimensions.

(b) Immaterial Discrepancies - The Contract Documents specify details for the construction and completion of the Work. If Contract Documents describe portions of the Work in sufficient detail but are silent in some minor respect, the Contractor may proceed utilizing the current best industry practices.

(c) Material Discrepancies - If the Contractor identifies a discrepancy, error, or omission in the Contract Documents that cannot be resolved by the approach specified in (b) above, the Contractor shall immediately request clarification from the Engineer.

00150.15 Construction Stakes, Lines, and Grades:

(a) General - The Contractor shall perform no Work until the Engineer establishes field controls. Work performed without field controls will be subject to removal at the Contractor's expense.

(b) Agency Responsibilities - The Engineer will:

- Lay out and set construction stakes and marks to establish the lines, grades, Slopes, Cross Sections, and curve super-elevations for roadwork;
- Provide one set of construction stakes for line and grade for each additional phase of the Work;
- Set bench marks and stakes for centerline of Bridges and bents;
- Calculate and provide finish deck grades; and
- Deduct from payments due the Contractor all costs incurred to replace stakes and marks negligently or intentionally damaged, removed, or destroyed by the Contractor.

(c) Contractor Responsibilities - The Contractor shall:

- Inform the Engineer of staking requirements at least 5 Calendar Days before the staking needs to begin;
- Coordinate construction to provide sufficient area for the Engineer to perform surveying work efficiently and safely;
- Accurately measure detailed dimensions, elevations, and Slopes from the Engineer's stakes and marks;
- Perform the Work in such a manner as to preserve stakes and marks; and
- Set any reference lines for automatic control from the control stakes provided by the Engineer.

00150.20 Inspection:

(a) Inspection by the Engineer - The Engineer may test Materials furnished and inspect Work performed by the Contractor to ensure Contract compliance.

If the Contractor performs Work without the Engineer's inspection or uses Materials that the Engineer has not approved, the Engineer may order affected portions of the Work removed at the Contractor's expense. The foregoing sentence shall not apply if the Engineer fails to inspect the Work within a specific period of time required in the Contract or, in the absence of a specific period of time, within a reasonable period of time after receiving the Contractor's timely written request for inspection or testing.

At the Engineer's direction, any time before the Work is accepted, the Contractor shall uncover portions of the completed Work for inspection. After inspection, the Contractor shall restore these portions of Work to the standard required by the Contract. If the Engineer rejects Work due to Materials or workmanship, or if the Contractor performed such Work without providing sufficient advance request for inspection to the Engineer, the Contractor shall bear all costs of uncovering and restoring the Work. If the Engineer accepts the uncovered Work, and the Contractor performed the Work only after providing the Engineer with sufficient advance notice, the costs of uncovering and restoring the Work will be paid for by the Agency according to 00195.20.

(b) Inspection Facilities - The Contractor shall furnish walkways, railings, ladders, shoring, tunnels, platforms, and other facilities necessary to permit the Engineer to have safe access to the Work to be inspected. The Contractor shall require producers and fabricators to provide safe inspection access as requested by the Engineer.

(c) Sampling - The Contractor shall furnish the Engineer with samples of Materials that the Engineer will test. All of the Contractor's costs related to this required sampling are Incidental.

(d) Inspection by Third Parties - Where third parties have the right to inspect the Work, the Contractor shall coordinate with the Engineer and shall provide safe inspection access.

(e) Contractor's Duty to Make Corrections - The Contractor shall perform all Work according to the Contract Documents. The Contractor shall correct Work that does not comply with the Contract Documents at its own expense. Inspection of the Work by the Engineer does not relieve the Contractor of responsibility for improper prosecution of the Work.

00150.25 Acceptability of Materials and Work - The Contractor shall furnish Materials and shall perform Work in Close Conformance to the Contract Documents. If the Engineer determines that the Materials furnished or the Work performed are not in Close Conformance with the Contract Documents, the Engineer may:

- Reject the Materials or Work and order the Contractor, at the Contractor's expense, to remove, replace, or otherwise correct any non-conformity; or

- Accept the Materials or Work as suitable for the intended purpose, adjust the amount paid for applicable Pay Items to account for diminished cost to the Contractor or diminished value to the Agency, document the adjustment, and provide written documentation to the Contractor regarding the basis of the adjustment.

The Engineer's decisions concerning acceptability of Materials or Work will be final.

00150.30 Delivery of Notices - Written notices to the Contractor by the Engineer or the Agency will be delivered:

- In person;
- By U.S. Postal Service first class mail or priority mail (which at the sender's option may include certified or registered mail return receipt requested), to the current office address as shown in the records of the Agency; or
- By overnight delivery service of a private industry courier, to the current office address as shown in the records of the Agency.

Notices shall be considered as having been received by the Contractor:

- At the time of actual receipt when delivered in person;
- At the time of actual receipt or seven (7) Calendar Days after the postmarked date when deposited for delivery by first class or priority mail, whichever is earlier; or
- At the time of actual receipt or three (3) Calendar Days after deposit with a private industry courier for overnight delivery service, whichever is earlier.

Written notices to the Engineer or the Agency by the Contractor shall be delivered to the Agency address shown in the Special Provisions, unless a different address is agreed to by the Engineer, and shall be delivered:

- In person;
- By U.S. Postal Service first class mail or priority mail (which at the sender's option may include certified or registered mail return receipt requested); or
- By overnight delivery service of a private industry courier.

Notices will be considered as having been received by the Agency:

- At the time of actual receipt when delivered in person;
- At the time of actual receipt or seven (7) Calendar Days after the postmarked date, when deposited for delivery by first class or priority mail, whichever is earlier; or
- At the time of actual receipt or three (3) Calendar Days after deposit with a private industry courier for overnight delivery service, whichever is earlier.

For purposes of this Subsection, the time zone is Pacific Standard Time (PST) to determine time of receipt of notices and other documents. For purposes of this Subsection, non-business days are Saturdays, Sundays and legal holidays as defined by ORS 187.010 and 187.020.

Claims must be submitted on paper documents according to Section 00199.

00150.35 Plans, 3D Engineered Models, Working Drawings, and 3D Construction Models:

(a) Plans and 3D Engineered Models - The Agency-prepared Plans and 3D Engineered Models will show details of lines, grades, Cross Sections, and Typical Section of the Roadway, and

locations and design details of Structures.

(b) Working Drawings and 3D Construction Models - The Contractor shall supplement the Agency-prepared Plans and 3D Engineered Models with stamped Working Drawings, unstamped Working Drawings, or 3D Construction Models that show all information necessary to complete the Work. The applicable Section or Subsection of the Standard Specifications will indicate the supplemental information required and whether the drawings are to be stamped or unstamped. Stamped Working Drawings, unstamped Working Drawings, and 3D Construction Models are defined as follows:

(1) Stamped Working Drawings - Working Drawings, calculations, and other data which are prepared by or under the direction of a Professional Engineer licensed in the State of Oregon, and which bear the engineer's signature, seal, and expiration date.

(2) Unstamped Working Drawings - Working Drawings, calculations, and other data that do not bear an engineering seal.

(3) 3D Construction Models - See 00110.20.

(c) Number, Size, and Format of Working Drawings and 3D Construction Models - The Contractor shall submit Working Drawings and 3D Construction Models according to one of the following methods:

(1) Paper Submittal - The Contractor shall submit to the Engineer seven copies of Working Drawings for steel Structures and six copies of Working Drawings for other Structures. The submitted copies shall be clear and readable. Drawing dimensions shall be 8 1/2 by 11 inches, 11 by 17 inches, or 22 by 36 inches in size. One copy of the submitted Working Drawings will be returned to the Contractor after processing. The Contractor shall submit such additional number of copies to the Engineer for processing that the Contractor would like to have returned.

The Contractor shall not submit 3D Construction Model data in paper format.

(2) Electronic Submittal - The Contractor shall submit electronic Working Drawings as required in 00170.08. The Contractor shall submit 3D Construction Model data in LandXML format or as directed by the Engineer.

(d) Processing Working Drawings and 3D Construction Models - The Engineer will process Working Drawings and 3D Construction Models as follows:

(1) Stamped Working Drawings - Stamped Working Drawings will be designated as "accepted", "accepted with comments", or "returned for correction" by the Engineer. If stamped Working Drawings are returned for correction by the Engineer, the Contractor shall address all comments and resubmit the stamped Working Drawings.

(2) Unstamped Working Drawings - Unstamped Working Drawings will be designated as "approved", "approved as noted", or "returned for correction" by the Engineer. If unstamped Working Drawings are returned for correction by the Engineer, the Contractor shall address all comments and resubmit the unstamped Working Drawings.

(3) 3D Construction Models - 3D Construction Models will be designated as "approved", "approved as noted", or "returned for correction" by the Engineer. If 3D Construction Models are returned for correction by the Engineer, the Contractor shall address all comments and resubmit the 3D Construction Models.

The Contractor shall not fabricate or construct any structural components until the stamped or unstamped Working Drawings are returned by the Engineer with a written designation of "accepted", "accepted with comments", "approved", or "approved as noted", as applicable for the Working Drawings.

The Contractor shall not begin construction activities that will utilize a 3D Construction Model until the Engineer has processed the model and designated it as "approved" or "approved as noted".

The Engineer's processing of the Working Drawings and 3D Construction Models does not amend any contractual obligations of the parties.

The Engineer will process and return Working Drawings and 3D Construction Models within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt by the Engineer. If the Engineer fails to return such drawings or models within this period of time, the Engineer will consider granting a Contract Time extension according to 00180.80. If the Contractor is required to resubmit Working Drawings or 3D Construction Models to the Engineer, the Engineer will process and return the Working Drawings or 3D Construction Models within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt of the resubmitted Working Drawings or 3D Construction Models by the Engineer.

00150.37 Equipment Lists and Other Submittals - The Contractor shall submit Equipment lists, and other required submittals for approval by the Engineer. The Engineer will respond to requests for approval within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt by the Engineer unless otherwise specified in the Section of the Specifications requiring such approval.

00150.40 Cooperation and Superintendence by the Contractor - The Contractor is responsible for full management of all aspects of the Work, including superintendence of all Work by Subcontractors, Suppliers, and other providers. The Contractor shall appoint a single Superintendent and may also appoint alternate Superintendents as necessary to control the Work. The form of appointment of the alternate shall state, in writing, the alternate's name, duration of appointment in the absence of the Superintendent, and scope of authority. The Contractor shall:

- Provide for the cooperation and superintendence on the Project by:
 - Furnishing the Engineer all data necessary to determine the actual cost of all or any part of the Work, added Work, or Changed Work.
 - Allowing the Engineer reasonable access to the Contractor's books and records at all times. To the extent permitted by public records laws, the Engineer will make reasonable efforts to honor the Contractor's request for protection of confidential information.
 - Keeping one complete set of Contract Documents on the Project Site at all times, available for use by all the Contractor's own organization, and by the Engineer if necessary.
- Appoint a single Superintendent, and any alternate Superintendent, who shall meet the following qualifications:
 - Appointees shall be competent to manage all aspects of the Work.
 - Appointees shall be from the Contractor's own organization.
 - Appointees shall have performed similar duties on at least one previous project of the size, scope and complexity as the current Contract.
 - Appointees shall be experienced in the types of Work being performed.
 - Appointees shall be capable of reading and thoroughly understanding the Contract Documents.
- The appointed single Superintendent, or any alternate Superintendent, shall:
 - Be present for all On-Site Work, regardless of the amount to be performed by the Contractor,

- Subcontractors, Suppliers, or other providers, unless the Engineer provides prior approval of the Superintendent's or alternate Superintendent's absence.
- Be equipped with a two-way radio or cell phone capable of communicating throughout the Project during all the hours of Work on the Project Site and be available for communication with the Engineer.
- Have full authority and responsibility to promptly execute orders or directions of the Engineer.
- Have full authority and responsibility to promptly supply the Materials, Equipment, labor, and Incidentals required for performance of the Work.
- Coordinate and control all Work performed under the Contract, including, without limitation, the Work performed by Subcontractors, Suppliers, and owner/operators.
- Diligently pursue progress of the Work according to the schedule requirements of Section 00180.
- Cooperate in good faith with the Engineer, Inspectors, and other contractors in performance of the Work.
- Provide all assistance reasonably required by the Engineer to obtain information regarding the nature, quantity, and quality of any part of the Work.
- Provide access, facilities and assistance to the Engineer in establishing such lines, grades and points as the Engineer requires.
- Carefully protect and preserve the Engineer's marks and stakes.

Any Superintendent or alternate Superintendent who repeatedly fails to follow the Engineer's written or oral orders, directions, instructions, or determinations, shall be subject to removal from the Project.

If the Contractor fails or neglects to provide a Superintendent, or an alternate Superintendent, and no prior approval has been granted, the Engineer has the authority to suspend the Work according to 00180.70. Any continued Work by the Contractor, Subcontractors, Suppliers, or other providers may be subject to rejection and removal. The Contractor's repeated failure or neglect to provide the superintendence required by these provisions constitutes a material breach of the Contract, and the Engineer may impose any remedies available under the Contract, including, but not limited to, Contract termination.

00150.50 Cooperation with Utilities:

(a) General - Unless otherwise specified in the Special Provisions or on the Plans, existing Utilities requiring adjustment may be adjusted by the Utility before, during, or after Project construction. "Adjustment of Utilities" shall mean the alteration, improvement, connection, disconnection, relocation, or removal of existing Utility lines, facilities, or systems in temporary or permanent manner.

(b) Agency Responsibilities - Before Bids are received, the Agency will make preliminary arrangements for planned Adjustment of Utilities. The Agency will list in the Special Provisions the estimated completion dates or times for adjustment work by the Utility owner, and will include a general statement describing any relocation. The Plans will not normally show the anticipated new location of Utilities that have been or will be adjusted.

(c) Contractor's Responsibilities - The Contractor shall:

- Follow applicable rules adopted by the Oregon Utility Notification Center;
- Contact Utility owners during Bid preparation and after the Contract is awarded to verify all Utilities' involvement on the Project Site;
- Coordinate Project construction with the Utilities' planned adjustments, take all precautions necessary to prevent disruption of Utility service, and perform its Work in the manner that

00150.50

results in the least inconvenience to the Utility owners;

- Include all Utility adjustment work, whether to be performed by the Contractor or the Utilities, on the Contractor's Project Work schedule submitted under 00180.41;
- Protect from damage or disturbance any Utility that remains within the area in which Work is being performed. Maintain and re-establish location marks according to OAR 952-001-0090(2)(a). Coordinate re-establishment of the location marks with the associated Utility;
- Not disturb an existing Utility if it requires an unanticipated adjustment, but shall protect the Utility from damage or disturbance and promptly notify the Engineer;
- Determine the exact location before excavating within the reasonable accuracy zone according to OAR 952-001-0090(2)(c);
- Backfill any exposed Utilities as recommended and approved by the Utility representative. Obtain Utility locate warning tape from the Utility and replace damaged or removed warning tape. Utility locate warning tape may not be present at all existing Utilities;
- Stake, place warning tape, and maintain no work limits around critical Utility facilities as shown or directed by the Engineer and the Utility;
- In addition to the notification required in OAR 952-001-0090(5), notify the Engineer and the Utility as soon as the Contractor discovers any previously unknown Utility conflicts or issues. Contrary to the OAR, stop excavating until directed by the Engineer and allow the Utility a minimum of two weeks to relocate or resolve the previously unknown Utility issues; and
- Report to the Engineer any Utility owner who fails to cooperate or fails to follow the planned Utility adjustment.

Subject to the Engineer's approval, the Contractor may adjust the Utilities by asking the Utility owners to move, remove, or alter their facilities in ways other than as shown on the Plans or in the Special Provisions. The Contractor shall conduct all negotiations, make all arrangements, and assume all costs that arise from such changes.

(d) Delays - If the Contractor complies with 00150.50(c), and if Utility adjustments are completed later than the date specified in the Special Provisions, thus causing Project completion to be delayed (provide notification under 00180.60), additional Contract Time will be considered under 00180.80, and additional compensation, if applicable, will be considered under 00195.40.

(e) Notification - Unless otherwise specified in the Special Provisions, the Project is located within the area served by the Oregon Utility Notification Center, which operates a Utilities notification system for notifying owners of Utilities about Work being performed in the vicinity of their facilities. The Contractor shall notify owners of Utilities prior to the performance of Work in the vicinity of their facilities. The Utilities notification system telephone number is 811 or 1-800-332-2344.

The Contractor shall comply with the rules of the Oregon Utility Notification Center, OAR 952-001-0010 through OAR 952-001-0090, and ORS 757.993. The Contractor may contact the Oregon Utility Notification Center at 503-232-1987 about these rules.

00150.55 Cooperation with Other Contractors - The Agency reserves the right to perform other work on or near the Project Site, including, without limitation, any Materials site, with forces other than those of the Contractor.

If such work takes place on or near the Project Site, the Contractor shall have the following obligations:

- The Contractor shall coordinate Work with other contractors or forces.
- The Contractor shall cooperate in good faith with all other contractors or forces.
- The Contractor shall perform the Work specified in the Contract in a way that will minimize

interference and delay for all forces involved.

- The Contractor shall place and dispose of the Materials being used so as not to interfere with the operations of other forces.
- The Contractor shall join the Work with that of other forces in a manner acceptable to the Engineer or the Agency, and shall perform it in the accepted sequence with the work of the other force.

The Engineer will resolve any disagreements under this Subsection that may arise among the Contractor and other work forces, or between the Contractor and the Agency. The Engineer's decision in these matters is final, as provided in 00150.00.

When the schedules for Work of the Contractor and the work of other forces overlap, each contractor involved shall submit a current, realistic progress schedule to the Engineer. Before the Engineer accepts the schedule, each party shall have the opportunity to review all schedules. After this review and any necessary consultations, the Engineer will determine acceptable schedules.

The Contractor waives any right it may have to make claims against the Agency for any damages or claims that may arise because of inconvenience, delay, or loss due solely to the presence of other contractors working on or near the Project Site.

If the Contract gives notice of work to be performed by other forces that may affect the Contractor's Work under the Contract, the Contractor shall include any costs associated with coordination of the Work in the appropriate Pay Item or as a portion of a Pay Item.

In an emergency, the Contractor most immediately able to respond may repair a facility or Utility of another contractor in order to prevent further damage to the facility, Utility, or other Structure as a result of the emergency.

00150.60 Construction Equipment Restrictions:

(a) Load and Speed Restrictions for Construction Vehicles and Equipment - The Contractor shall comply with legal weight and speed restrictions when moving Materials or Equipment beyond the limits of the Project Site.

The Contractor shall control vehicle and Equipment loads and speeds within the Project Site according to the following restrictions, unless the Special Provisions provide otherwise:

- The Contractor shall restrict loads and speeds as necessary to avoid displacement or loss of Materials on Subgrades and Aggregate Bases.
- The Contractor shall restrict weights to legal loads, and shall travel at speeds of no more than 45 mph or the posted construction speed, whichever is less, on treated Bases, Pavement, or wearing Courses.
- The Contractor shall not cross Bridges or other Structures with Equipment or vehicles exceeding the legal load limit without prior written permission of the Engineer. The Contractor shall make any such request in writing, describing the loading details and the arrangement, movement, and position of the Equipment on the Structure. The Contractor shall comply with any restrictions or conditions included in the Engineer's written permission.

(b) Protection of Buried Items - The Contractor shall use temporary fill or other methods to avoid overload of pipes, box culverts, and other items that are covered, or to be covered, by fill or backfill.

(c) Responsibility for Damages - The Contractor shall assume responsibility for damages caused by excessive Equipment speed or loads while performing the Work, both inside and outside the Project Site. The Engineer's permission to cross Bridges and other Structures, according to 00150.60(a), will not relieve the Contractor from responsibility for load-caused damages.

00150.70 Detrimental Operations - The Contractor shall avoid operations whose methods, conditions, or timing may injure people or damage property or the Work. Damage may include, without limitation, staining surfaces with mud or asphalt or damaging Utilities and foundations. (See also 00150.60, 00150.75, and Section 00170.)

When any such damage occurs, the Engineer will determine if it is to be corrected by repair, replacement, or compensatory payment by the Contractor. If compensatory payment is required, the Engineer will determine the amount. Compensatory payment may be deducted from monies due or to become due to the Contractor under the Contract.

00150.75 Protection and Maintenance of Work During Construction - The Contractor shall protect and maintain the Work during construction and until Third Notification has been issued, unless otherwise provided in the Contract. For the purposes of this Subsection, "maintenance" shall include measures to prevent deterioration of Roadway and Structures at the Project Site, and to keep them in good condition at all times during the prosecution of the Work. The Contractor shall continuously allocate sufficient Equipment and workers to achieve such maintenance.

If the Contract requires the placement of a Course upon a previously constructed Course or Subgrade, the Contractor shall maintain the previous Course or Subgrade during all construction operations.

The Contractor shall include costs of protecting and maintaining the Work during construction in the unit prices bid for the various Pay Items. The Contractor will not be paid an additional amount for this Work, unless otherwise specified.

The Engineer will notify the Contractor of the Contractor's noncompliance with this Subsection. If the Contractor fails to remedy unsatisfactory protection or maintenance within 24 hours after receipt of such notice, the Engineer may proceed to remedy the deficiency, and deduct the entire cost from monies due or to become due the Contractor under the Contract.

00150.80 Removal of Unacceptable and Unauthorized Work - The Contractor shall correct or remove unacceptable Work and remove unauthorized work, as directed by the Engineer in writing. The Contractor shall replace such work with Work and Materials conforming to the requirements of the Contract.

For the purposes of this Subsection, "unauthorized work" shall include without limitation the following:

- Work that extends beyond lines shown on the Plans or otherwise established by the Engineer;
- Work that is contrary to the Engineer's instructions; and
- Work that is conducted without the Engineer's written authorization.

The Agency will not pay the Contractor for unacceptable Work, except as provided in 00150.25, or for unauthorized work. The Engineer may issue a written order for the correction or removal of such work at the Contractor's sole expense.

If, when ordered by the Engineer, the Contractor fails to correct or remove unacceptable Work or remove unauthorized work, the Engineer may have the correction, removal or removal and replacement, done by others and deduct the entire cost from monies due or to become due the Contractor under the Contract.

00150.90 Final Inspection:

(a) On-site Construction Work - The Engineer will inspect the Project at a time close to the completion of On-Site Work.

When all On-Site Work on the Project is completed, including, but not limited to, Change Order

Work and Extra Work, the Engineer will issue Second Notification as specified in 00180.50(g).

Within 15 Calendar Days after the Engineer receives the Contractor's written notification that all punch list items, final trimming and cleanup according to 00140.90 have been completed, the Engineer will review the Project and notify the Contractor that all Work is complete, or will give the Contractor written instruction regarding incomplete or unsatisfactory Work.

(b) All Contract Work - The Engineer will issue the Third Notification when the Contractor has satisfactorily accomplished all of the following:

- The Contractor has completed all On-Site Work required under the Contract, including the punch list items from (a) above;
- The Contractor has removed all Equipment, other than that incorporated into the Work; and
- The Contractor has submitted all required certifications, bills, forms, warranties and other documents.

00150.91 Post-Construction Review - The Contractor or the Engineer may request a Post-Construction Review meeting, to be held at a time prior to issuance of Third Notification but not earlier than 45 Days following the date of Second Notification. The meeting may be held if agreed to by both parties. The party making the request will conduct the meeting, and will announce the time and place of the meeting at least 15 Days prior to the meeting date. The purpose of this meeting is to examine the Project for possible process improvements that may benefit future projects.

00150.95 Final Acceptance - After the Engineer completes Final Inspection of all Work and sends Third Notification to the Contractor, the Agency will acknowledge Final Acceptance. The Agency will notify the Contractor in writing of the date of Final Acceptance within 7 Calendar Days after Final Acceptance, or as soon thereafter as is practicable.

00150.96 Maintenance Warranties and Guarantees - Prior to Third Notification, the Contractor shall transfer to the Agency all unexpired manufacturers' warranties and guarantees for Materials and Equipment installed on the Project. Such warranties and guarantees shall recite that they are enforceable by the Agency.

00150.97 Responsibility for Materials and Workmanship:

(a) The Contractor shall perform the Work according to the terms, conditions, and requirements of the Contract.

(b) Whether before or after the Agency's acceptance of the Work, the Contractor shall be responsible for:

- Correcting or repairing any defects in, or damage to, the Work that results from the use of improper or defective materials or workmanship; or
- Replacing, in its entirety, the Work affected by the use of improper or defective materials or workmanship to the extent provided by law; and
- Correcting or repairing any Work, Materials, Structures, Existing Surfacing, Pavement, Utilities, or sites, including, without limitation, Wetlands, damaged or disturbed in that correction, repair, or replacement. (See 00170.80 to 00170.85.)

(c) Full or partial termination of the Contract under 00180.90 shall not relieve the Contractor of responsibility for completed or performed Work, or relieve the Contractor's Surety of the obligation for any just claims arising from the completed or performed Work.

Section 00160 - Source of Materials

00160.00 Definitions - The following definitions apply to Section 00160:

(a) Prospective Source - Agency-furnished Materials source, use of which by the Contractor is optional. The Agency makes no guarantee or representation, by implication or otherwise, of the land use status, quantity, quality, or acceptability of Materials available from it, except as may be stated in the Special Provisions.

(b) Mandatory Source - Agency-furnished Materials source, use of which by the Contractor is required.

(c) Blue Sheets - Prequalified products and submittals for qualification of electrical equipment and materials.

(d) Green Sheets - Conditionally prequalified products and submittals for conditional qualification of controller equipment.

(e) Red Sheets - Statewide list of certification exempt traffic management systems components pursuant to ORS 479.540 and OAR 918-261-0037.

00160.01 Notification of Source of Supply and Materials:

(a) All Materials - The Contractor shall notify the Engineer in writing of all proposed Materials sources of supply, including, without limitation, any steel or other fabricators within the following time frames:

- At least 15 Calendar Days before using or fabricating Materials, if the source is within the State; or
- At least 45 Calendar Days before using or fabricating Materials, if the source is outside the State

The Contractor shall identify if the material source is a DBE or non-DBE. For DBE Suppliers, the Contractor shall identify an estimated value of the materials to be supplied. For each committed DBE Supplier, the Contractor shall submit a copy of the materials purchase order or supply agreement. For non-committed DBE suppliers, when the estimated value is over \$10,000, the Contractor shall submit a copy of the materials purchase order or supply agreement.

For this purpose, a committed DBE firm is one that was identified by the Contractor to meet an assigned DBE goal, including DBE firms substituting for DBE firms committed as a condition of Contract Award.

(b) Prospective Source Materials - When given an option to use Prospective Sources of Materials to be incorporated into the Work, the Contractor shall notify the Engineer in writing of the option selected within 15 Calendar Days from date of Notice to Proceed. Otherwise, such Materials sources may become unavailable.

(c) Approval Required - Before allowing production or delivery of Materials to begin from any source, the Contractor must obtain the Engineer's approval. Approval to use any source does not imply that Materials from that source will be accepted. If approved sources do not provide Materials that meet Specifications, the Materials will be rejected. The Contractor will then be responsible for locating other sources and obtaining the Engineer's approval.

(d) Terms Required - The Contractor shall comply with 00170.07.

00160.05 Qualified Products List (QPL) - The QPL is a listing of manufactured products available on the market (shelf items) that ODOT has evaluated and found suitable for a specified use in highway construction. The QPL is available from ODOT's Construction Section website.

The most current published PDF version of the QPL on ODOT's Construction Section website at the time of Advertisement is the version in effect for the Project. When the Contract specifies the use of the QPL, unless specified as the subject of an exemption per ORS 279C.345, the Agency may approve for use a conditionally qualified product, a product qualified for inclusion in a later edition of the QPL, or other equivalent product that meets the requirements of the QPL, following the Standard Guidelines for Product Review, if the Agency finds the product acceptable for use on the Project.

Use of listed products shall be restricted to the category of use for which they are listed. The Contractor shall install all products as recommended by the manufacturer. The Contractor shall replace qualified products not conforming to Specifications or not properly handled or installed at no additional cost to the Agency.

00160.07 Electrical Equipment and Materials - The Blue Sheets and Green Sheets are a listing of manufactured products available on the market (shelf items) that ODOT has evaluated and found suitable for use as electrical and controller equipment and materials for highway construction. The Blue Sheets and Green Sheets are available on the ODOT Traffic-Standards website (see 00110.05(e)). The most current version of the Blue Sheets and Green Sheets on the date of Advertisement is the version in effect for the Project.

When the Contract specifies the use of the Blue Sheets and Green Sheets, unless specified as the subject of an exemption per ORS 279C.345, the Agency may approve for use a product qualified for inclusion in a later edition of the Blue Sheets and Green Sheets or other equivalent product that meets the requirements of the Blue Sheets, following the Blue Sheet Qualification/Specification Information, or the Green Sheets, following the ODOT *Standard Specification for Microcomputer Signal Controller* and errata information, if the Agency finds the product acceptable for use on the Project.

Use of listed products shall be restricted to the category of use for which they are listed. The Contractor shall install all products as recommended by the manufacturer. The Contractor shall replace qualified products not conforming to the Specifications or not properly handled or installed at no additional cost to the Agency.

00160.10 Ordering, Producing, and Furnishing Materials - The Contractor shall not place orders for or produce full quantities of Materials anticipated to be required to complete the Work until the Work has advanced to a stage that allows the quantities to be determined with reasonable accuracy. Upon request, the Engineer will notify the Contractor in writing of the quantities required. Quantity estimates by the Engineer before this notification are only approximate.

(a) Contractor's Duties - In purchasing, producing, or delivering Materials, the Contractor shall take into account the following:

- Kind of work involved;
- Amount of work involved;
- Time required to obtain Materials; and
- Other relevant factors.

(b) Approval of Quantity of Materials Ordered - Materials quantities shown on the Plans, or indicated by quantities and Pay Items, are subject to change or elimination. Therefore, the Contractor is cautioned to order or produce Materials only after having received the approval of the Engineer. The Contractor is responsible for payment for excess Materials delivered to the Project

Site or storage sites without advance authorization from the Engineer. Unless otherwise specified in the Contract, the Agency will not be responsible for:

- Materials the Contractor may deliver or produce in excess of Contract requirements;
- Extra expense the Contractor may incur because Materials were not ordered or produced earlier; or
- The Contractor's expenses related to Materials ordered by the Contractor that are not subsequently approved for use.

Excess Materials ordered or produced by the Contractor without approval of the Engineer may be purchased by the Agency at the sole discretion of the Agency. (See 00195.80.)

00160.20 Preferences for Materials:

(a) Buy America - If federal highway funds are involved on the Project, the Contractor shall limit the quantity of foreign Materials incorporated into the Work as follows. Section 635.410 of Title 23, Code of Federal Regulations, and the Intermodal Surface Transportation Efficiency Act require that all iron or steel manufacturing processes, including, without limitation, the casting of ingots, for iron or steel Materials permanently incorporated into the Project shall occur in the United States, unless the cost of foreign-origin iron or steel Materials does not exceed one-tenth of one percent (0.1%) of the Contract Amount or \$2,500, whichever is greater. The Contractor shall not incorporate foreign-origin iron or steel Materials in excess of this amount into the Project. All foreign-origin iron or steel Materials incorporated in the Project in excess of the amount indicated above shall be removed and replaced with domestic iron or steel Materials at the Contractor's expense. For purposes of this Specification, the cost of foreign-origin iron or steel Materials shall be the value of the iron or steel products as of the date they are delivered to the Project Site.

Manufacturing processes include without limitation the application of coatings to finished iron or steel products or components. Coatings include epoxy coating, galvanizing, painting, and any other coating that protects or enhances the value of the steel or iron product or component.

The Contractor shall provide the Engineer with a Certificate of Materials Origin, on a form furnished by the Engineer, before incorporating any iron or steel products into the Project. Unless a Certificate of Materials Origin has been provided to the Engineer, the Materials shall be considered of foreign origin.

The Contractor shall retain manufacturers' certificates verifying the origin of all domestic iron or steel Materials for 3 years after the date of final payment for the Project, and shall furnish copies to the Engineer upon request.

(b) Buy Oregon - According to ORS 279A.120, the Contractor shall give preference to goods or services produced in Oregon if price, fitness, availability, and quality are equal. This provision does not apply to contracts financed wholly or in part by federal funds.

(c) Recycled Materials - According to ORS 279A.010, ORS 279A.125, ORS 279A.145, ORS 279A.150, and ORS 279A.155, and subject to the approval of the Engineer, the Contractor shall use recycled products to the maximum extent economically feasible.

00160.21 Cargo Preference Act Requirements - If federal highway funds are involved on the Project, the Contractor shall comply with the Cargo Preference Act and implementing regulations (46 CFR Part 381) for use of United States flag ocean vessels transporting materials or equipment acquired specifically for the Project. Strict compliance is required, including, but not limited to, the clauses in 46 CFR 381.7(a) and (b), which are incorporated by reference. The Contractor shall also include this provision in all subcontracts.

00160.30 Agency-Furnished Materials - Unless otherwise specified in the Special Provisions, Materials listed as Agency-furnished will be available to the Contractor free of charge.

The Contractor shall be responsible for all Materials furnished by the Agency and shall pay all demurrage and storage charges. The Contractor shall replace at its expense Agency-furnished Materials lost or damaged due to any cause.

The locations at which Agency-furnished Materials are available will be specified in the Special Provisions. If the locations are not listed in the Special Provisions, the Agency-furnished Materials will be furnished to the Contractor at the Project Site. In either case, all costs of handling, hauling, unloading, and placing Agency-furnished Material shall be considered included in the price paid for the Pay Item involving such Material.

All Agency-furnished Materials not incorporated into the Work remain the property of the Agency. The Contractor shall deliver such Materials as directed by the Engineer.

00160.40 Agency-Furnished Sources - The Agency may list in the Special Provisions, or show on the Plans, Borrow pits or Aggregate sources from which the Contractor may, or shall, obtain Materials. These sources will be identified and referred to as Prospective or Mandatory Sources. A development plan will be included in Section 00235 of the Special Provisions when such sources are shown on the Plans.

(a) Working in a Different Area of the Materials Source - If the Contractor desires to work in a different area of the Materials source than that shown on the development plan, the Contractor must submit a written request stating the reasons for the requested change. If a new land use permit, development plan, or reclamation plan is needed, the Contractor must submit it and obtain approval from the Engineer before starting work in any area other than that shown on the Plans. Approval for work in a different area will not entitle the Contractor to any added compensation or adjustment of Contract Time.

The Agency will not be responsible for the availability of sources other than as stated in the Special Provisions. If the Contractor has given notice of intent to use, but does not use the source(s) on the Project, the Contractor shall reimburse the Agency for any costs the Agency incurs in making such source(s) available.

(b) Cost of Sources - Unless otherwise specified in the Special Provisions, any Prospective or Mandatory Source will be provided by the Agency for use without payment of royalty or other charge. (See 00160.50.)

(c) Exhaustion of Sources - If the Engineer determines that the quantities of specified Materials that can be produced from a Mandatory Source are insufficient for the Work, and it becomes necessary to move to another source, the Agency will pay for the reasonable cost of moving the plant to, and erecting it at, a new approved source from which specified Materials can be produced. Adjustment in hauling costs, other costs, and Contract Time will be determined as provided in 00140.30.

No allowance, reimbursement, compensation, or adjustment will be made for changes in the use of sources, or for moving from one source to another, except as provided above.

00160.50 Agency-Controlled Land; Limitations and Requirements:

(a) General - The Contractor shall have no property rights in, or right of occupancy on, Agency-Controlled Land. Nor shall the Contractor have the right to sell, use, remove, or otherwise

dispose of any material from Agency-Controlled Land, areas, or property, except as specified or by the written authorization of the Engineer.

Unless authorized in the Contract, the Contractor shall not disturb any material within Rights-of-Way without written authorization from the Engineer.

Unless otherwise specified in the Contract, the ownership of all materials originating on Agency-Controlled Lands will at all times vest in, and remain within the control of, the Agency.

(b) Waste, Excess, and By-Product Materials - All waste, excess, and by-product materials, collectively referred to in this Subsection as "By-Products", from the manufacture or production of Aggregate Materials from Agency-Controlled Lands shall remain Agency property. Unless otherwise ordered by the Engineer in writing, By-Products shall be placed as required by the development plan:

- In stockpiles at designated locations;
- At locations and in shapes that are readily accessible; and
- In such a manner as to avoid fouling areas containing useable materials, or interfering with future plant setups to use materials from the property.

The Agency will not compensate the Contractor for handling and stockpiling By-Products according to the development plan requirements. If by written order the Engineer directs the Contractor to stockpile or place designated By-Products at alternate sites, the By-Products designated shall be loaded, hauled, and placed as directed, and this work will be paid for according to 00195.20.

00160.60 Contractor-Furnished Materials and Sources:

(a) General - The Contractor shall furnish, at its own expense, all products and Materials required for the Project from sources of its own choosing, unless such sources have been specified in the Special Provisions or Plans as Prospective or Mandatory Sources.

(b) Acquisition of Sources - The Contractor shall acquire, at its own expense, the rights of access to, and the use of, all sources the Contractor chooses that are not Agency-controlled and made available by the Agency to the Contractor.

(c) Additional Requirements - Except for continuously-operated commercial sources, Work shall not begin, nor will any Materials be accepted by the Engineer, until the Contractor has:

(1) Given to the Engineer a copy of permits from, or proof that permits are not required from:

- The Department of Geology and Mineral Industries, as required under ORS 517.790;
- The Department of State Lands, as required under ORS 196.815 (when removing material from the bed or banks of any waters or from any Wetland); and
- Local governmental authorities having jurisdiction over land use at the source location.

(2) Furnished to the Engineer written approval of the property owner, if other than the Contractor, for the Contractor's proposed plans of operation in, and reclamation of, the source.

00160.70 Requirements for Plant Operations - Before operating mixing plants, Rock crushers, or other Equipment, the Contractor shall provide the Engineer copies of all applicable discharge permits for noise, air contaminants, and water pollutants from DEQ or applicable local jurisdictions, or a letter from DEQ or the local jurisdiction stating that no permits are required for the use of the Equipment and sites.

00160.80 Requirements for Sources of Borrow and Aggregate - The Contractor shall conduct operations according to all applicable federal, State, and local laws (including, without limitation, ORS Chapter 517 and OAR 632-030) when developing, using, and reclaiming all sources of Borrow material and Aggregate. The Contractor shall provide erosion control at Borrow sources that are not within the Project Site. The Contractor shall not operate in Wetlands except as allowed by permit. The Contractor shall comply with all requirements for pollution and sediment control, including, without limitation, the National Pollutant Discharge Elimination System where applicable.

Except for continuously-operated commercial sources, the Contractor shall also conform to the following:

(a) If a natural growth of trees or shrubs is present, preserve a border of such to conceal land scars.

(b) Excavate Borrow sources and Aggregate sources, except for those in streams and rivers, to provide:

- Reasonably uniform depths and widths;
- Natural drainage so no water stands or collects in excavated areas, when practicable;
- Slopes trimmed to blend with the adjacent terrain upon completion of operations;
- Slopes covered with native Soil, or acceptable plant rejects to support plant growth, if required by Specifications, Plans, or permits; and
- A vegetative cover that blends with the adjacent natural growth.

(c) Excavate in quarries so that:

- Faces will not be steeper than vertical (no overhang);
- Vertical faces conform to Oregon OSHA standards, Division 3, and as shown on an approved development plan;
- Floors or benches are excavated to a uniform Slope free of depressions and will drain and not interfere with the downland owner's property; and
- Upon completion, the quarry is left appearing neat and compatible with surrounding terrain.

(d) Obliterate haul roads specifically built for access to sources, and restore the areas disturbed by these roads as nearly as practicable to the conditions that existed before the roads were built, unless otherwise directed by the landowner or regulatory body.

Section 00165 - Quality of Materials

Description

00165.00 General - The Contractor shall incorporate into the Work only Materials conforming to the Specifications and approved by the Engineer. The Contractor shall incorporate into the Work only manufactured products made of new materials unless otherwise specified in the Contract. The Agency may require additional testing or retesting to determine whether the Materials or manufactured products meet Specifications.

Materials or manufactured products not meeting the Specifications at the time they are to be used are unacceptable and must be removed immediately from the Project Site, unless otherwise directed by the Engineer.

00165.01 Rejected Materials - The Engineer may reject any Materials that appear to be defective (see 00150.25) or that contain asbestos. The Contractor shall not incorporate any rejected Materials into the Work. Rejected Materials whose defects have been corrected may not be incorporated into the Work until the Engineer has approved their use. The Engineer may order the removal and replacement by the Contractor, at the Contractor's expense, of any defective Materials. (See also 00150.20.)

00165.02 Materials Conformance and Quality Compliance Documents - For purposes of this Section, "Materials Conformance Documents" means the Contractor's quality-control, the Agency's verification, and the independent assurance test results, and the identity of the testing facility, as specified in the ODOT *Manual of Field Test Procedures* (MFTP), unless otherwise specified in the Contract.

For purposes of this Section, "Quality Compliance Documents" means those documents specified in ODOT's *Nonfield-Tested Materials Acceptance Guide*, unless otherwise specified in the Contract.

00165.03 Testing by Agency - When testing Materials, the Agency will conduct the tests in its central laboratory, field laboratories, or other laboratories designated by the Engineer, even though certain AASHTO, ASTM, and other materials specifications may require testing at the place of manufacture. Results of the Agency's tests will be made available to the Contractor.

00165.04 Costs of Testing - When the Contract requires that the Agency perform the testing, the testing will be at the Agency's expense. The Agency will pay the cost of Contractor-requested source-review tests on unprocessed Aggregates from no more than two sources for each Project, and on no more than three unprocessed samples from each source. Additional source-review tests performed at the Contractor's request shall be at the Contractor's expense.

Unless otherwise provided in the Contract, all testing required to be performed by the Contractor will be at the Contractor's expense.

Provisions and Requirements

00165.10 Materials Acceptance Guides - Unless otherwise specified elsewhere in the Contract, Materials will be accepted according to the following guides:

(a) Field-Tested Materials - Field-tested Materials will be accepted according to the MFTP. The MFTP is published once per year and is available from the ODOT Construction Section; 800 Airport Road SE; Salem, OR 97301-4798; phone 503-986-3000. The MFTP is also available on the ODOT Construction Section website. The most current version of the MFTP on the date of Advertisement is the version in effect for the Project.

(b) Nonfield-Tested Materials - Nonfield-tested Materials will be accepted according to the ODOT *Nonfield Tested Materials Acceptance Guide* (NTMAG), unless otherwise specified in the Contract. The NTMAG is available on the ODOT Construction Section website. The most current version of the NTMAG on the date of Advertisement is the version in effect for the Project.

00165.20 Materials Specifications and Test Method References - References to materials specifications and test methods of ODOT, WAQTC, AASHTO, ASTM, other governmental agencies, or other recognized organizations mean those officially adopted and in current use by the agency or organization on the date of Advertisement.

If there are conflicting references, or if no reference is made to materials specifications, sampling and testing frequencies, or test method, the Engineer will resolve any discrepancies between these documents in the following orders of precedence:

Field-Tested Materials:

- Contract Change Orders;
- Special Provisions;
- ODOT *Laboratory Manual of Test Procedures*;
- MFTP; and
- Standard Specifications.

Nonfield-Tested Materials:

- Contract Change Orders;
- Special Provisions;
- ODOT *Laboratory Manual of Test Procedures*; and
- Standard Specifications.

Material test methods:

- ODOT;
- WAQTC;
- AASHTO;
- ASTM;
- Other recognized national organizations, such as ANSI, AWWA, IMSA, ISSA, and UL; and
- Industry standards in the location where the Work is being performed.

Sampling and testing frequencies:

- Contract Change Orders;
- Special Provisions;
- MFTP; and
- Standard Specifications.

If the Contractor identifies conflicting references or if no reference is made, the Contractor shall immediately request a clarification from the Engineer.

00165.30 Field-Tested Materials:**(a) Contractor's Duties** - The Contractor shall:

- Furnish Materials of the quality specified in the Contract;
- Provide and administer a quality control program as described in the Quality Assurance Program portion of the MFTP. Upon request, the Contractor shall provide to the Engineer the names, telephone numbers, and copies of certifications for all personnel performing field testing; and
- Perform other testing as required by the Contract.

(b) Types of Tests - The types of tests and testing methods generally required by ODOT are described in the MFTP.**(c) Acceptance of Field-Tested Materials** - The Contractor's test results for field-tested Materials will be verified by the Agency according to the Quality Assurance program outlined in the MFTP. If the Agency's QA test results verify the Contractor's results, the Materials will be analyzed for acceptance according to one of the following methods before the Engineer will accept them for incorporation into the Work:

- Statistically, according to 00165.40, to determine "Pay Factors" for produced Aggregate;
- Statistically, according to 00165.40, to determine "Composite Pay Factors" for mixtures; or
- Other methods determined by the Engineer.

If the Agency's verification test results do not verify the Contractor's test results, the Agency may require additional testing to determine whether the Materials meet Specifications. The Contractor shall perform additional testing or provide samples to the Agency for testing as directed. If the Materials do not meet Specifications, the Contractor shall reimburse the Agency for the cost of the additional testing, which may be deducted from monies due or to become due the Contractor under the Contract. Incorporated Materials that do not meet Specifications will be evaluated according to 00165.01 and 00150.25. If the Materials meet Specifications, the Agency will pay the cost for the additional testing.

00165.35 Nonfield-Tested Materials - The Contractor shall furnish Materials meeting Specifications, along with all Materials Conformance and Quality Compliance Documents.**(a) Test Results Certificate** - The certificate shall:

- Be from the manufacturer, verifying that the Material furnished has been sampled and tested and the test results meet the Specifications.
- Include, or be accompanied by, a copy of the specified test results (ODOT, AASHTO, ASTM, UL or other).
- Identify the testing agency and the representative responsible for the test results.
- Permit positive determination that Material delivered to the Project is the same Material covered by the test results.
- Be delivered to the Engineer with the shipment of the material.

(b) Quality Compliance Certificate - The certificate shall be from the manufacturer and shall:

- Verify that the Material meets the Specifications, and identify by number the specified test methods used, (ODOT, AASHTO, ASTM, UL, or other)

- Permit positive determination that Material delivered to the Project is the same Material covered by the certificate,
- Be delivered to the Engineer with the shipment of the Material, or be an identification plate or mark, decal, sticker, label, or tag attached to the container or Material,

(c) Equipment List and Drawings - These consist of lists of proposed Equipment and Materials, such as:

- Shop drawings
- Material lists
- Equipment lists
- Catalog description sheets
- Manufacturer's brochures

Submit these lists to the Engineer for review of conformance with the Specifications.

(d) Certificate of Origin of Steel Materials - When specified, complete this document (ODOT Form 734-2126) as required by 00160.20 for Federal-aid projects.

Materials will be subject to acceptance testing if the Engineer so elects. The Engineer may reject damaged or non-specification materials regardless of the Materials Conformance Documents furnished.

00165.40 Statistical Analysis - When 00165.30(c) or 00165.50 applies, the Contractor shall divide the Materials into lots and sublots, randomly sample and test them as required, and analyze the results statistically to determine whether the Materials conform to the Specifications.

All acceptance test results of lots and sublots will be analyzed collectively using the Quality Level Analysis procedure set out in this Subsection. This procedure shall not be used for a lot with less than three sublots. Sampling of Material for a lot that contains two or fewer sublots shall be increased to obtain at least three sublots. The Engineer has discretion to either accept or reject lots originating with two or fewer sublots, even after sampling is increased.

(a) Lot - A lot is the quantity of Materials produced by a single process or JMF that is sampled, tested, and statistically evaluated, as specified in this Subsection.

(b) Sublot - A sublot is a portion of a lot, for which a sample test value may be normally obtained.

(c) Quality Level Analysis - Quality Level Analysis is a statistical procedure to determine, for each lot:

- The percentage of each constituent of the Materials meeting Specifications;
- The Pay Factor for each constituent; and
- The Composite Pay Factor, when specified.

(d) Pay Factor and Composite Pay Factor Computation - Procedures for determining the percent meeting Specifications, Pay Factors, and Composite Pay Factor for a lot of Materials are as follows:

- (1) Compute lot arithmetic mean (\bar{X}) for each constituent:

$$\bar{X} = \frac{\sum X}{n}$$

Where $\sum X$ = summation of sample test values
 n = total number of samples

- (2) Compute standard deviation (sd) for each constituent:

$$sd = \sqrt{\frac{\sum X^2 - n\bar{X}^2}{n-1}}$$

Where $\sum X^2$ = summation of the squares of each sample test value
 \bar{X}^2 = square of the lot arithmetic mean

- (3) Compute the upper quality index (Q_U) for each constituent:

$$Q_U = \frac{USL - \bar{X}}{sd}$$

Where USL (upper specification limit) is the target value plus allowable tolerance

- (4) Compute the lower quality index (Q_L) for each constituent:

$$Q_L = \frac{\bar{X} - LSL}{sd}$$

Where LSL (lower specification limit) is the target value minus allowable tolerance

- (5) From Table 00165-1, for each constituent, determine the percent within the upper specification limit (P_U) which corresponds to a given Q_U . If USL is 100% or is not specified, P_U will be 100.

- (6) From Table 00165-1, for each constituent, determine the percent within the lower specification limit (P_L) which corresponds to a given Q_L . If LSL is 0 or not specified, P_L will be 100.

- (7) Compute the quality level, or total percent within Specification limits (P_T), for each constituent:

$$P_T = (P_U + P_L) - 100$$

- (8) Using the P_T from Step 7, determine the Pay Factor (PF) from Table 00165-2 for each constituent tested. A minimum PF of 1.00 will be used when all subplot test values are within the upper and lower Specification limits, regardless of the calculated PF.

(9) Compute the Weighted Pay Factor (WPF) for each constituent:

$$\text{WPF} = (\text{PF}) \times (f_i)$$

Where f_i = weighting factor listed in the Specifications for each constituent tested.

(10) Compute the Composite Pay Factor (CPF) for the lot and report the results to three decimal places.

$$\text{CPF} = \frac{\sum \text{WPF}}{\sum f_i}$$

Where $\sum \text{WPF}$ = sum of the weighted pay factors for each constituent

$\sum f_i$ = sum of the weighting factors listed in the Specifications

Table 00165-1

QUALITY LEVEL ANALYSIS BY THE STANDARD DEVIATION METHOD								
P _U or P _L PERCENT WITHIN LIMITS FOR POSITIVE VALUES OF Q _U or Q _L	UPPER QUALITY INDEX Q _U OR LOWER QUALITY INDEX Q _L							
	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9	n = 10 to n = 11
100	1.16	1.50	1.79	2.03	2.23	2.39	2.53	2.65
99	-	1.47	1.67	1.80	1.89	1.95	2.00	2.04
98	1.15	1.44	1.60	1.70	1.76	1.81	1.84	1.86
97	-	1.41	1.54	1.62	1.67	1.70	1.72	1.74
96	1.14	1.38	1.49	1.55	1.59	1.61	1.63	1.65
95	-	1.35	1.44	1.49	1.52	1.54	1.55	1.56
94	1.13	1.32	1.39	1.43	1.46	1.47	1.48	1.49
93	-	1.29	1.35	1.38	1.40	1.41	1.42	1.43
92	1.12	1.26	1.31	1.33	1.35	1.36	1.36	1.37
91	1.11	1.23	1.27	1.29	1.30	1.30	1.31	1.31
90	1.10	1.20	1.23	1.24	1.25	1.25	1.26	1.26
89	1.09	1.17	1.19	1.20	1.20	1.21	1.21	1.21
88	1.07	1.14	1.15	1.16	1.16	1.16	1.16	1.17
87	1.06	1.11	1.12	1.12	1.12	1.12	1.12	1.12
86	1.04	1.08	1.08	1.08	1.08	1.08	1.08	1.08
85	1.03	1.05	1.05	1.04	1.04	1.04	1.04	1.04
84	1.01	1.02	1.01	1.01	1.00	1.00	1.00	1.00
83	1.00	0.99	0.98	0.97	0.97	0.96	0.96	0.96
82	0.97	0.96	0.95	0.94	0.93	0.93	0.93	0.92
81	0.96	0.93	0.91	0.90	0.90	0.89	0.89	0.89
80	0.93	0.90	0.88	0.87	0.86	0.86	0.86	0.85
79	0.91	0.87	0.85	0.84	0.83	0.82	0.82	0.82
78	0.89	0.84	0.82	0.80	0.80	0.79	0.79	0.79
77	0.87	0.81	0.78	0.77	0.76	0.76	0.76	0.75
76	0.84	0.78	0.75	0.74	0.73	0.73	0.72	0.72
75	0.82	0.75	0.72	0.71	0.70	0.70	0.69	0.69
74	0.79	0.72	0.69	0.68	0.67	0.66	0.66	0.66
73	0.76	0.69	0.66	0.65	0.64	0.63	0.63	0.62
72	0.74	0.66	0.63	0.62	0.61	0.60	0.60	0.59
71	0.71	0.63	0.60	0.59	0.58	0.57	0.57	0.57
70	0.68	0.60	0.57	0.56	0.55	0.55	0.54	0.54
69	0.65	0.57	0.54	0.53	0.52	0.52	0.51	0.51
68	0.62	0.54	0.51	0.50	0.49	0.49	0.48	0.48
67	0.59	0.51	0.47	0.47	0.46	0.46	0.46	0.45
66	0.56	0.48	0.45	0.44	0.44	0.43	0.43	0.43
65	0.52	0.45	0.43	0.41	0.41	0.40	0.40	0.40
64	0.49	0.42	0.40	0.39	0.38	0.38	0.37	0.37
63	0.46	0.39	0.37	0.36	0.35	0.35	0.35	0.34
62	0.43	0.36	0.34	0.33	0.32	0.32	0.32	0.32
61	0.39	0.33	0.31	0.30	0.30	0.29	0.29	0.29
60	0.36	0.30	0.28	0.27	0.27	0.27	0.26	0.26
59	0.32	0.27	0.25	0.25	0.25	0.24	0.24	0.24
58	0.29	0.24	0.23	0.22	0.21	0.21	0.21	0.21
57	0.25	0.21	0.20	0.19	0.19	0.19	0.18	0.18
56	0.22	0.18	0.17	0.16	0.16	0.16	0.16	0.16
55	0.18	0.15	0.14	0.14	0.13	0.13	0.13	0.13
54	0.14	0.12	0.11	0.11	0.11	0.11	0.10	0.10
53	0.11	0.09	0.08	0.08	0.08	0.08	0.08	0.08
52	0.07	0.06	0.06	0.05	0.05	0.05	0.05	0.05
51	0.04	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

NOTE: For negative values of Q_U or Q_L, P_U or P_L is equal to 100 minus the table value for P_U or P_L. If the value of Q_U or Q_L does not correspond exactly to a figure in the table, use the next higher figure.

Table 00165-1

QUALITY LEVEL ANALYSIS BY THE STANDARD DEVIATION METHOD							
P _U or P _L PERCENT WITHIN LIMITS FOR POSITIVE VALUES OF Q _U OR Q _L	UPPER QUALITY INDEX Q _U OR LOWER QUALITY INDEX Q _L						
	n = 12 to n = 14	n = 15 To n = 18	n = 19 to n = 25	n = 26 to n = 37	n = 38 to n = 69	n = 70 to n = 200	n = 201 to n = ∞
100	2.83	3.03	3.20	3.38	3.54	3.70	3.83
99	2.09	2.14	2.18	2.22	2.26	2.29	2.31
98	1.91	1.93	1.96	1.99	2.01	2.03	2.05
97	1.77	1.79	1.81	1.83	1.85	1.86	1.87
96	1.67	1.68	1.70	1.71	1.73	1.74	1.75
95	1.58	1.59	1.61	1.62	1.63	1.63	1.64
94	1.50	1.51	1.52	1.53	1.54	1.55	1.55
93	1.44	1.44	1.45	1.46	1.46	1.47	1.47
92	1.37	1.38	1.39	1.39	1.40	1.40	1.40
91	1.32	1.32	1.33	1.33	1.33	1.34	1.34
90	1.26	1.27	1.27	1.27	1.28	1.28	1.28
89	1.21	1.22	1.22	1.22	1.22	1.22	1.23
88	1.17	1.17	1.17	1.17	1.17	1.17	1.17
87	1.12	1.12	1.12	1.12	1.12	1.13	1.13
86	1.08	1.08	1.08	1.08	1.08	1.08	1.08
85	1.04	1.04	1.04	1.04	1.04	1.04	1.04
84	1.00	1.00	1.00	1.00	0.99	0.99	0.99
83	0.96	0.96	0.96	0.96	0.95	0.95	0.95
82	0.92	0.92	0.92	0.92	0.92	0.92	0.92
81	0.88	0.88	0.88	0.88	0.88	0.88	0.88
80	0.85	0.85	0.85	0.84	0.84	0.84	0.84
79	0.81	0.81	0.81	0.81	0.81	0.81	0.81
78	0.78	0.78	0.78	0.78	0.77	0.77	0.77
77	0.75	0.75	0.75	0.74	0.74	0.74	0.74
76	0.71	0.71	0.71	0.71	0.71	0.71	0.71
75	0.68	0.68	0.68	0.68	0.68	0.68	0.67
74	0.65	0.65	0.65	0.65	0.65	0.64	0.64
73	0.62	0.62	0.62	0.62	0.62	0.61	0.61
72	0.59	0.59	0.59	0.59	0.59	0.58	0.58
71	0.56	0.56	0.56	0.56	0.56	0.55	0.55
70	0.53	0.53	0.53	0.53	0.53	0.53	0.52
69	0.50	0.50	0.50	0.50	0.50	0.50	0.50
68	0.48	0.48	0.47	0.47	0.47	0.47	0.47
67	0.45	0.45	0.45	0.44	0.44	0.44	0.44
66	0.42	0.42	0.42	0.42	0.41	0.41	0.41
65	0.39	0.39	0.39	0.39	0.39	0.39	0.39
64	0.37	0.37	0.36	0.36	0.36	0.36	0.36
63	0.34	0.34	0.34	0.34	0.33	0.33	0.33
62	0.31	0.31	0.31	0.31	0.31	0.31	0.31
61	0.29	0.29	0.28	0.28	0.28	0.28	0.28
60	0.26	0.26	0.26	0.26	0.26	0.25	0.25
59	0.23	0.23	0.23	0.23	0.23	0.23	0.23
58	0.21	0.21	0.20	0.20	0.20	0.20	0.20
57	0.18	0.18	0.18	0.18	0.18	0.18	0.18
56	0.15	0.15	0.15	0.15	0.15	0.15	0.15
55	0.13	0.13	0.13	0.13	0.13	0.13	0.13
54	0.10	0.10	0.10	0.10	0.10	0.10	0.10
53	0.08	0.08	0.08	0.08	0.08	0.08	0.08
52	0.05	0.05	0.05	0.05	0.05	0.05	0.05
51	0.03	0.03	0.03	0.03	0.03	0.03	0.02
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00

NOTE: For negative values of Q_U or Q_L, P_U or P_L is equal to 100 minus the table value for P_U or P_L. If the value of Q_U or Q_L does not correspond exactly to a figure in the table, use the next higher figure.

Table 00165-2

	REQUIRED QUALITY LEVEL FOR A GIVEN SAMPLE SIZE (n) AND A GIVEN PAY FACTOR							
PAY FACTOR	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9	n = 10 to n = 11
1.05	100	100	100	100	100	100	100	100
1.04	90	91	92	93	93	93	94	94
1.03	80	85	87	88	89	90	91	91
1.02	75	80	83	85	86	87	88	88
1.01	71	77	80	82	84	85	85	86
1.00	68	74	78	80	81	82	83	84
0.99	66	72	75	77	79	80	81	82
0.98	64	70	73	75	77	78	79	80
0.97	62	68	71	74	75	77	78	78
0.96	60	66	69	72	73	75	76	77
0.95	59	64	68	70	72	73	74	75
0.94	57	63	66	68	70	72	73	74
0.93	56	61	65	67	69	70	71	72
0.92	55	60	63	65	67	69	70	71
0.91	53	58	62	64	66	67	68	69
0.90	52	57	60	63	64	66	67	68
0.89	51	55	59	61	63	64	66	67
0.88	50	54	57	60	62	63	64	65
0.87	48	53	56	58	60	62	63	64
0.86	47	51	55	57	59	60	62	63
0.85	46	50	53	56	58	59	60	61
0.84	45	49	52	55	56	58	59	60
0.83	44	48	51	53	55	57	58	59
0.82	42	46	50	52	54	55	57	58
0.81	41	45	48	51	53	54	56	57
0.80	40	44	47	50	52	53	54	55
0.79	38	43	46	48	50	52	53	54
0.78	37	41	45	47	49	51	52	53
0.77	36	40	43	46	48	50	51	52
0.76	34	39	42	45	47	48	50	51
0.75	33	38	41	44	46	47	49	50
REJECT	QUALITY LEVELS LESS THAN THOSE SPECIFIED FOR A 0.75							

NOTE: If the computed QUALITY LEVEL does not correspond exactly to a figure in the table, use the next lower value.

Table 00165-2

	REQUIRED QUALITY LEVEL FOR A GIVEN SAMPLE SIZE (n) AND A GIVEN PAY FACTOR						
PAY FACTOR	n = 12 to n = 14	n = 15 to n = 18	n = 19 to n = 25	n = 26 to n = 37	n = 38 to n = 69	n = 70 to n = 200	n = 201 to n = ∞
1.05	100	100	100	100	100	100	100
1.04	95	95	96	96	97	97	99
1.03	92	93	93	94	95	95	97
1.02	89	90	91	92	93	94	95
1.01	87	88	89	90	91	93	94
1.00	85	86	87	89	90	91	93
0.99	83	85	86	87	88	90	92
0.98	81	83	84	85	87	88	90
0.97	80	81	83	84	85	87	89
0.96	78	80	81	83	84	86	88
0.95	77	78	80	81	83	85	87
0.94	75	77	78	80	81	83	86
0.93	74	75	77	78	80	82	84
0.92	72	74	75	77	79	81	83
0.91	71	73	74	76	78	80	82
0.90	70	71	73	75	76	79	81
0.89	68	70	72	73	75	77	80
0.88	67	69	70	72	74	76	79
0.87	66	67	69	71	73	75	78
0.86	64	66	68	70	72	74	77
0.85	63	65	67	69	71	73	76
0.84	62	64	65	67	69	72	75
0.83	61	63	64	66	68	71	74
0.82	60	61	63	65	67	70	72
0.81	58	60	62	64	66	69	71
0.80	57	59	61	63	65	67	70
0.79	56	58	60	62	64	66	69
0.78	55	57	59	61	63	65	68
0.77	52	56	57	60	62	64	67
0.76	51	55	56	58	61	63	66
0.75	51	53	55	57	59	62	65
REJECT	QUALITY LEVELS LESS THAN THOSE SPECIFIED FOR A 0.75						

NOTE: If the computed QUALITY LEVEL does not correspond exactly to a figure in the table, use the next lower value.

00165.50 Statistical Acceptance Sampling and Testing - The Contractor shall sample and test Materials for acceptance, as required by the Contract. The Contractor may statistically evaluate test results for purposes of quality control or to predict a Pay Factor or Composite Pay Factor. The following apply:

(a) Statistical Acceptance - The Engineer will perform statistical analysis according to 00165.40 for acceptance and to determine a Pay Factor (PF) or Composite Pay Factor (CPF). The Engineer's determination of the PF or CPF shall be controlling.

(b) Pay Adjustments - As an incentive to produce quality Materials, the Engineer's acceptance will be based upon the following:

(1) Specification Materials - For Materials accepted by a PF, when all constituents of a Material have a PF of 1.00 or greater, that Material will be considered specification Materials. For Materials accepted by a CPF, all Materials with a CPF of 1.0000 or greater will be considered specification Materials. Materials with a CPF greater than 1.0000, when specified, may earn a CPF adjustment of greater than 1.0000, up to a maximum of 1.0500.

(2) Non-specification Materials - For Materials accepted by a PF, when any constituent of a Material has a PF of less than 1.00, that Material will be considered non-specification Material. For Materials accepted by a CPF, all Materials with a CPF less than 1.0000 will be considered non-specification Materials. A lot containing non-specification Materials will be evaluated as described in 00165.50(c).

(c) Non-specification Materials:

(1) Isolation of a Partial Sublot - The Engineer may isolate from a sublot or adjoining sublots any Material that the Contractor's test results show to be non-specification. The Contractor shall perform additional testing or provide samples to the Agency as directed. The Engineer will accept or reject the Material according to 00150.25.

(2) Isolation of an Entire Sublot - The Engineer may isolate a sublot or a series of sublots in which the Contractor's test results show the Material to be non-specification. The Contractor shall perform additional testing or provide samples to the Agency as directed. The isolated Material will be evaluated as a separate lot. The Engineer will accept or reject the Material according to 00150.25.

(3) A Lot-in-Progress - The Contractor shall shut down production when any of the following occurs:

- The CPF for a lot-in-progress drops below 1.0000, and the Contractor is taking no corrective action;
- The CPF is less than 0.7500; or
- Any constituent test is continually out of Specification limits, regardless of whether or not the CPF is below 0.7500.

The Contractor shall not resume production until the Engineer has determined that Specification Materials can be produced, and has given approval to resume.

(4) An Entire Lot - The Engineer may reject an entire lot of Materials with a CPF between 0.7500 and 1.0000, or may take action according to 00150.25.

For a lot of Material with a CPF below 0.7500, the Engineer will take one or more of the following actions:

a. Remain in Place - Allow Materials to remain in place with an appropriate price reduction that may range from 25% to 100% (no payment);

b. Corrective Work - Require corrective work, at the Contractor's expense, with an appropriate price reduction that may range from zero (full payment) to 100% (no payment); or

c. Remove and Replace - Require complete removal and replacement with Specification Materials. No payment will be made for the rejected Materials, the cost of removal, or for the costs of sampling and testing.

00165.70 Use of Materials without Acceptable Materials Conformance Documents:

(a) General - The Contractor shall not incorporate Materials into the Project prior to submittal of Materials Conformance Documents acceptable to the Engineer. The Engineer may waive this requirement temporarily if Materials are necessary for immediate traffic safety.

(b) Materials Incorporated for Immediate Traffic Safety - If Materials are incorporated into the Project for immediate traffic safety before acceptable Materials Conformance Documents are available, no payment will be made for the value of the Materials, or the costs of incorporating them, until Materials Conformance Documents have been submitted to and approved by the Engineer, or the Materials are otherwise found through testing to comply with Specifications.

(c) Contractor's Request for Testing Assistance - If acceptable Materials Conformance Documents are not available, the Contractor may either have the necessary tests performed at a private laboratory or request in writing that the Engineer:

- Determine if the Agency or its agents can sample and test;
- Estimate the cost to the Contractor for the testing service; and
- Estimate the time required to obtain the test results.

The Engineer will provide this information to the Contractor in writing. If the Contractor requests the Engineer, in writing, to proceed, the Engineer will arrange for the sampling and testing, at the Contractor's expense. If these tests determine the Material complies with the Specifications, the Materials may be incorporated into the Project, or for Materials previously incorporated according to (b) above, payment will be authorized.

00165.75 Storage and Handling of Materials - The Contractor shall store and handle Materials so as to preserve their quality and fitness for incorporation into the Work. The Contractor shall restore all storage sites to their original condition according to 00140.90, or to comply with any applicable permits, orders, or agreements, at the Contractor's expense.

Stored Materials:

- Shall be readily accessible for inspection;
- May be stored on approved parts of the Right-of-Way; and
- May be stored on private property if written permission of the owner or lessor is obtained.

Measurement

00165.80 Measurement - No separate measurement will be made of Work performed under this Section.

Payment

00165.90 Incidental Basis - No separate or additional payment will be made for sampling, testing, certification, or other associated Work performed under this Section, whether performed by the Contractor, manufacturer, producer or Supplier. No payment will be made for providing quality control personnel.

00165.91 Fabrication Inspection Expense - Fabrication of certain items outside of the State creates additional shop and plant inspection expense to the Agency. It is impractical, and extremely difficult, to determine the actual additional expenses incurred. Therefore, each time that inspection by or on behalf of the Agency is necessary, payment to the Contractor will be reduced by an amount computed at the following rates:

Zone	Place of Fabrication	Reduction in Payment
1	All of State of Oregon, and those portions of adjacent states within 50 airline miles of the Oregon border	\$0
2	Outside of Zone 1, and up to 300 airline miles from the Oregon border	\$200 per Calendar Day
3	Outside of Zone 2, up to 3,000 airline miles from the Oregon border, and within the continental United States.	Round trip coach airfare from Portland, Oregon plus \$200 per Calendar Day
4	Outside of Zone 3, or outside of the continental United States.	Round trip coach airfare from Portland, Oregon plus \$250 per Calendar Day

Calendar Day charges begin on the first day the Agency's Inspector begins travel to begin work at the fabrication site, and continue without interruption through the final day of travel back to the State. The Contractor will be notified in writing of the beginning and ending dates of the Calendar Days used in computing payment reduction.

This Subsection applies to all fabricated items or manufactured Materials that are inspected by or on behalf of the Agency, which include, but are not limited to:

- Structural steel fabrication;
- Prestressed concrete members;
- Precast concrete;
- Signs;
- Preservative treatment of wood products;
- Epoxy coating of reinforcing steel; and
- Other items specifically identified in the Specifications as requiring fabrication site or in-plant inspection by the Agency.

Section 00170 - Legal Relations and Responsibilities

Description

00170.00 General - The Contractor shall comply with all laws, ordinances, codes, regulations and rules (collectively referred to as "Laws" in this Section) that relate to the Work or to those engaged in the Work. Where the provisions of the Contract are inconsistent or in conflict, the Contractor shall comply with the more stringent standard.

The Contractor shall indemnify, defend, and hold harmless the Agency and its representatives from liability arising from or related to the violation of Laws by those engaged in any phase of the Work. This provision does not apply to Work performed by Agency employees.

In any litigation, the entire text of any order or permit issued by a governmental or regulatory authority, as well as any documents referenced or incorporated therein by reference, shall be admissible for the purpose of Contract interpretation.

The characterization of provisions of the Contract as material provisions or the failure to comply with certain provisions as a material breach of the Contract shall in no way be construed to mean that any other provisions of the Contract are not material or that failure to comply with any other provisions is not a material breach of the Contract.

All rights and remedies available to the Agency under applicable Laws are incorporated herein by reference and are cumulative with all rights and remedies under the Contract.

The Contract shall not be construed against either party regardless of which party drafted it. Other than as modified by the Contract, the applicable rules of contract construction and evidence shall apply. This Contract shall be governed by and construed and enforced according to the laws of the State of Oregon without regard to principles of conflict of laws.

Any dispute between the Agency and the Contractor that arises from or relates to this Contract and that is not resolved under the provisions of Section 00199 shall be brought and conducted solely and exclusively within the Circuit Court for the State of Oregon in the county where the Agency's main office is located; provided, however, if a dispute must be brought in a federal forum, then it shall be brought and conducted solely and exclusively within the United States District Court for the District of Oregon. In no event shall this Subsection be construed as a waiver by the State of Oregon on any form of defense or immunity, whether sovereign immunity, governmental immunity, immunity based on the Eleventh Amendment to the Constitution of the United States, or otherwise, from any claim or from the jurisdiction of any court. CONTRACTOR BY EXECUTION OF THE CONTRACT HEREBY CONSENTS TO THE IN PERSONAM JURISDICTION OF THE COURTS REFERENCED IN THIS SECTION.

It is the Agency's intention to make all payments due under the Contract if funds are legally available for such purpose. The Agency reasonably believes that at the time of entering into the Contract sufficient funds are available and authorized for expenditure to finance the cost of the Contract within the Agency's appropriation or limitation, or other funding sources. Agency's payment of amounts under the Contract is contingent on the Agency receiving adequate appropriations, limitations or other expenditure authority or funds to allow the Agency to continue to make payments under the Contract. In the event the Agency becomes aware that sufficient funds are not available and authorized, the Agency will provide prompt written notice to the Contractor, and the Agency may terminate the Contract as provided in 00180.90(c).

Provisions and Requirements

00170.01 Other Agencies Affecting Agency Contracts - Representatives of regulatory bodies or units of government whose Laws may apply to the Work shall have access to the Work according to 00150.20(d). These may include but are not limited to those in the following (a), (b), (c), and (d).

(a) Federal Agencies:

Agriculture, Department of
 Forest Service
 Natural Resource Conservation Service
Army, Department of the
 Corps of Engineers
Commerce, Department of
 National Marine Fisheries Service
Defense, Department of
Energy, Department of
Environmental Protection Agency
Federal Energy Regulatory Commission
Geology Survey
Health and Human Services, Department of
Homeland Security, Department of
 U.S. Coast Guard
Housing and Urban Development, Department of
Interior, Department of
 Heritage, Conservation, and Recreation Service
 Bureau of Indian Affairs
 Bureau of Land Management
 Bureau of Mines
 Bureau of Reclamation
 Geological Survey
 Minerals Management Service
 Office of Surface Mining, Reclamation, and Enforcement
Minerals Management Service
National Oceanic and Atmospheric Administration
Solar Energy and Energy Conservation Bank
U.S. Fish and Wildlife Service
Labor, Department of
 Mine Safety and Health Administration
 Occupational Safety and Health Administration
Transportation, Department of
 Federal Highway Administration
Water Resources Council

(b) State of Oregon Agencies:

Administrative Services, Department of

Agriculture, Department of
 Natural Resources Division
 Soil and Water Conservation District
 Columbia River Gorge Commission
 Consumer and Business Services, Department of
 Insurance Division
 Oregon Occupational Safety and Health Division
 Energy, Office of
 Environmental Quality, Department of
 Fish and Wildlife, Department of
 Forestry, Department of
 Geology and Mineral Industries, Department of
 Human Resources, Department of
 Labor and Industries, Bureau of
 Land Conservation and Development Department
 Parks and Recreation, Department of
 State Lands, Department of
 Water Resources Department

(c) Local Agencies:

City Councils
 County Courts
 County Commissioners, Boards of
 Design Commissions
 Historical Preservation Commissions
 Lane Regional Air Pollution Authority
 Planning Commissions
 Port Districts
 Special Districts

(d) Oregon Federally Recognized Tribal Governments:

Burns Paiute Tribe
 Confederated Tribes of Coos, Lower Umpqua and Siuslaw Indians
 Confederated Tribes of Grand Ronde
 Confederated Tribes of Siletz
 Confederated Tribes of Umatilla Indian Reservation
 Confederated Tribes of Warm Springs
 Coquille Tribe
 Cow Creek Band of Umpqua Indians
 Klamath Tribe

00170.02 Permits, Licenses, and Taxes - As required to accomplish the Work, the Contractor shall do the following:

- Obtain all necessary permits and licenses, except for those noted in 00170.03;
- Pay all applicable charges, fees and taxes, except for those noted in 00170.03;
- Give all notices required by applicable Laws, or under the terms of the Contract;
- Comply with ORS 274.530 relating to lease of stream beds by Oregon Division of State Lands;
- License, in the State of Oregon, all vehicles subject to licensing;
- Comply with ORS 477.625 and ORS 527.670 relating to clearing and fire hazards on forest lands; and
- Comply with all orders and permits issued by a governmental authority, whether local, State, or federal.

00170.03 Furnishing Right-of-Way and Permits - Unless required to be obtained in the name of the Contractor, the Agency will obtain and pay for the following when they are required by the applicable Laws or by Plans or Specifications:

- All necessary Rights-of-Way;
- Permits required for crossing or encroaching upon navigable streams;
- Permits required for removing materials from or depositing materials in waterways;
- Permits required for operating in Agency-controlled source of Materials or disposal area;
- System development fees charged by local units of government;
- Building construction permits, not including specialty work such as heating, ventilation, air conditioning, or electrical;
- Cost of referencing and replacing endangered survey monuments; and
- Environmental permits, including erosion control permits.

00170.04 Patents, Copyrights, and Trademarks - Prior to use of designs, devices, materials, or processes protected by patent, copyright, or trademark, the Contractor shall obtain from the Entity entitled to enforce the patent, copyright, or trademark all necessary evidence of Contractor's legal right to use such design, device, material, or process.

The Contractor shall indemnify, defend and hold harmless the Agency and all third parties and political subdivisions having a possessory or ownership interest or regulatory authority over the Project or Project Site from claims of patent, copyright or trademark infringement, and from costs, expenses and damages the Contractor or Agency may be obligated to pay as a result of such infringement during or after completing the Work.

00170.05 Assignment of Antitrust Rights - The Contractor irrevocably assigns to the Agency any claim for relief or cause of action the Contractor acquires during the term of the Contract, or which may accrue thereafter, by reason of any violation of:

- Title 15 (Commerce and Trade), United States Code;
- ORS 646.725; or
- ORS 646.730.

In connection with this assignment, it is an express obligation of the Contractor to take no action that would in any way impair or diminish the value of the rights assigned to the Agency according to the provisions of this Subsection. Further, it is the express obligation of the Contractor to take all action

necessary to preserve the rights assigned. It is an express obligation of the Contractor to advise the Agency's legal counsel:

- In advance, of its intention to commence any action involving such claims for relief or causes of action;
- Immediately upon becoming aware of the fact that an action involving such claims for relief or causes of action has been commenced by some other person or persons;
- Of the date on which it notified the obligor(s) of any such claims for relief or causes of action of the fact of the Contractor's assignment to the Agency according to the provisions of this Subsection; and
- Immediately upon the discovery of any such antitrust claim for relief or cause of action.

In the event any payment is made to the Contractor under any such claims for relief, the Contractor shall promptly pay the full sum over to the Agency. In the event the Contractor fails to make such payment, the Agency may deduct the amount from monies due or to become due the Contractor under the Contract.

00170.07 Record Requirements - For purposes of this Subsection, the term "Contractor" includes the Contractor, all Subcontractors, Material Suppliers, and providers of rented operated Equipment (except non-DBE truck drivers), at all tiers, for all subcontracts with first-tier Subcontractors, all subcontracts between the first-tier Subcontractors and their Subcontractors and any other lower-tier subcontracts, and "Related Entities" as that term is defined in OAR 734-010-0400. The Material Suppliers included in this definition are those for Aggregates, asphalt cement concrete, portland cement concrete and the supply and fabrication of structural steel items, and Material Suppliers that provide quotes.

(a) Records Required - The Contractor shall maintain all records, whether created before or after execution of the Contract, or during Contract performance, or after Contract completion, to clearly document:

- The Contractor's performance of the Contract or a subcontract;
- The Contractor's ability to continue performance of the Contract or a subcontract; and
- All claims arising from or relating to performance under the Contract or a subcontract.

These records shall include all records, including fiscal records, regardless of when created for the Contractor's business. The records for the Contractor's business include, without limitation:

- Bidding estimates and records, worksheets, tabulations or similar documents.
- Job cost detail reports, including monthly totals.
- Payroll records (including, without limitation, the ledger or register, and tax forms) and all documents that establish the periods, individuals involved, the hours for the individuals, and the rates for the individuals.
- Records that identify the Equipment used by the Contractor and Subcontractors in the performance of the Contract or subcontracts, including, without limitation, Equipment lists, rental contracts and any records used in setting rental rates.
- Invoices from vendors, rental agencies, and Subcontractors.
- Material quotes, invoices, purchase orders and requisitions.
- Contracts with Subcontractors and contracts with Material Suppliers, Suppliers and providers of rented equipment.
- Contracts or documents of other arrangements with any Related Entity as defined in OAR 734-010-0400.

- General ledger.
- Trial Balance.
- Financial statements (including, without limitation, the balance sheet, income statement, statement of cash flows, and financial statement notes).
- Income tax returns.
- All worksheets used to prepare bids or claims, or to establish the cost components for the Pay Items, including, without limitation, the labor, benefits and insurance, Materials, Equipment, and Subcontractors.

The following are examples, but not an exhaustive list, of records that would be included, if generated by the Contractor. If the Contractor generates such records, or equivalent records, they are included among the records subject to 00170.07.

- Daily time sheets and supervisors' daily reports.
- Collective bargaining agreements.
- Earnings records.
- Journal entries and supporting schedules.
- Insurance, welfare, and benefits records.
- Material cost distribution worksheet.
- Subcontractors' and lower-tier Subcontractors' payment certificates.
- Payroll and vendor's cancelled checks.
- Cash disbursements journal.
- All documents related to each and every claim together with all documents that support the amount of damages as to each claim.
- Additional financial statements (including, without limitation, the balance sheet, income statement, statement of cash flows, and financial notes) preceding the execution of the Contract and following final payment of the Contract.
- Depreciation records on all business Equipment maintained by the business involved, its accountant, or other Entity. (If a source other than depreciation records is used to develop cost for the Contractor's internal purposes in establishing the actual cost of owning and operating Equipment, all such other source documents.)

The Contractor shall maintain all fiscal records in material compliance with generally accepted accounting principles, or other accounting principles that are accepted accounting principles and practices for the subject industry and adequate for the nature of the Contractor's business, and in such a manner that providing a complete copy is neither unreasonably time-consuming nor unreasonably burdensome for the Contractor or the Agency. Failure to maintain the records in this manner shall not be an excuse for not providing the records.

The Contractor shall include in its subcontracts, purchase orders, and all other written agreements, a provision requiring all Subcontractors, Material Suppliers and providers of rented operated Equipment (except non-DBE truck drivers), at all tiers, to comply with 00170.07. The Contractor shall also require all Subcontractors, Material Suppliers, and providers of rented operated Equipment (except non-DBE truck drivers), at all tiers, and Related Entities to include in their contracts, purchase orders, and all other written agreements, a provision requiring all lower-tier Subcontractors, Material Suppliers and providers of rented operated Equipment (except non-DBE truck drivers) to comply with 00170.07. The Material Suppliers to which this applies are those for Aggregates, asphalt cement concrete, portland cement concrete and the supply and fabrication of

structural steel items and Material Suppliers that provide Material quotes and Related Entities as defined in OAR 734-010-0400.

(b) Access to Records - The Contractor shall provide the Engineer access to or a copy of all Contractor records upon request. A Project Manager's authority to request or access records is subject to OAR 734-010-0400(9). During the record retention period the Engineer, employees of the Agency, representatives of the Agency, or representatives of regulatory bodies or units of government may:

- Inspect, examine and copy or be provided a copy of all Contractor records;
- Audit the records, a Contract or the performance of a Contract;
- Inspect, examine and audit the records when, in the Agency's sole discretion, the records may be helpful in the resolution of any claim, litigation, administrative proceeding or controversy arising out of or related to a Contract.

Reasons for access to audit, inspect, examine and copy records include without limitation, general auditing, reviewing claims, checking for collusive bidding, reviewing or checking payment of required wages, performance and contract compliance, workplace safety compliance, evaluating Related Entities, environmental compliance, and qualifications for performance of the Contract, including the ability to perform and the integrity of the Contractor.

Where such records are stored in a computer or in other digital media, the Engineer may request, and the Contractor shall provide, a copy of the data files and such other information or access to software to allow the Engineer review of the records.

Nothing in 00170.07 is intended to operate as a waiver of the confidentiality of any communications privileged under the Oregon Evidence Code. Nothing in 00170.07 limits the records or documents that can be obtained by legal process.

(c) Record Retention Period - The Contractor shall maintain the records and keep the records accessible and available at reasonable times and places for at least 3 years from the date of final payment under the Contract, or until the conclusion of all audits, litigation, administrative proceedings, disputes and claims arising out of or related to the Contract, whichever date is later.

(d) Public Records Requests - If records provided under this section contain any information that may be considered exempt from disclosure as a trade secret under either ORS 192.345(2) or ORS 646.461(4), or under other grounds specified in Oregon Public Records Law, ORS 192.311 through ORS 192.478, the Contractor shall clearly designate on or with the records the portions which the Contractor claims are exempt from disclosure, along with a justification and citation to the authority relied upon. Entire records or documents should not be designated as a trade secret or otherwise exempt from disclosure. Only specific information within a record or document should be so designated.

To the extent allowed by the Oregon Public Records Law or other applicable law related to the disclosure of public records, the Agency will not disclose records or portions of records the Contractor has designated as trade secrets to a third party, who is not a representative of the Agency, to the extent the records are exempt from disclosure as trade secrets under the Oregon Public Records Law or other applicable law, except to the extent the Agency is ordered to disclose in accordance with the Oregon Public Records Law or by a court of competent jurisdiction. Application of the Oregon Public Records Law or other applicable law shall determine whether any record, document or information is actually exempt from disclosure.

In addition, in response to a public records request, the Agency will not produce or disclose records so identified as exempt by the Contractor to any person other than representatives of the Agency,

and others with authorized access under 00170.07(b), without providing the Contractor a copy of the public records request, unless:

- The Contractor consents to such disclosure; or
- The Agency is prohibited by applicable law or court order from providing a copy of the public records request to the Contractor.

00170.10 Required Payments by Contractors - The Contractor shall comply with ORS 279C.505 and ORS 279C.515 during the term of the Contract.

(a) Prompt Payment by Contractor for Labor and Materials - As required by ORS 279C.505, the Contractor shall:

- Make payment promptly, as due, to all Entities supplying labor or Materials under the Contract;
- Pay all contributions or amounts due the Industrial Accident Fund, whether from the Contractor or a Subcontractor, incurred in the performance of the Contract;
- Not permit any lien or claim to be filed against the State or any political subdivision thereof, on account of any labor or Material furnished in performance of the Contract; and
- Pay to the Department of Revenue all sums withheld from employees according to ORS 316.167.

(b) Prompt Payment by Contractor to First-Tier Subcontractor(s) - According to ORS 279C.580(3)(a), after the Contractor has determined and certified to the Agency that one or more of its Subcontractors has satisfactorily performed subcontracted Work, the Contractor may request payment from the Agency for the Work, and shall pay the Subcontractor(s) within 10 Calendar Days out of such amounts as the Agency has paid to the Contractor for the subcontracted Work.

(c) Interest on Unpaid Amount - If the Contractor or a first-tier Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract within 30 Days after the Contractor's receipt of payment, the Contractor or first-tier Subcontractor shall owe the Entity the amount due plus interest charges that begin at the end of the 10 day period within which payment is due under ORS 279C.580(3) and that end upon final payment, unless payment is subject to a good-faith dispute as defined in ORS 279C.580(5)(b). As required by ORS 279C.515(2), the rate of interest on the amount due shall be 9 percent per annum. The amount of interest shall not be waived.

(d) Agency's Payment of the Contractor's Prompt Payment Obligations - If the Contractor fails, neglects or refuses to make prompt payment of any invoice or other demand for payment for labor or services furnished to the Contractor or a Subcontractor by any Entity in connection with the Contract as such payment becomes due, the Agency may pay the Entity furnishing the labor or services and charge the amount of the payment against monies due or to become due the Contractor under the Contract. (The Agency has no obligation to pay these Entities, and the Agency will not normally do so, but will refer them to the Contractor and the Contractor's Surety.)

The payment of a claim by the Agency in the manner authorized in this Subsection shall not relieve the Contractor or the Contractor's Surety from obligations with respect to any such claims.

(e) Right to Complain to the Construction Contractors Board - If the Contractor or a Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract, the Entity may file a complaint with the Construction Contractors Board, unless payment is subject to a good-faith dispute as defined in ORS 279C.580(5)(b).

(f) Notice of Claim Against Bond - An Entity (which by definition includes a natural person) claiming not to have been paid in full for labor or Materials supplied for the prosecution of the Work may have a right of action on the Contractor's Payment Bond as provided in ORS 279C.600 and ORS 279C.605.

The Commissioner of the Bureau of Labor and Industries (BOLI) may have a right of action on the Contractor's and Subcontractors' public works bonds and Payment Bonds for workers who have not been paid in full, as provided in ORS 279C.600 and ORS 279C.605.

(g) Paid Summary Report - The Contractor shall submit a "Paid Summary Report", form 734-2882, to the Engineer certifying payments made to all of the following:

- All Subcontractors
- Committed DBE suppliers
- Non-committed DBE suppliers and service providers with estimated total payments for the Project over \$10,000.

For this purpose, a committed DBE firm is one that was identified by the Contractor to meet an assigned DBE goal including DBE firms substituting for DBE firms committed as a condition of Contract Award.

Submit the completed and signed Paid Summary Report to the Engineer within 20 Calendar Days of receipt of payment from the Agency for each month in which payments were made to each Subcontractor, each committed DBE Supplier, and each non-committed DBE Supplier or service provider with estimated total payments for the Project over \$10,000. At the completion of the Project, submit form 734-2882 recapping the total amounts paid to each Subcontractor, each committed DBE Supplier, and each non committed DBE Supplier or service provider with estimated total payments for the Project over \$10,000.

The Contractor shall require each Subcontractor at every tier to comply with the requirement to submit form 734-2882 within 20 Calendar Days of receipt of payment from its controlling contractor and provide a recap of the total amounts paid at the completion of the Project or completion of their Work.

Forms shall be submitted to an email address provided to the Contractor at the preconstruction conference.

00170.20 Public Works Bond - Before starting Work, the Contractor and Subcontractors shall each file with the Construction Contractors Board, and maintain in full force and effect, a separate public works bond, in the amount of \$30,000 unless otherwise exempt, as required by ORS 279C.830(2) and ORS 279C.836. The Contractor shall verify Subcontractors have filed a public works bond before the Subcontractor begins Work.

00170.32 Protection of Navigable Waters - The Contractor shall comply with all applicable Laws, including, without limitation, the Federal River and Harbor Act of March 3, 1899 and its amendments.

The Contractor shall not interfere with waterway navigation or impair navigable depths or clearances, except as U.S. Coast Guard or Corps of Engineer permits allow.

00170.60 Safety, Health, and Sanitation Provisions - The Contractor shall comply with all Laws concerning safety, health, and sanitation standards. The Contractor shall not require workers to perform Work under conditions that are hazardous, dangerous, or unsanitary.

Workers exposed to traffic shall wear upper body garments or safety vests that are highly visible and meet the requirements of 00221.20.

Workers exposed to falling or flying objects or electrical shock shall wear hard hats.

Upon their presentation of proper credentials, the Contractor shall allow inspectors of the U.S. Occupational Safety and Health Administration (OSHA) and the Oregon Occupational Safety and Health Division (OR-OSHA) to inspect the Work and Project Site without delay and without an inspection warrant.

According to ORS 468A.715 and ORS 468A.720, the Contractor or a Subcontractor who performs Project Work involving asbestos abatement shall possess a valid DEQ asbestos abatement license.

00170.61 Industrial Accident Protection:

(a) Workers' Compensation - The Contractor shall provide workers' compensation coverage for on-the-job injuries as required by 00170.70(d).

(b) Longshoremen's and Harbor Workers' Compensation - If Work to be performed is over or adjacent to navigable waters, the Longshoremen's and Harbor Workers' Compensation Act, (Chapter 18, Title 33 of the USC) may apply, and the Contractor shall be responsible for complying with its provisions (which may include the provision of additional workers' compensation benefits to employees).

00170.62 Labor Nondiscrimination - The Contractor shall comply with all Laws concerning equal employment opportunity, including, without limitation, those prohibiting discrimination because of race, religion, color, sex, disability, or national origin.

It is a material term of this Contract that the Contractor certifies by entering into this Contract that the Contractor has a written policy and practice that meets the requirements described in ORS 279A.112 (House Bill 3060, 2017) for preventing sexual harassment, sexual assault and discrimination against employees who are members of a protected class and that the Contractor shall maintain the policy and practice in force during the entire term of this Contract.

00170.63 Payment for Medical Care - According to ORS 279C.530, the Contractor shall promptly, as due, make payment to any person, copartnership, association or corporation furnishing medical, surgical and hospital care services or other needed care and attention, incident to sickness or injury, to the employees of the Contractor, of all sums that the Contractor agrees to pay for the services and all moneys and sums that the Contractor has collected or deducted from the wages of employees under any law, contract or agreement for the purpose of providing or paying for the services.

00170.65 Minimum Wage and Overtime Rates for Public Works Projects:

(a) General - The Contractor is responsible for investigating local labor conditions. The Agency does not imply that labor can be obtained at the minimum hourly wage rates specified in State or federal wage rate publications, and no increase in the Contract Amount will be made if wage rates paid are more than those listed.

As required by ORS 279C.520, the Contractor shall comply with ORS 652.220 and shall not unlawfully discriminate against any of the Contractor's employees in the payment of wages or other compensation for work of comparable character on the basis of an employee's membership in a protected class. "Protected class" means a group of persons distinguished by race, color, religion, sex, sexual orientation, national origin, marital status, veteran status, disability, or age. The Contractor's compliance with this provision constitutes a material element of the Contract and failure to comply constitutes a material breach that entitles the Agency to exercise any remedies available under the Contract, including, but not limited to, termination for default.

As required by ORS 279C.520, the Contractor shall not prohibit any of the Contractor's employees from discussing the employee's rate of wage, salary, benefits or other compensation with another employee or another person and shall not retaliate against an employee who discusses the employee's rate of wage, salary, benefits or other compensation with another employee or another person.

(b) State Prevailing Wage Requirements - The Contractor shall comply with the prevailing wage provisions of ORS 279C.800 through ORS 279C.870.

(1) Minimum Wage Rates - The Bureau of Labor and Industries (BOLI) determines and publishes the existing State prevailing wage rates in the publication *Prevailing Wage Rates for Public Works Contracts in Oregon*. The Contractor shall pay workers not less than the specified minimum hourly wage rate according to ORS 279C.838 and ORS 279C.840, and shall include this requirement in all subcontracts.

See the Project Wage Rates page included with the Contract Documents for additional information about which wage rates apply to the Project and how to access the applicable wage rates.

The applicable BOLI wage rates will be included in the Contract.

(2) Payroll and Certified Statements - As required in ORS 279C.845, the Contractor and every Subcontractor shall submit written certified statements to the Engineer on the form prescribed by the Commissioner of BOLI in OAR 839-025-0010 certifying compliance with wage payment requirements and accurately setting out the Contractor's or Subcontractor's weekly payroll records for each worker employed on the Project.

The Contractor and Subcontractors shall preserve the certified statements for a period of 6 years from the date of completion of the Contract.

(3) Additional Retainage:

a. Agency - As required in ORS 279C.845(7) the Agency will retain 25% of any amount earned by the Contractor on the Project until the Contractor has filed the certified statements required in ORS 279C.845 and in FHWA Form 1273, if applicable. The Agency will pay to the Contractor the amount retained within 14 Days after the Contractor files the required certified statements, regardless of whether a Subcontractor has failed to file certified statements.

b. Contractor - As required in ORS 279C.845(8) the Contractor shall retain 25% of any amount earned by a first-tier Subcontractor on the Project until the first-tier Subcontractor has filed with the Agency the certified statements required in ORS 279C.845 and in FHWA Form 1273, if applicable. Before paying any amount retained, the Contractor shall verify that the first-tier Subcontractor has filed the certified statement. Within 14 Days after the first-tier Subcontractor files the required certified statement, the Contractor shall pay the first-tier Subcontractor any amount retained.

(4) Owner/Operator Data - The Contractor shall furnish data to the Engineer for each owner/operator providing trucking services. Furnish the data before the time the services are performed and include without limitation for each owner/operator:

- Driver's name;
- Copy of driver license;
- Vehicle identification number;
- Copy of vehicle registration;

- Motor vehicle license plate number;
- Motor Carrier account number;
- Copy of ODOT Motor Carrier 1A Permit; and
- Name of owner/operator from the side of the truck.

(c) State Overtime Requirements - As a condition of the Contract, the Contractor shall comply with the pertinent provisions of ORS 279C.520 and ORS 279C.540.

(1) Maximum Hours of Labor and Overtime Pay - According to ORS 279C.540, no person shall be employed to perform Work under this Contract for more than 10 hours in any 1 Day, or 40 hours in any 1 week, except in cases of necessity, emergency, or where public policy absolutely requires it. In such instances, the Contractor shall pay the employee at least time and a half pay:

- For all overtime in excess of 8 hours a day or 40 hours in any 1 week when the work week is 5 consecutive days, Monday through Friday; or
- For all overtime in excess of 10 hours a day or 40 hours in any 1 week when the work week is 4 consecutive days, Monday through Friday; and
- For all Work performed on Saturday and on any legal holiday specified in ORS 279C.540.

For additional information on requirements for overtime and establishing a work schedule see OAR 839-025-0050 and OAR 839-025-0034.

(2) Notice of Hours of Labor - The Contractor shall give written notice to employees of the number of hours per day and days per week the employees may be required to work. Provide the notice either at the time of hire or before commencement of work on this Contract, or by posting a notice in a location frequented by employees.

(3) Exception - The maximum hours of labor and overtime requirements under ORS 279C.540 will not apply to the Contractor's Work under this Contract if the Contractor is a party to a collective bargaining agreement in effect with any labor organization. For a collective bargaining agreement to be in effect it shall be enforceable within the geographic area of the Project, and its terms shall extend to workers who are working on the Project (see OAR 839-025-0054).

(d) State Time Limitation on Claim for Overtime - According to ORS 279C.545, any worker employed by the Contractor is foreclosed from the right to collect any overtime provided in ORS 279C.540 unless a claim for payment is filed with the Contractor within 90 Days from the completion of the Contract, provided the Contractor posted and maintained a circular as specified in this provision. Accordingly, the Contractor shall:

- Cause a circular, clearly printed in boldfaced 12-point type and containing a copy of ORS 279C.545, to be posted in a prominent place alongside the door of the timekeeper's office or in a similar place that is readily available and freely visible to any or all workers employed to perform Work; and
- Maintain such circular continuously posted from the inception to the completion of the Contract on which workers are or have been employed.

(e) Additional Requirements When Federal Funds are Involved - When federal funds are involved, the following requirements shall apply in addition to the requirements of 00170.65(a) through 00170.65(d). The Contractor shall include these provisions in all subcontracts as well as ensure that all Subcontractors include these provisions in their lower-tier subcontracts.

(1) FHWA Requirements - For Federal-aid projects, the Contractor shall comply with the provisions of FHWA Form 1273, *Required Contract Provisions Federal-aid*

Construction Contracts.

(2) Minimum Wage Rates - The Contractor shall pay each worker in each trade or occupation employed to perform any work under the Contract not less than the existing State (BOLI) prevailing wage rate or the applicable federal prevailing wage rate required under the Davis-Bacon Act (40 U.S.C. 3141 et seq.), whichever is higher. The Contractor shall include this provision in all subcontracts.

See the Project Wage Rates page included with the Contract Documents for additional information about which wage rates apply to the Project and how to access the applicable wage rates.

The applicable Davis-Bacon and BOLI wage rates will be included in the Contract.

(3) Payroll and Certified Statements - In addition to providing the payroll information and certified statements required under ORS 279C.845 (see 00170.65(b)(2)), the Contractor and every Subcontractor shall submit written certified statements that also meet the requirements in Section IV of FHWA Form 1273, except the Contractor and every Subcontractor shall preserve the certified statements for a period of 6 years from the date of completion of the Contract.

(4) Overtime - With regard to overtime pay, the Contractor shall comply with the overtime provision affording the greatest compensation required under FHWA Form 1273 and ORS 279C.540.

00170.70 Insurance:

(a) Insurance Coverages -

Contractor - The Contractor shall obtain the insurance specified below prior to the execution of the Contract. The Contractor shall maintain the insurance in full force at the Contractor's expense throughout the duration of the Contract and all warranty periods that apply.

Subcontracting - If the Contractor specifies prior to the execution of the Contract that a Subcontractor will satisfy an insurance requirement, that is permitted to be satisfied by a Subcontractor, the Contractor shall obtain Agency approval of Subcontractor and Subcontractor's insurance coverage(s), as required by 00180.21, prior to commencement of Subcontracted work. After the Contractor receives Agency approval of the Subcontractor, the Contractor may contractually obligate the Subcontractor to obtain and maintain, at the Subcontractor's expense or at the Contractor's expense, the insurance permitted.

The Contractor shall require that all Subcontractors carry insurance coverage that the Contractor deems appropriate based on the risks of the subcontracted work. The Contractor shall obtain proof of the required insurance coverages, as applicable, from any Subcontractor providing Services related to the Contract.

Neither the insurance provided by Subcontractor(s) nor any agreements Contractor or Subcontractor(s) may enter into shall place any limitation on the liability or indemnification obligations of the Contractor under applicable law or the Contract.

Insurance Provisions - The Contractor and Subcontractor(s), if any, shall obtain insurance from insurance companies or entities that are authorized to transact the business of insurance and issue coverage in the State and that are acceptable to the Agency. Insurance coverage shall be primary and noncontributory with any other insurance and self-insurance, with the exception of Workers' Compensation. The Contractor, or appropriate Subcontractor, but not the Agency, shall pay for all deductibles, self-insurance retentions and self-insurance, if any.

- **Commercial General Liability** – The Contractor shall provide Commercial General Liability

Insurance written on an occurrence basis and covering the Contractor's liability for bodily injury and property damage. This insurance shall include personal and advertising injury liability, products and completed operations coverage, and contractual liability coverage. Coverage may be written in combination with Commercial Automobile Liability Insurance with separate limits for Commercial General Liability and Commercial Automobile Liability. Combined single limit per occurrence shall not be less than \$1,000,000. The annual aggregate limit shall not be less than \$2,000,000. The policy shall be endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.

When Work to be performed includes operations or activity within 50 feet of any railroad property, bridge, trestle, track, roadbed, tunnel, underpass or crossing, the Contractor shall provide the Contractual Liability – Railroads CG 24 17 endorsement, or equivalent, on the Commercial General Liability policy.

- **Commercial Automobile Liability** – The Contractor shall provide Commercial Automobile Liability Insurance covering all owned, non-owned, and hired vehicles for bodily injury and property damage. This coverage may be written in combination with the Commercial General Liability Insurance with separate limits for Commercial Automobile Liability and Commercial General Liability. Combined single limit per occurrence shall not be less than \$500,000. If this coverage is written in combination with the Commercial General Liability, the policy shall be endorsed to state that the Commercial General Liability annual aggregate limit shall apply separately to the Contract.
- **Pollution Liability** - If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing the pollution related Work, shall provide Pollution Liability Insurance written on an occurrence or claims made basis and covering the Contractor's or Subcontractor's liability, for bodily injury, property damage, and environmental damage resulting from sudden, accidental, and gradual pollution, and related clean-up costs. If the coverage is obtained by the Contractor, the coverage may be written in combination with the Commercial General Liability Insurance with separate limits for Pollution Liability and Commercial General Liability. Combined single limit per occurrence shall not be less than the dollar amount specified in the Special Provisions. The annual aggregate limit shall not be less than the dollar amount specified in the Special Provisions. The policy shall be endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.
- **Asbestos Liability** - If indicated by Special Provision, the Contractor, or Subcontractor, whichever is performing asbestos related Work, shall provide the Pollution Liability coverage with an Asbestos Liability endorsement. If an endorsement cannot be obtained, the Contractor or Subcontractor shall provide separate Asbestos Liability Insurance at the same combined single limit per occurrence and annual aggregate limit as the Pollution Liability Insurance with the policy endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.
- **Lead Liability** - If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing lead related Work, shall provide the Pollution Liability coverage with a Lead Liability endorsement. If an endorsement cannot be obtained, the Contractor or Subcontractor shall provide separate Lead Liability Insurance at the same combined single limit per occurrence and annual aggregate limit as the Pollution Liability Insurance with the separate policy endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.
- **Commercial Automobile Liability with Pollution Coverage** - If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing the pollution related

Work, shall provide Commercial Automobile Liability Insurance with Pollution coverage covering the Contractor's or Subcontractor's liability for bodily injury, property damage, natural resource damage, and environmental damage arising out of the use of all owned, non-owned, or hired vehicles while performing Work under the Contract. Combined single limit per occurrence shall not be less than the dollar amount specified in the Contract. If the coverage is obtained by the Contractor, the coverage may be written in combination with the Commercial General Liability Insurance with separate limits for Commercial Automobile Liability with Pollution Coverage and Commercial General Liability. If this coverage is written in combination with the Commercial General Liability, the policy shall be endorsed to state that the Commercial General Liability annual aggregate limit shall apply separately to the Contract.

- **Marine Insurance (watercraft)** - If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing watercraft related Work, entails the use of watercraft, including but not limited to barges, tug boats, work boats, and supply boats, shall provide the following insurance:
 - **Marine Liability Insurance** - For the performance of the Work that requires the use of any watercraft, whether owned, non-owned, leased, rented, or chartered by Contractor or any Subcontractors, Marine Liability insurance shall not be less than the dollar amount specified in the Special Provisions per occurrence for bodily injury and property damage. Such insurance shall also include coverage for collision liability, tower's liability, marine contractual liability, wreck/debris removal, and liability for seepage, pollution, containment and cleanup.
 - **Hull and Machinery Insurance** - Including collision liability, with sister-ship clause un-amended, with limits of liability at least equal to the full value of all vessels used in connection with performance of the Work required under this Contract and with navigational limitations adequate for the Contractor to perform the specified Work. Where vessels engage in towing operations, said insurance shall include full towers' liability with the sister-ship clause un-amended.
 - **Protection and Indemnity Insurance** - To be evidenced through a full entry with a Group P&I Club, including collision liability, towers' liability, marine contractual liability, tankermans' liability, and specialist operations. Alternatively, if a full entry in a Group P&I Club is not available or applicable, Protection and Indemnity Insurance coverage shall be evidenced on the SP-23 form or equivalent, including, by endorsement or otherwise, collision liability, tower's liability, specialist operations, and liability for seepage, pollution, containment and cleanup, with extensions for marine contractual liability, shall not be less than the dollar amount specified in the Special Provisions.
 - **Pollution Liability Insurance** - If pollution coverage is provided outside of a P&I Club entry or outside of Protection and Indemnity Insurance coverage evidenced on the SP-23 form or equivalent, the amount shall not be less than the dollar amount specified in the Special Provisions. Pollution liability coverage shall cover bodily injury, property damage, including cleanup costs and defense costs resulting from sudden and gradual pollution conditions of contaminants or pollutants into or upon the land, the atmosphere or any water course or body of water.

With respect to the aforementioned Hull & Machinery Insurance, Protection and Indemnity Insurance and Pollution Insurance, the policy or policies shall be endorsed as follows:

- Other than owner provisions of all policies shall be deleted with respect to the naming of Company as an Additional Assured/Insured;
- Delete any as owner clause and any other language, which limits or purports to limit the

- coverage afforded to an insured or an additional insured who is not a ship-owner, with coverage to be afforded to all additional insureds in any capacity in which they may be held liable; and
- Operator warrants that COFR's are on file with the U.S. Coast Guard as per Federal requirements.

If Subcontractor(s) are utilized to perform any Work that requires the use of watercraft under the Contract, all such Subcontractor(s) shall maintain insurance including limits, coverages, terms and conditions as required herein unless said Subcontractor(s) are insured by Contractor. Where Contractor provides coverage for a Subcontractor, the Contractor shall issue a Certificate of Insurance, along with related endorsement(s) required to effect coverage, evidencing Subcontractor's "Additional Insured/Assured" status under Contractor's coverage.

An Excess Marine Liability insurance policy may be used to meet the required limits of insurance. Excess coverage must follow form and be as broad as that provided by the underlying primary liability insurance policies.

ORS 15.320 provides Oregon law applies to the Contract. The parties also agree that Oregon law applies to the Contract, even if ORS 15.320 is determined to be inapplicable or invalid.

(b) Extended Reporting - If any of the required insurance is permitted to be and is on a "claims made" basis, the Contractor or Subcontractor who provided the insurance coverage, shall obtain an extended reporting period on the claims made policy or maintain the claims made policy, for a duration of at least 24 months from the date the applicable work has been completed and accepted by the Agency or the date of Final Acceptance. This extended reporting requirement shall be satisfied with documentation of one of the following:

- Extended Reporting Endorsement;
- Tail Coverage; or
- Maintaining the applicable continuous claims made policy with liability coverage.

The Contractor or Subcontractor shall furnish certification of this extended reporting requirement as a condition to receive Third Notice under 00150.90(b) and 00180.50(g).

(c) Excess/Umbrella Liability - A combination of primary and Excess/Umbrella Insurance may be used to meet the required limits of insurance. Excess/Umbrella coverage must be at least as broad as that provided by the underlying primary insurance policies. In addition, the limits of the underlying primary insurance must be sufficient to prevent any gap between such minimum limits and the attachment point of the coverage provided by the Excess/Umbrella Liability policy.

(d) Additional Insured - The liability insurance coverages of 00170.70(a) shall include an Additional Insured Endorsement specifying the "City of The Dalles and its respective officers, members, agents, and employees" as Additional Insureds, but only with respect to the Contractor's activities to be performed under the Contract. Coverage shall be primary and non-contributory with any other insurance and self-insurance. The liability coverages of 00170.70(a) that are permitted by the Agency to be obtained by an appropriate Subcontractor shall include all of the foregoing as Additional Insureds and shall also include the Contractor and its officers and employees as Additional Insureds.

Additional Insured Endorsements on the Commercial General Liability shall be written on ISO Form CG 20 10 07 04, or equivalent, with respect to liability arising out of ongoing operations and ISO Form CG 20 37 07 04, or equivalent, with respect to liability arising out of completed operations. Additional Insured Endorsements shall be submitted with the Certificate(s) of Insurance and must be acceptable to the Agency.

(e) Workers' Compensation - All employers, including the Contractor and Subcontractor(s), if any, that employ subject workers, as defined in ORS 656.027, shall comply with ORS 656.017 and shall provide Workers' Compensation Insurance coverage, unless such employers meet the requirement for an exemption under ORS 656.126(2). The coverage shall include Employer's Liability Insurance with limits not less than \$500,000 each accident.

The Contractor shall certify in the Contract that the Contractor is registered by the Oregon Workers' Compensation Division either as a carrier-insured employer, a self-insured employer, an exempt employer, or is an independent contractor who will perform the Work without the assistance of others.

The Contractor shall require and verify that its insurance carrier files a guaranty contract with the Oregon Workers' Compensation Division before performing any Work.

All employers, including the Contractor and Subcontractor(s), if any, exempt under ORS 656.126(2) and subject to any other state's Workers' Compensation law, shall provide Workers' Compensation Insurance coverage as required by applicable Workers' Compensation laws. The coverage shall also include Employer's Liability Insurance with limits not less than \$500,000 each accident.

If the Contractor's and Subcontractor's, if any, operations include use of watercraft on navigable waters and employ persons in applicable positions, a Maritime Coverage Endorsement must be added to the Workers' Compensation policy, unless coverage for captain and crew is provided in a Protection and Indemnity policy.

If the Contractor and Subcontractor, if any, conducts its operations in proximity to navigable waters and employ persons in applicable positions, United States Longshore and Harbor Workers' Compensation Act coverage must be endorsed onto the Workers' Compensation policy.

The Contractor shall require compliance with these requirements in all Subcontractor contracts.

(f) Notice of Cancellation or Change - The Contractor shall provide at least 30 Days' written notice to the Agency before cancellation of, material change to, potential exhaustion of aggregate limits, or non-renewal of the required insurance coverages. If a Subcontractor is providing insurance to meet the contract requirements, the Contractor shall provide at least 30 Days' written notice to the Agency before cancellation of, material change to, potential exhaustion of aggregate limits, or non-renewal of the required insurance coverage(s). Any failure to comply with the reporting provisions of this insurance shall not affect the coverage(s) provided to the State, Agency, County, City, or other applicable political jurisdiction or to the Agency's governing body, board, or Commission and its members, and the Agency's officers, agents, and employees.

(g) Certificate(s) of Insurance - As evidence of the insurance coverages required by the Contract, the Contractor shall furnish Certificate(s) of Insurance to the Agency at the time(s) provided in 00130.50(a). As evidence of insurance coverages required by the Contract but permitted by the Agency under 00170.70(a) to be obtained by an appropriate Subcontractor, the Contractor shall furnish Certificate(s) of Insurance to the Agency for such coverages together with the Contractor's request under 00180.21 for approval of the subcontract with that Subcontractor. The Certificate(s) shall:

- List the "City of The Dalles and its respective officers, members, agents and employees" as a Certificate holder and as an endorsed Additional Insured;
- Include all required endorsements or copies of the applicable policy language effecting coverage required by the Contract;
- Specify that all liability insurance coverages shall be primary and non-contributory with any other insurance and self-insurance, with exception of Workers' Compensation;

- Include a list of all policies that fall under the Excess/Umbrella Insurance if Excess or Umbrella Insurance is used to meet the minimum insurance requirement.

(h) Agency Acceptance - All insurance and insurance providers are subject to Agency acceptance. If requested by Agency, the Contractor shall provide complete copies of insurance policies, endorsements, self-insurance documents and related insurance documents to Agency's representatives responsible for verification of the insurance coverages required by the Contract.

(i) Insurance Requirement Review - The Contractor agrees to periodic review of insurance requirements by Agency under the Contract and to provide updated requirements as mutually agreed upon by the Contractor and Agency.

(j) Builder's Risk - If specified by Special Provision, the Contractor shall obtain, at its expense, and keep in effect during the term of the Contract, Builder's Risk Insurance on an all risks of direct physical loss basis, including, without limitation, earthquake and flood damage, for an amount equal to at least the value specified in the Special Provisions. The policy shall not contain a coinsurance clause or any collapse exclusions. Any deductible shall not exceed \$50,000 for each loss, except that the earthquake and flood deductible shall not exceed 5% of each loss or \$50,000, whichever is greater. The policy shall include the City of The Dalles as loss payee.

(k) Builder's Risk Installation Floater - The Contractor shall obtain, at its expense, and keep in effect during the term of the Contract, Builder's Risk Installation Floater Insurance covering the Contractor's labor, Materials and Equipment to be used for completion of the Work performed under the Contract. The minimum amount of coverage to be carried shall be equal to the full amount of the contractor's labor, equipment, materials, or fixtures to be installed, in-transit, or stored off-site during the performance of the Contract. This insurance shall include as loss payees the City of The Dalles, the Owner, the Contractor and Subcontractors as their interests may appear.

00170.71 Independent Contractor Status - The service or services to be rendered and the Work to be completed under this Contract are those of an independent contractor as defined in ORS 670.600. The Contractor is not an officer, employee, or agent of the Agency or the State as those terms are used in ORS 30.265.

00170.72 Indemnity/Hold Harmless - To the fullest extent permitted by law, and except to the extent otherwise void under ORS 30.140, the Contractor shall indemnify, defend (with counsel approved by the Agency) and hold harmless the Agency, Agency's Authorized Representative, Architect/Engineer, Architect/Engineer's consultants, and their respective officers, directors, agents, employees, partners, members, stockholders and affiliated companies (collectively "Indemnitees") from and against all liabilities, damages, losses, claims, expenses (including reasonable attorney fees), demands and actions of any nature whatsoever that arise out of, result from or are related to the following:

- Any damage, injury, loss, expense, inconvenience or delay described in this Subsection.
- Any accident or occurrence that happens or is alleged to have happened in or about the Project Site or any place where the Work is being performed, or in the vicinity of either, at any time prior to the time the Work is fully completed in all respects.
- Any failure of the Contractor to observe or perform any duty or obligation under the Contract Documents that is to be observed or performed by the Contractor, or any breach of any agreement, duty, obligation, responsibility, covenant, provision, requirement, representation or warranty of the Contractor contained in the Contract Documents or in any subcontract.
- The negligent acts or omissions of the Contractor, a Subcontractor or anyone directly or indirectly employed by them or any one of them or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss or expense is caused in part by a party indemnified hereunder.
- Any failure to comply with all applicable Laws by the Contractor or any Subcontractor, or anyone employed by any one of them, or anyone for whose acts they may be liable.

- Any lien filed upon the Project or bond claim in connection with the Work.

Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity which would otherwise exist as to a party or person described in this Subsection.

In claims against any person or Entity indemnified under this Subsection by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, the indemnification obligation under this Subsection shall not be limited by a limitation on amount or type of damages, compensation or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts or other employee benefit acts.

Notwithstanding the Contractor's foregoing defense obligations, neither the Contractor nor any attorney engaged by the Contractor shall defend any claim in the name of the Agency, nor purport to act as legal representative of the Agency or any of its agencies, without the prior written consent of the Agency's legal counsel, which in the case of the City of The Dalles its City Attorney. The Agency may, at any time at its election, assume its own defense and settlement in the event that it determines that the Contractor is prohibited from defending the Agency, or that the Contractor is not adequately defending the Agency's interests, or that an important governmental principle is at issue or that it is in the best interests of the Agency to do so. The Agency reserves all rights to pursue any claims it may have against the Contractor.

00170.74 Employee Drug Testing Program - As required by ORS 279C.505(2), the Contractor shall have in place, and maintain during the period of the Contract, an employee drug-testing program. The Agency retains the right to audit and/or monitor the program. On request by the Engineer, the Contractor shall furnish a copy of the employee drug-testing program.

00170.78 Conflict of Interest - The Contractor shall not give or offer any gift, loan, or other thing of value to any member of the Agency's governing body or employee of the Agency in connection with the award or performance of any Contract.

The Contractor shall not rent, lease, or purchase Materials, supplies, or Equipment, with or through any Agency employee or member of the Agency's governing body.

No ex-employee of the Agency who has worked for the Agency on any phase of the Project within the prior 2 years may be employed by the Contractor to perform Work on the Project.

The Contractor shall also be and remain in compliance with the Agency's Conflict of Interest Guidelines. (See 00120.40(g) and 00180.21(b).)

00170.79 Third Party Beneficiary - There are no third-party beneficiaries of the Contract.

00170.80 Responsibility for Damage to Work:

(a) Responsibility for Damage in General - The Contractor shall perform Work, and furnish Materials and Equipment for incorporation into the Work, at the Contractor's own risk, until the entire Project has been completed and accepted by the Agency. The Contractor shall repair all damages to Work performed, Materials supplied, and Equipment incorporated into the Work, except as otherwise provided in this Section.

(b) Repair of Damage to Work - Until Final Acceptance, the Contractor shall promptly rebuild, repair, restore, and make good damages to all portions of the permanent or temporary Work, except to the extent the Agency has assumed responsibility according to the provisions of (c) below. The Contractor shall perform all repairs of damage to Work at no additional cost to the Agency, except for repairs necessitated by damage caused by:

- Acts of God or Nature, as defined in Section 00110; or
- Actions of governmental authorities.

(c) Responsibility for Damage to Work Caused by Public Traffic - The Contractor may apply for relief of responsibility for damage to Work caused by Public Traffic by submitting a signed Contractor's Request for Relief of Responsibility to the Engineer by mail, personal delivery, courier, scanned and submitted via email, or other agreed-upon method.

The Engineer will process a maximum of two requests per month and return the requests within seven (7) Calendar Days indicating each item as "approved" or "denied".

The approval of the Engineer is limited, and is made only for the purposes of determining relief of responsibility for damage to completed portions of the Work caused by Public Traffic. The completed portions of the Work are not considered accepted, and are not finally accepted for any other purposes under the Contract until Final Acceptance.

If the Contractor disagrees with the Engineer's findings, the Contractor may request a Region level review according to 00199.40(b).

(1) Request for Relief - The Agency will only accept a request for relief from and will only assume responsibility for damages caused by Public Traffic, to the following completed portions of the Work:

- A segment of Roadway, drainage facilities, Slopes, lighting, traffic control devices and access facilities;
- A Bridge or other Structure within a segment of Roadway;
- Traffic signals and appurtenances at an intersection;
- Permanent, passive traffic control devices;
- Complete circuits of a highway lighting system; and
- Portions of a building open to public use.

The Agency will approve a request for the Agency to assume responsibility for damages to the completed portions of the Work caused by Public Traffic only under the following conditions:

- The completed portions of the Work are completed according to Contract Change Orders, the Plans or approved stage construction Plans;
- The traffic control complies with approved traffic control Plans; and
- All required Materials conformance and quality compliance documents pertaining to the completed portions of the Work are on file with the Engineer (see Section 00165).

(2) Scope of Relief - When the Agency assumes responsibility for damage to completed portions of the Work caused by Public Traffic, any damages will be repaired by the Contractor on a Changed Work basis, or by Agency forces, or by other means as determined by the Engineer. If completed portions of the Work are damaged by Public Traffic before Final Inspection, and the Agency requires the Contractor to repair the damages, the Engineer will reimburse the Contractor for the Changed Work at 75% of the total amount calculated according to Section 00197.

If completed portions of the Work are damaged by Public Traffic after Final Inspection, and the Agency requires the Contractor to repair the damages, the Engineer will reimburse the Contractor for the Work at 100% of the total amount calculated according to Section 00197.

If any additional Work is performed by the Contractor on completed portions of the Work for which the Agency has assumed responsibility for damages caused by Public Traffic, and the Work is performed outside of the approved stage construction Plans or approved traffic control Plans, the Contractor shall become fully responsible and liable, and shall make good all damages caused by Public Traffic at no additional cost to the Agency.

(d) Vandalism and Theft - Vandalism includes damage to or destruction of Work or portions of Work that remain on the Project Site resulting from vandalism, criminal mischief, arson, or other criminal or illegal behavior.

The Contractor shall provide reasonable protection of the Work from vandalism until Third Notification. If reasonable protection has been provided, the Contractor's responsibility for damage resulting from vandalism will be limited to \$5,000.00 per occurrence. Requests for reimbursement of amounts in excess of \$5,000.00 shall be in writing and directed to the Engineer. Upon receipt, the Engineer will investigate, evaluate the amount of damages and their cause, determine the number of occurrences, and determine whether, and how much, the Contractor will be compensated.

Theft includes the loss of Work or portions of Work that are lost or stolen or otherwise unaccounted for from the Project Site or from Materials or fabrication locations. The Contractor shall remain solely responsible for all losses caused by theft, including, without limitation, theft that occurs in conjunction with vandalism.

00170.82 Responsibility for Damage to Property and Facilities:

(a) In General - As used in this Subsection, the term "Contractor" shall include the Contractor's agents, Subcontractors, and all workers performing Work under the Contract; and the term "damage" shall include without limitation soiling or staining surfaces by tracking or splashing mud, asphalt, and other materials, as well as damage of a more serious nature.

The Contractor shall be solely responsible for damages arising from:

- The Contractor's operations;
- The Contractor's negligence, gross negligence, or intentional wrongful acts; and
- The Contractor's failure to comply with any Contract provision.

The Agency may withhold funds due the Contractor or the Contractor's Surety until all lawsuits, actions, and claims for injuries or damages are resolved, and satisfactory evidence of resolution is furnished to the Agency.

(b) Protection and Restoration of Agency Property and Facilities - The following requirements apply to Highways, Highway Structures and other improvements that are existing, under construction, or completed. The Contractor shall:

- Provide adequate protection to avoid damaging Agency property and facilities;
- Be responsible for damage to Agency property and facilities caused by or resulting from the Contractor's operations; and
- Clean up and restore such damage by repair, rebuilding, replacement, or compensation, as determined by the Engineer.

(c) Protection and Restoration of Non-Agency Property and Facilities - The Contractor shall determine the location of properties and facilities that could be damaged by the Contractor's operations, and shall protect them from damage. The Contractor shall protect monuments and property marks until the Engineer has referenced their location and authorized their removal. The

Contractor shall restore property or facilities damaged by its operations to the condition that existed before the damage, at no additional compensation.

The Contractor shall provide temporary facilities when needed, (e.g., to maintain normal service or as directed by the Engineer), until the required repair, rebuilding, or replacement is accomplished.

The Contractor shall protect specific service signs, (e.g., business logos, and tourist-oriented directional signs (TODS)) from damage, whether the signs are to remain in place or be placed on temporary supports. The Contractor shall repair or replace damaged signs at no cost to the Agency. Liquidated damages will be assessed against the Contractor in the amount of \$200 per Day for each sign out of service for more than 5 Calendar Days because of the Contractor's operations.

00170.85 Responsibility for Defective Work - The Contractor shall make good any defective Work, Materials or Equipment incorporated into the Work, according to the provisions of Section 00150.

(a) Latent Defects - The Contractor shall remain liable for all latent defects resulting from causes other than fraud or gross mistakes that amount to fraud until the expiration of all applicable statutes of limitation and ultimate repose, the Performance Bond, Warranty Bond, or warranty period, whichever expires last. The Contractor shall remain liable for all latent defects resulting from fraud or gross mistakes that amount to fraud regardless of when those latent defects may be discovered, and regardless of whether such discovery occurs outside any applicable statutes of limitation or ultimate repose or any applicable Performance Bond, Warranty Bond, or warranty period.

(b) Contractor Furnished Warranties:

(1) Contractor Warranty for Specific Items - For those Items with Specifications referencing this 00170.85(b)(1) warranty, the Contractor warrants that the Work for those Items, including Changed Work, Additional Work, Incidental Work, On-Site Work, and Extra Work, and Materials and Equipment incorporated into the Work, shall meet the technical and performance Specifications required under the Contract. The warranty period will be identified in each applicable Specification or elsewhere in the Contract and will begin on the date of Second Notification. The Contractor shall be responsible for making good the Work, and for all repairs of damage to the Work and other improvements, natural and artificial structures, systems, equipment, and vegetation caused by, or resulting in whole or in part from, defects in warranted Materials, Equipment, and workmanship. The Contractor shall be responsible for all costs caused by, or resulting in whole or in part from, defects in warranted Materials, Equipment, or workmanship.

When the Agency makes written notification of failure of an item covered by this warranty, the warranty period will stop for the effected item or the portion of the effected item that failed, as applicable, until the required repairs or replacements are made and accepted. All repaired or replaced items shall meet current Specifications, unless otherwise specified in the Contract, and will be warranted for the remaining warranty period.

This warranty provision shall survive expiration or termination of the Contract.

(2) General Warranty for Local Agency Projects - For those Contracts that are developed, advertised, awarded, and administered by Local Agencies, and do not contain federal funding, this 00170.85(b)(2) warranty applies.

The Contractor shall warrant all Work and workmanship, including Changed Work, Additional Work, Incidental Work, On-Site Work, and Extra Work, and Materials and Equipment incorporated in the Work, for 1 year from the date of Second Notification, except that warranties according to 00170.85(b)(1) and manufacturers' warranties and extended warranties according to 00170.85(c) shall not be abridged.

The Contractor shall be responsible for meeting the technical and performance Specifications required, making good the Work, and for all repairs of damage to the Work and other improvements, natural and artificial structures, systems, equipment, and vegetation caused by, or resulting in whole or in part from, occurrences beginning during the warranty period and are the result of defects in Materials, Equipment, and workmanship. The Contractor shall be responsible for all costs associated with completing the repair of the defects and for associated Work including, but not limited to, permitting, mobilization, traffic control, erosion control, surface restoration, site cleanup and remediation caused by, or resulting in whole or in part from, defects in Materials, Equipment, or workmanship, and other Work determined by the Engineer to be necessary to complete the repair of the defects.

Within 10 Calendar Days of the Agency's written notice of defects, the Contractor, or the Contractor's Surety, shall vigorously and continuously correct and repair the defects and all related damage. If the Contractor or the Contractor's Surety fails to correct and repair the defects, the Agency may have the correction and repair done by others. The Contractor or Contractor's Surety shall promptly reimburse the Agency for all expenses incurred to correct and repair the defects.

In the event of an emergency, where delay could result in serious loss or damage, the Agency may make emergency corrections and repairs without written notice. The Contractor or Contractor's Surety shall promptly reimburse the Agency for all expenses incurred to correct and repair the defects.

Corrections, repairs, replacements or changes shall be warranted for an additional 1 year period beginning on the date of the Agency's acceptance of the corrections, repairs, replacements or changes.

Without limiting the general applicability of other survival clauses under the Contract, this warranty provision shall survive expiration or termination of the Contract.

(c) Manufacturer Warranties and Guarantees:

(1) Manufacturer Warranties - For those Specification Sections referencing 00170.85(c)(1), the Contractor shall furnish Warranties from the Manufacturer and signed by a Manufacturer's Representative.

The warranty period will be specified in the applicable Specification Section for which it applies.

The warranty period will begin on the date of Second Notification.

When the Agency makes written notification to the Manufacturer of failure of an item covered by this warranty, the warranty period will stop for the effected item or the portion of the effected item that failed, as applicable, until the required repairs or replacements are made and accepted. All repaired or replaced items shall meet current Specifications, unless otherwise specified in the Contract, and will be warranted for the remaining warranty period.

If, in the opinion of the Engineer, temporary repairs are necessary, the temporary repairs will be made by the Agency or an independent contractor at the Manufacturer's expense. The Manufacturer shall replace all temporary repairs at no additional cost to the Agency.

The Manufacturer shall provide all required traffic control during repair or replacement of failed items at no additional cost to the Agency.

Warranty work shall be performed when weather permits.

(2) Trade Practice Guarantees - For those Items installed on the Project that have customary

trade practice guarantees, the Contractor shall furnish the guarantees to the Engineer at the completion of the Contract.

00170.89 Protection of Utility, Fire-control, and Railroad Property and Services; Repair; Roadway Restoration:

(a) Protection of Utility, Fire-Control, and Railroad Property and Services; Coordination -

The Contractor shall avoid damaging the properties of Utilities, Railroads, railways, and fire-control authorities during performance of the Work. The Contractor shall cooperate with and facilitate the relocation or repair of all Utilities and Utility services, as required under 00150.50, and of Railroad and fire-control property and railways.

The Contractor shall conduct no activities of any kind around fire hydrants until the local fire-control authority has approved provisions for continued service.

The Contractor shall immediately notify any Utility, Railroad, or fire-control authority whose facilities have been damaged.

If an Entity has a valid permit from the proper authority to construct, reconstruct, or repair Utility, Railroad, or fire-control service in the Roadway, the Contractor shall allow the permit holder to perform the work.

(b) Restoration of Roadway after Repair Work - The Contractor shall restore the Roadway to a condition at least equal to that which existed before the repair work addressed under this Subsection was performed, as directed by the Engineer, at no additional cost to the Agency.

00170.92 Fencing, Protecting Stock, and Safeguarding Excavations - The Contractor shall be responsible for loss, injury, or damage that results from its failure to restrain stock and persons.

(a) At the Contractor's Expense - The Contractor shall restrain stock to lands on which they are confined using temporary fences or other adequate means. The Contractor shall provide adequate temporary fences or other protection around excavations to prevent animals and unauthorized persons from entering.

The Contractor shall repair, at Contractor's expense and to the Engineer's satisfaction, fences damaged by the Contractor's operations and the operations of the Contractor's agents, employees and Subcontractors.

(b) At the Agency's Expense - The Contractor shall construct fences, or move and reconstruct fences, as shown on the Contract Documents or as directed by the Engineer. The Contractor shall tear down and remove fencing within the Right-of-Way when no longer needed, as part of the removal Work described in and paid for according to Section 00310.

00170.93 Trespass - The Contractor shall be responsible for its own, its agents' and employees', and its Subcontractors' trespass or encroachment upon, or damage to, property during performance of the Contract.

00170.94 Use of Explosives - The Contractor shall comply with all Laws pertaining to the use of explosives. The Contractor shall notify anyone having facilities near the Contractor's operations of the Contractor's intended use or storage of explosives. The Contractor shall be responsible for all damage resulting from its own, its agents' and employees', and its Subcontractors' use of explosives. (See 00330.41(e) and Section 00335.)

Section 00180 - Prosecution and Progress

00180.00 Scope - This Section consists of requirements for assignment of the Contract, subcontracting, time for performance, Contract responsibility, suspensions, terminations, and related provisions.

00180.05 Assignment/Delegation of Contract - Unless the Agency gives prior written consent, which will not be unreasonably withheld, the Contractor shall not assign, delegate, sell, or otherwise transfer or dispose of any rights or obligations under the Contract, whether voluntarily or involuntarily, and whether by merger, consolidation, dissolution, operation of law, or any other manner, including, without limitation:

- The power to execute or duty to perform the Contract; or
- Any of its right, title or interest in the Contract.

Any purported or attempted assignment, delegation, sale, transfer or disposition without prior Agency consent shall be voidable.

If written Agency consent is given to assign, delegate, sell, or otherwise transfer or dispose of any rights or obligations under the Contract, such consent shall not relieve the Contractor or its Surety of any part of their duties, obligations, responsibilities, or liabilities under or pursuant to the Contract.

00180.06 Assignment of Funds Due under the Contract - Assignment of funds due or to become due under the Contract to the Contractor will not be permitted unless:

- The assignment request is made on the form provided by the Agency;
- The Contractor secures the written consent of the Contractor's Surety to the assignment; and
- The Engineer gives prior written consent to the assignment, which will not be unreasonably withheld.

00180.10 Responsibility for Contract - The Contractor shall direct and coordinate the operations of its employees, Subcontractors and agents performing Work, and see that the Engineer's orders are carried out promptly. The Contractor's failure to direct, supervise and control its employees, Subcontractors and agents performing Work will result in one or more of the following actions, as the Engineer deems appropriate:

- Suspension of the Work;
- Withholding of Contract payments, as necessary to protect the Agency;
- Ordering removal of individuals from the Project Site; or
- Termination of the Contract.

00180.15 Agency's Right to Do Work at Contractor's Expense - Except as otherwise provided in 00150.75 and 00220.60, if the Contractor neglects to prosecute the Work properly or fails to perform any provision of the Contract, the Agency may, after 2 Calendar Days' written notice, correct the deficiencies at the Contractor's expense. In situations where the Engineer reasonably believes there is danger to life or property, the Agency may immediately and without notice correct the deficiencies at the Contractor's expense.

Action by the Agency under this provision will not prejudice any other remedy it may have.

00180.20 Subcontracting Limitations:

(a) General - The Contractor's own organization shall perform Work amounting to at least 30% of the original Contract Amount. The value of subcontracted Work is the full compensation to be paid to the Subcontractor(s) for all pay items in the subcontract(s).

(b) Own Organization - The term "own organization", as used in Section 00180, includes only employees of the Contractor, Equipment owned or rented by the Contractor, Incidental rental of operated Equipment, truck hauling of Materials not included in or requiring a subcontract, and Materials and Equipment to be incorporated into the Work purchased or produced by the Contractor.

(c) Rental of Operated Equipment - The use of Equipment rented with operators, except truck hauling of materials which is addressed in 00180.20(e), will be allowed without a subcontract only when the following requirements are met:

(1) Written Request - The Contractor has submitted to the Engineer a written request describing the work or service to be provided, its estimated cost, and its estimated duration. The Engineer must approve the request before the work or service is provided.

(2) Limitations - The use of Equipment rented with operators is limited to performing minor, Incidental, short-duration work or services under the direct supervision of the Contractor or Subcontractor, with Equipment not customarily owned, rented, leased, or operated by a Contractor, or with Equipment that is temporarily unavailable to the Contractor.

(3) Submittals - The Contractor shall provide the Engineer with a copy of the rental agreement or purchase order covering the work or service to be provided. The Contractor shall make certain that the provider of approved work or services submits payrolls required under Section 00170 and complies with applicable Contract provisions, including, without limitation, 00170.07. The work or service provider will not be considered a Subcontractor under the Contract, but the work or services will be considered to have been performed by the Contractor's own organization for the purposes of determining compliance with 00180.20(a).

(4) Revocation of Approval - The Engineer may revoke approval for the work or services provided through rented, operated Equipment at any time the Engineer determines that the work is outside that authorized under 00180.20(c)(2). Unless the Contractor promptly submits to the Engineer a subcontract agreement for consent under 00180.21, the work or service provider shall be immediately removed from the Project Site.

(d) Disadvantaged Business Enterprise (DBE) - Every agreement to perform Work, including, without limitation, subcontracts, trucking services agreements, purchase orders, and rental agreements, shall indicate whether the Work will be performed by a DBE or non-DBE.

(e) Trucking - This Section does not apply to delivery of Materials by or for or from a Supplier. This Subsection applies to all truck hauling of Materials not performed with trucks owned (or rented) and operated by the Contractor. If the services under Rental of Operated Equipment or Trucking are provided by a committed DBE firm, a subcontract is required under 00180.21. For this purpose a committed DBE firm is one that was identified by the Contractor to meet an assigned DBE goal including DBE firms substituting for DBE firms committed as a condition of Contract Award.

(1) Trucking Services Agreement - The Contractor shall submit at the preconstruction conference one or more proposed trucking services agreements for all trucking services for hauling materials. The proposed agreements shall include:

- Statement specifying whether the services will be provided by a DBE;

- Statement specifying whether the services will be provided by an owner/operator;
- Prompt payment clause (10 days) (ORS 279C.580);
- Interest penalty clause (ORS 279C.580);
- Lower-tier clause (ORS 279C.580);
- Statement about the provider's ability to file a complaint with the Construction Contractors Board (ORS 279C.515);
- Statement that workers shall be paid not less than the specified minimum hourly rate of wage (ORS 279C.830) as applicable;
- Provision requiring the provider to have a public works bond filed with the Construction Contractors Board before starting work on the Project, unless exempt under ORS 279C.836(4) or (9), or has elected to not file a bond under ORS 279C.836(7) or (8), or is otherwise not applicable;
- Insurance clauses that include Commercial Automobile Liability and Workers Compensation (ORS 656.017 unless exempt under ORS 656.126);
- Provision requiring the provider to comply with applicable Contract provisions, including, without limitation, Record Requirements in 00170.07; and
- Construction Contractors Board License Number if applicable.

The Agency must review and consent to the proposed trucking services agreements prior to use.

(2) Limitations - The approved trucking services agreements shall be used for all trucking services for hauling Materials not provided by trucks owned (or rented) and operated by the Contractor except for trucking services provided by committed DBEs that require a subcontract under 00180.21. The Contractor shall execute a trucking services agreement with every trucking services provider for hauling Materials prior to the trucking services provider doing any Work on the Project Site.

(3) Submittals - The Contractor shall provide the Engineer with an executed copy of the trucking services agreement not later than 2 Days after the trucking services provider for hauling Materials has started work. The Contractor shall make certain that the provider of approved trucking services submits payrolls required under Section 00170, complies with applicable Contract provisions, including, without limitation, 00170.07, and complies with applicable trucking services agreement provisions. The work or service provider will not be considered a Subcontractor under the Contract, but the work or services will be considered to have been performed by the Contractor's own organization for the purposes of determining compliance with 00180.20(a). If the trucking services are provided by an owner/operator:

- Attach a copy of the data required under 00170.65(b)(4) to the trucking services agreement; and
- Each truck shall have the name of the owner/operator clearly displayed on the side of the truck.

(4) Revocation of Approval - The Engineer may revoke approval for trucking services provided under the trucking services agreement at any time the Engineer determines that the work or service is outside that authorized under 00180.20(e). Upon revocation of approval, the service provider shall be immediately removed from the Project Site.

00180.21 Subcontracting:

(a) General - The Contractor shall not subcontract or perform any portion of the Contract by other than the Contractor's own organization without the Agency's prior written consent. A request for consent to subcontract, at any tier, solely for the furnishing of a labor force will not be considered.

A written request for consent to subcontract any portion of the Contract at any tier shall be submitted to the Engineer, and when required by the Engineer, shall be accompanied by background information showing that the organization proposed to perform the Work is experienced and equipped for such Work. The Agency will review the Contractor's submission to verify compliance with Contract requirements, confirm the percentage of Work subcontracted, and evaluate the proposed Subcontractor's ability to perform the Work. If the Agency approves the Contractor's request to subcontract, the Agency will provide its consent to the Contractor's request as follows:

- If the Subcontractor is not providing any of the insurance coverages as permitted under 00170.70(a), the Agency will respond within 7 Calendar Days after the Engineer's receipt of the request.
- If the Subcontractor is providing any of the insurance coverages as permitted under 00170.70(a), the Agency will respond within 35 Calendar Days after the Engineer's receipt of the request. (28 Calendar Days for the Agency to review and approve the Certificates of Insurance required by 00170.70(f) plus 7 Calendar Days to review and approve the subcontract request.)

The Engineer may revoke consent to subcontract. If the Engineer revokes consent to subcontract, the Subcontractor shall be immediately removed from the Project Site.

(b) Submittal of Requests - The Contractor must submit requests for consent to subcontract any portion of the Contract, at any tier, on the Agency's form, available from the Engineer. The Contractor shall attach a duplicate original subcontract agreement. The Contractor must also submit in writing any amendments or modifications proposed to Agency-approved subcontract agreements, at any tier, before the affected Work begins. The Agency's written consent will be required before such amendments or modifications become effective.

The Contractor and proposed Subcontractors shall review the Agency's Conflict of Interest Guidelines, and if any disclosures are required, they shall complete the Conflict of Interest Disclosure Form(s) and submit them with the request for consent to subcontract. The City of The Dalles Conflict of Interest Guidelines and Conflict of Interest Disclosure Form are included in the Contract Documents.

If disclosures are not required under the Agency's Conflict of Interest Guidelines, no disclosures need be submitted.

The Subcontractors shall also otherwise be and remain in compliance with the Agency's Conflict of Interest Guidelines. (See 00170.78.)

(c) Substitution of Disclosed Subcontractors - The Contractor may only substitute a previously undisclosed first-tier Subcontractor according to the provisions of ORS 279C.585. The Contractor shall provide the Engineer with a written notification that identifies the name of the proposed new Subcontractor and the reason for the substitution. Authorized reasons for substitution are limited to the following circumstances (see ORS 279C.585(1) through ORS 279C.585(10)):

- The disclosed Subcontractor fails or refuses to execute a written contract that is reasonably based either upon the Project Plans and Specifications, or the terms of the Subcontractor's written Bid, after having had a reasonable opportunity to do so;

- The disclosed Subcontractor becomes bankrupt or insolvent;
- The disclosed Subcontractor fails or refuses to perform the contract;
- The disclosed Subcontractor fails or refuses to meet the bond requirements of the prime Contractor that had been identified prior to the Bid submittal;
- The Contractor demonstrates to the Agency that the Subcontractor was disclosed as the result of an inadvertent clerical error;
- The disclosed Subcontractor does not hold a license from the Construction Contractors Board and is required to be licensed by the board;
- The Contractor determines that the Work performed by the disclosed Subcontractor is not in substantial compliance with the Plans and Specifications, or that the Subcontractor is substantially delaying or disrupting the progress of the Work;
- The disclosed Subcontractor is ineligible to work on a public improvement according to the applicable statutory provisions;
- The substitution is for "good cause" as defined by State Construction Contractors Board rule; or
- The substitution is reasonably based on the Contract alternates chosen by the Agency.

(d) Terms of Subcontracts - All subcontracts shall provide that Work performed under the subcontract shall be conducted and performed according to, and shall include, the pertinent requirements, provisions, terms, and conditions of the Contract. Compliance with 00170.07 is required. All subcontracts, including Contractor's with the first-tier Subcontractors and those of the first-tier Subcontractors with their Subcontractors, and any other lower-tier subcontracts shall contain a clause or condition that if the Contractor or a Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract, the Entity may file a complaint with the Construction Contractors Board, unless payment is subject to a good-faith dispute as defined in ORS 279C.580. Additionally, according to the provisions of ORS 279C.580, subcontracts shall include:

(1) A payment clause that obligates the Contractor to pay the first-tier Subcontractor for satisfactory performance under the subcontract within ten (10) Calendar Days out of amounts the Agency pays to the Contractor under the Contract.

(2) A clause that requires the Contractor to provide the first-tier Subcontractor with a standard form that the first-tier Subcontractor may use as an application for payment or as another method by which the Subcontractor may claim a payment due from the Contractor.

(3) A clause that requires the Contractor, except as otherwise provided in this Subsection, to use the same form and regular administrative procedures for processing payments during the entire term of the subcontract. The Contractor may change the form or the regular administrative procedures the Contractor uses for processing payments if the Contractor:

- Notifies the Subcontractor in writing at least 45 Calendar days before the date on which the Contractor makes the change; and
- Includes with the written notice a copy of the new or changed form or a description of the new or changed procedure.

(4) An interest penalty clause that obligates the Contractor, if the Contractor does not pay the first-tier Subcontractor within 30 Calendar Days after receiving payment from the Agency, to pay the first-tier Subcontractor an interest penalty on amounts due in each payment the Contractor does not make in accordance with the payment clause included in the subcontract under 00180.21(d)(1). The Contractor or first-tier Subcontractor is not obligated to pay an interest penalty if the only reason that the Contractor or first-tier Subcontractor did not make

payment when payment was due is that the Contractor or first-tier Subcontractor did not receive payment from the Agency or the Contractor when payment was due. The interest penalty applies to the period that begins on the day after the required payment date and ends on the date on which the amount due is paid; and shall be computed at the rate specified in 00170.10(c).

(5) A clause that requires the Contractor's first-tier Subcontractor to include a payment clause and an interest penalty clause that conform to the standards of ORS 279C.580 (see 00180.21(d)(1) and 00180.21(d)(4)) in each of the first-tier Subcontractor's subcontracts and to require each of the first-tier Subcontractor's Subcontractors to include such clauses in its subcontracts with each lower-tier Subcontractor or Material supplier.

These payment clauses shall require the Contractor to return all retainage withheld from the Subcontractor, whether held by the Contractor or the Agency, as specified in 00195.50(d).

As required by ORS 279C.800 through ORS 279C.870, subcontracts shall include:

- A provision requiring the Subcontractor to have a public works bond filed with the Construction Contractors Board before starting Work on the Project, unless exempt.
- A provision requiring that the workers shall be paid not less than the specified minimum hourly rate of wage.

As and when applicable, the Contractor shall require in its subcontracts that Subcontractors maintain the certifications required by ORS 279A.107.

(e) Contractor's Responsibilities - As a condition of the Agency's grant of consent to subcontract, whether or not stated in the subcontract agreement itself, the Contractor shall remain solely responsible for administration of the subcontract, including, but not limited to:

- Performance of subcontracted Work;
- Progress of subcontracted Work;
- Payments for accepted subcontracted Work; and
- Disputes and claims for additional compensation regarding subcontracted Work.

The Engineer's consent to subcontract will not create a contract between the Agency and the Subcontractor, will not convey to the Subcontractor any rights against the Agency, and will not relieve the Contractor or the Contractor's Surety of any of their responsibilities under the Contract.

(f) Failure to Comply - Failure to comply with 00180.21 will be cause for the Engineer to take action reasonably necessary to obtain compliance. This action may include, but is not limited to:

- Suspension of the Work;
- Withholding of Contract payments as necessary to protect the Agency; and
- Termination of the Contract.

00180.22 Payments to Subcontractors and Agents of the Contractor - To the extent practicable, the Contractor shall pay in the same units and on the same basis of measurement as listed in the Schedule of Items for subcontracted Work or other Work not done by the Contractor's own organization. The Agency will not be responsible for any overpayment or losses resulting from overpayment by the Contractor to Subcontractors and to its other agents, work providers, service providers, and trucking services providers.

If requested, the Engineer will make estimates of the Work quantities performed by Subcontractors or by others on the Project, and of Materials eligible for advances on Materials in the progress payments. These estimates are approximate only, and will be made in units of measure as listed in the Schedule of Items. The Agency does not guarantee the accuracy of these estimates, and an incorrect estimate will not bind the Agency in final settlement.

If requested in writing by a first-tier Subcontractor, the Contractor shall send to the Subcontractor, within 10 Calendar Days of receiving the request, a copy of that portion of any invoice or request for payment submitted to the Agency, or pay document provided by the Agency to the Contractor, specifically related to any labor, Equipment, or Materials supplied by the first-tier Subcontractor.

00180.30 Materials, Equipment, and Work Force - The Contractor shall furnish suitable and sufficient Materials, Equipment, and personnel to properly prosecute and complete the Work. The Contractor shall use only Equipment of adequate size and condition to meet the requirements of the Work and Specifications, and to produce a satisfactory quality of Work. Upon receipt of the Engineer's written order, the Contractor shall immediately remove, and not use again on the Project without the Engineer's prior written approval, Equipment that, in the Engineer's opinion, fails to meet Specifications or produce a satisfactory product or result.

The work force shall be trained and experienced for the Work to be performed. Upon receipt of the Engineer's written order, the Contractor shall immediately remove from the Project Site, and shall not employ again on the Project without the Engineer's prior written approval, any supervisor or employee of the Contractor or any Subcontractor who, in the Engineer's opinion, does not perform satisfactory Work or whose conduct interferes with the progress of the Work.

If the Contractor fails to remove Equipment or persons as ordered, or fails to furnish suitable and sufficient Materials, Equipment and personnel for the proper prosecution of the Work, the Engineer may suspend the Work by written notice until such orders are complied with and such deficiencies are corrected, or the Engineer may terminate the Contract under the provisions of 00180.90(a).

00180.31 Required Materials, Equipment, Products, and Methods - The Engineer's decisions under this Section are final. Substitutions after Award will be considered as provided below unless specified as the subject of an exemption per ORS 279C.345. See 00120.16 for possible substitutions before Bid Opening.

(a) General - When the Equipment and methods to be used are not specified in the Contract, any Equipment or methods that accomplish the Work as required by the Contract will be permitted.

When the Contract specifies certain Equipment or methods, the Contractor shall use the Equipment or methods specified unless otherwise authorized by the Engineer in writing.

(b) Substitution of Materials, Products, and Equipment to be Incorporated into the Work - After execution of the Contract, the Engineer may approve substitution of Materials, products, and Equipment to be incorporated into the Work as follows:

(1) Reasons for Substitution - The Engineer will consider substitution only if:

- The proposed Materials, products, or Equipment are equal to or superior to the specified items in construction, efficiency and utility; or
- Due to reasons beyond the control of the Contractor, the specified Materials, products, or Equipment cannot be delivered to the Project in sufficient time to complete the Work in proper sequence.

(2) Submittal of Request - The Contractor shall submit requests for substitution to the Engineer, including manufacturers' brochures and other information needed to verify equality of the proposed item(s).

(c) Substitution of Equipment Specified to Perform Work - The Agency encourages development of new or improved Equipment and innovative use of Equipment. When the Specifications require Equipment of a particular size or type to be used to perform certain portions of the Work, the Contractor may submit a request to the Engineer to use Equipment of a different size or type. The request will not be considered as a cost reduction proposal under 00140.70. The request shall:

- Be in writing and include a full description of the Equipment proposed and its intended use;
- Include the reasons for requesting the substitution; and
- Include evidence, obtained at the Contractor's expense and satisfactory to the Engineer, that the proposed Equipment is capable of functioning as well as or better than the specified Equipment.

The Engineer will consider the Contractor's request and will provide a written response to the Contractor, either permitting or denying use of the proposed Equipment.

Permission may be granted on a trial basis to test the quality of Work actually produced, subject to the following:

- There will be no cost to the Agency, either in Contract Amount or in Contract Time;
- The permission may be withdrawn by the Engineer at any time if, in the Engineer's opinion, the Equipment is not performing in all respects equivalent to the Equipment specified in the Contract;
- If permission is withdrawn, the Contractor shall perform the remaining Work with the originally-specified Equipment; and
- The Contractor shall remove and replace non-specification work resulting from the use of the Contractor's proposed Equipment, or otherwise correct it as the Engineer directs, at no additional compensation.

(d) Substitution of Methods - The Agency encourages development of new, improved, and innovative construction methods. When the Plans or Specifications require a certain construction method for a portion of the Work, the Contractor may submit a request for a change by following the provisions of 00140.70, "Cost Reduction Proposals".

00180.32 Alternative Materials, Equipment, and Methods - Whenever the Contract authorizes certain alternative Materials, Equipment, or methods of construction for the Contractor's use to perform portions of the Work, and leaves the selection to the Contractor, the Agency does not guarantee that all listed alternative Materials, Equipment, or methods of construction can be used successfully throughout all or any part of the Work.

The Contractor shall employ only those alternatives that can be used to satisfactorily perform the Work. No additional compensation will be paid for corrective work necessitated by the Contractor's use of an inappropriate alternative.

00180.40 Limitation of Operations:

(a) In General - The Contractor shall comply with all Contract provisions and shall:

- Conduct the Work at all times so as to cause the least interference with traffic, and
- Not begin Work that may allow damage to Work already started.

(b) On-Site Work - The Contractor shall not begin On-Site Work until the Contractor has:

- Received Notice to Proceed;
- Filed with the Construction Contractors Board the public works bond as required in 00170.20;
- An approved Project Work schedule;
- An approved Traffic Control Plan;
- An approved Pollution Control Plan;
- An approved Erosion and Sediment Control Plan;
- Met with the Engineer at the required preconstruction conference; and
- Assembled all Materials, Equipment, and labor on the Project Site, or has reasonably assured that they will arrive on the Project Site, so the Work can proceed according to the Project Work schedule.

00180.41 Project Work Schedules - The Contractor shall submit a Project Work schedule meeting the requirements of this Subsection to the Engineer. The Project Work schedule is intended to identify the sequencing of activities and time required for prosecution of the Work. The schedule is used to plan, coordinate, and control the progress of construction. Therefore, the Project Work schedule shall provide for orderly, timely, and efficient prosecution of the Work, and shall contain sufficient detail to enable both the Contractor and the Engineer to plan, coordinate, analyze, document, and control their respective Contract responsibilities. Sufficient detail shall also include all required double shifts, overtime work, or combination of both necessary to complete Contract Work within the Contract Time.

Contractor's activity related to developing, furnishing, monitoring, and updating these required schedules is Incidental.

The Contractor shall submit a supplemental "look ahead" Project Work schedule each week to the Engineer. The "look ahead" Project Work schedule is supplemental to the Type A, B, or C schedule specified below. The supplemental "look ahead" Project Work schedule shall:

- Identify the sequencing of activities and time required for prosecution of the Work.
- Provide for orderly, timely, and efficient prosecution of the Work.
- Contain sufficient detail to enable both the Contractor and the Engineer to plan, coordinate, analyze, document, and control their respective Contract responsibilities.

The supplemental "look ahead" Project Work schedule shall be written in common terminology and show the planned Work activities broken down into logical, separate activities by area, stage, and size and include the following information:

- The resources the Contractor, Subcontractors, or services will use.
- The locations of each activity that will be done including the limits of the Work by mile posts, stations, or other indicators.
- The time frames of each activity by Calendar Days, shifts, and hours.
- All anticipated Shoulder, lane, and road closures.

At a minimum, the Contractor shall prepare a bar chart that:

- Shows at least 3 weeks of activity including the week the bar chart is issued.
- Uses a largest time scale unit of 1 Calendar Day. Smaller time scale units may be used if needed.
- Is appropriate to the activities.
- Identifies each Calendar Day by month and day.

Include the Contract name, Contract number, Contractor's name, and date of issue on each page of the bar chart.

The Contractor shall submit the supplemental "look ahead" Project Work schedule starting at First Notification and continuing each week until Second Notification has been issued and all punch list items and final trimming and clean-up has been completed. The Contractor shall meet with the Engineer each week to review the supplemental "look ahead" Project Work schedule. If the Engineer or the Contractor determines that the current supplemental "look ahead" Project Work schedule requires changes or additions, either notations can be made on the current schedule or the Engineer may require the submittal of a revised supplemental "look ahead" Project Work schedule. Review of the current and subsequent supplemental "look ahead" Project Work schedules does not relieve the Contractor of responsibility for timely and efficient execution of the Contract.

One of the following Type "A", "B", or "C" schedules will be required under the Contract. The type of schedule will be identified in the Special Provisions.

(a) Type "A" Schedule - When a Type "A" schedule is required, the Contractor shall do the following:

(1) Schedule - At least 10 Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer four copies of a Project Work schedule, including a time-scaled bar chart and narrative, showing:

- Expected beginning and completion dates of each activity, including all staging; and
- Elements of the Traffic Control Plan as required under 00221.06.

The schedule shall show detailed Work activities as follows:

- Construction activities;
- The time needed for completion of the Utility relocation work;
- Submittal and approval of Materials samples and shop drawings;
- Fabrication, installation, and testing of special Materials and Equipment; and
- Duration of Work, including completion times of all stages and their sub phases.

For each activity, the Project Work schedule shall list the following information:

- A description in common terminology;
- The quantity of Work, where appropriate, in common units of measure;
- The activity duration in Calendar Days; and
- Scheduled start, completion, and time frame shown graphically using a time-scaled bar chart.

The schedule shall show the Work broken down into logical, separate activities by area, stage, or size. The duration of each activity shall be verifiable by manpower and Equipment allocation, in common units of measure, or by delivery dates.

The bar chart shall be prepared as follows:

- The length of bar shall represent the number of workdays scheduled.
- The time scale shall be appropriate for the duration of the Contract.
- The time scale shall be in Calendar Days.
- The smallest unit shown shall be 1 Calendar Day.
- The first day and midpoint of each month shall be identified by date.
- Distinct symbols shall be used to denote multiple shift, holiday, and weekend Work.

Each page of the bar chart shall include a title block showing the Contract name and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the bar chart shall be drawn on a reasonable size of paper up to a maximum of 36 inch by 36 inch, using multiple sheets when needed.

Within 7 Calendar Days after the preconstruction conference, the Engineer and the Contractor shall meet to review the Project Work schedule as submitted. The Engineer will review the schedule for compliance with all Contract Time limitations and other restraints. Review of this and subsequent schedules by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract. Within 10 Calendar Days of this meeting, the Contractor shall resubmit to the Engineer four copies of the Project Work schedule, including required revisions.

(2) Review by the Engineer - The Project Work schedule may need revision as the Work progresses. Therefore, the Contractor shall periodically review the Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the Project Work schedule.

The Contractor shall compile an updated Project Work schedule incorporating any changes to the Project completion time(s). The bar chart shall reflect the updated information. The Contractor shall submit four copies of the updated Project Work schedule to the Engineer within 7 Calendar Days after the meeting. The report shall include without limitation the following:

- Sufficient narrative to describe the past progress, anticipated activities, and stage Work;
- A description of any current and expected changes or delaying factors and their effect on the construction schedule; and
- Proposed corrective actions.

(b) Type "B" Schedule - When a Type "B" Schedule is required, the Contractor shall do the following:

(1) Initial Schedule - At least 10 Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer four copies of a time-scaled bar chart Project Work schedule showing:

- Expected beginning and completion date of each activity, including all staging; and
- Elements of the Traffic Control Plan as required under 00221.06.

The initial schedule shall show all Work intended for the first 60 Days of the Contract to the level of detail described in (2) below, and shall show the priority and interdependence (sequencing and network logic) of all major segments of the remainder of the Work.

(2) Detailed Schedule - In addition to the above requirements, and within 30 Calendar Days after the Notice to Proceed, the Contractor shall provide the Engineer one digital copy and four paper copies of a detailed time-scaled bar chart Project Work schedule indicating the critical course of the Work. The digital copy shall be compatible with the current version of Microsoft Project, the current version of Primavera P6 by Oracle, or another scheduling program approved by the Engineer.

Detailed work schedule activities shall include the following:

- Construction activities;
- The time needed for completion of the Utility relocation work;
- Submittal and approval of Material samples and shop drawings;
- Procurement of critical Materials;
- Fabrication, installation, and testing of special Material and Equipment; and
- Duration of Work, including completion times of all stages and their sub phases.

For each activity, the Project Work schedule shall list the following information:

- A description in common terminology;
- The quantity of Work, where appropriate, in common units of measure;
- The activity duration in normal workdays; and
- Scheduled start, completion, and time frame shown graphically using a time-scaled bar chart.

The schedule shall show the Work broken down into logical, separate activities by area, stage, or size. The duration of each activity shall be verifiable by manpower and Equipment allocation, in common units of measure, or by delivery dates.

The bar chart shall be prepared as follows:

- The length of bar shall represent the number of normal workdays scheduled.
- The time scale shall be appropriate for the duration of the Contract.
- The time scale shall be in normal workdays (every day except Saturday, Sunday, and legal holidays).
- The smallest unit shown shall be 1 Calendar Day.
- The first day and midpoint of each month shall be identified by date.
- Distinct symbols shall be used to denote multiple shift, holiday, and weekend Work.

The bar chart drawing(s) shall include a title block showing the Contract name and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the bar chart shall be drawn on a reasonable size of paper up to a maximum of 36 inch x 36 inch, using multiple sheets when needed.

Within 10 Calendar Days after submission of the Project schedule the Engineer and the Contractor shall meet to review the Project schedule as submitted. Within 10 Days of the review meeting, the Contractor shall resubmit to the Engineer one digital and four paper copies of the Project schedule, including required revisions.

The accepted Project schedule shall represent all Work, as well as the planned sequence and time for the Work. Review of this and subsequent schedules by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract.

(3) Review and Reporting - The Project Work schedule may require revision as the Work progresses. Therefore, the Contractor shall monitor and when necessary revise the Project Work schedule as follows:

a. Review with the Engineer - The Contractor shall perform ongoing review of the Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the Project Work schedule. After any necessary action has been agreed upon, the Contractor shall make required changes to the Project Work schedule.

The Contractor shall collect information on all activities worked on or scheduled to be worked on during the previous report period, including shop drawings, Material procurement, and Contract Change Orders that have been issued. Information shall include commencement and completion dates on activities started or completed, or if still in progress, the remaining time duration.

The Contractor shall develop detailed sub-networks to incorporate changes, Additional Work, and Extra Work into the Project Work schedule. Detailed sub-networks shall include all necessary activities and logic connectors to describe the Work and all restrictions on it. The restraints shall include those activities from the Project Work schedule that initiated the sub-network as well as those restrained by it.

The Contractor shall evaluate this information and compare it with the Contractor's Project schedule. If necessary, the Contractor shall make an updated bar chart schedule to incorporate the effect changes may have on the Project completion time(s). For any activity that has started, the Contractor shall add a symbol to show the actual date the activity started and the number of normal workdays remaining until completion. For activities that are finished, a symbol shall be added to show the actual date. The Contractor shall submit one digital and four paper copies of the updated bar chart to the Engineer within 7 Days after the progress meeting, along with a progress report as required by "b." below.

b. Progress Report - The Contractor shall submit a progress report to the Engineer each month. The report shall include the following:

- Sufficient narrative to describe the past progress, anticipated activities, and stage Work;
- A description of any current and expected changes or delaying factors and their effect on the construction schedule; and
- Proposed corrective actions.

(c) Type "C" Schedule - When a Type "C" Schedule is required, the Contractor shall do the following:

(1) Initial Schedule - At least 10 Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer one digital copy and four paper copies of a time-scaled bar chart Project Work schedule. The digital copy shall be compatible with the current version of Microsoft Project, the current version of Primavera P6 by Oracle, or another scheduling program approved by the Engineer. The initial schedule shall show:

- The expected beginning and completion date of each activity, including all stages and phases;
- The time needed for completion of the Utility relocation work; and
- The elements of the traffic control plan as required under 00221.06.

A logic diagram and a time-scaled bar chart will be acceptable in lieu of a time-scaled logic diagram.

The initial schedule shall show all Work intended for the first 60 Days of the Contract to the level of detail described in (2) below, and shall show the priority and interdependence (sequencing and network logic) of all major segments of the remainder of the Work.

(2) Detailed Project Work Schedule - In addition to the above requirements, and within 30 Calendar Days after First Notification, the Contractor shall provide the Engineer one digital copy and four paper copies of a detailed time-scaled critical path method (CPM) network Project Work schedule and computer analysis printout, both clearly indicating the critical path. The digital copy shall be compatible with the current version of Microsoft Project, the current version of Primavera P6 by Oracle, or another scheduling program approved by the Engineer. The first submitted detailed time-scaled critical path method (CPM) network Project Work schedule shall also contain a listing of the quantity of Work for each activity, when appropriate, in common units of measure.

Detailed work schedule activities shall include the following:

- Construction activities;
- Any limitations of operation specified in 00180.40;
- The time needed for completion of the Utility relocation work;
- Implementation of TCP for each stage and phase;
- Submittal and approval of Material samples, mix designs, and shop drawings;
- Agency timeframes to process and return Contractor submitted plans, Working Drawings, Equipment lists and other submittals;
- Procurement of critical Materials;
- Fabrication, installation, and testing of special Material and Equipment;
- Duration of Work, including completion times of all stages and their sub-phases; and
- Specified cure times for all concrete elements.

The activities shall be separately identifiable by coding or use of sub-networks or both. The duration of each activity shall be verifiable and consistent with the description in the Project narrative required in (3) below.

Detailed sub-networks shall include all necessary activities and logic connectors to describe the Work and all restrictions on it. In the restraints, include those activities from any Project Work schedule that initiated the sub-network as well as those restrained by it.

The time scale used on the Contractor's detailed time-scaled critical path method (CPM) network Project Work schedule shall be appropriate for the duration of the activities and the Project duration. The time scale shall be in normal workdays, defined as every day except Saturday, Sunday and legal holidays, with calendar dates identified no less than the first and midpoint of each calendar month. The smallest unit shown shall be 1 Day. The network shall show the length of the activity or part scaled to accurately represent the number of normal workdays scheduled. Distinct symbols or graphics shall be used to show multiple shift, holiday, or weekend work.

The schedule network drawing(s) shall include a title block showing the Contract name and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the drawings shall be on a reasonable size of paper up to a maximum of 36 inch x 36 inch, using multiple sheets when needed.

The Contractor shall include a tabulation of each activity in the computer mathematical analysis of the network diagram. The following information represents the minimum required for each activity:

- Event (node) number(s) for each activity;
- Maintain event (node) numbers throughout the Project;
- Activity description;
- Original duration of activities (in normal workdays);
- Estimated remaining duration of activities (in normal workdays);
- Earliest start date and actual start date (by calendar date);
- Earliest finish date and actual finish date (by calendar date);
- Latest start date (by calendar date);
- Latest finish date (by calendar date); and
- Slack or float time (in workdays).

Computer print-outs shall consist of at least a node sort and an "early start/total-float" sort.

Within 14 Calendar Days after submission of the detailed time-scaled critical path method (CPM) network Project Work schedule, the Engineer and the Contractor shall meet to review the detailed time-scaled critical path method (CPM) network Project Work schedule as submitted. Within 7 Calendar Days of the meeting, the Contractor shall resubmit to the Engineer one digital and four paper copies of the detailed time-scaled critical path method (CPM) network Project Work schedule, including required revisions.

This first accepted detailed time-scaled critical path method (CPM) network Project Work schedule, also called the accepted Project Work schedule, shall represent all Work, as well as the planned sequence and time for the Work. Review and acceptance of any Project Work schedules and Project narratives by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract.

(3) Project Narrative - In addition to the above requirements, and within 30 Calendar Days after First Notification, the Contractor shall provide to the Engineer a final written Project

narrative that discusses the planning, coordinating, scheduling and resourcing of the Work. The Project narrative shall include the following written description:

- Plans for staging the Project.
- All critical activities.
- All near critical activities defined as those with less than 30 Days of float.
- All Subcontractor activities that are critical, near critical, and those that are greater than two weeks in duration.
- Labor resourcing, by stage and phase, to include the number of crews, average crew size and planned night/weekend shifts including that of Subcontractors.
- Equipment allocation, by stage and phase to include mobilization, demobilization and planned activities including that of Subcontractors.
- Notifications required under the Contract during each stage and phase which may include but is not limited to road closures, lanes closures, night work, cold plane Pavement removal, and pile driving.
- Provide discussion on addressing reasonably predictable weather conditions and their impact on all weather sensitive activities. Also, provide discussion on other weather limitations that may affect the Project schedule.
- Submittal and approval of material samples, mix designs, and shop drawings.
- Procurement of critical materials.
- Plans for dealing with "unique" construction items.
- Coordination of utilities and any immediate concerns for impacts/delays.
- Constructability issues.
- Cost Reduction Proposals and/or immediate requests for changes to the Specifications.
- Concerns/issues that need to be addressed within the first 90 Days following First Notification.

The accepted Project narrative shall represent all critical and near critical Work, as well as the planned sequence and time for the Work.

(4) Review and Reporting - The Project Work schedule may require revision as the Work progresses. Therefore, the Contractor shall monitor and when necessary revise the Project Work schedule as follows:

a. Review with the Engineer - The Contractor shall perform ongoing review of the accepted Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the accepted Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the accepted Project Work schedule. After any necessary action has been agreed upon, the Contractor shall make required changes to the accepted Project Work schedule and associated Project narrative. Upon acceptance by the Engineer, this will become the new accepted Project Work schedule and associated Project narrative.

The Contractor shall collect information on all activities worked on or scheduled to be worked on during the previous report period, including shop drawings, Material procurement, and Contract Change Orders that have been issued. Information shall include actual start and completion dates on activities started or completed, or if still in progress, the remaining time duration.

The Contractor shall develop detailed sub-networks to incorporate changes, Additional Work, and Extra Work into the Project Work schedule. Detailed sub-networks shall include all necessary activities and logic connectors to describe the Work and all restrictions on it. The restraints shall include those activities from the Project Work schedule that initiated the sub-network as well as those restrained by it. The procedure for acceptance of the revised or updated Project Work schedule as the new accepted Project Work schedule will be as provided above.

The Contractor shall evaluate this information each month and compare it with the accepted Project Work schedule. The Contractor shall make an updated bar chart schedule to incorporate the effect changes may have on the Project completion time(s). For any activity that has started, the Contractor shall add a symbol to show the actual date the activity started and the number of normal workdays remaining until completion. For activities that are finished, a symbol shall be added to show the actual date. The Contractor shall submit, digitally and in paper, copies of the updated bar chart to the Engineer within 7 Days after the progress meeting, along with a progress report as required by "b." below.

b. Progress Report - Each month the Contractor shall submit a progress report and an update of the Project Work schedule to the Engineer. The report and updated schedule shall be submitted both digitally and in paper copy and shall include the following:

- A sufficient description, in narrative form, to describe the past progress, anticipated activities, and stage Work;
- A description of any current and expected changes or delaying factors and their effect on the construction schedule;
- Proposed corrective actions;
- Proposals to keep the Project on schedule in the event of a delay; and
- Any changes to the logic as compared to the accepted Project Work schedule.

(d) Substitution of Schedules - When a Type "A" schedule is required, a Type "B" or Type "C" schedule may be substituted for the Type "A" schedule.

When a Type "B" schedule is required, a Type "C" schedule may be substituted for the Type "B" schedule.

(e) Specified Contract Time Not Superseded by Schedule Revisions - The completion dates in any Project Work schedule and any revised or updated Project Work schedules shall be within the Contract Time(s) specified for the Project, or within adjusted Contract Times approved according to 00180.80(c). Acceptance of any Project Work schedule or any revised or updated Project Work schedules shall not constitute approval of any completion dates that exceed such Contract Time(s). If the Contractor believes that additional Contract Time is due, the Contractor shall submit, with a revised Project Work schedule, a request for adjustment of Contract Time according to 00180.80(c). A request for an adjustment of Contract Time will be evaluated using the most recently accepted Project Work schedule.

(f) Float Time - Float time shown on the Project Work schedule, including any time between a Contractor's scheduled completion date and the specified Contract Time(s), does not exist for the exclusive use of either party to the Contract and belongs to the Project.

(g) Schedules Do Not Constitute Notice - Submittal of a Project Work schedule, with supporting Project narrative, does not constitute or substitute for any notice the Contractor is required under the terms of the Contract to give the Agency.

(h) Failure to Provide Schedule - The Project Work schedule is essential to the Agency. The Contractor's failure to provide the schedule, schedule information, progress reports, Project narratives, or schedule updates when required will be cause to suspend the Work, or to withhold Contract payments as necessary to protect the Agency, until the Contractor provides the required information to the Engineer.

00180.42 Preconstruction Conference - Unless otherwise approved in writing by the Engineer, before any Work is performed and within 30 Calendar Days of the Notice to Proceed, the Contractor shall meet with the Engineer for a preconstruction conference at a time mutually agreed upon.

00180.43 Commencement and Performance of Work - From the time of commencement of the Work to the time of Final Acceptance the Contractor shall:

- Provide adequate Materials, Equipment, labor, and supervision to perform and complete the Work within the Contract Time or the adjusted Contract Time;
- Perform the Work as vigorously and as continuously as conditions permit, and according to a Project Work schedule that ensures completion within the Contract Time or the adjusted Contract Time;
- Not voluntarily suspend or slow down operations without prior written approval from the Engineer, and if approved submit an updated Project Work schedule according to 00180.41 that ensures completion within the Contract Time or the adjusted Contract Time; and
- Not resume suspended Work without the Engineer's written authorization.

00180.50 Contract Time to Complete Work:

(a) General - The time allowed to complete the Work or Pay Item is stipulated in the Solicitation Documents, and will be known as the "Contract Time". (See 00110.20.)

(b) Kinds of Contract Time - The Contract Time will be expressed in one or more of the following ways:

(1) Fixed Date Calculation - The calendar date on which the Work or Pay Item shall be completed; or

(2) Calendar Day Calculation - The number of Calendar Days from a specified beginning point in which the Work or Pay Item shall be completed.

(c) Beginning of Contract Time - When the Contract Time is stated in Calendar Days, counting of Contract Calendar Days will begin on the day the Contractor begins On-Site Work as defined in 00110.20.

(d) Recording Contract Time - All Contract Time will be recorded and charged to the nearest one-half Day.

On Contracts with Calendar Day counts, the Engineer will furnish the Contractor a weekly statement of Contract Time charges. The statement will show the number of Calendar Days counted for the preceding week and the number of Calendar Days remaining prior to the established completion date for the specified Work in 00180.50(h).

For Contracts with fixed completion dates for Pay Items, the Engineer will furnish the Contractor a weekly statement of Contract Time charges only after expiration of the Contract Time. The statement will show the number of Calendar Days of liquidated damages that have been assessed, if any.

These statements will include any exclusions from, or adjustments to, Contract Time.

(e) Exclusions from Contract Time - Regardless of the way Contract Time is expressed in the Contract, certain Calendar Days will not be charged against Contract Time. These exclusions will be allowed when the Contractor is prevented from performing Work due to one of the following reasons, resulting in delay:

- Acts of God or Nature;
- Court orders enjoining prosecution of the Work;
- Strikes, labor disputes or freight embargoes that, despite the Contractor's reasonable efforts to avoid them, cause a shutdown of the entire Project or one or more major operations. "Strike" and "labor dispute" may include union action against the Contractor, a Subcontractor, a materials Supplier, or the Agency; or
- Suspension of the Work by written order of the Engineer for reasons other than the Contractor's failure or neglect.

(f) Time Calculation Protest - In the event the Contractor disputes the accuracy of the statement of Contract Time charges, it shall immediately contact the Engineer and attempt to resolve the dispute. If the dispute cannot be resolved informally, the Contractor shall submit a formal written protest to the Engineer within 7 Calendar Days of the date the Engineer mailed or delivered the statement. Failure to submit a formal written protest within the 7 Calendar Day period constitutes the Contractor's approval of the time charges, or adjusted time charges, itemized in the statement.

(g) End of Contract Time - When the Engineer determines that the On-Site Work has been completed, except for the items listed below, the Engineer will issue a Second Notification.

The Second Notification will list:

- The date the time charges stopped;
- Final trimming and cleanup tasks (see 00140.90);
- Equipment to be removed from the Project Site;
- Minor corrective work not involving additional payment to be completed; and
- Submittals, including, without limitation, all required certifications, bills, forms, warranties, certificate of insurance coverage (00170.70(b)), and other documents, required to be provided to the Engineer before Third Notification will issue.

The Contractor shall complete all tasks listed in the Second Notification in an expeditious manner within the time frame proposed by the Contractor and accepted by the Engineer. Unless otherwise agreed by the Agency, failure of the Contractor to complete all tasks listed in the Second Notification within the time frame accepted, will result in the Agency rescinding the Second Notification. Counting of time charges will resume upon expiration of the accepted time frame.

00180.60 Notice of Delay - The Contractor shall notify the Engineer of any delay that will likely prevent completion of the Work or a Pay Item by the date specified in the Project Work schedule. The notice shall be in writing and shall be submitted within 7 Calendar Days of when the Contractor knew or should have known of the delay. The notice shall include, to the extent available, the following:

- The reasons or causes for the delay;
- The estimated duration of the delay and the estimated resulting cumulative delay in Contract completion;
- Except for 00180.50(e) and 00180.65 delays, whether or not the Contractor expects to request an adjustment of Contract Time due to the delay;

- Whether or not the Contractor expects to accelerate due to the delay; and
- Whether or not the Contractor expects to request additional compensation due to the delay. Except for 00180.50(e) and 00180.65 delays, failure to include this information will constitute waiver of the Contractor's right to later make such a request.

00180.65 Right-of-Way and Access Delays - Right-of-Way and access delays will be taken into consideration in adjusting Contract Time, and in approving additional compensation if the performance of the Work is delayed because of the Agency's failure to make available to the Contractor:

- Necessary Rights-of-Way;
- Agency-owned or Agency-controlled Materials sources that are offered in the Contract for the Contractor's use; or
- Access to, or rights of occupancy of, buildings and other properties the Contractor is required to enter or to disturb according to Contract requirements.

If the ending date of an anticipated delay is stated in the Special Provisions, only the delay occurring after that date will be considered for adjusting Contract Time or providing additional compensation.

00180.70 Suspension of Work:

(a) General - The Engineer has authority to suspend the Work, or part of the Work, for any of the following causes:

- Failure of the Contractor to correct unsafe conditions;
- Failure of the Contractor to carry out any provision of the Contract;
- Failure of the Contractor to carry out orders issued by the Engineer, the Agency, or any regulatory authority;
- Existence of conditions unsuitable to proper or safe performance of the Work; or
- Any reason considered by the Agency to be in the public interest.

When Work has been suspended for any reason, the Contractor shall not resume Work without the Engineer's written authorization.

(b) Contractor's Responsibilities during and after Suspension - During periods of suspension of the Work, the Contractor shall continue to be responsible for protecting and repairing the Work according to 00170.80, and for ensuring that a single designated representative responsible for the Project remains available according to 00150.40.

When Work is resumed after suspension, unless otherwise specified in the Contract, the Contractor shall perform the following at no additional compensation:

- Replace or repair any Work, Materials, and Equipment to be incorporated into the Work that was lost or damaged because of the temporary use of the Project Site by the public; and
- Remove Materials, Equipment, and temporary construction necessitated by temporary maintenance during the suspension, as directed by the Engineer.

(c) Compensation and Allowances for Suspension - Compensation and allowance of additional Contract Time due to suspension of any portion of the Work will be authorized only for Agency-initiated suspensions for reasons other than the Contractor's failure or neglect. (See 00180.50(e), 00180.65, and 00195.40.)

00180.80 Adjustment of Contract Time:

(a) General - Contract Time established for the Work will be subject to adjustment, either by increase or decrease, for causes beyond the control of the Contractor, according to the terms of this Subsection. After adjustment, the Contract Time will become, and be designated as, the "Adjusted Contract Time". Except as provided in 00180.65 and 00195.40, an adjustment of Contract Time shall be the Contractor's only remedy for any delay arising from causes beyond the control of the Contractor.

(b) Contractor's Request Not Required - The Engineer may increase or decrease the Contract Time or the Adjusted Contract Time if Change Orders or Extra Work orders issued actually increase or decrease the amount of time required to perform the Work. The Engineer may also increase Contract Time in the event of Right-of-Way and Access delays (see 00180.65), and those delays due to causes beyond the Contractor's control specified in 00180.50(e). The Engineer will promptly inform the Contractor of adjustments made to Contract Time according to this Subsection, and will include the reasons for adjustment.

If the Agency anticipates delay during performance of the Contract, and specifies its expected duration in the Special Provisions, the Engineer will only consider additional delay beyond the stipulated duration in determining whether to adjust Contract Time.

(c) Contractor's Request Required - In the event the Contractor believes that additional Contract Time is due, the Contractor shall submit to the Engineer a timely request for adjustment of Contract Time. The Engineer will not consider untimely requests. The Agency regards as timely only those requests for adjustment of Contract Time that:

- Accompany a proposed revised Project Work schedule submitted according to 00180.41, for comparison with the last revision of the Project Work schedule; or
- Are not otherwise deemed waived and are submitted within 45 Days after the date of Second Notification, if Second Notification has been issued.

The Engineer will not grant an adjustment of Contract Time for events that occurred prior to the date of the last revision of the Project Work schedule. The Engineer will not authorize, nor the Agency pay, acceleration costs incurred by the Contractor prior to its submittal of a request for adjustment of Contract Time to which the acceleration costs relate.

The Contractor's request for adjustment of Contract Time shall be submitted to the Engineer on a form provided by, or in a format acceptable to, the Engineer, and shall include a copy of the written notice required under 00180.60. The request shall include without limitation:

- Consent of the Contractor's Surety if the request totals more than 30 Calendar Days of additional Contract Time;
- Sufficient detail for the Engineer to evaluate the asserted justification for the amount of additional Contract Time requested;
- The cause of each delay for which additional Contract Time is requested, together with supporting analysis and data;
- Reference to the Contract provision allowing Contract Time adjustment for each cause of delay;
- The actual or expected duration of delay resulting from each cause of delay, expressed in Calendar Days; and
- A schedule analysis based on the current approved Project Work schedule for each cause of delay, indicating which activities are involved and their impact on Contract completion.

(d) Basis for Adjustment of Contract Time - In the adjustment of Contract Time, the Engineer will consider causes that include, but are not limited to:

- Failure of the Agency to submit the Contract and bond forms to the Contractor for execution within the time stated in 00130.50, or to submit the Notice to Proceed within the time stated in 00130.90;
- Errors, changes, or omissions in the Supplemental Drawings, quantities, or Specifications;
- Performance of Extra Work;
- Failure of the Agency or Entities acting for the Agency to act promptly in carrying out Contract duties and obligations;
- Acts or omissions of the Agency or Entities acting for the Agency that result in unreasonable delay referenced in 00195.40;
- Causes cited in 00180.50(e); and
- Right-of-way and access delays referenced in 00180.65.

The Engineer will not consider requests for adjustment of Contract Time based on any of the following:

- Contentions that insufficient Contract Time was originally specified in the Contract;
- Delays that do not affect the specified or Adjusted Contract Time;
- Delays that affect the Contractor's planned early completion, but that do not affect the specified or adjusted Contract Time;
- Shortage or inadequacy of Materials, Equipment or labor;
- Late delivery of Materials and Equipment to be incorporated into the Work, except under those conditions referenced in 00180.50(e);
- Different area of Material source in 00160.40(a);
- Substitution of Equipment in 00180.31(c);
- Reasonably predictable weather conditions; or
- Other matters within the Contractor's control or Contract responsibility.

(e) Consideration and Response by Agency - The Engineer will only consider a Contractor's request for Contract Time adjustment submitted according to the requirements of 00180.80(c). The Engineer may elect not to consider claimed delays that do not affect the specified or adjusted Contract Time required to complete the Work.

The Engineer may adjust Contract Time for causes not specifically identified by the Contractor in its request.

The Engineer will review a properly submitted request for Contract Time adjustment, and within a reasonable time will advise the Contractor of the Engineer's findings. If the Contractor disagrees with the Engineer's findings, the Contractor may request review according to the procedure specified in 00199.40.

00180.85 Failure to Complete on Time; Liquidated Damages:

(a) Time is of the Essence - Time is of the essence in the Contractor's performance of the Contract. It is essential and in the public interest that the Contractor prosecute the Work vigorously to Contract completion and within Contract Time or adjusted Contract Time.

The Agency does not waive any rights under the Contract by permitting the Contractor to continue to perform the Contract, or any part of it, after the Contract Time or adjusted Contract Time has expired.

(b) Liquidated Damages - Delays in the Contractor's performance of the Work will cause the Agency to sustain damages; increase risk to, inconvenience, and interfere with the traveling public and commerce; and increase costs to taxpayers. Because the Agency finds it is unduly burdensome and difficult to demonstrate the exact dollar value of such damages, the Contractor agrees to pay to the Agency, not as a penalty but as liquidated damages, the amount(s) determined as specified below for each Calendar Day the Work remains incomplete after the expiration of the Contract Time or adjusted Contract Time applicable to that Work. The liquidated damages shall constitute payment in full only of damages incurred by the Agency due to the Contractor's failure to complete the Work on time.

Payment by the Contractor of liquidated damages does not release the Contractor from its obligation to fully and timely perform the Contract according to its terms. Nor does acceptance of liquidated damages by the Agency constitute a waiver of the Agency's right to collect any additional damages it may sustain by reason of the Contractor's failure to fully perform the Contract according to its terms.

If the Contract is terminated according to 00180.90(a), and if the Work has not been completed by other means on or before the expiration of Contract Time or adjusted Contract Time, liquidated damages will be assessed against the Contractor for the duration of time reasonably required to complete the Work.

(1) Single Contract Time - The liquidated damages per Calendar Day* for failure to complete the Work on time as required by 00180.50(h) when a single Contract Time is listed under 00180.50(h) will be established using the following formula:

The Liquidated Damages per Calendar Day* are 21.2 percent of C divided by T as defined in this Section.

C = The Contractor's Bid amount for the Contract.

T = The total Calendar Days between the latest completion date or time listed under 00180.50(h) in the Solicitation Documents and the Bid Opening that will result in the greatest value for T.

* Calendar Day amounts are applicable when the Contract Time is expressed on the Calendar Day or fixed date basis.

(2) Multiple Contract Times - The liquidated damages per Calendar Day* for failure to complete the Work on time as required by 00180.50(h) when multiple Contract Times are listed under 00180.50(h) will be established for each individual Contract Time as follows:

The Agency-determined percentage of the value of all Work required to be complete by a given Contract Time multiplied by the rate determined using the formula specified in 00180.85(b)(1).

When multiple Contract Times are listed under 00180.50(h), the Agency-determined percentages of the value of Work required to be complete by the Contract Times listed under 00180.50(h) will be listed in the Special Provisions.

If liquidated damages should become payable concurrently under any combination of liquidated damage rates, the rate that will be assessed will be the highest applicable rate.

* Calendar Day amounts are applicable when the Contract Time is expressed on the Calendar Day or fixed date basis.

00180.90 Termination of Contract and Substituted Performance:

(a) Termination for Default - Termination of the Contract for default may result if the Contractor:

- Fails to comply with the requirements for records;
- Violates any material provision of the Contract;
- Disregards applicable laws and regulations or the Engineer's instructions;
- Refuses or fails to supply enough Materials, Equipment or skilled workers for prosecution of the Work in compliance with the Contract;
- Fails to make prompt payment to Subcontractors;
- Makes an unauthorized general assignment for the benefit of the Contractor's creditors;
- Has a receiver appointed because of the Contractor's insolvency;
- Is adjudged bankrupt and the court consents to the Contract termination; or
- Otherwise fails or refuses to faithfully perform the Contract according to its terms and conditions.
- Has liquidated and delinquent debt owed to the State or any department or agency of the State.

If the Contract is terminated by the Agency, upon demand the Contractor and the Contractor's Surety shall provide the Engineer with immediate and peaceful possession of the Project Site, and of all Materials and Equipment to be incorporated into the Work, whether located on and off the Project Site, for which the Contractor received progress payments under 00195.50.

If the Contract is terminated for default, neither the Contractor nor its Surety shall be:

- Relieved of liability for damages or losses suffered by the Agency because of the Contractor's breach of Contract; or
- Entitled to receive any further progress payments until the Work is completed. However, progress payments for completed Work that remain due and owing at the time of Contract termination may be made according to the terms of 00195.50, except that the Engineer will be entitled to withhold sufficient funds to cover costs incurred by the Agency as a result of the termination. Final payment to the Contractor will be made according to the provisions of Section 00195.

If a termination under this provision is determined by a court of competent jurisdiction to be unjustified, the termination shall be deemed a termination for public convenience.

(b) Substituted Performance - According to the Agency's procedures, and upon the Engineer's recommendation that sufficient cause exists, the Agency, without prejudice to any of its other rights or remedies and after giving the Contractor and the Contractor's Surety at least 10 Calendar Days' written notice, may:

- Terminate the Contract;
- Substitute the Contractor with another Entity to complete the Contract;
- Take possession of the Project Site;
- Take possession of Materials on the Project Site;
- Take possession of Materials not on the Project Site, for which the Contractor received progress payments under 00195.50;
- Take possession of Equipment on the Project Site that is to be incorporated into the Work;

- Take possession of Equipment not on the Project Site that is to be incorporated into the Work, and for which the Contractor received progress payments under 00195.50; and
- Finish the Work by whatever method the Agency deems expedient.

If, within the 10 Calendar Day notice period provided above, the Contractor and/or its Surety corrects the basis for declaration of default to the satisfaction of the Engineer, or if the Contractor's Surety submits a proposal for correction that is acceptable to the Engineer, the Contract will not be terminated.

(c) Termination for Public Convenience - The Engineer may terminate the Contract for convenience in whole or in part whenever the Engineer determines that termination of the Contract is in the best interest of the public.

The Engineer will provide the Contractor and the Contractor's Surety 7 Calendar Days' written notice of termination for public convenience. After such notice, the Contractor and the Contractor's Surety shall provide the Engineer with immediate and peaceful possession of the Project Site, and of Materials and Equipment to be incorporated into the Work, whether located on and off the Project Site, for which the Contractor received progress payments under 00195.50.

Compensation for Work terminated by the Engineer under this provision will be determined according to the provisions of 00195.70(b).

Section 00190 - Measurement of Pay Quantities

Description

00190.00 Scope - The Engineer will measure pay quantities for accepted Work according to the United States standard measure unless otherwise provided in the Contract. Unless otherwise specified in the Contract, the Engineer will round off all quantity computations using the following convention:

- The final significant digit will not be changed when the succeeding digit is less than 5.
- The final significant digit will be increased by one when the succeeding digit is 5 or greater.

The measurement provisions contained in the Specifications for each Pay Item will supplement or modify the above convention by:

- Imposing measurement limitations
- Describing measurement or computation procedures
- Giving conversion factors or adjustment conditions
- Providing for determination of reasonably accurate and representative Pay Item quantities

Measurements required or allowed to be made by the Contractor will be subject to the Engineer's verification. The Engineer's decision about measurement is final.

00190.10 Measurement Guidelines - Measurement of quantities will be made on the following bases, unless otherwise specified in the Contract:

(a) Unit Basis - Unit will be each, unless otherwise specified in the Contract and will be determined by actual count of units in place.

(b) Length Basis - Length will be feet or mile, unless otherwise specified in the Contract and will be determined by measuring the length at least to the nearest 0.1 foot or at least to the nearest 0.1 mile, as applicable, unless otherwise specified in the Contract. Measurements will be limited to the dimensions shown or specified, or as directed by the Engineer.

(c) Area Basis - Area will be square foot, square yard, or acre, unless otherwise specified in the Contract and will be determined by measuring the width and the length (or height) at least to the nearest 0.1 foot and computed at least to the nearest 0.1 square foot, nearest 0.1 square yard, or nearest 0.1 acre, as applicable, unless otherwise specified in the Contract.

(d) Weight Basis - Weight will be pound or ton, unless otherwise specified in the Contract and will be determined as follows:

(1) Pound - Pound weight will be determined by the net weight identified on the manufacturer's packaged labels, subject to periodic check weighing. Weight by pound will be measured at least to the nearest 1.0 pound unless otherwise specified in the Contract.

Provide a certificate with each shipment together with a certified copy of the weight of each delivery. If the check weight is less than the manufacturer weight by more than 0.4%, the discrepancy will be resolved by the Engineer.

(2) Ton - Ton weight will be determined on Contractor-provided scales as required under 00190.20 unless otherwise allowed by the Specifications. Weight by ton will be measured at least to the nearest 0.01 ton unless otherwise specified in the Contract.

If bituminous materials, portland cement, lime, and similar bulk Materials are shipped by truck or rail, the supplier's shipping invoice with net scale weights, or volumes converted to weights, may be used for Pay Item quantity determination in place of weights determined on the Contractor-provided vehicle scales.

Shipping invoice weights of the supplier's truck or transport shall be subject to periodic check weighing on the Contractor's vehicle scales, or other scales designated, according to 00190.20. If the check weight is less than the supplier weight by more than 0.4%, the discrepancy will be resolved by the Engineer.

No payment will be made:

- For quantities in excess of the supplier weight
- When Materials have been lost, wasted, or otherwise not incorporated into the Work
- For additional hauling costs resulting from the check weighing

(e) Volume Basis - Volume will be cubic yard truck measure or in-place measure, gallons, foot board measure (FBM), or thousand foot board measure (MFBM), unless otherwise specified in the Contract and will be measured at least to the nearest 0.1 cubic yard, nearest 1.0 gallon, nearest 0.1 FBM, or nearest 0.1 MFBM, as applicable, unless otherwise specified in the Contract.

Truck measure will be the measured and calculated maximum "water level" capacity of the vehicle. Quantities will be determined at the point of delivery, with no allowance for settlement of Material during transit. When required to facilitate measurement, the vehicle load shall be leveled at the point of delivery. Payment will not be made for Material in excess of the maximum "water level" capacity. Deductions will be made for loads below the maximum "water level" capacity.

When bituminous materials are measured by volume, the volume will be measured at 60 °F or will be corrected to the volume at 60 °F using the correction factors found in the MFTP (ODOT TM 321).

(f) Time Basis - Time will be hour, Day, or year, unless otherwise specified in the Contract, and will be measured to at least the nearest 0.5 hour, nearest 1.0 Day, or nearest 1.0 year, as applicable, unless otherwise specified in the Contract.

(g) Standard Manufactured Items - If standard manufactured items, such as fence, wire, plates, rolled shapes, pipe, conduit and other similar items are specified in the Contract by properties such as gauge, unit weight, or section dimensions, the manufacturing tolerances established by the industry involved will be accepted unless more stringent tolerances are cited in the Contract.

(h) Lump Sum Basis - Lump sum, when used, means the Work described shall be completed and accepted without measurement unless changes are ordered in writing by the Engineer. If estimated quantities of the Work to be performed are listed in the Special Provisions, they provide only a basis for adjusting payment amounts. Estimated quantities are approximate only, and are made from a reasonable interpretation of the Contract Documents. Computations based on the details and dimensions shown on the Contract Documents are not guaranteed to equal estimated quantities.

If the Agency issues no Change Order, the Agency will make no pay adjustment for quantities based on the Contractor's computations that overrun or underrun the estimated quantities.

If the Agency issues Change Orders for changes in the Work, the Engineer will measure such changes according to the standards set by 00195.20 to determine adjustment of payment.

00190.20 Contractor to Provide Vehicle Weigh Scales:

(a) General - If the Specifications require measurement by weighing on vehicle weigh scales, the Contractor shall provide vehicle weigh scales and shall transport Materials to the scales. Subject to the Engineer's approval, weights may be determined by plant or hopper scales according to 00190.30.

Contractor-provided scales shall be furnished, installed and maintained by the Contractor or its supplier, or, subject to the Engineer's approval, may be commercial scales located in the vicinity of the Project.

Unless otherwise provided in the Contract, Pay Items to be measured by weight shall include all Contractor costs for providing, maintaining, inspecting, and testing scales; for furnishing appropriate weigh tickets; for self-printing scales; and for transporting Materials to the scales or to check weighing.

(b) Requirements - The scales shall conform to ORS Chapter 618, or the laws of the state in which they are located, and NIST *Handbook 44*, and shall be:

- Licensed by the Oregon Department of Agriculture, or by the analogous regulatory body for scales located outside the State;
- Technically suitable for weighing the Materials;
- Properly installed and maintained; and
- Accurate to the required tolerances.

The weight of any Materials weighed by anyone other than the Engineer will be subject to check weighing as the Engineer directs.

(c) Approaches - Vehicle scale approaches shall be:

- At each end of the scale platform;
- Straight and in line with the platform; and
- Long enough to accommodate combination vehicles longer than the scale platform so that they are level and allow release of brakes before weighing.

(d) Inspections - Contractor shall have all scales certified, that is inspected and their accuracy tested, by the Oregon Department of Agriculture, an analogous regulatory body for scales located outside the State, or a scale service company, as follows:

- Before use if installed at a new site;
- 60 Calendar Days after initial inspection;
- As otherwise required by the Oregon Department of Agriculture, or an analogous regulatory body for scales located outside the State; and
- When the Engineer directs additional inspections.

No Materials weighed on scales without current certifications according to this Subsection will be accepted. The Contractor shall provide a copy of all required certifications to the Engineer.

Testing by a scale service company within the State of Oregon shall comply with ORS Chapter 618.

If additional inspections directed by the Engineer confirm that the scale accuracy is within the required tolerances, the Agency will pay the cost for inspecting and testing the scales. If the scale

accuracy is not within these tolerances, the Contractor shall pay the cost for inspecting and testing the scales.

(e) Inspection Results - If an inspection indicates the scales have been under-weighing (indicating less than the true weight), the Agency will make no additional payment to the Contractor for Materials previously weighed.

If an inspection indicates the scales have been over-weighing (indicating more than the true weight), the weights will be reduced for Materials received after the time the Engineer determines the overweighing began or, if that is not possible, after the last acceptable certification of the scales. The reduction will be the amount of error in excess of the 0.2% maintenance tolerance allowed in the Contract.

(f) Contractor-Provided Weigh Technician - The Contractor shall provide a technician to operate Contractor-provided vehicle weigh scales. The Agency may observe procedures and require check weighing according to the following:

(1) Scale with Automatic Printer - If the scales have an automatic weigh memo printer that does not require manual entry of gross weight information, the Agency may periodically have a representative at the scales to observe the weighing procedures. In addition, the Engineer may periodically check the weight for a load of Materials by directing the haul vehicle to reweigh on a different scale that has been inspected and certified according to 00190.20(b) and 00190.20(d).

If a different scale is not available within a 30-mile round trip from the regular haul route, the Agency will allow check weighing on an approved alternate basis. Check weights within 0.4% of the Contractor-provided weight are acceptable.

The Engineer will resolve discrepancies found by check weighing. Agency employee costs will be paid by the Agency. The Contractor shall pay all other costs resulting from the check weighings, including, without limitation, the use of other scales.

When 2,000 tons or less of all types of Materials are received from a scale, check weighing will be at the discretion of the Engineer.

The Contractor shall make at least one check weighing on projects where more than 2,000 Tons of all types of Materials are received from a scale. If more than 50 Tons per Day of all types of Materials are received from a scale, the Contractor shall make random check weighings at least once every ten Days on which more than 50 Tons is received or at each interval that 10,000 Tons has been weighed, whichever occurs first, or as directed by the Engineer. The check weighing frequency does not apply to total quantities less than 2,000 Tons of all types of Materials from a scale. The Contractor shall provide the Engineer with the results of the check weighing.

(2) Scale Without Automatic Printer - If the scales require manual entry of gross weight information, the Agency may periodically have a representative weigh witness at the scales to observe the weighing procedures. The Contractor shall inform the Engineer of his intent to use a scale without an automatic printer at least 3 working days before weighing begins or before the Contractor changes to a scale that does not have an automatic printer. The Contractor shall pay costs for the weigh witness. The hourly cost of the weigh witness will be as stated in the Special Provisions. In addition, the Engineer may periodically check the weight for a load of Materials by directing the haul vehicle to reweigh on a different scale that has been inspected and certified according to 00190.20(b) and 00190.20(d).

If a different scale is not available within a 30-mile round trip from the regular haul route, the Agency will allow check weighing on an approved alternate basis. Check weights within 0.4% of the Contractor-provided weight are acceptable.

The Engineer will resolve discrepancies found by check weighing. Agency employee costs for check weighings will be paid by the Agency. The Contractor shall pay all other costs resulting from the check weighings, including, without limitation, the use of other scales.

If more than 50 tons per Day of all types of Materials are received from a scale, the Contractor shall make random check weighings at least every tenth day on which more than 50 tons is received or at each interval that 10,000 tons has been weighed, whichever occurs first, or as directed by the Engineer. The Contractor shall make at least one check weighing on all projects where materials are received from a scale without an automatic printer. The Contractor shall provide the Engineer with the results of the check weighing.

(3) Duties of Weigh Technician - The Contractor's weigh technician shall:

- Determine twice a Day, or as otherwise directed by the Engineer, the empty haul weights (tare weights) of hauling vehicles, unless vehicles are tared before each load;
- Furnish daily a listing of the tare weights if 10 or more loads are hauled during that Day;
- Furnish a note listing the net weight for each consecutive ten loads with the following load;
- Furnish a daily listing of the net weights and total weight for each type of Material hauled during that Day; and
- Furnish a legible, serially numbered weigh memo for each load of Materials to the Agency's Materials receiver at the point of delivery, or as directed by the Engineer. The memo shall identify the Project, the Materials, the date, net weight (gross and tare as appropriate), and identification of the vehicle and weigh technician.

(g) Agency-Provided Weigh Technician - If the Contractor provides vehicle weigh scales without a weigh technician meeting the requirements of this Subsection, the Agency will provide a weigh technician at the Contractor's expense. The hourly cost for the weigh technician will be as stated in the Special Provisions. The Contractor shall provide a weighhouse for the weigh technician as specified in the Special Provisions. The Agency's weigh technician will:

- Determine tare weights;
- Prepare weigh memos for each load;
- Compile the weigh records; and
- Not participate in the production of Materials or the loading of haul vehicles.

00190.30 Plant Scales - The Contractor, with the Engineer's written approval, may weigh plant-mixed Materials on scales that have either:

- An automatic weight batching and mixing control printer system; or
- A weigh hopper printer system.

Any additional costs resulting from the use of these scales shall be borne by the Contractor. Check weighing will be done according to 00190.20(f).

Except for 00190.20(c) regarding approaches, the Contractor's use of plant scales shall comply with all provisions of 00190.20.

The Engineer's approval for the Contractor's use of plant scales to determine pay weights will be rescinded if check weighing or scale inspections indicate the scales do not consistently determine weights within the tolerances allowed by state law.

Section 00195 - Payment

Description

00195.00 Scope and Limit:

(a) General - The Agency will pay only for measured Pay Item quantities incorporated into the Work or performed according to the terms of the Contract. The Contractor understands and agrees that Pay Item quantities listed in the Schedule of Items do not govern payment.

Payment constitutes full compensation to the Contractor for furnishing all Materials, Equipment, labor, and Incidentals necessary to complete the Work; and for risk, loss, damage, and expense arising from the nature or prosecution of the Work or from the action of the elements, subject to the provisions of 00170.80. The Contractor shall include the costs of bonds and insurance for the Project in the unit price for each Pay Item of Work to be performed.

(b) Essential or Incidental Materials or Work - When the Specifications state that the unit price for a Pay Item is compensation for certain Materials or Work essential or Incidental to the Pay Item, the same Materials or Work will not be measured or paid under any other Pay Item.

Provisions and Requirements

00195.10 Payment For Changes in Materials Costs - On certain projects, as identified in the Special Provisions, an escalation/de-escalation clause with respect to certain materials will be in effect during the life of the Contract.

00195.12 Steel Material Price Escalation/De-Escalation Clause - Subsections 00195.12, 00195.12(a), 00195.12(b), 00195.12(c), and 00195.12(d) contain the price escalation/de-escalation clause relating to steel materials (as defined in 00195.12(d)) that is included in this Contract. This exclusive steel material price escalation/de-escalation clause, and the steel escalation/de-escalation program described in 00195.12 through 00195.12(d), are in effect for the life of this Contract regardless of the number of steel material Pay Items, if any, that are included, and whether or not the Contractor elects to participate in the steel escalation/de-escalation program according to 00195.12(d).

(a) Steel Material Price Escalation/De-Escalation Participation - The Contractor may select individual Pay Items to include in the steel escalation/de-escalation program from those Pay Items listed for this Project under 00195.12(d) by following the directions provided in 00195.12(d). The Contractor is not obligated to select any Pay Items. Before or within seven Calendar Days after the date of the preconstruction conference, the Contractor shall submit in writing to the Project Manager the Pay Items selected by the Contractor to be included in the steel escalation/de-escalation program, in the manner required under 00195.12(d). If the Contractor elects to not participate in the steel escalation/de-escalation program for the Project, no response from the Contractor is required. If the Contractor fails to inform the Project Manager of Pay Items to include in the steel escalation/de-escalation program in the manner and within the time limits stated in 00195.12(d) (or the Contractor otherwise elects not to participate in the program), the Contractor thereby elects not to participate in the program and forfeits all present and future rights to participate in the program for this Project.

The Agency reserves all of its rights under the Contract, including, but not limited to, its rights for suspension of the Work under 00180.70 and its rights for termination of the Contract under 00180.90, and this steel material price escalation/de-escalation provision will not limit those rights. Adjustment for fluctuations in the cost of steel material will apply only to the Pay Items individually selected by the Contractor from the Pay Items listed under 00195.12(d), and will be made using the respective steel cost basis (CB) listed.

(b) Monthly Steel Materials Value (MV) and Base Steel Materials Value (BV) - The Monthly Steel Materials Value (MV) will be established by the Agency from the IDWPUSISTEEL1 Bureau of Labor Statistics (BLS), Producer Price Indexes (PPI) using non-seasonally adjusted indexes only. Preliminary numbers may be referenced on the IDWPUSISTEEL1 BLS PPI for 6 months or more before IDWPUSISTEEL1 BLS PPI determines they are final numbers.

The Base Steel Materials Value (BV) for this Project will be the MV published on the ODOT Estimating website (see 00110.05(e)) for the month of the Bid Opening for this Project. The Agency will only publish values on the ODOT Estimating website for use after the IDWPUSISTEEL1 BLS PPI establishes the numbers as final numbers. The final values of MV and BV will be available at the ODOT Estimating website.

The Agency has no control of when the IDWPUSISTEEL1 BLS PPI establishes final values. The Agency steel material price escalation/de-escalation adjustments made under 00195.12 through 00195.12(d) may not be reflected on payments made to the Contractor for up to 2 months after the IDWPUSISTEEL1 BLS PPI applicable values become final. This timing for steel material price escalation/de-escalation adjustments is an agreed term of this Contract and shall not constitute late payment under ORS 279C.570, nor shall the Agency be responsible to pay interest on any such steel material price adjustments.

If the Agency-selected index ceases to be available for any reason, the Agency in its discretion will select and begin using a substitute price source or index to establish the MV each month. The MV will only apply to Pay Items selected by the Contractor and provided in writing to the Project Manager from the Pay Item list contained under, and in the manner and within the time limits required by, 00195.12(d). The Agency does not guarantee that steel material will be available at any stated or implied materials price.

(c) Monthly Steel Materials Price Adjustment - If the Contractor has properly informed the Project Manager of Pay Items to include in the steel escalation/de-escalation program as required by 00195.12(a) and 00195.12(d), a price adjustment evaluation will be made for the Pay Items individually selected. No adjustments will be made using the BV or MV until such time as they are listed as final values by the IDWPUSISTEEL1 BLS PPI. The price adjustment as calculated in this provision for a given Pay Item will use the MV for the month the Work associated with that Pay Item is performed and added to the monthly progress estimate. A price adjustment for that Pay Item will only be made if the MV for the month the Work associated with the Pay Item is performed and added to the monthly progress estimate differs by more than 10% from the BV. A price adjustment will be made, as and when required by 00195.12 through 00195.12(d), only for the Pay Items, if any, that were selected by the Contractor in the manner and within the time limits required under 00195.12(a) and 00195.12(d).

The Monthly Steel Materials Price Adjustment will be determined as follows:

- If the MV is within 10% \pm of the BV, there will be no adjustment.
- If the MV is more than 110% of the BV, then:

$$PA = (((MV - BV) \div BV) - 0.10) \times (CB \times PIP)$$
- If the MV is less than 90% of the BV, then:

$$PA = (((MV - BV) \div BV) + 0.10) \times (CB \times PIP)$$

Where:

PA = Price Adjustment, dollars

MV = Monthly Steel Materials Value from BLS PPI for the month determined above (after becomes final)

BV = Base Steel Materials Value from month of the Bid Opening (after becomes final)

PIP = Amount paid for the Pay Item for the month for which the adjustment is made

CB = Cost Basis for the applicable steel material, in percent (see 00195.12(d))

(d) Steel Materials Pay Item Selection - The Agency has a process using estimated quantities to determine which Pay Items containing steel material qualify for the steel escalation/de-escalation program by meeting a minimum threshold, and are therefore included in the eligible Pay Items listed in the Special Provisions.

For purposes of 00195.12 through 00195.12(d), "steel material" means structural and reinforcing steel, steel studs, sheet piling, guardrail, ductile iron pipe and other steel products used for the construction, reconstruction or major renovation of a road or Highway.

The Contractor may elect to participate in the steel escalation/de-escalation program for this Project by marking the list in the Special Provisions, checking each box next to each Pay Item the Contractor wants included in the program and submitting this information in writing, signed and dated by the Contractor, to the Project Manager before or within 7 Calendar Days after the date of the preconstruction conference. The steel material price escalation/de-escalation clause for price adjustments for fluctuations in the cost of steel material will apply only to the Pay Items selected by the Contractor, from the Pay Item list included in the Special Provisions, and provided in writing to the Project Manager in the manner and within the time limits stated above.

If the Contractor fails to inform the Project Manager of Pay Items to include in the steel escalation/de-escalation program in the manner and within the time limits stated above (or the Contractor otherwise elects not to participate in the program), the Contractor thereby elects not to participate in the program and forfeits all present and future rights to participate in the program for this Contract and this Project.

00195.20 Changes to Plans or Character of Work:

(a) Insignificant Changed Work - If the changes made under 00140.30 do not significantly change the character or unit cost of the Work to be performed under the Contract, the Agency will pay for such Work at the Pay Item price.

If the Work involved in the change is measured on a lump sum basis and its character is not significantly changed, payment for the Changed Work will be determined:

- As described in the applicable Section of the Specifications;
- If not described there, on a theoretical unit price determined by dividing the Contractor's lump sum price by the estimated quantity of the Pay Item listed in the Special Provisions; or
- If neither of the above apply, the Engineer will make an equitable adjustment.

(b) Significant Changed Work - If the changes made under 00140.30 significantly alter the character, unit cost, or lump sum cost of the Work, the Agency will adjust the Contract. Adjustments will exclude any loss of anticipated profits. The parties shall agree upon the basis for payment and the amount of adjustment prior to the Contractor commencing the Changed Work. If the basis and amount cannot be agreed upon, the Engineer will make an equitable adjustment, which may increase or decrease the Contract Amount and Contract Time.

Any such adjustments may be less than, but will not be more than the amount justified by the Engineer on the basis of the established procedures set out in Section 00197 for determining rates. This does not limit the application of Section 00199.

The term "Significant Changed Work" shall apply only to that circumstance in which the character of the Work, as changed, differs materially in kind, nature, or unit cost from that involved or included in the originally proposed construction.

00195.30 Differing Site Conditions - Upon written notification, as required in 00140.40, the Engineer will investigate the identified conditions. If the Engineer determines that the conditions materially differ and cause an increase or decrease in the cost or time required to perform any Work under the Contract, an adjustment in the Contract Amount or Contract Time, excluding loss of anticipated profits, will be made, and the Contract modified accordingly, in writing. The Engineer will notify the Contractor as to whether or not an adjustment of the Contract is warranted.

No Contract adjustment which benefits the Contractor will be allowed unless the Contractor has provided the required written notice. Any such adjustments will be made according to 00195.20.

00195.40 Unreasonable Delay by the Agency - If the Contractor believes that performance of all or any portion of the Work is suspended, delayed, or interrupted for an unreasonable period of time in excess of that originally anticipated or customary in the construction industry, due to acts or omissions of the Agency, or persons acting for the Agency, and that additional compensation, Contract Time, or both, are due the Contractor because of the suspension, delay or interruption, the Contractor shall immediately file a written notice of delay according to 00180.60. The Contractor shall then promptly submit a properly supported request for any additional compensation, Contract Time, or both, according to the applicable provisions in 00180.60 through 00180.80 and Section 00199.

The Engineer will promptly evaluate a properly submitted request for additional compensation. If the Engineer determines that the delay was unreasonable, and that the cost required for the Contractor to perform the Contract has increased as a result of the unreasonable suspension, delay or interruption, the Engineer will make an equitable adjustment, excluding profit, and modify the Contract in writing accordingly. The Engineer will notify the Contractor of the determination and whether an adjustment to the Contract is warranted.

Under this provision, no Contract adjustment will be allowed:

- Unless the Contractor has provided the written notice required by 00180.60;
- For costs incurred more than 10 Calendar Days before the Engineer receives the Contractor's properly submitted written request;
- For any portion of a delay that the Engineer deems to be a reasonable delay, or for which an adjustment is provided for or excluded under other terms of the Contract; or
- To the extent that performance would nevertheless have been suspended, delayed or interrupted by causes other than those described in this Subsection.

00195.50 Progress Payments and Retained Amounts:

(a) Progress Payments - The Agency's payment of progress payments, or determination of satisfactory completion of Pay Items or Work or release of retainage under 00195.50(d), shall not be construed as Final Acceptance or approval of any part of the Work, and shall not relieve the Contractor of responsibility for defective Materials or workmanship or for latent defects and warranty obligations.

The estimates upon which progress payments are based are not represented to be accurate estimates. All estimated quantities are subject to correction in the final estimate. If the Contractor uses these estimates as a basis for making payments to Subcontractors, the Contractor assumes all risk and bears any losses that result.

If the estimated amount due the Contractor for any given month is less than \$1,000, the Agency will make no payment for that month unless requested by the Contractor.

(1) Progress Estimates - At the same time each month, the Contractor will make an estimate of the amount and value of Pay Item Work completed. The amount of Work completed will be the sum of the estimated number of units completed for unit price Pay Items plus the estimated percentage completed of lump sum Pay Items.

The estimated value of the Work completed will then be determined by using the Contract unit price for unit price Pay Items, and by using one of the following methods to determine the value of the lump sum Pay Items:

- The "theoretical unit price", when the Special Provisions contain an estimated number of units;
- A Contractor-submitted, Engineer-approved Schedule of Values, when there is no theoretical unit price available; or
- Engineer's determination, when there is neither an available theoretical unit price, nor an approved, Contractor-submitted Schedule of Values.

The amounts to be allowed for lump sum Pay Items in progress payments will not exceed the reasonable value of the Work performed, as determined by the Engineer.

Incidentals such as formwork, falsework, shoring, and cribbing shall be included in the unit prices for the various Pay Items requiring their use, unless specified as a separate Pay Item. No payment will be made for Pay Items that include Incidentals until units or portions of such Pay Item Work are in place and completed. The costs of Incidentals will be paid in proportion to the percentage of Pay Item Work completed.

(2) Value of Materials on Hand - The Contractor will also make an estimate of the amount and value of acceptable Materials on hand, (i.e., already delivered and stored) according to 00195.60(a), to be incorporated into the Work.

(3) Value of Work Accomplished - The sum of the values in (1) and (2) above will be collectively referred to in this Subsection as the "value of Work accomplished", subject to (4) below.

(4) Limitations on Value of Work Accomplished - In determining the "value of Work accomplished", the Engineer's estimate will be based on the unit prices for the various Pay Items. Any amounts not included in progress payments due to substantial mathematical unbalancing of Pay Item prices will be included in the final payment issued according to 00195.90(b).

(5) Reductions to Progress Payments - With each progress payment, the Contractor will receive a Contract payment voucher and summary setting forth the value of Work accomplished reduced by the following:

- Amounts previously paid;
- Amounts deductible or owed to the Agency for any cause specified in the Contract;
- Additional amounts retained to protect the Agency's interests according to Subsection (e) below.

(b) Retainage - The Agency reserves the right in its sole discretion to not withhold retainage from progress payments or to begin withholding retainage at any time. If the Agency withholds retainage from progress payments, the amount to be retained from progress payments will be 5% of the value of Work accomplished, and will be retained in one of the forms specified in Subsection (c) below.

No retainage will be withheld from Work performed as Force Account Work, escalation/de-escalation, bonuses, or other items decided by the Agency.

As provided in 00170.65(b)(3) in addition to any retainage, a withholding of 25% of amounts earned will be withheld and released according to ORS 279C.845 when the Contractor fails to file the certified statements required in ORS 279C.845, FHWA Form 1273, and 00170.65.

(c) Forms of Retainage - If the Agency withholds retainage, forms of acceptable retainage are specified below in Subsections (1) through (3). Unless the Contractor requests and the Agency accepts a form of retainage under Subsections (2) or (3), the Agency will use the "Cash, Alternate A" in this Subsection. If the Agency incurs additional costs as a result of the Contractor's election to use a form of retainage other than Cash, Alternate A, the Agency may recover such costs from the Contractor by a reduction of the final payment.

(1) Cash, Alternate A - Retainage will be deducted from progress payments and held by the Agency until final payment is made according to 00195.90, unless otherwise specified in the Contract.

Except as otherwise provided, the Agency will deposit the cash retainage withheld in an interest-bearing escrow account as required by ORS 279C.570(2). The Contractor shall execute such documentation and instructions respecting the interest-bearing escrow account as the Agency may require to protect its interests, including but not limited to a provision that no funds may be paid from the account to anyone without the Agency's advance written authorization. Interest earned on the account shall accrue to the Contractor. Amounts retained and interest earned will be included in the final payment made according to 00195.90, unless otherwise specified in the Contract.

For a contract over \$500,000, if the Contractor requests that the Agency deposit the retainage in an interest-bearing account under ORS 279C.560(5), the Agency will use the "Cash, Alternate A" in this Subsection. For a contract \$500,000 or less, if the Contractor requests that the Agency deposit the retainage in an interest-bearing account under ORS 279C.560(5), the Agency will use an interest-bearing account (in a bank, savings bank, trust company, or savings association) as provided under ORS 279C.560(5).

Any retainage withheld on Work performed by a Subcontractor will be released to the Contractor according to 00195.50(d).

(2) Cash, Alternate B (Retainage Surety Bond) - Upon receipt of an approved retainage surety bond, the Agency will limit the amount of cash retainage withheld to \$10,000, which will be deposited in an interest-bearing escrow account as described in (1) above. The surety bond must be in the bond form provided by the Agency. The bond must be provided by the same Surety that provides the Performance and Payment Bonds.

If the Contractor elects this form of retainage, the Agency will withhold from progress payments up to 2.5% of the value of the Work accomplished as cash retainage until the retained amount equals \$10,000. After that amount is retained, no further cash retainage will be withheld until the additional required retainage that would have been withheld exceeds the face amount of the retainage surety bond provided. Thereafter, retainage will be withheld from progress payments according to these Specifications. According to 00195.50(b), if at any time the Agency determines that satisfactory progress is not being made on the Work, the Agency may withhold up to 5% of the value of the Work accomplished from subsequent progress payments.

If an acceptable retainage surety bond is provided, the Contractor shall notify all Subcontractors of the existence of the retainage surety bond and shall advise them of their rights under ORS 279C.560(7) and ORS 701.435.

Amounts retained and interest earned will be included in the final payment made according to 00195.90, unless otherwise specified in the Contract.

Any retainage withheld on Work performed by a Subcontractor shall be released to the Contractor according to 00195.50(d).

(3) Bonds, Securities, and Other Instruments - In accordance with ORS 279C.560, unless the Agency finds in writing that accepting a bond, security or other instrument poses an extraordinary risk that is not typically associated with the bond, security or other instrument, the Agency will approve the Contractor's written request to deposit bonds, securities or other instruments with the Agency or in a custodial account or other account satisfactory to the Agency with an approved bank or trust company, to be held instead of cash retainage for the benefit of the Agency. In such event, the Agency will reduce the cash retainage by an amount equal to the value of the bonds, securities and other instruments. Interest or earnings on the bonds, securities and other instruments shall accrue to the Contractor.

Bonds, securities and other instruments deposited instead of cash retainage shall be assigned to or made payable to the Agency and shall be of a kind approved by the Director of the Oregon Department of Administrative Services, including, but not limited to:

- Bills, certificates, notes or bonds of the United States;
- Other obligations of the United States or agencies of the United States;
- Obligations of a corporation wholly owned by the federal government;
- Indebtedness of the Federal National Mortgage Association;
- General obligation bonds of the State of Oregon or a political subdivision of the State of Oregon;
- Irrevocable letters of credit issued by an insured institution, as defined in ORS 706.008.

The Contractor shall execute and provide such documentation and instructions respecting the bonds, securities and other instruments as the Agency may require to protect its interests. When the Engineer determines that all requirements for the protection of the Agency's interest have been fulfilled, the bonds and securities deposited instead of cash retainage will be released to the Contractor.

(d) Release of Retainage - As the Work progresses, release of the amounts retained under (b) above will only be considered for Pay Items that have been satisfactorily completed. For purposes of this Subsection, a Pay Item will be considered satisfactorily completed only if all of the Work for the Pay Item is complete and all contractual requirements pertaining to the Pay Item and Work have been satisfied. Work not included in a Pay Item, or which constitutes part of an uncompleted Pay Item, will not be regarded as satisfactorily completed Work for the purposes of this Subsection.

Beginning with the fourth month after First Notification and every third month thereafter, the Agency will release retainage for satisfactorily completed Pay Items in the Schedule of Items, or for satisfactorily completed Pay Items added by Contract Change Order. Retainage will be released with the scheduled progress payment for the fourth month after First Notification and with the scheduled progress payment for each third month thereafter. Within 10 Calendar Days of receipt of retainage, the Contractor shall pay to each Subcontractor all such released retainage that pertains to the Work of that Subcontractor.

A determination of satisfactory completion of Pay Items or Work or release of retainage shall not be construed as acceptance or approval of the Work and shall not relieve the Contractor of responsibility for defective Materials or workmanship or for latent defects and warranty obligations.

The Contractor shall comply with all applicable legal requirements for withholding and releasing retainage and for prompt payments, including but not limited to those in ORS Chapters 279C and 701, and 49 CFR 26.29.

(e) Withholding Payments - The Engineer may withhold such amounts from progress payments or final payment as may reasonably protect the Agency's interests until the Contractor has:

- Complied with all orders and directives issued by the Engineer under or pursuant to the Contract;
- Corrected or cured its failure to comply with the Contract;
- Satisfied all legal actions filed against the Agency, the Agency's governing body and its members, and Agency employees that the Contractor is obliged to defend. (See 00170.72.); and
- Paid all liquidated and delinquent debt owed to the State or any department or agency of the State. (In addition to Agency's other rights and remedies, the Agency may also undertake collection by administrative offset, or garnishment if applicable, of all monies due to recover such debt. Offsets or garnishment may be initiated after the Contractor has been given notice if required by law.)

Notwithstanding ORS 279C.555 or ORS 279C.570 or 00195.50(d), if a Contractor is required to file statements on the prevailing rate of wages, but fails to do so, the Agency will withhold 25% of any amount earned as required in 00170.65.

(f) Prompt Payment Policy - Payments shall be made promptly according to ORS 279C.570, ORS 279C.580 and other applicable legal requirements.

00195.60 Advance Allowance for Materials on Hand:

(a) General - If the total value of Materials on hand is at least \$1,000, or the total value of a single class of Materials on hand is at least \$500, the Engineer may authorize an advance allowance for the Materials in the progress payments. The Agency will not make advance allowances on the Materials unless the following three conditions are satisfied:

(1) Request for Advance Allowance - If Materials on hand meet the requirement of (2) below, an advance allowance will be made if:

- A written request for advance allowance for Materials on hand has been received by the Engineer at least 5 Calendar Days before the pay period cutoff date; and
- The request is accompanied by written consent of the Contractor's Surety, if required by the Agency.

(2) Stored or Stockpiled Conditions - The Materials shall have been delivered and/or acceptably stored or stockpiled according to the Specifications and as follows:

- At the Project Site;
- On Agency-owned property;
- On property in the State of Oregon on which the property owner has authorized storage in writing. The written authorization must allow the Agency to enter upon the property and remove Materials for at least 6 months after completion of the Project. The Contractor shall furnish a copy of the written permission to the Agency; or
- On property outside the State of Oregon on which the property owner has authorized storage in writing, provided that such storage location is allowed by the Special Provisions

or authorized in writing by the Engineer. The permit must allow the Agency to enter upon the property and remove Materials for at least 6 months after completion of the Project. The Contractor shall furnish a copy of the written permission to the Agency.

To be eligible for advance allowance, the Materials shall:

- Meet Specification requirements;
- Have the required Materials conformance and quality compliance documents on file with the Engineer (see Section 00165);
- Be in a form ready for incorporation into the permanent Work; and
- Be clearly marked and identified as being specifically fabricated, or produced, and reserved for use on the Project.

(3) Responsibility for Protection - The Contractor has full control and responsibility for the protection of Materials on hand from the elements and against damage, loss, theft, or other impairment until the entire Project has been completed and accepted by the Agency.

If Materials are damaged, lost, stolen, or otherwise impaired while stored, the monetary value advanced for them, if any, will be deducted from the next progress payment.

If these conditions in 00195.60(a)(1) through 00195.60(a)(3) have been satisfied, the amount of advance allowance, less the retainage described in 00195.50, will be determined by one of the following methods as elected by the Engineer:

- Net cost to the Contractor of the Materials, f.o.b. the Project Site or other approved site; or
- Price (or portion of it attributable to the Materials), less the cost of incorporating the Materials into the Project, as estimated by the Engineer.

(b) Proof of Payment - The Contractor shall provide the Engineer with proof of payment to the materials Suppliers for purchased Materials within 30 Calendar Days of the date of the progress payment that includes the advance allowance.

If proof of payment is not provided, sums advanced will be deducted from future progress payments, and the Engineer will not approve further prepayment advance allowance requests.

(c) Terminated Contract - If the Contract is terminated, the Contractor shall provide the Agency immediate possession of all Materials for which advance allowances have been received, as provided above. If, for any reason, immediate possession of the Materials cannot be provided, the Contractor shall immediately refund to the Agency the total amount advanced for the Materials. The Agency may deduct any amount not so refunded from final payment.

00195.70 Payment under Terminated Contract - Payment for Work performed under a Contract that is terminated according to the provisions of 00180.90 will be determined under (a) or (b) of this Subsection.

(a) Termination for Default - Upon termination of the Contract for the Contractor's default, the Agency will make no further payment until the Project has been completed. The Agency will make progress payments to the party to whom the Contract is assigned, but may withhold an amount sufficient to cover anticipated Agency costs, as determined by the Engineer, to complete the Project.

Upon completion of the Project, the Engineer will determine the total amount that the defaulting Contractor would have been entitled to receive for the Work, under the terms of the Contract, had the Contractor completed the Work (the "cost of the completed Work").

If the cost of the completed Work, less the sum of all amounts previously paid to the Contractor, exceeds the expense incurred by the Agency in completing the Work, including, without limitation, expense for additional managerial and administrative services, the Agency will pay the excess to the Contractor, subject to the consent of the Contractor's Surety.

If the expense incurred by the Agency in completing the Work exceeds the Contract Amount, the Contractor or the Contractor's Surety shall pay to the Agency the amount of the excess expense.

The Engineer will determine the expense incurred by the Agency and the total amount of Agency damage resulting from the Contractor's default. That determination will be final as provided in 00150.00.

If a termination for default is determined by a court of competent jurisdiction to be unjustified, it shall be deemed a termination for public convenience, and payment to the Contractor will be made as provided in Subsection (b) below.

(b) Termination for Public Convenience:

(1) General - Full or partial termination of the Contract shall not relieve the Contractor of responsibility for completed or performed Work, or relieve the Contractor's Surety of the obligation for any just claims arising from the completed or performed Work.

(2) Mobilization - If mobilization is not a separate Pay Item, and payment is not otherwise provided for under the Contract, the Agency may pay the Contractor for mobilization expenses, including moving Equipment to and from the Project Site. If allowed, payment of mobilization expenses will be based on cost documentation submitted by the Contractor to the Engineer.

(3) All Other Work - The Agency will pay the Contractor at the unit price for the number of Pay Item units of completed, accepted Work. For units of Pay Items partially completed, payment will be as mutually agreed, or, if not agreed, as the Engineer determines to be fair and equitable. No claim for loss of anticipated profits will be allowed. The Agency will purchase Materials left on hand according to 00195.80.

00195.80 Allowance for Materials Left on Hand:

(a) Purchase of Unused Materials - If Materials are delivered to the Project Site, or otherwise acceptably stored at the order of the Engineer, but not incorporated into the Work due to complete or partial elimination of Pay Items, changes in Plans, or termination of the Contract for public convenience according to 00180.90, and it is not commercially feasible for the Contractor to return them for credit or otherwise dispose of them on the open market; the Agency will purchase them according to the formula and conditions specified in Subsection (b) below.

(b) Purchase Formula and Conditions:

(1) Formula - The Agency will apply the following formula in determining the Contractor's allowance for Materials left on hand:

Contractor's Actual Cost, plus 5% Overhead Allowance, minus Advance Allowances under 00195.60, but no markup or profit.

(2) Conditions - The Agency will not purchase the Contractor's Materials left on hand unless the Contractor satisfies the following conditions:

- Requests the Agency's purchase of unused Materials;

- Shows acquisition of the Materials according to 00160.10;
- Shows that the Materials were acquired prior to the Agency change or termination;
- Shows that the Materials meet Specifications; and
- Provides receipts, bills and other records of actual cost of Materials delivered to the designated delivery points.

00195.90 Final Payment:

(a) Final Estimate - As soon as practicable after Final Inspection of the Project, as provided in 00150.90, the Contractor will prepare a final estimate of the quantities of the Pay Items completed. With this estimate of quantities as a base, the total amount due the Contractor will be determined according to the terms of the Contract, including, without limitation, any amounts due for Extra Work performed.

(b) Final Payment - The amount of final payment will be the difference between the total amount due the Contractor and the sum of all payments previously made. All prior partial estimates and payments shall be subject to correction in the final estimate and payment.

After computation of the final amount due, and after Final Acceptance of the Project, final payment will be mailed to the Contractor's last known address as shown in the records of the Agency.

Beginning 30 Calendar Days after the date of Third Notification, interest will begin to accrue at the rate established by ORS 279C.570 on any money due and payable to the Contractor as final payment, determined as described above. No interest will be paid on money withheld due to outstanding amounts owed by the Contractor under the provisions of 00170.10.

(c) No Waiver of Right to Make Adjustment - The fact that the Agency has made any measurement, estimate, determination or certification either before or after completion of the Project, Final Acceptance, Agency assumption of possession of the Project Site, determination of satisfactory completion of Pay Items or Work or release of retainage under 00195.50(d) or payment for any part of the Work, shall not prevent either party from:

- Showing the true amount and character of the Work;
- Showing that any measurement, estimate, determination or certification is incorrect;
- Recovering from the other party damages that may have been suffered because the other party failed to comply with the Contract.

00195.95 Error in Final Quantities and Amounts:

(a) Request for Correction of Compensation - If the Contractor believes the quantities and amounts detailed in the final Contract payment voucher, prepared by the Engineer according to 00195.90, to be incorrect, the Contractor shall submit an itemized statement to the Engineer detailing all proposed corrections.

This statement must be submitted to the Engineer within 90 Calendar Days from the date the voucher was mailed to the Contractor, according to 00195.90(b). Any request for compensation not submitted and supported by an itemized statement within the 90 Calendar Day period will not be paid by the Agency. This does not limit the application of Section 00199.

(b) Acceptance or Rejection of Request:

(1) Consideration of Request - The Engineer will consider and investigate the Contractor's request for correction of compensation submitted according to 00195.95(a), and will promptly advise the Contractor of acceptance or rejection of the request in full or in part.

(2) Acceptance of Request - If the Engineer accepts the Contractor's request(s) in full or in part, the Engineer will prepare a post-final Contract payment voucher, including all accepted corrections, and will forward it to the Contractor.

(3) Rejection of Request - If the Engineer rejects the request(s) in full, the Engineer will issue a written notice of rejection and mail it to the Contractor.

(4) Contractor Objection to Revised Voucher or Notice of Rejection - If the Contractor disagrees with the revised voucher or notice of rejection, the Contractor may request review according to the procedure specified in 00199.40. If the Contractor fails to submit a request for 00199.40 review within 30 Calendar Days after the Engineer mails a post-final Contract payment voucher or notice of rejection, the Contractor waives all rights to a claim based on errors in quantities and amounts.

If the Engineer rejects the Contractor's request on the basis that the issue was not one that qualified for treatment under this Section, no review according to 00199.40 will be allowed.

Section 00196 - Payment for Extra Work**Description**

00196.00 General - Only work not included in the Contract as awarded but deemed by the Engineer to be necessary to complete the Project (see 00140.60) will be paid as Extra Work. Regardless of alterations and changes, any item of Work provided for in the Contract will not constitute Extra Work. Payment for alterations and changes to Work will be made according to 00195.20.

Compensation for Extra Work will be paid only for Work authorized in writing by the Engineer and performed as specified. Work performed before issuance of the Engineer's written authorization shall be at the Contractor's risk. Extra Work will be paid as determined by the Engineer, according to 00196.10 and 00196.20.

Provisions and Requirements

00196.10 Negotiated Price - If the Engineer can reasonably determine a price estimate for Extra Work, the Engineer may then give written authorization to the Contractor to begin the Extra Work. As soon as practicable, but within 10 Calendar Days after that authorization, the Contractor shall respond in writing to the Engineer's Extra Work price estimate by submitting to the Engineer an Extra Work price quote. The price quote shall detail the following items related to the Extra Work:

- Types and amounts of Materials
- Hours of Equipment use and hours of labor
- Travel
- Overhead and profit
- Other costs associated with the proposed Extra Work

Pending approval of the price quote, the Engineer will maintain force account records of the Extra Work. As soon as practicable, but within 10 Calendar Days of receipt of a properly supported price quote, the Engineer will review the price quote and advise the Contractor if it is accepted or rejected. The Engineer will not accept a price quote that cannot be justified on a Force Account basis. If the Contractor's price is accepted, the Engineer will issue a Change Order, and the Extra Work will be paid at the accepted price.

00196.20 Force Account - If the Engineer and the Contractor cannot agree on a price for the Extra Work, the Engineer may issue an Extra Work order requiring the Extra Work to be paid as Force Account Work. Force Account Work records and payment will be made according to Section 00197.

Section 00197 - Payment for Force Account Work

Force Account Work

00197.00 Scope - The Materials, Equipment and labor rates and procedures established in this Section apply to Extra Work ordered by the Engineer to be performed as Force Account Work. With the exceptions identified in 00197.01(b), these rates and procedures also apply to other Work when according to other Sections this Section 00197 applies, including, without limitation, the following:

- 00140.70 - Cost Reduction Proposals
- 00195.20 - Changes to Plans or Character of Work
- 00195.30 - Differing Site Conditions
- 00199.30(b) - Claims Requirements

00197.01 General:

(a) Extra Work on a Force Account Basis - Before ordering Force Account Work, the Engineer will discuss the proposed work with the Contractor, and will seek the Contractor's comments and advice concerning the formulation of Force Account Work specifications. The Engineer is not bound by the Contractor's comments and advice, and has final authority to:

- Determine and direct the Materials, Equipment and labor to be used on the approved Force Account Work; and
- Determine the time of the Contractor's performance of the ordered Force Account Work.

If the Engineer orders the performance of Extra Work as Force Account Work, the Engineer will record, on a daily basis, the Materials, Equipment, labor, and Special Services used for the Force Account Work during that day. The Engineer and the Contractor shall sign the record daily to indicate agreement on the Materials, Equipment, labor, and Special Services used for the Force Account Work performed on that day.

The following shall be reflected on the daily record:

- Materials used in the Force Account Work as directed by the Engineer, except those furnished and paid under rental rates for use of Equipment;
- Equipment that the Engineer considers necessary to perform the Force Account Work. Equipment hours will be recorded to the nearest quarter hour;
- Labor costs, including that of Equipment operators and supervisors in direct charge of the specific operations while engaged in the Force Account Work;
- Special Services; and
- The Engineer's and Contractor's signatures confirming its accuracy.

(b) Other Work - When according to other Sections this Section 00197 applies, the following exceptions apply to the Work under those other Sections, except for Extra Work ordered by the Engineer to be performed as Force Account Work.

- 00197.01(a) does not apply.
- Cost Efficiency - The Agency will not be responsible for additional costs that are a direct or indirect result of the Contractor's inefficient means and methods or that reasonably could have been avoided if the Materials, Equipment, labor or services had been obtained at a more commercially reasonable cost.

- **Standby Time** - Equipment that is necessary for the Work but is not being operated to progress the Work will be considered to be on standby and will be limited to the standby rates and hour limitations in 00197.20(e). Equipment costs will be limited to a combination of operating time and standby time of not more than 8 hours in a 24 hour period or 40 hours in a 1 week period. The Equipment must be onsite and available for use to be eligible for standby time.

For a period of 7 or fewer Calendar Days: If a continuous period of standby time for a piece of Equipment does not exceed 7 Calendar Days, the accumulated standby cost for that continuous period of standby time shall be limited to the standby rates and hour limitations in 00197.20(e).

For a period of more than 7 Calendar Days: Unless the Engineer has otherwise agreed in advance in writing, if a continuous period of standby time for a piece of Equipment exceeds 7 Calendar Days, the accumulated standby cost shall be limited to:

- For the first 7 Calendar Days, the standby rates and hour limitations in 00197.20(e), and
- For the portion of the continuous period of standby time after the first 7 Calendar Days, the lesser of:
 - The standby rates and hour limitations in 00197.20(e); or
 - The cost for moving that piece of Equipment to and from the Project Site according to 00197.20(d).

00197.10 Materials:

(a) General - The Contractor will be paid for Materials actually used in the Force Account Work as directed by the Engineer, except for those furnished and paid for under rental rates included with the use of Equipment. Payments will be at actual cost, including transportation costs to the specified location, from the supplier to the purchaser, whether the purchaser is the Contractor, a Subcontractor, or other forces. All costs are subject to the provisions of this Subsection.

(b) Trade Discount - If a commercial trade discount is offered or available to the purchaser, it shall be credited to the Agency, even though the discount may not have actually been taken. The Agency will not take any discounts for prompt or early payment, whether or not offered or taken.

(c) Not Directly Purchased From Supplier - If Materials cannot be obtained by direct purchase from and direct billing by the supplier, the cost shall be considered to be the price billed to the purchaser less commercial trade discounts, as determined by the Engineer, but not more than the purchaser paid for the Materials. No markup other than actual handling costs will be permitted.

(d) Purchaser-Owned Source - If Materials are obtained from a supply or source wholly or partly owned by the purchaser, the cost shall not exceed the price paid by the purchaser for similar Materials furnished from that source on Pay Items, or the current wholesale price for the Materials delivered to the Project Site, whichever is lower.

00197.20 Equipment:

(a) General - Equipment approved by the Engineer to perform the Force Account Work will be eligible for payment at the established rates only during the hours it is operated or on standby if so ordered by the Engineer. Equipment hours will be recorded on the daily record to the nearest quarter hour.

Except as modified by these provisions, Equipment use approved by the Engineer will be paid at the rental rates given in the most current edition of the EquipmentWatch Cost Recovery (Blue Book)

published by EquipmentWatch, a division of Penton Business Media, Inc., and available from EquipmentWatch (phone 1-800-669-3282).

(b) Equipment Description - On the billing form for Equipment costs, the Contractor shall submit to the Engineer sufficient information for each piece of Equipment and its attachments to enable the Engineer to determine the proper rental rate from the Blue Book.

(c) Rental Rates (without Operator):

(1) Rental Rate Formula - Rental rates for Equipment will be paid on an hourly basis for Equipment and for attachments according to the following formula:

$$\text{Hourly Rate} = \frac{\text{Monthly Base Rate} \times \text{Rate Adjustment Factor}}{176 \text{ hours/month}} + \text{Hourly Operating Rate}$$

Some attachments are considered "standard Equipment" and are already included in the monthly base rate for the Equipment. That information can be obtained from EquipmentWatch.

(2) Monthly Base Rate - The monthly base rate used above for the machinery and for attachments represents the major costs of Equipment ownership, such as depreciation, interest, taxes, insurance, storage, and major repairs.

(3) Rate Adjustment Factor - The rate adjustment factor used above will be determined by applying only the Model Year Adjustment to the Blue Book Rates. The Regional and User Defined Ownership/Operating Adjustments shall not apply.

(4) Hourly Operating Rate - The hourly operating rate used above for the machinery and for attachments represents the major costs of Equipment operations, such as fuel and oil, lubrications, field repairs, tires or ground engaging components, and expendable parts.

(5) Limitations - If multiple attachments are included with the rental Equipment, and are not considered "standard Equipment", only the attachment having the higher rental rate will be eligible for payment, provided the attachment has been approved by the Engineer as necessary to the Force Account Work.

Rental will not be allowed for small tools that have a daily rental rate of less than \$5, or for unlisted Equipment that has a fair market value of \$400 or less.

The above rates apply to approved Equipment in good working condition. Equipment not in good working condition, or larger than required to efficiently perform the work, may be rejected by the Engineer or accepted and paid for at reduced rates.

(d) Moving Equipment - If it is necessary to transport Equipment located beyond the Project Site exclusively for Force Account Work, the actual cost to transport the Equipment to, and return it from, its On-Site Work location will be allowed as an additional item of expense. However, the return cost will not exceed the original delivery cost. These costs will not be allowed for Equipment that is brought to the Project Site for Force Account Work if the Equipment is also used on Pay Item or related Work.

If transportation of such Equipment is by common carrier, payment will be made in the amount paid for the freight. No markups will be allowed on common carrier transportation costs. If the Equipment is hauled with the Contractor's own forces, transportation costs will include the rental rate of the hauling unit and the hauling unit operator's wage. If Equipment is transferred under its own power, the rental rate allowed for transportation time will be 75% of the appropriate hourly rate for the Equipment, without attachments, plus the Equipment operator's wage.

(e) Standby Time - If ordered by the Engineer, standby time will be paid at 40% of the hourly rental rate calculated according to this Subsection, excluding the hourly operating rate. Rates for standby time that are calculated at less than \$1 per hour will not be paid. Payment will be limited to not more than 8 hours in a 24-hour period or 40 hours in a 1 week period.

(f) Blue Book Omissions - If a rental rate has not been established in the Blue Book, the Contractor may:

- If approved by the Engineer, use the rate of the most similar model found in the Blue Book, considering such characteristics as manufacturer, capacity, horsepower, age and fuel type;
- Request EquipmentWatch to furnish a written response for a rental rate on the Equipment, which shall be presented to the Engineer for approval; or
- Request that the Engineer establish a rental rate.

(g) Outside Rental Equipment - If Contractor-owned or Subcontractor-owned Equipment is not available, and Equipment is rented from outside sources, payment will be based on the actual paid invoice.

If the invoice specifies that rental rate does not include fuel, lubricants, field repairs, and servicing, an amount equal to the Blue Book hourly operating cost may be added for those items that were excluded.

The Agency may reduce the payment when the invoice amount plus allowance is higher than the amount authorized under (c) through (f) of this Subsection.

The provisions of 00180.20(c) apply to owner-operated Equipment.

00197.30 Labor - The Contractor will be paid for all labor engaged directly on Force Account Work, including Equipment operators and supervisors in direct charge of the specific force account operations, as follows:

(a) Wages - The actual wages paid to laborers and supervisors, if those wages are paid at rates not more than those for comparable labor currently employed on the Project, or at the recognized, current, prevailing rates in the locality of the Project.

(b) Required Contributions - The actual cost of industrial accident insurance, unemployment compensation contributions, payroll transit district taxes, and social security for old age assistance contributions incurred or required under statutory law and these Specifications. The actual cost of industrial accident insurance is the National Council on Compensation Insurance (NCCI) rate for the assigned risk pool for the appropriate work class multiplied by the experience modification factor for the Contractor.

(c) Required Benefits - The actual amount paid to, or on behalf of, workers as per diem and travel allowances, health and welfare benefits, pension fund benefits, or other benefits when such other benefits are required by a collective bargaining agreement or other employment contract generally applicable to the classes of labor employed on the Project.

00197.40 Invoices for Special Services - Invoices for Special Services that reflect current market pricing may be accepted without complete itemization of Materials, Equipment, and labor costs, if the itemization is impractical or not customary. The invoice for Special Services shall show credit for commercial trade discounts offered or available.

No percentage markup will be allowed other than that specified in 00197.80.

00197.80 Percentage Allowances - To the Contractor's actual costs incurred, as limited in this Section 00197, amounts equal to a percentage markup of such costs will be allowed and paid to the Contractor as follows:

Subsection	Percent
00197.10 Materials	17
00197.20 Equipment	17
00197.30 Labor	22
00197.40 Special Services	17

When a Subcontractor performs ordered Force Account Work, the Contractor will be allowed a supplemental markup of 8% on each Force Account Work order.

These allowances made to the Contractor will constitute complete compensation for overhead, general and administrative expense, profit, and all other Force Account Work costs that were incurred by the Contractor, or by other forces that the Contractor furnished. No other reimbursement, compensation, or payment will be made.

00197.90 Billings - Billings for Force Account Work by the Contractor shall be submitted for the Engineer's approval on forms provided by the Agency or approved by the Engineer. Billings for Materials (other than Incidental items out of the inventory of the Contractor or Subcontractors), rental Equipment from sources other than the Contractor or Subcontractors, and Special Services, shall be accompanied by copies of invoices for the goods and services. The invoices shall be fully itemized showing dates, quantities, unit prices, and complete descriptions of goods and services provided. Invoices for amounts of \$10 or less per invoice are not required, unless requested by the Engineer.

Costs included on the billings shall comply with 00197.01(a) and 00197.10 through 00197.40.

When a billing for Force Account Work has been paid at the Project level, no further corrections will be made because of further review if those corrections amount to less than \$10.

Section 00199 - Disagreements, Protests, and Claims

Description

00199.00 General - This Section details the process through which the parties agree to resolve any disagreement concerning additional compensation or concerning a combination of additional compensation and Contract Time. (See 00180.80 for disagreements and claims concerning additional Contract Time only, and 00195.95 for disagreements and claims concerning correction of final compensation.) The Agency will not consider direct disagreements, protests, or claims from Subcontractors, Suppliers, or any other Entity not a party to the Contract.

Provisions and Requirements

00199.10 Procedure for Resolving Disagreements - When disagreements occur concerning additional compensation or a combination of additional compensation and Contract Time, the Contractor shall first pursue resolution through the Engineer of all issues in the dispute, including, without limitation, the items to be included in the written notice in 00199.20. If the discussion fails to provide satisfactory resolution of the disagreement, the Contractor shall follow the protest procedures outlined in 00199.20. If the Engineer denies all or part of the Contractor's protest, and the Contractor desires to further pursue the issues, the Contractor shall submit a claim for processing according to 00199.30.

00199.20 Protest Procedure - If the Contractor disagrees with anything required in a Change Order or other written or oral order from the Engineer, including any direction, instruction, interpretation, or determination, or if the Contractor asserts a disagreement or dispute on any other basis, except 0195.95, that, in the Contractor's opinion, entitles or would entitle the Contractor to additional compensation or a combination of compensation and Contract Time, the Contractor shall do all of the following in order to pursue a protest and preserve its claim:

(a) Oral Notice - Give oral notice of protest to the Engineer and outline the areas of disagreement before starting or continuing the protested Work.

(b) Written Notice - File a proper written notice of protest with the Engineer within 7 Calendar Days after receiving the protested order. In the notice the Contractor shall:

- Describe the acts or omissions of the Agency or its agents that allegedly caused or may cause damage to the Contractor, citing specific facts, persons, dates and Work involved;
- Describe the nature of the damages;
- Cite the specific Contract provision(s) that support the protest;
- Include the estimated dollar cost, if any, of the protested Work, and furnish a list of estimated Materials, Equipment and labor for which the Contractor might request additional compensation; and
- If additional compensation is estimated to be due, include the estimated amount of additional time required, if any.

Failure to comply with these notice requirements renders the notice improper.

(c) Records - Keep complete records of all costs and time incurred throughout the protested Work, and allow the Engineer access to those and other supporting records. Provide daily records of protested Work, on a weekly basis, on a schedule to be set by agreement with the Engineer.

(d) Comparison of Records - Provide the Engineer adequate facilities for keeping cost and time records of the protested Work. The Contractor and the Engineer will compare records and either bring them into agreement at the end of each day, or record and attempt to explain any differences.

(e) Work to Proceed - In spite of any protest, proceed promptly with the Work ordered by the Engineer.

(f) Evaluation of Protest - The Engineer will promptly evaluate all protests, after the Contractor has fully complied with the requirements described in 00199.20(b). If the protest is denied, the Engineer will notify the Contractor in writing of the reasons for full or partial denial. If a protest is found to be valid, the Engineer will, within a reasonable time, make an equitable adjustment of the Contract. Adjustment of time will be evaluated according to 00180.80.

The Engineer has no responsibility for evaluating and may reject a protest that does not comply with 00199.20(b). If the protest is rejected, the Engineer will notify the Contractor in writing of the reasons for rejection.

(g) Protest Evaluation by Third Party Neutral - If the Engineer agrees that the Contractor has fully complied with the requirements described in 00199.20(b), and if the Engineer fully or partially denies, in writing, the Contractor's protest according to 00199.20(f), the Contractor may request that a mutually selected Third Party Neutral review the protest. Procedures for selecting, using, and paying for the cost of the Third Party Neutral will be specified by Change Order.

If the Contractor does not accept the Engineer's evaluation of the protest, or either the Contractor or Engineer disagrees with the resolution recommended by the Third Party Neutral, the Contractor may pursue a claim as described in 00199.30.

00199.30 Claims Procedure:

(a) General - If the Contractor believes that additional compensation is due, or a combination of additional compensation and Contract Time, and has pursued and exhausted all the procedures provided in 00199.10 and 00199.20 to resolve a disagreement and protest, the Contractor may file a claim.

The Agency's Contract is with the Contractor. There is no contractual relationship between the Agency and any Subcontractors, Suppliers or any Entity other than the Contractor. It is the Contractor's responsibility to fully evaluate any claim before presenting it to the Agency. In addition, when a claim includes Work done or costs incurred by any Subcontractors, Suppliers, or any Entity other than the Contractor, the Contractor remains solely responsible for presenting the claim to the Agency.

Claims that include Work done or costs incurred by any Subcontractors, Suppliers, or any Entity other than the Contractor will not be considered by the Agency unless the Contractor has:

- Completed and provided its own written evaluation of the claim;
- Verified by its own independent review and evaluation of the amount of compensation sought; and
- Certified the claim according to 00199.30(b) (Part 10).

(b) Claims Requirements - At any time during the progress of the Work, but not later than 45 Calendar Days following the date of the Second Notification, the Contractor shall submit to the Engineer in writing, claims for additional compensation or a combination of additional compensation and Contract Time additional to that specified in the Contract. For a claim not submitted within the 45-day limit, that has not met the requirements of 00199.20, or is not filed as provided in 00199.30, the Contractor waives any claim for additional compensation or for additional compensation and Contract Time, and the Agency may reject the claim.

Written claims to the Engineer or the Agency by the Contractor shall be delivered to the Agency address shown in the Special Provisions, unless a different address is agreed to by the Engineer, and shall be delivered:

- By U.S. Postal Service first class mail or priority mail (which at the sender's option may include certified or registered mail return receipt requested); or
- By overnight delivery service of a private industry courier.

Claims will be considered as having been received by the Agency:

- At the time of actual receipt or 7 Calendar Days after the postmarked date when deposited for delivery by first class or priority mail, whichever is earlier; or
- At the time of actual receipt or 3 Calendar Days after deposit with a private industry courier for overnight delivery service, whichever is earlier.

The Agency reserves the right at any time and at any step in the claim decision or review process to request additional information, records or documentation related to the claim or the Contract either directly or through agents working toward resolution of the disputed or claimed events and issues.

Claims shall be made in writing, and shall include all information, records and documentation necessary for the Agency to properly and completely evaluate the claim.

To be considered, claims for additional compensation, or for additional compensation and Contract Time, shall be completed according to 00199.30 and shall be submitted with the required information and in the format below and labeled as required below for each claimed issue:

(Part 1) Summary (label page 1.1 through page 1.X) - In the summary, include a detailed, factual statement of the claim for additional compensation and Contract Time, if any, with necessary dates and locations of Work involved in the claim and the dates of when the event arose. Also include detailed facts supporting the Contractor's position relative to the Engineer's decision (see 00199.20(f));

(Part 2) Proof of notice (label page 2.1 through page 2.X) - Submit a copy of form 734-2887, with all attachments, that was given to the Agency. Include the date when that written notice and the date when oral notice was given:

(Part 3) Copies of the Contract Specifications that support the Contractor's claim (label page 3.1 through page 3.X);

(Part 4) Theory of entitlement supporting the claim (label page 4.1 through page 4.X) - Include a narrative of how or why the specific Contract Specifications support the claim and a statement of the reasons why such Specifications support the claim;

(Part 5) Itemized list of claimed amounts (label page 5.1 through page 5.X) - Claimed damages that resulted from the event with a narrative of the theories and records and documents used to arrive at the value of the damages;

(Part 6) Additional Contract Time requests (label page 6.1 through page 6.X) - If the claim is for a combination of additional compensation and Contract Time, submit a copy of the schedule that was in effect when the event occurred and a detailed narrative which explains how the event impacted Contract Time. In addition, if an Agency-caused delay is claimed:

- Include the specific days and dates under claim;

- Provide detailed facts about the specific acts or omissions of the Agency that allegedly caused the delay, and the specific reasons why the resulting delay was unreasonable; and
- Provide a schedule evaluation that accurately describes the impacts of the claimed delay.

Also see 00180.80 for additional requirements regarding claims for Contract Time and causes that are eligible and ineligible for consideration;

(Part 7) Copies of actual expense records (label page 7.1 through page 7.X) - Include documents that contain the detailed records and which support and total to the exact amount of additional compensation sought. Include the information and calculations necessary to support that amount. That amount may be calculated on the basis of Section 00197, if applicable, or may be calculated using direct and indirect costs presented in the following categories:

- Direct Materials;
- Direct Equipment. The rate claimed for each piece of Equipment shall not exceed the actual cost. In the absence of actual Equipment costs, the Equipment rates shall not exceed 75 percent of those calculated under the provisions of 00197.20. For each piece of Equipment, the Contractor shall include a detailed description of the Equipment and attachments, specific days and dates of use or standby, and specific hours of use or standby;
- Direct labor;
- Job overhead;
- General and administrative overhead; and
- Other categories as specified by the Contractor or the Agency;

(Part 8) Supporting records and documents (label page 8.1 through page 8.X) - Include copies of, or excerpts from the following:

- Any documents that support the claim, such as manuals standard to the industry and used by the Contractor; and
- Any daily reports or diaries related to the event, photographs or media that help explain the issue or event (optional), or all other information the Contractor chooses to provide (optional);

(Part 9) Certification (label page 9.1 through 9.X) - A certified statement, signed by a person authorized to execute Change Orders, by the Contractor, Subcontractor, Supplier, or Entity, originating the claim, as to the validity of facts and costs with the following certification:

Under penalty of law for perjury or falsification, the undersigned, (Name), (Title), (Company) certifies that this claim for additional compensation for Work on the Contract is a true statement of the actual costs incurred (in the amount of \$_____, exclusive of interest) and is fully documented and supported under the Contract between the parties.

Signature: _____

Date: _____, 20____

Subscribed and sworn before me this _____ day of _____, 20____

Notary Public

My commission expires _____.

(Part 10) Contractor evaluation of a lower-tier claim (label page 10.1 through 10.X) - If the claim includes Work done or costs incurred by any Subcontractors, Suppliers, or any Entity other than the Contractor, the following are required:

- Data required by the other Subsections of 00199.30(b);
- Copies of the Contractor's, Subcontractor's, Supplier's and Entity's, at all tiers above the level of which the claim originates, separate evaluation of entitlement;
- Copies of the Contractor's, Subcontractor's, Supplier's and Entity's, at all tiers above the level of which the claim originates, independent verification and evaluation of the amount of damages sought; and
- A person authorized to execute Change Orders on behalf of the Contractor, Subcontractor, Supplier and Entity, at all tiers above the level of which the claim originates, must sign a statement with the following certification:

Under penalty of law for perjury or falsification, the undersigned, (Name) (Title), (Company) certifies that this claim originating from the Subcontractor, Supplier or Entity (Company) for additional compensation for Work on the Contract is a reasonable statement, independently verified, of the costs incurred (in the amount of \$_____, exclusive of interest) and is fully documented and supported under the Contract between the parties.

Signature:_____

Date:_____, 20__

Subscribed and sworn before me this____ day of_____, 20__

Notary Public

My commission expires_____.

If the Engineer determines that additional information, records or documentation is needed to allow proper evaluation of the claim submittal, the Engineer will request the information, records or documentation. The Contractor shall submit to the Engineer within 14 Calendar Days, or as otherwise agreed by the parties, the required additional information, records and documentation.

If the Engineer determines that the claim submittal with the additional information, records and documentation submitted is incomplete and not accepted as a claim, the Engineer will notify the Contractor in writing and the submittal will be rejected and will not be considered under 00199.40.

(c) Records Requirements - The Contractor shall comply with 00170.07.

(d) Compliance Required - Full compliance by the Contractor with the provisions of this Section is a condition precedent to the commencement of any lawsuit by the Contractor to enforce any claim.

00199.40 Claim Decision; Review; Exhaustion of Administrative Remedies - The Agency intends to resolve all claims at the lowest possible administrative level. The Engineer will also determine whether multiple claims should be advanced separately or together.

If the Engineer denies the claim for additional compensation or a combination of additional compensation and Contract Time, in full or in part, according to 00199.40(a), the Contractor may request review of the denial. The disputed claim for additional compensation or a combination of

additional compensation and Contract Time may then be resolved, in full or in part, at any of the four progressive steps of claim review procedure as specified in (b) through (e) of this Subsection.

If the Engineer has denied a claim, in full or in part, for Contract Time only according to 00180.80, or has denied a claim, in full or in part, for correction of final compensation according to 00195.95, those disputed claims may then be resolved, in full or in part, at any of the four progressive steps of claim review procedure as specified in (b) through (e) of this Subsection.

A person authorized by the Contractor to execute Change Orders on behalf of the Contractor must be present and attend all claim hearings. For all claims, all of the actions and review under each step of the review process shall occur before the review can be advanced to the next higher step.

The Engineer may determine to skip the Step 1: Region Level Review, in which case the claim or claims will advance to Step 2: Agency Level Review.

(a) Decision by the Engineer - The Engineer will, as soon as practicable, consider, investigate, and evaluate a Contractor's claim for additional compensation, or for a combination of additional compensation and Contract Time, if submitted as required by 00199.30.

Once the Engineer determines the Agency is in receipt of a properly submitted claim, the Engineer will arrange a meeting, within 21 Calendar Days or as otherwise agreed by the parties, with the Contractor in order to present the claim for formal review and discussion.

If the Engineer determines that the Contractor must furnish additional information, records or documentation to allow proper evaluation of the claim, the Engineer will schedule a second meeting, to be held within 14 Calendar Days or as otherwise agreed by the parties, at which the Contractor shall present the requested information, records and documentation.

The Engineer will provide a written decision to the Contractor within 30 Calendar Days of the last Engineer-level meeting.

If the Contractor does not accept the Engineer's decision, the Contractor may, within 10 Calendar Days of receipt of the written decision, request in writing that the Engineer arrange a review at Step 1 (see (b) below).

(b) Step 1: Director Review - The Contractor shall request the Engineer arrange a meeting with the Public Works Director in order to present the denied or partially denied claim for formal review and discussion. The meeting will take place within 21 Calendar Days of the Agency's receipt of the request, or as otherwise agreed by the parties.

If the Public Works Director determines the Contractor must furnish additional information, records or documentation to allow proper evaluation of the claim, the reviewer will schedule a second meeting, to be held within 14 Calendar Days, or as otherwise agreed by the parties, at which the Contractor shall present the requested information, records and documentation.

The Public Works Director will provide a written decision to the Contractor within 30 Calendar Days of the last Director Review meeting.

If the Contractor does not accept the Step 1 decision, the Contractor may, within ten (10) Calendar Days of receipt of the written decision, request in writing that the Engineer arrange a review at Step 2 (see (c) below).

(c) Step 2: City Manager Level Review - The Contractor shall request a meeting with the City Manager to present the claim for final Agency review. The presentation will take place within

21 Calendar Days of the Agency's receipt of the Contractor's written request, or as otherwise agreed by the parties.

If the City Manager determines the Contractor must furnish additional information, records or documentation to allow proper evaluation of the claim, the City Manager will schedule a second meeting to be held within 14 Calendar Days or as otherwise agreed by the parties, at which the Contractor shall present the requested information, records and documentation.

The claim is subject to 00199.60, if not all of the records requested by the City Manager were furnished.

The City Manager will provide a written decision to the Contractor, subject to 00199.60, if applicable, regarding the claim within 30 Calendar Days of the final Step 2 meeting.

If the Contractor does not accept the Step 2 decision, the Contractor may, within 10 Calendar Days of receipt of the written decision, request in writing through the Engineer that the claim be advanced to Step 3 or 4 (see (d) and (e) below), as applicable. For purposes of determining which process to use for claims under Step 3 or 4 concerning a combination of additional compensation and Contract Time or for Contract Time only, the value of the claim or portion of the claim for Contract Time will be assumed to be the appropriate Liquidated Damages given in 00180.50 of the Special Provisions multiplied by the number of Calendar Days in question. If applicable, advancement of the claim is subject to the provisions of 00199.60 regarding waiver and dismissal of the claim or portions of the claim.

(d) Step 3: Arbitration; Local Contract Review Board:

(1) Claims Less Than \$50,000 - At this step, the claim will be resolved by binding arbitration before a single arbitrator according to the Construction Industry Arbitration Rules of the American Arbitration Association or such other arbitration service and rules as agreed by the parties.

Arbitration filing costs and any arbitrator's fees will be divided equally between the Agency and the Contractor.

(2) Claims of \$50,000 to \$500,000 - At this step, the Contractor shall present the claim to Local Contract Review Board (referred to as "Board") for consideration, review and recommended resolution.

The Board may request the Engineer to designate a person not associated with the Contract to act as the recording secretary for the Board. The recording secretary is not a Board member, and will only assist the Board with administrative tasks related to its consideration and review of the referred claim.

The Agency and the Contractor will equally share the costs of the Board members. The Agency will pay the costs of the Board's recording secretary.

Members of the Board are to act impartially and independently in the consideration of facts and conditions surrounding the dispute. Board recommendations concerning the dispute are considered advisory only, shall not be binding on either party, and shall not constitute evidence in any legal proceeding for any reason.

The Board will schedule and conduct an informal hearing at which the Contractor and the Agency will each have an opportunity to present evidence and argument. The Contractor and the Agency shall each submit a brief written summary of the claim to each Board member and the other party at least 10 Calendar Days before the hearing. Unless directed otherwise by the Board Chair, the summary shall include, for each issue under dispute:

- A short statement describing the disputed issue;
- A short position statement by the party on the issue;
- A clear and concise explanation of the contractual basis for that position, including specific reference to Contract Documents;
- A clear and concise description of the costs claimed for each issue, including, without limitation, specific documents demonstrating productivity, time and costs; and
- Exhibits, including, without limitation, copies of plan sheets, extracts from the Standard Specifications and Special Provisions, correspondence, photographs, or other evidence to support the position.

The proceedings will be conducted in a manner determined by the Chair, in consultation with the other Board members. Unless directed otherwise by the Chair, the hearing will be conducted according to the following guidelines:

- The hearing will be informal;
- The witnesses will not be sworn;
- The Contractor will present its case first;
- The Agency will then present its case;
- Both parties will then have opportunity to present rebuttal;
- The Board may ask questions and, to promote open discussion of the issues, both parties may respond or emphasize issues;
- The parties' attorneys may observe the hearing and may respond to direct questions from the Board, but may not make factual presentations or legal arguments; and
- The Board will conclude the hearing when it appears to the Board Chair that each party has had sufficient opportunity to support its case and the Board has no further questions.

Within 10 Calendar Days after conclusion of the hearing, the Board will forward to the Agency's designated representative and the Contractor the Board's written recommendation for resolution of the claim. Within 10 Calendar Days of its receipt of the Board's recommendation, the Agency will provide to the Contractor the Agency's written decision regarding the claim.

If the Contractor does not accept the Agency's decision regarding the claim, the Contractor may proceed to litigation as described in Step 4 (see (e) below).

(3) Claims Over \$500,000 - If the Contractor and the Engineer agree, the parties may employ the Step 3 Board review process according to 00199.40(d)(2). If not, the Contractor may proceed to Step 4 (see (e) below).

(e) Step 4: Litigation - This step applies to:

- Claims over \$500,000;
- Appeals of arbitration awards issued in Step 3 at 00199.40(d)(1) above, according to ORS 36.600 through ORS 36.740; and
- Agency decisions issued under Step 3 at 00199.40(d)(2) above.

The Contractor must follow each step in order, and exhaust all available administrative remedies before resorting to litigation. Lawsuits must be properly filed in a court of competent jurisdiction within 6 months from the date of the final decision that exhausted the Contractor's available administrative remedies under this Section 00199.

The Contractor shall comply with 00170.00.

00199.50 Mediation - Notwithstanding the formal claims procedure specified above, the parties may enter into nonbinding mediation by mutual agreement at any time, in which case the parties may also agree to suspend the time requirements in Section 00199 pending the outcome of the mediation process. The rules, time and place for mediation, as well as selection of the mediator, shall be established by mutual agreement. Costs shall be divided equally between the Contractor and the Agency. Either party may terminate mediation at any time upon 5 Calendar Days' notice to the other, after which the time requirements of Section 00199 shall be automatically reinstated and shall resume from the point at which the time requirements were suspended.

00199.60 Review of Determination Regarding Records - If not all of the records requested by the City Manager under 00199.40(c) Step 2 were provided, then the City Manager will determine:

- If the records are of the type described in 00170.07; and
- If the records have not been maintained or the records, or access to the records, has not been provided to the Agency as required by 00170.07 and this Section; and
- If the records are material and necessary for proper evaluation of part or all of the claim; and
- The portions of the claim for which the records are material and necessary for proper evaluation.

If the City Manager makes the foregoing determinations, then subject to the review process described below, all portions of the claim for which the City Manager determined the records are material and necessary for proper evaluation are immediately waived and irrevocably dismissed.

Even if the records have not been maintained or the records, or access to the records, have not been provided to the Agency in a given instance, the City Manager may determine that sufficient records have been provided for the Agency to properly evaluate the claim in that instance. If the CAE makes this determination, the claim or portions of the claim will not be waived or dismissed under this provision.

If the Contractor does not accept the City Manager's written determination that the records are material and necessary for proper evaluation of part or all of the claim, and the portions of the claim for which the records are material and necessary, the Contractor may, within 14 Calendar Days of receipt of the City Manager's determination, request, in writing, a review of such determination by the Construction Engineer (CE). If the Contractor does not request a review of the City Manager's determination, the City Manager's determination shall then become the Agency's final determination as of the expiration of the time limit to request review

If the Contractor requests the review, the CE will schedule a review meeting within 14 Calendar Days, or as otherwise agreed by the parties, of when the CE receives the written review request. The Agency and the Contractor will each have an opportunity to explain their respective positions at the review meeting in a manner determined by the CE.

Within 10 Calendar Days of the review meeting, the CE will issue a written proposed finding of whether the records not maintained or not provided to the Agency, or for which access was not provided to the Agency, are material and necessary for proper evaluation of part or all of the claim. If the CE makes that finding, then the CE will also make a proposed written finding as to what portions of the claim the records are material and necessary and, therefore, waived and irrevocably dismissed.

Even if the records have not been maintained or the records, or access to the records, have not been provided to the Agency in a given instance, the CE may determine that sufficient records have been provided for the Agency to properly evaluate the claim in that instance. If the CE makes this determination, then the claim or portions of the claim will not be waived or dismissed under this provision.

The CE's proposed findings will be submitted to the Contractor and the Agency's Director. The Contractor may submit written objections concerning the proposed findings to the Director within 5 Calendar Days of receipt of such findings. If written objections are submitted, the Director may

adopt or modify the proposed findings, and the Director's findings shall be the Agency's final determination. If no written objections are submitted within the 5 Calendar Day time limit, the CE's proposed findings shall then become the Agency's final determination as of the expiration of the time limit to submit written objections.

If the Agency's final determination is that the records are material and necessary for proper evaluation of part or all of the claim, then the claim or that portion of the claim for which the records are material and necessary is waived and irrevocably dismissed, unless the Contractor provides the records, or access to the records, to the CAE within 5 Calendar Days of the Agency's final determination. If the Contractor provides the records, or access to the records, within this time limit, the CAE will schedule a meeting with the Contractor within 14 Calendar Days or as otherwise agreed by the parties, to discuss the records.

The Agency's final determination that records are material and necessary for proper evaluation of part or all of the claim, and the Agency's final determination of the portions of the claim for which the records are material and necessary, shall be final and binding.

If the entire claim is waived and irrevocably dismissed pursuant to the Agency's final determination there will be no further decision by the Agency on the claim or further review of the claim under 00199.40 and the claim will not be eligible for mediation under 00199.50. If only portions of the claim are waived and irrevocably dismissed pursuant to the Agency's final determination, the CAE will provide a written decision to the Contractor regarding the remaining portions of the claim within 30 Calendar Days of the final Step 2 meeting, or the Agency's final determination regarding the records, whichever is later. There will be no further decision by the Agency on or further review under 00199.40 of the portions of the claim waived and irrevocably dismissed pursuant to Agency's final determination and those portions will not be eligible for mediation under 00199.50.



PART 4

SPECIAL PROVISIONS

2023 ADA IMPROVEMENT PROJECT
CONTRACT NO. 2023-003

00120.05 Request for Plans, Special Provisions, and Bid Booklets

(REPLACE) *Delete the first paragraph and replace it with below:*

Bidders shall obtain Solicitation Documents from the City's website at **http://www.ci.the-dalles.or.us/current_job_openings.htm**. Bidders will be responsible for checking the website regularly for addendums and additional information for the project.

00120.40 Preparation of Bids (e)

(REPLACE) *Delete the second and third paragraph and replace it with below:*

The Bid guaranty shall be a Surety bond using the Agency's standard Bid Bond form included with the Bid Booklet. The Bid guaranty shall be submitted with the bid booklet as described in 00120.45.

00120.45 Submittal of Bids

(REPLACE) *Delete the paragraph and replace it with below:*

Bids shall be submitted as instructed in the Advertisement for Bids and Invitation to Bidders.



PART 5

DRAWINGS

2023 ADA IMPROVEMENT PROJECT
CONTRACT NO. 2023-003

NO.	DATE	REVISIONS



EXPENSE: 03/25/24

CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401



2023 ADA IMPROVEMENT PROJECT

THE VALLEY,

THE VALLEY,

NAME	TMS
DATE	12/16/2022
SCALE	NTS
CHECKED	
SHEET	
C0.1	
OF	60 SHEETS
JOB NO.	2023-003



VICINITY MAP

NO SCAL

SHEET INDEX

[illegible]

GENERAL NOTES

- 1.ALL WORK AND MATERIALS SHALL CONFORM TO THE CURRENT CITY OF THE DALLES STANDARD SPECIFICATIONS AND DRAWINGS. COPIES CAN BE DOWNLOADED FROM THE CITY’S WEBSITE AT <http://www.ci.the--dalles.or.us/engineering>
- 2.THE LOCATION OF KNOWN UTILITIES IN THE PROJECT AREA HAVE BEEN SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR. NO RESPONSIBILITY IS ASSUMED BY THE CITY OR THE ENGINEER FOR THE COMPLETENESS OR ACCURACY OF THE LOCATION, TYPE OR NUMBER OF EXISTING UTILITIES. ALL UTILITY LOCATIONS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CALL 1–800–332–2344 or 811 FOR UTILITY LOCATIONS AT LEAST 48 HOURS PRIOR TO BEGINNING EXCAVATION IN ACCORDANCE WITH STATE LAW.
- 3.NO WORK SHALL DEVIATE FROM THESE PLANS UNLESS PRIOR APPROVAL IS OBTAINED FROM THE CITY. FINAL ACCEPTANCE OF ALL WORK SHALL BE MADE BY THE CITY OF THE DALLES.
- 4.THE CONTRACTOR AGREES THAT, IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD THE CITY AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXEMPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE ENGINEER.
- 5.EXCAVATIONS SHALL BE ADEQUATELY SHORED, BRACED AND SHEETED SO THAT THE EARTH WILL NOT SLIDE OR SETTLE AND SO THAT ALL EXISTING IMPROVEMENTS OF ANY KIND WILL BE FULLY PROTECTED FROM DAMAGE. ANY DAMAGE RESULTING FROM A LACK OF ADEQUATE SHORING, BRACING AND SHEETING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND HE SHALL EFFECT NECESSARY REPAIRS OR RECONSTRUCTION AT HIS OWN EXPENSE. WHERE THE EXCAVATION FOR A CONDUIT TRENCH AND/OR STRUCTURE IS FIVE FEET OR MORE IN DEPTH, THE CONTRACTOR SHALL PROVIDE ADEQUATE SHEETING, WHICH SHALL CONFORM TO THE APPLICABLE CONSTRUCTION SAFETY ORDERS OF THE STATE OF OREGON OSHA. THE CONTRACTOR SHALL ALWAYS COMPLY WITH OSHA REQUIREMENTS.
- 6.IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN PERMITS NECESSARY TO PERFORM THE WORK SHOWN IN THESE PLANS FROM THE APPROPRIATE AGENCIES.
- 7.THE CONTRACTOR SHALL PROVIDE FOR INGRESS AND EGRESS FOR PRIVATE PROPERTY ADJACENT TO WORK THROUGHOUT THE PERIOD OF CONSTRUCTION.
- 8.THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGGERS, OR OTHER DEVICES NECESSARY TO PROVIDE FOR SAFETY. TRAFFIC CONTROL AND ALL TRAFFIC CONTROL DEVICES SHALL BE IN CONFORMANCE WITH THE ODOT STANDARD SPECIFICATION, LATEST EDITION.
- 9.THE CONTRACTOR SHALL POST EMERGENCY TELEPHONE NUMBERS FOR POLICE, FIRE, AMBULANCE, AND THOSE AGENCIES RESPONSIBLE FOR THE MAINTENANCE OF UTILITIES IN THE JOBSITE.
- 10.ALL QUANTITIES AND PAY ITEMS ARE AND WILL BE BASED ON HORIZONTAL MEASUREMENTS.
- 11.ALL EXISTING UTILITIES AND IMPROVEMENTS THAT BECOME DAMAGED DURING CONSTRUCTION SHALL BE COMPLETELY RESTORED TO THE SATISFACTION OF THE CITY ENGINEER OR OWNER, AT THE CONTRACTOR’S SOLE EXPENSE.
- 12.IF ARCHAEOLOGICAL MATERIAL ARE UNCOVERED DURING DEMOLITION, GRADING, TRENCHING, OR OTHER EXCAVATION, EARTHWORK WITHIN 100 FEET OF THESE MATERIALS SHALL BE STOPPED UNTIL A PROFESSIONAL ARCHAEOLOGIST WHO IS CERTIFIED BY THE SOCIETY OF PROFESSIONAL ARCHAEOLOGY (SOPA) HAS HAD AN OPPORTUNITY TO EVALUATE THE SIGNIFICANCE OF THE FIND AND SUGGEST APPROPRIATE MITIGATION MEASURES, IF THEY ARE DEEMED NECESSARY.
- 13.SHOULD IT APPEAR THAT THE WORK TO BE DONE OR ANY MATTER RELATIVE THERETO IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS, THE CONTRACTOR SHALL CONTACT THE CITY OF THE DALLES ENGINEERING DEPARTMENT (541) 296–5401 FOR SUCH FURTHER EXPLANATIONS AS MAY BE NECESSARY.
- 14.THE CONTRACTOR SHALL MEET AND FOLLOW ALL NPDES REQUIREMENTS IN EFFECT AT THE TIME OF CONSTRUCTION.

PROJECT SPECIFIC NOTES

- 1.OWNER: CITY OF THE DALLES
1215 W. 1st STREET
THE DALLES, OR 97058
CONTACT: DAVE ANDERSON
PHONE:(541) 296–5401
- ENGINEER: CITY OF THE DALLES PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION
1215 W. 1st STREET
THE DALLES, OR 97058
CONTACT: TODD STEPHENS
PHONE: (541) 296–5401
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING SURVEY MONUMENTS AND OTHER SURVEY MARKERS DURING CONSTRUCTION. ALL SUCH MONUMENTS OR MARKERS DESTROYED DURING CONSTRUCTION SHALL BE REPLACED BY A LICENSED SURVEYOR AT THE CONTRACTOR’S EXPENSE.
3. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT WRITTEN AUTHORIZATION FROM THE CITY.
4. ALL SALVAGE OF PUBLIC WORKS FACILITIES SHALL BE THE PROPERTY OF THE CITY OF THE DALLES AND SHALL BE DELIVERED TO THE CITY PUBLIC WORKS DEPARTMENT.
5. RIGHT OF WAY LINES AND PROPERTY LINES SHOWN ON THESE PLANS ARE APPROXIMATE.
6. CONTRACTOR SHALL NOT STORE MATERIALS AND/OR EQUIPMENT ON PRIVATE PROPERTY UNLESS PERMISSION IS GRANTED BY PROPERTY OWNER.
7. ALL QUANTITIES AND PAY ITEMS ARE AND WILL BE BASED ON HORIZONTAL MEASUREMENTS.
8. THE CONTRACTOR SHALL ATTEND A PRE–CONSTRUCTION MEETING WITH THE CITY TO DISCUSS THE SCOPE, SCHEDULE, AND REQUIRED COORDINATION FOR THE PROJECT
9. RESTORE EXISTING LANDSCAPE OR OTHER ABUTTING IMPROVEMENTS TO PRE CONSTRUCTION CONDITION OR BETTER. FENCES NEEDING TO BE RELOCATED SHALL BE RELOCATED TO THE BACK OF WALK TO PROVIDE FOR A MINIMUM 4.0FT PEDESTRIAN ROUTE.
10. REMOVE PAVEMENT ADJACENT TO NEW CONCRETE CURB AND SIDEWALK. FILL AREA BETWEEN EXISTING ASPHALT AND NEW CURB WITH 3/4" MINUS GRAVEL AFTER WORK IS COMPLETE. CATCH BASIN INSTALLATION AND ASPHALT PATCHES WILL BE PERFORMED BY CITY STAFF. COORDINATE WORK WITH CITY STAFF.
11. LOCATIONS OF KNOWN SURVEY MONUMENTS THAT WILL BE DESTROYED DURING CONSTRUCTION ARE NOTED ON THE PLANS. SURVEY MONUMENTS SHALL BE REPLACED BY A LICENSED SURVEYOR. SURVEYOR SHALL NOTIFY THE COUNTY SURVEYOR AND FOLLOWING THE REQUIREMENTS OF ORS 209.140, ORS 209.150 AND ORS 209.155.
12. COORDINATE THE RELOCATION OF EXISTING STREET SIGNS WITH CITY STAFF. CITY WILL PROVIDE SIGN BASES TO BE USED.
13. COORDINATE THE INSTALLATION OF CATCH BASINS WITH CITY STAFF SO THAT CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.
- 14.THE CITY WILL BE CONTRACTING OUT WORK TO ASPHALT GRIND AND OVERLAY SEVERAL OF THE STREETS ADJACENT TO THIS PROJECT. THIS WORK IS ANTICIPATED TO START AT THE END OF APRIL. ALL WORK ADJACENT TO THE ASPHALT GRIND AND OVERLAY WORK SHALL BE COMPLETED BY APRIL 28TH, 2023. CONTRACTOR TO SUBMIT SCHEDULE SHOWING PRIORITY TO THESE AREAS AND TO SHOW A COMPLETION OF WORK BY APRIL 28, 2023. ALL OTHER WORK SHALL BE COMPLETED BY JUNE 2, 2023.

CONSTRUCTION NOTES – CONCRETE IMPROVEMENTS

- 1.ALL CONCRETE USED SHALL BE COMMERCIAL GRADE CONCRETE MEETING SECTION 00440 OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION (3,000 PSI). COPIES OF THE DELIVERY TICKETS SHALL BE DELIVERED TO THE CITY. PROJECTS INVOLING CONCRETE POURS OVER 20 CY SHALL BE SUBJECT TO HARDENED CONCRETE TESTING. CONTRACTOR’S QUALITY CONTROL TECHNICIAN SHALL OBTAIN CYCLINDERS ACCORDING TO AASHTO T23 AND TEST CYCLINDERS TO ASSHTO T22 TO DETERMINE IF CONCRETE IS MEETING REQUIREMENTS OF SECTION 00440.
- 2.ALL CURBING, SIDEWALK AND CONCRETE IMPROVEMENTS SHALL BE INSTALLED FREE OF CRACKS. IF CRACKING OCCURS, CONCRETE WILL BE REPLACED AT CONTRACTOR’S EXPENSE.
- 3.ALL WORK SHALL CONFORM TO SECTION 00759 OF THE STANDARD SPECIFICATIONS AND CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED SUBMITTALS PRIOR TO BEGINNING ON–SITE WORK. CONTRACTOR SHALL NOTE THE LIMITED SLOPE TOLERANCES ON THE PROJECT. WHILE DEVELOPING WORKING DRAWINGS FOR THE PROJECT NOTIFY THE ENGINEER OF ANY DEFICIENCIES OR NON–COMPLIANCE WITH THE STANDARD DRAWINGS OR PLANS.
- 4.ALL FINISHED CONCRETE SURFACES OF SIDEWALK AND RAMPS TO BE WITHIN ESTABLISHED SLOPES AND DIMENSIONS ALLOWED BY THE STANDARD DRAWINGS AND PLANS. REPAIR OR REMOVE AND REPLACE SIDEWALKS AND RAMPS NOT MEETING THE STANDARD DRAWINGS AND PLANS AT NO ADDITIONAL COST TO THE CITY.
- 5.VERTICAL SURFACE DISCONTINUITIES SHALL BE LESS THAN 1/2 INCHES. VERTICAL DISCONTINUITIES BETWEEN 1/4 AND 1/2 INCHES SHALL BE BEVELED WITH A SLOPE NO STEEPER THAN 50 PERCENT.
- 6.TOP/BOTTOM OF CURB TO BE FLUSH WITH ADJACENT SURFACES. VERTICAL LIPS NOT PERMITTED AT THE BOTTOM OF CURB RAMP WHERE THE RAMP MEETS STREET LEVEL.
- SIDEWALK
- 7.SIDEWALK CROSS SLOPE SHALL BE DESIGNED FOR A MAXIMUM CROSS SLOPE OF 1.5%. CONSTRUCTED SIDEWALK SECTION WITHIN THE PEDESTRIAN ACCESS ROUTE SHALL NOT EXCEED 2.0% CROSS SLOPE. EXCEPTION: WHERE A SIDEWALK TRANSITION PANEL IS INSTALLED TO MATCH NEW IMPROVEMENTS TO EXISTING SIDEWALK.
- 8.SIDEWALKS SHALL BE A MINIMUM OF 5.0 FT IN WIDTH AND MAINTAIN A MINIMUM 4.0 FT WIDTH WITHIN THE PEDESTRIAN ACCESS ROUTE.
- 9.ANY SIGN POSTS, UTILITY POLES, FIRE HYDRANTS, AND OTHER OBJECTS SHALL NOT REDUCE THE CLEAR WIDTH TO LESS THAN 4.0 FT. CURB RAMP
- 10.RUNNING SLOPE OF THE CURB RAMP SHALL BE DESIGNED FOR A 7.5% MAX SLOPE AND A LENGTH NOT TO EXCEED 15.0 FT. CONSTRUCTED RUNNING SLOPES SHALL NOT EXCEED 8.3% SLOPE UNLESS RAMP RUN HAS EXTENDED 15 FT AND A DESIGN EXCEPTION IS APPROVED FOR THE RAMP RUN.
- 11.INSTALL CURB AND GUTTER SECTION ALONG ALL CURB RAMPS. CURB AND GUTTER COUNTER SLOPE SHALL BE 4.0% MAX DESIGN AND 5.0% MAX CONSTRUCTED. BOTTOM OF CURB RAMP SHALL BE FLUSH WITH ADJACENT GUTTER SECTION. NO VERTICAL LIP PERMITTED AT THE BOTTOM OF THE CURB RAMP.
- 12.CONSTRUCT LEVEL TURNING SPACES (2.0% MAX CONSTRUCTED) WITH AN AREA OF 4.5FT X 4.5FT WITH A MINIMUM AREA OF 4FT X 4FT. IF THE TURNING SPACE IS CONSTRAINED AT THE BACK OF SIDEWALK THE TURNING SPACE SHALL BE AN AREA OF 4.5 FT X 5.5FT WITH A MINIMUM AREA OF 4.0 FT X 5.0 FT. THE LONGER DIMENSION IS IN THE DIRECTION OF THE PEDESTRIAN CROSSING.
- 13.GRADE BREAKS AT THE TOP AND BOTTOM OF CURB RAMPS SHALL BE PERPENDICULAR TO THE DIRECTION OF THE CURB RAMP RUN. GRADE BREAKS SHALL NOT BE PERMITTED ON THE SURFACE OF THE SURFACE OF CURB RAMP RUNS AND TURNING SPACES. SURFACE SLOPES THAT MEET AT GRADE BREAKS SHALL BE FLUSH.
- 14.DETECTABLE WARNING SURFACES CONSISTING OF TRUNCATED DOMES SHALL BE USED WHERE CURB RAMPS OR PEDESTRIAN ACCESS ROUTES PROVIDES A PEDESTRIAN CONNECTION TO THE STREET.

CONSTRUCTION NOTES – EROSION CONTROL NOTES

- 1.THE CONTRACTOR SHALL TAKE EFFECTIVE ACTION TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE BY INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO AND CONCURRENT WITH LAND DISTURBING ACTIVITIES. THE CONTRACTOR SHALL PREVENT THE FORMATION OF ANY AIRBORNE DUST NUISANCE AND SHALL BE RESPONSIBLE FOR ANY DAMAGE RESULTING FROM FAILURE TO DO SO.
- 2.EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AT NO ADDITIONAL COST TO THE CITY.
- 3.THE CONTRACTOR SHALL IMPLEMENT THE FOLLOWING DUST, EROSION AND SEDIMENT CONTROL PRACTICES:
- A. PRIOR TO CONSTRUCTION
- 1) CONTRACTOR SHALL SUBMIT TO THE CITY AN EROSION AND SEDIMENT CONTROL PLAN AND MONITORING SCHEDULE FIVE (5) DAYS PRIOR TO THE PRECONSTRUCTION MEETING.
- 2) INSTALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO BEGINNING WORK ON SITE. ITEMS SUCH AS SEDIMENT FENCE, INLET PROTECTION AND OTHER BMPs SHALL BE IN PLACE BEFORE WORK ON SITE BEGINS.
- 3) THE CONTRACTOR SHALL INSTALL CONSTRUCTION ENTRANCES AT THE BEGINNING OF THE PROJECT AND THESE ENTRANCES SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT.
- B. DURING CONSTRUCTION
- 1) AREAS OF EARTH EXPOSED BY CLEARING, EARTHMOVING, OR EXCAVATION SHALL BE MINIMIZED AT ALL TIMES.
- 2) MATERIAL EXCAVATED OR GRADED SHALL BE SUFFICIENTLY WATERED OR TREATED WITH AN APPROVED DUST CONTROL ADDITIVE TO PREVENT DUST TO THE SATISFACTION OF THE PROJECT MANAGER OR INSPECTOR.
- 3) DURING GRADING, TRENCHING AND CONSTRUCTION, STREETS AND ALLEYS NEXT TO WORK AREA SHALL BE SWEEPED AT LEAST ONCE A DAY, AND AS REQUIRED BY THE CITY TO REMOVE SILT AND OTHER DEBRIS WHICH MAY HAVE ACCUMULATED FROM CONSTRUCTION ACTIVITIES. FAILURE TO MANAGE SEDIMENTS ON SITE MAY REQUIRE ADDITIONAL MEASURES TO BE TAKEN TO MANAGE THE SEDIMENT.
- 4) INSPECT AND MAINTAIN EROSION AND SEDIMENT CONTROL MEASURES FOR THE DURATION OF THE PROJECT TO PREVENT ANY ACCUMULATION OF SEDIMENTS FROM ENTERING THE STORM WATER SYSTEM. ANY ACCUMULATION OF SEDIMENT WITHIN THE STORM WATER SYSTEM AS A RESULT OF THE PROJECT WILL REQUIRE THE CONTRACTOR TO CLEAN THE EFFECTED STORM WATER STRUCTURE. CLEANING OF THE STORM WATER STRUCTURES SHALL BE DONE IN A MANNER AS TO NOT FLUSH THE SEDIMENTS INTO A DOWNSTREAM SYSTEM.
- 5) ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR SEEDING UNLESS SITE CONDITIONS OR WEATHER WARRANT SOIL STABILIZATION INSTALLATION OF THE SOIL STABILIZATION TO OCCUR SOONER.
- C. AFTER CONSTRUCTION
- 1) WHEN AREAS OF EXISTING VEGETATION ARE DISTURBED FROM EXCAVATION OR STORAGE, THE CONTRACTOR SHALL ADEQUATELY SEED THE DISTURBED AREA TO PROTECT THE AREA FROM EROSION. IF THE AREA ISN’T OR CANNOT BE ADEQUATELY SEEDED THEN THE AREA SHALL BE COVERED BY A PROTECTIVE MATERIAL SUCH AS STRAW OR MULCH TO PREVENT EROSION.
- 2) REMOVE WORK AREA TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES. REMOVE ANY ACCUMULATED SEDIMENTS FROM THESE BMPs AND ADJACENT STREETS AND ALLEYS.
- 4.THE CONTRACTOR SHALL PROVIDE AN ACTION PLAN AND KEEP THE NECESSARY MATERIALS ON SITE FOR THE CAPTURE AND DISPOSAL OF ANY PETROLEUM PRODUCT LEAKS OR SPILLS ASSOCIATED WITH SERVICING, REFUELING OR OPERATION OF ANY EQUIPMENT UTILIZED ON THE PROJECT.
5. THE CONTRACTOR SHALL PROVIDE A CONCRETE WASHOUT AREA ON SITE TO PREVENT CONCRETE WASH WATER FROM ENTERING THE STORM WATER SYSTEM OR WATERBODY. WASHOUT AREA SHOULD NOT BE LOCATED IN AN AREA WHERE SHALLOW GROUNDWATER MAY BE PRESENT, SUCH AS NEAR NATURAL DRAINAGES, SPRINGS, OR WETLANDS.

REVISIONS	
NO.	DATE



A GENERAL NOTES SHEET FOR:

2023 ADA IMPROVEMENT PROJECT

THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	NTS
CHECKED	
SHEET	
C0.2	
OF	60 SHEETS
JOB NO.	2023-003

TRAFFIC CONTROL / PEDESTRIAN DETOUR


GENERAL TRAFFIC CONTROL NOTES

1. THE CONTRACTOR SHALL SUBMIT TO THE CITY A DETAILED TRAFFIC CONTROL PLAN FOR PERFORMING ALL WORK FOR THE PROJECT. THE TRAFFIC CONTROL PLAN SHALL BE SPECIFIC TO EACH ROAD SECTION. THE TRAFFIC CONTROL PLAN SHALL INCLUDE ANY TEMPORARY PEDESTRIAN ACCESS ROUTES AS NEEDED. ALL TRAFFIC CONTROL MEASURES AND WORK ACTIVITIES SHALL COMPLY WITH SECTIONS 00220 AND 00225 OF THE CITY'S STANDARD SPECIFICATIONS.
2. IF A TRAFFIC CONTROL PLAN IS PROVIDED AS PART OF THE PROJECT PLANS SUBMIT TO THE CITY FOR APPROVAL ANY PROPOSED CHANGES, TRAFFIC CONTROL LAYOUT AND DETAILS, STAGING SEQUENCES AND DETAILS FOR WORK AFFECTING VEHICULAR, PEDESTRIAN AND BICYCLE TRAFFIC, AND PROPOSED ORDER AND DURATION OF THE TRAFFIC CONTROL MEASURES.
3. NO WORK SHALL BEGIN UNTIL THE TRAFFIC CONTROL PLAN IS REVIEWED AND APPROVED BY THE CITY.
4. ALL SIGNS, BARRICADES, FLAGMEN AND OTHER TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AND THE OREGON TEMPORARY TRAFFIC CONTROL HANDBOOK.
5. THE CONTRACTOR SHALL PROVIDE ACCESS TO ALL ADJACENT PROPERTIES DURING WORK HOURS. CONSTRUCTION OPERATIONS SHALL BE CONSTRUCTED IN SUCH A MANNER AS TO CAUSE AS LITTLE INCONVENIENCE AS POSSIBLE TO ADJUTING PROPERTY OWNERS/OPERATORS.
6. THE CITY RESERVES THE RIGHT TO OBSERVE THE TRAFFIC CONTROL OPERATIONS AND TO MAKE ANY NECESSARY CHANGES. ANY DIRECTED CHANGES SHALL SUPERSEDE APPROVED PLANS AND SHALL BE IMPLEMENTED AT THE SOLE EXPENSE OF THE CONTRACTOR.
7. IF THE TRAFFIC CONTROL PLAN REQUIRE CLOSURE OF A ROAD SECTION OR IF DELAYS ARE TO BE EXPECTED WITH THE TRAFFIC CHANGE THE CONTRACTOR SHALL SUBMIT A PRESS RELEASE TO BE APPROVED BY THE CITY. PRESS RELEASE SHALL STATE WHAT THE CONSTRUCTION ACTIVITY IS, WHAT TRAFFIC CHANGES WILL BE EXPECTED, THE LOCATION OF THE TRAFFIC CHANGES AND ANY DETOUR ROUTES USED, DATES AND TIMES FOR THE TRAFFIC CHANGE.
8. TEMPORARY "NO PARKING" SIGNS SHALL BE POSTED 48 HOURS PRIOR TO COMMENCING WORK.
9. TRENCHES MUST BE BACK FILLED OR PLATED DURING NON-WORKING HOURS. SHIM THE EDGES OF ALL STEEL PLATES WITH COLD MIX ASPHALT. CONTRACTOR SHALL MAINTAIN BACKFILLED TRENCH SURFACE PRIOR TO PAVING.
10. THE CONTRACTOR SHALL REPLACE WITHIN 24 HOURS, ALL STRIPING REMOVED OR DAMAGED BY CONSTRUCTION WORK. (STRIPING MAY BE REPLACED TEMPORARILY WITH TAPE)
11. A MINIMUM OF ELEVEN (11) FOOT TRAVEL LANES MUST BE MAINTAINED UNLESS OTHERWISE APPROVED BY THE CITY.
12. ALL NIGHT WORK WILL REQUIRE WRITTEN APPROVAL FROM THE CITY MANAGER. LANE CLOSURES, ROAD DETOURS, ROAD CLOSURES, AND TRAFFIC SIGNAL MODIFICATIONS ASSOCIATED WITH OVERNIGHT CONSTRUCTION ACTIVITIES WILL REQUIRE WARNING SIGNS BEING PLACED AT LEAST ONE WEEK IN ADVANCE OF STARTING CONSTRUCTION.
13. WHEN PEDESTIAN PATHS AND PEDESTRIAN ROAD CROSSINGS ARE DISTURBED PROVIDE ALTERNATE ACCESSIBLE ROUTE AROUND THE WORK. SEE STANDARD DRAWING TM844 FOR TEMPORARY PEDESTRIAN ACCESS ROUTING DETAILS.
14. CONTRACTOR SHALL POST "BUMP" SIGNS FOR PAVEMENT SURFACE DISRUPTIONS OF 1/2" OR GREATER. PAVEMENT DISRUPTIONS OF 1" OR GREATER SHALL BE BEVELED TO FOUR (4) HORIZONTAL TO ONE (1) VERTICAL.
15. CONTRACTOR SHALL POST "STEEL PLATES AHEAD" SIGNS IN ADVANCE OF STEEL PLATE BRIDGING IN THE ROADWAY.

PROJECT SPECIFIC TRAFFIC CONTROL NOTES


1. CONTRACTOR TO PROVIDE ALL PEDESTRIAN AND TRAFFIC CONTROL DEVICES FOR THE PROJECT UNLESS OTHERWISE NOTED.
2. WORK SHALL BE STAGED TO PROVIDE MINIMAL IMPACT TO PEDESTRIANS USING THE SYSTEM. WORK SHALL BE CONFINED TO ONE AREA AT A TIME TO AVOID LENGTHY DETOURS AROUND THE WORK AREA. NO MORE THEN ONE CORNER PER INTERSECTION SHALL BE CLOSED AT A TIME UNLESS APPROVED BY THE CITY.
3. FOR WORK AT THE INTERSECTIONS, PROVIDE ROAD WORK AHEAD SIGNS, CONE TAPER AND CONES ALONG EDGE OF TRAVEL WAY ON EACH LEG OF THE INTERSECTION TO GIVE ADVANCED NOTICE TO DRIVERS SIMILAR TO DIAGRAM 210 FROM ODOT TEMPORARY TRAFFIC CONTROL HANDBOOK. FOR THE TEMPORARY PEDESTRIAN ACCESSIBLE ROUTE PROVIDE A DETOUR SIMILAR TO ONE OF THE OPTIONS ON STANDARD DETAIL TM844.

Work on Shoulder Diagram 210



01-JUL-2017

TM844



TM844

NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

TRAFFIC CONTROL AND PEDESTRIAN DETOUR PLAN FOR:
2023 ADA IMPROVEMENT PROJECT
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	NTS
CHECKED	
SHEET	
C0.3	
OF 60 SHEETS	
JOB NO.	2023-003

CHERRY HEIGHTS ROAD


WEST 9TH STREET

CONTROL POINT 1
MAG NAIL
ELEV. = 149.77

- NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 2. CONTROL POINT #2 IS OFF SHEET AT NW CORNER OF 8TH AND CHERRY HEIGHTS ROAD.



REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
**2023 ADA IMPROVEMENT PROJECT
9TH AND CHERRY HEIGHTS ROAD**
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.1
OF 60 SHEETS	
JOB NO.	2023-003

NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.



BRIDGE STREET

WEST 10TH STREET

CONTROL POINT 3
MAG NAIL
ELEV. = 172.02


169


170

171

172

NO.	DATE	REVISIONS






CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401


A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
10TH AND BRIDGE STREET
THE DALLES, OREGON


NAME	TWS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.2
OF	60 SHEETS
JOB NO.	2023-003



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

REVISIONS		
NO.	DATE	






CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
**2023 ADA IMPROVEMENT PROJECT
9TH AND BRIDGE STREET**
THE DALLES, OREGON


NAME	TWS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.3
OF 60 SHEETS	
JOB NO.	2023-003



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

CONTROL POINT 5
1" NAIL
ELEV. = 106.25


REVISIONS		
NO.	DATE	



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401


A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 4TH STREET
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.4
OF 60 SHEETS	
JOB NO.	2023-003



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.


NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 5TH STREET
THE DALLES, OREGON


NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.5
OF	60 SHEETS
JOB NO.	2023-003



- NOTES:**
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 2. CONTROL POINT #7 IS OFF PAGE, 90 FEET NORTH OF NE CORNER OF 7TH AND UNION, MIDDLE OF SIDEWALK.

REVISIONS		
NO.	DATE	





CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 6TH PLACE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C16
OF	60 SHEETS
JOB NO.	2023-003

E 16TH PLACE

E 18TH STREET

CONTROL POINT 8
MAG NAIL
ELEV. = 431.93

CONTROL POINT 9
MAG NAIL
ELEV. = 436.40

433

434

435

436


437



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
E 16TH PL AND E 18TH STREET
THE DALLES, OREGON


NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.7
OF	60 SHEETS
JOB NO.	2023-002



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401


NO.	DATE	REVISIONS

CONTROL POINT 10
MAG NAIL
ELEV. = 296.36



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.


NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND VIEW COURT
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.8
OF 60 SHEETS	
JOB NO.	2023-003



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND DRY HOLLOW RD
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C19
OF	60 SHEETS
JOB NO.	2023-003

E 11TH STREET

DRY HOLLOW ROAD


CONTROL POINT 12
MAG NAIL
ELEV. = 259.22


258
259
260
261
262



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

REVISIONS		
NO.	DATE	






CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND DRY HOLLOW RD
THE DALLES, OREGON

NAME	TWS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.10
OF	60 SHEETS
JOB NO.	2023-003

E 11TH STREET

OREGON AVENUE




CONTROL POINT 13
MAG NAIL
ELEV. = 274.03



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.11
OF	60 SHEETS
JOB NO.	2023-003


A TOPOGRAPHIC SURVEY FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND OREGON AVENUE
THE DALLES, OREGON



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401




NO.	DATE	REVISIONS



NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

NO.	DATE	REVISIONS





CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A TOPOGRAPHIC SURVEY FOR:
**2023 ADA IMPROVEMENT PROJECT
BRENTWOOD AND COLUMBIA VIEW**
THE DALLES, OREGON


NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.12
OF	60 SHEETS
JOB NO.	2023-003

ROYAL CREST DRIVE

BRENTWOOD DRIVE

CONTROL POINT 14
FD SPIKE
ELEV. = 331.08

NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.



NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C1.13
OF	60 SHEETS
JOB NO.	2023-003

A TOPOGRAPHIC SURVEY FOR:
**2023 ADA IMPROVEMENT PROJECT
BRENTWOOD AND ROYAL CREST**
THE DALLES, OREGON



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

NO.	DATE	REVISIONS

CHERRY HEIGHTS ROAD

WEST 9TH STREET

CORNER #2
INSTALL PARALLEL CURB RAMP,
20 FT OF CURB AND GUTTER AND
22 SY OF CONCRETE SIDEWALK

INSTALL TYPE G2 CATCH BASIN
REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB \approx 148.27
GRATE \approx 147.60

INSTALL TYPE G2 CATCH BASIN
REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB \approx 147.45
GRATE \approx 146.87

CORNER #3
INSTALL PARALLEL CURB RAMP,
31 FT OF CURB AND GUTTER AND
27 SY OF CONCRETE SIDEWALK

ESTIMATED PAVEMENT MATCH LINE (TYP)

CORNER #2, RAMP #1

CORNER #3, RAMP #1



- NOTES:
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.1 - C7.2 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.

NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
**2023 ADA IMPROVEMENT PROJECT
9TH AND CHERRY HEIGHTS ROAD
THE DALLES,
OREGON**

NAME	TWS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.1
OF 60 SHEETS	
JOB NO.	2023-003

- NOTES:
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.3 - C7.4 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.
 - 6. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

CORNER #1
INSTALL 2 PERPENDICULAR CURB RAMPS,
23 FT OF CURB AND GUTTER, 5 FT OF CURB
AND 22 SY OF CONCRETE SIDEWALK

ESTIMATED PAVEMENT MATCH LINE (TYP)

☉ CORNER #1, RAMP #1

☉ CORNER #1, RAMP #2

CORNER #4
INSTALL 2 PERPENDICULAR CURB RAMPS,
25 FT OF CURB AND GUTTER, 8 FT OF CURB
AND 22 SY OF CONCRETE SIDEWALK

☉ CORNER #4, RAMP #2

☉ CORNER #4, RAMP #1

INSTALL TYPE G2 CATCH BASIN
REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB ≈ 171.80
GRATE ≈ 171.22
TOP OF RISER ≈ 171.55

BRIDGE STREET

WEST 10TH STREET

NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
10TH AND BRIDGE STREET
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.2
OF	60 SHEETS
JOB NO.	2023-003

WEST 9TH STREET

CORNER #2
INSTALL 2 PERPENDICULAR CURB RAMPS,
22 FT OF CURB AND GUTTER, 12 FT OF CURB
AND 21 SY OF CONCRETE SIDEWALK

INSTALL TYPE G2 CATCH BASIN
REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB ≈ 166.15
GRATE ≈ 165.55

ESTIMATED PAVEMENT MATCH LINE (TYP)

☉ CORNER #2, RAMP #1

REINSTATE SURVEY MARKER

☉ CORNER #2, RAMP #2

☉ CORNER #3, RAMP #1

REINSTATE SURVEY MARKER

☉ CORNER #3, RAMP #2

INSTALL TYPE G2 CATCH BASIN
REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB ≈ 167.35
GRATE ≈ 166.77

CORNER #3
INSTALL 2 PERPENDICULAR CURB RAMPS,
27 FT OF CURB AND GUTTER, 15 FT OF CURB
AND 21 SY OF CONCRETE SIDEWALK

BRIDGE STREET



NOTES:

1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
3. SEE SHEETS C7.5 - C7.6 FOR CURB RAMP DETAIL DRAWINGS.
4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.
6. REINSTATE SURVEY MARKERS ON EACH CORNER AFTER RAMPS ARE INSTALLED
7. REINSTATE FENCE TO NEW BACK OF SIDEWALK ON CORNER #2.
8. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401


A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
9TH AND BRIDGE STREET
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.3
OF	60 SHEETS
JOB NO.	2023-003

4TH STREET

UNION STREET

- NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 3. SEE SHEETS C7.7 - C7.10 FOR CURB RAMP DETAIL DRAWINGS.
 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.
 6. REINSTATE SURVEY MARKERS ON EACH CORNER AFTER RAMPS ARE INSTALLED




REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 4TH STREET
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.4
OF	60 SHEETS
JOB NO.	2023-003



- NOTES:**
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 3. SEE SHEETS C7.11 - C7.14 FOR CURB RAMP DETAIL DRAWINGS.
 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.


REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 5TH STREET
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.5
OF	60 SHEETS
JOB NO.	2023-003



- NOTES:**
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.15 - C7.16 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.

CORNER #1
INSTALL PERPENDICULAR CURB RAMP,
8 FT OF CURB AND GUTTER, 19 FT OF
CURB AND 32 SY OF CONCRETE SIDEWALK

REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)

CL CORNER #1, RAMP #1

INSTALL TYPE G2 CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB ≈ 134.04
GRATE ≈ 133.46
TOP OF RISER ≈ 133.79

INSTALL TYPE G2 CATCH BASIN
REMOVE EXISTING CATCH BASIN
(TO BE DONE BY OTHERS)
TOP OF CURB ≈ 132.75
GRATE ≈ 132.20

ESTIMATED PAVEMENT MATCH LINE (TYP)

CL CORNER #4, RAMP #1

CORNER #4
INSTALL PERPENDICULAR CURB RAMP,
11 FT OF CURB AND GUTTER, 21 FT OF
CURB AND 26 SY OF CONCRETE SIDEWALK

UNION STREET

6TH PLACE

CORNER #3
21 FT OF CURB AND 14 SY
OF CONCRETE SIDEWALK

REVISIONS		
NO.	DATE	



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:

2023 ADA IMPROVEMENT PROJECT
UNION AND 6TH PLACE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.6
OF 60 SHEETS	
JOB NO.	2023-003

E 16TH PLACE

E 18TH STREET

ESTIMATED PAVEMENT MATCH LINE (TYP)

☉ CORNER #4, RAMP #1

CORNER #4
INSTALL END OF WALK CURB RAMP,
EW-1 TAPER, 22 FT OF CURB AND GUTTER
AND 13 SY OF CONCRETE SIDEWALK



- NOTES:
1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 3. SEE SHEETS C7.17 FOR CURB RAMP DETAIL DRAWINGS.
 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 5. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

REVISIONS		
NO.	DATE	



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401


A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 16TH PL AND E 18TH STREET
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.7
OF	60 SHEETS
JOB NO.	2023-003


VIEW COURT



- NOTES:
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.18 - C7.19 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.



E 13TH PLACE



NO.	DATE	REVISIONS





CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND VIEW COURT
THE DALLES, OREGON

NAME	TWS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.8
OF	60 SHEETS
JOB NO.	2023-003

E 13TH PLACE



DRY HOLLOW ROAD



- NOTES:**
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.20 - C7.21 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

REVISIONS	
NO.	DATE




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND DRY HOLLOW RD
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.9
OF	60 SHEETS
JOB NO.	2023-003

E 11TH STREET

DRY HOLLOW ROAD



- NOTES:**
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.22 - C.23 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.
 - 6. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

REVISIONS		
NO.	DATE	




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND DRY HOLLOW RD
THE DALLES, OREGON


NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.10
OF 60 SHEETS	
JOB NO.	2023-003

E 11TH STREET

CORNER #1
INSTALL PARALLEL CURB RAMP,
25 FT OF CURB AND GUTTER, 9 FT CURB
AND 21 SY OF CONCRETE SIDEWALK



CORNER #2
INSTALL PARALLEL CURB RAMP, 32 FT
OF CURB AND GUTTER, 29 FT CURB
AND 22 SY OF CONCRETE SIDEWALK



OREGON AVENUE




- NOTES:**
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.24 - C7.25 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401



A LAYOUT SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND OREGON AVENUE
THE DALLES, OREGON


NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.11
OF	60 SHEETS
JOB NO.	2023-003

COLUMBIA VIEW DRIVE

BRENTWOOD DRIVE



- NOTES:
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.26 - C7.27 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. COORDINATE CATCH BASIN INSTALLATION WITH CITY STAFF SO CATCH BASINS CAN BE INSTALLED AHEAD OF CONCRETE IMPROVEMENTS.
 - 6. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.




REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:
**2023 ADA IMPROVEMENT PROJECT
BRENTWOOD AND COLUMBIA VIEW**
THE DALLES,
OREGON


NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	C5.12
OF 60 SHEETS	
JOB NO.	2023-003



- NOTES:**
- 1. SEE SHEETS C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - 3. SEE SHEETS C7.3 - C7.4 FOR CURB RAMP DETAIL DRAWINGS.
 - 4. COORDINATE SIGN BASE LOCATIONS WITH CITY STAFF.
 - 5. WORK AT THIS LOCATION IS ADJACENT TO AN ASPHALT GRIND AND OVERLAY PROJECT. ALL WORK AT THIS LOCATION SHALL BE COMPLETED BY APRIL 28, 2023.

REVISIONS		
NO.	DATE	






CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A LAYOUT SHEET FOR:

**2023 ADA IMPROVEMENT PROJECT
BRENTWOOD AND ROYAL CREST**

THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 20'
CHECKED	
SHEET	
	C5.13
OF	60 SHEETS
JOB NO.	2023-003



- NOTES:
- 1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SLOPES HOLD OVER ELEVATIONS.
 - 3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	1.0%
	COUNTER SLOPE	4.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	4.0%
	CROSS SLOPE	1.0%
	RAMP LENGTH	5.0 ft
RAMP RUN 3	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	10 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	7.7 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	148.38	147.74	707146.74	8022491.08
C2	147.63	147.63	707153.85	8022498.11
C3	147.58	147.58	707157.40	8022501.62
C4	147.74	147.42	707160.96	8022505.14

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
9TH AND CHERRY HTS RD - SW
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.1
OF 60 SHEETS
JOB NO. 2023-003

CHERRY HEIGHTS ROAD

WEST 9TH STREET



Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	147.91	147.42	707112.91	8022518.88
C2	146.80	146.80	707123.21	8022529.42
C3	146.75	146.75	707124.09	8022539.52
C4	147.02	146.64	707121.38	8022543.50

- NOTES:
- SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - SLOPES HOLD OVER ELEVATIONS.
 - SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.5%
RAMP RUN 2	COUNTER SLOPE	4.0%
	RAMP LENGTH	NA
	RUNNING SLOPE	7.5%
RAMP RUN 3	CROSS SLOPE	1.0%
	RAMP LENGTH	15.0 ft
	RUNNING SLOPE	5.6%
TURNING	CROSS SLOPE	1.0%
	RAMP LENGTH	4.8 ft
	WIDTH X	7.1 ft
	LENGTH Y	7.4 ft
	SLOPE X	0.5%
	SLOPE Y	1.0%

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
9TH AND CHERRY HTS RD - SE
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.2
OF 60 SHEETS
JOB NO. 2023-003

BRIDGE STREET

WEST 10TH STREET




NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION



SIDEWALK




TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)



TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)



TRUNCATED DOME



CONCRETE PLANTER



SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)



SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)



COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)



STATION, OFFSET, ELEVATION POINT




LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	1.6%	7.4%
	CROSS SLOPE	2%	0.0%
	GUTTER FLOW SLOPE	4.0%	1.5%
	COUNTER SLOPE	4.0%	-2.0%
	RAMP LENGTH	3.1 ft	3.1 ft
RAMP RUN 2	RUNNING SLOPE	5.9%	NA
	CROSS SLOPE	1.0%	NA
	RAMP LENGTH	9.6 ft	NA
RAMP RUN 3	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.5 ft	5.0 ft
	SLOPE X	1.3%	1.0%
	SLOPE Y	0.0%	1.3%

Location	Elevation	Northing	Easting
S1	171.45	705838.23	8023997.77
S2	171.45	705834.08	8023994.96
S3	171.38	705841.38	8023993.25

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	171.72	171.47	705829.13	8023993.33
C2	171.75	171.45	705830.33	8023991.63
C3	171.33	171.33	705834.30	8023988.30
C4	171.49	171.24	705836.77	8023987.53
C5	171.15	171.15	705839.35	8023987.41
C6	171.08	171.08	705844.22	8023989.17
C7	171.27	170.87	705848.33	8023992.02

NO.	DATE	REVISIONS




A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
10TH AND BRIDGE STREET - NE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.4
OF 60 SHEETS	
JOB NO.	2023-003

Location	Elevation	Northing	Easting
S1	165.87	706055.58	8024078.37
S2	165.82	706059.61	8024081.20
S3	165.87	706052.56	8024082.57
S4	166.16	706048.11	8024078.77

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	166.15	165.45	706045.28	8024083.61
C2	165.60	165.60	706049.92	8024086.63
C3	165.65	165.65	706054.63	8024088.56
C4	165.95	165.70	706057.36	8024088.45
C5	165.65	165.65	706059.94	8024087.52
C6	165.80	165.60	706063.58	8024083.97



NOTES:

- SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
- SLOPES HOLD OVER ELEVATIONS.
- SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES	VALUES
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	5.2%	5.2%
	CROSS SLOPE	0.0%	1.0%
	GUTTER FLOW SLOPE	1.0%	1.0%
	COUNTER SLOPE	4.0%	4.0%
	RAMP LENGTH	3.3 ft	3.3 ft
RAMP RUN 2	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
RAMP RUN 3	RUNNING SLOPE	NA	5.7%
	CROSS SLOPE	NA	1.0%
	RAMP LENGTH	NA	4.3 ft
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	0.0%	1.0%
	SLOPE Y	1.0%	0.0%

NO.	DATE	REVISIONS




A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
9TH AND BRIDGE STREET - SW
 THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.5
OF 60 SHEETS	
JOB NO.	2023-003

BRIDGE STREET

WEST 9TH STREET



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	5.1%	2.6%
	CROSS SLOPE	1.0%	1.0%
	GUTTER FLOW SLOPE	1.0%	1.0%
	COUNTER SLOPE	-2.0%	4.0%
RAMP RUN 2	RAMP LENGTH	3.1 ft	3.1 ft
	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
RAMP RUN 3	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
	RAMP LENGTH	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	1.0%	1.0%
	SLOPE Y	1.0%	1.0%

Location	Elevation	Northing	Easting
S1	167.03	706023.52	8024124.95
S2	167.25	706020.93	8024117.13
S3	166.98	706026.52	8024120.64

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	167.28	166.72	706020.34	8024110.26
C2	167.20	166.70	706024.44	8024113.11
C3	166.75	166.75	706029.37	8024116.53
C4	166.80	166.80	706032.71	8024120.49
C5	167.07	166.82	706033.51	8024123.00
C6	166.85	166.85	706033.63	8024125.64
C7	167.30	166.90	706031.84	8024130.50
C8	167.40	166.97	706025.65	8024139.27
C9	166.98	166.98	706027.75	8024127.63

REVISIONS

NO.	DATE	

REGISTERED PROFESSIONAL

1000 W. MAIN ST. SUITE 100
DALES, OREGON 97058
EXP. 06/30/24

CITY OF THE DALLES

PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:

2023 ADA IMPROVEMENT PROJECT
9TH AND BRIDGE STREET - SE
THE DALLES, OREGON

NAME TMS

DATE 12/16/2022

SCALE 1" = 5'


CHECKED

SHEET

C7.6

OF 60 SHEETS

JOB NO. 2023-003



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	7.4%	7.4%
	CROSS SLOPE	0.0%	0.0%
	GUTTER FLOW SLOPE	1.0%	1.0%
	COUNTER SLOPE	4.0%	4.0%
	RAMP LENGTH	3.1 ft	3.1 ft
RAMP RUN 2	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
RAMP RUN 3	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	1.0%	1.0%
	SLOPE Y	1.0%	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	108.27	107.77	706035.87	8026648.03
C2	107.97	107.97	706032.47	8026652.95
C3	108.02	108.02	706030.24	8026657.78
C4	108.30	108.05	706030.30	8026660.18
C5	108.02	108.02	706031.08	8026662.46
C6	107.97	107.97	706034.86	8026666.20
C7	108.10	107.60	706040.58	8026670.19

Location	Elevation	Northing	Easting
S1	108.20	706040.26	8026658.39


REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 4TH STREET - NW
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.7
OF 60 SHEETS
JOB NO. 2023-003



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION



SIDEWALK




TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)



TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)



TRUNCATED DOME



CONCRETE PLANTER



SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)




SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)



COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)



STATION, OFFSET, ELEVATION POINT



LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	6.2%	4.2%
	CROSS SLOPE	0.0%	1.0%
	GUTTER FLOW SLOPE	0.6%	1.0%
RAMP RUN 2	COUNTER SLOPE	1.0%	4.0%
	RAMP LENGTH	3.4 ft	3.6 ft
	RUNNING SLOPE	NA	NA
RAMP RUN 3	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
	RUNNING SLOPE	NA	8.4%
TURNING	CROSS SLOPE	NA	1.0%
	RAMP LENGTH	NA	15.0 ft
	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	0.0%	1.0%
	SLOPE Y	1.0%	0.0%

Location	Elevation	Northing	Easting
S1	108.85	705991.75	8026626.30
S2	108.80	705993.03	8026633.30

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	109.56	109.26	705979.28	8026629.78
C2	109.20	108.70	705986.13	8026634.54
C3	108.65	108.65	705990.94	8026636.77
C4	108.87	108.62	705993.69	8026636.64
C5	108.59	108.59	705996.23	8026635.58
C6	108.56	108.56	705999.60	8026631.84
C7	108.87	108.37	706003.05	8026626.95
C8	108.50	108.12	706004.40	8026618.11

REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 4TH STREET - SW
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.8
OF 60 SHEETS	
JOB NO.	2023-003


4TH STREET

UNION STREET


NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION



SIDEWALK




TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)



TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)



TRUNCATED DOME



CONCRETE PLANTER



SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)




SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)



COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)



STATION, OFFSET, ELEVATION POINT



LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	7.1%	7.2%
	CROSS SLOPE	1.0%	0.0%
	GUTTER FLOW SLOPE	4.0%	4.0%
	COUNTER SLOPE	1.2%	1.2%
	RAMP LENGTH	4.2 ft	3.2 ft
	RAMP RUN 2		
	RUNNING SLOPE	8.5%	NA
	CROSS SLOPE	0.0%	NA
	RAMP LENGTH	15.0 ft	NA
RAMP RUN 3	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	1.0%	0.0%
	SLOPE Y	0.0%	1.0%


MATCH EXISTING

MATCH EXISTING

Location	Elevation	Northing	Easting
S1	108.88	705959.04	8026673.86
S2	108.83	705965.98	8026672.59

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	109.52	109.32	705955.64	8026658.37
C2	109.20	108.80	705965.17	8026664.97
C3	108.74	108.74	705968.67	8026668.68
C4	108.95	108.70	705969.43	8026671.65
C5	108.66	108.60	705969.02	8026674.69
C6	108.96	108.56	705966.43	8026678.98
C7	108.96	108.56	705963.04	8026683.93
C8	108.88	108.65	705959.64	8026688.87


REVISIONS	
NO.	DATE



A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 4TH STREET - SE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.9
OF	60 SHEETS
JOB NO.	2023-003

UNION STREET



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION



SIDEWALK



TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)



TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)



TRUNCATED DOME



CONCRETE PLANTER



SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)




SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)



COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)



STATION, OFFSET, ELEVATION POINT



LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	7.1%	7.1%
	CROSS SLOPE	0.0%	0.0%
	GUTTER FLOW SLOPE	1.0%	1.0%
	COUNTER SLOPE	2.0%	2.0%
RAMP RUN 2	RAMP LENGTH	3.5 ft	3.5 ft
	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
RAMP RUN 3	RUNNING SLOPE	NA	NA
	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
	RAMP LENGTH	NA	NA
TURNING	WIDTH X	5.0 ft	5.3 ft
	LENGTH Y	5.3 ft	6.3 ft
	SLOPE X	0.5%	0.5%
	SLOPE Y	0.5%	0.5%

Location	Elevation	Northing	Easting
S1	108.05	706006.38	8026709.03
S2	108.29	706003.55	8026713.15

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	108.20	107.70	705995.23	8026707.46
C2	108.15	107.75	705998.80	8026702.24
C3	107.80	107.80	706002.42	8026698.40
C4	108.07	107.82	706004.91	8026697.49
C5	107.80	107.80	706007.57	8026697.45
C6	107.75	107.75	706012.32	8026699.76
C7	107.69	107.39	706018.07	8026703.75
C8	108.00	108.00	706002.70	8026704.95


REVISIONS	
NO.	DATE



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 4TH STREET - NE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.10
OF 60 SHEETS	
JOB NO.	2023-003



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	7.4%
	CROSS SLOPE	1.4%
	GUTTER FLOW SLOPE	1.4%
	COUNTER SLOPE	2.0%
	RAMP LENGTH	4.4 ft
RAMP RUN 2	RUNNING SLOPE	7.3%
	CROSS SLOPE	1.0%
	RAMP LENGTH	15.0 ft
RAMP RUN 3	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	RAMP LENGTH	NA
TURNING	WIDTH X	5.0 ft
	LENGTH Y	5.0 ft
	SLOPE X	1.4%
	SLOPE Y	1.0%

Location	Elevation	Northing	Easting
S1	123.42	705797.61	8026499.89
S2	123.35	705801.73	8026502.72

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	123.53	123.13	705791.54	8026501.68
C2	123.09	123.09	705794.84	8026503.94
C3	123.02	123.02	705798.97	8026506.76
C4	123.04	122.74	705802.27	8026509.02


NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 5TH STREET - NW
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.11
OF 60 SHEETS	
JOB NO.	2023-003



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	7.4%
	CROSS SLOPE	1.4%
	GUTTER FLOW SLOPE	1.4%
	COUNTER SLOPE	4.0%
	RAMP LENGTH	4.7 ft
RAMP RUN 2	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	RAMP LENGTH	NA
RAMP RUN 3	RUNNING SLOPE	7.4%
	CROSS SLOPE	1.0%
	RAMP LENGTH	9.2 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	5.0 ft
	SLOPE X	1.4%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	125.45	125.15	705752.89	8026475.37
C2	125.25	124.92	705757.03	8026478.18
C3	125.10	124.85	705761.16	8026480.99
C4	124.80	124.50	705765.30	8026483.80
C5	125.26	125.26	705759.93	8026473.89
C6	125.19	125.19	705764.06	8026476.72

REVISIONS

NO.	DATE	


CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
202 ADA IMPROVEMENT PROJECT
UNION AND 5TH STREET – SW
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	
C7.12	
OF	60 SHEETS
JOB NO.	2023-003

UNION STREET


5TH STREET




NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION



SIDEWALK



TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)



TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)



TRUNCATED DOME



CONCRETE PLANTER



SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)




SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)



COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)



STATION, OFFSET, ELEVATION POINT




LANDSCAPING

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	125.90	125.40	705723.48	8026503.35
C2	125.52	125.02	705727.18	8026505.87
C3	125.30	124.90	705734.95	8026506.90
C4	125.02	124.77	705737.83	8026508.88
C5	124.72	124.72	705741.96	8026511.70
C6	124.90	124.65	705744.07	8026514.91

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C7	124.57	124.57	705743.28	8026518.66
C8	124.90	124.57	705740.48	8026522.80
C9	124.83	124.50	705738.52	8026525.70
C10	124.70	124.20	705731.87	8026529.63
C11	124.95	124.95	705735.03	8026513.02
C12	124.90	124.90	705736.35	8026519.98

RAMP	ITEM	VALUES	
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	4.0%	7.5%
	CROSS SLOPE	1.0%	0.0%
	GUTTER FLOW SLOPE	1.0%	0.0%
RAMP RUN 2	COUNTER SLOPE	4.0%	-4.0%
	RAMP LENGTH	4.5 ft	4.5 ft
	RUNNING SLOPE	7.5%	NA
RAMP RUN 3	CROSS SLOPE	0.5%	NA
	RAMP LENGTH	15 ft	NA
	RUNNING SLOPE	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	1.0%	0.0%
	SLOPE Y	0.0%	1.0%

REVISIONS	
NO.	DATE




A RAMP DETAIL SHEET FOR:
**2023 ADA IMPROVEMENT PROJECT
UNION AND 5TH STREET - SE**
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.13
OF 60 SHEETS	
JOB NO.	2023-003

UNION STREET

5TH STREET



NOTES:
1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	123.19	122.69	705763.44	8026553.76
C2	123.30	123.05	705764.64	8026544.90
C3	123.37	123.12	705766.61	8026542.01
C4	123.05	123.05	705769.53	8026537.86
C5	123.21	122.96	705772.60	8026535.75

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C6	122.87	122.87	705776.29	8026535.25
C7	122.80	122.80	705781.16	8026537.42
C8	122.73	122.37	705787.18	8026541.62
C9	123.27	123.27	705770.33	8026544.55

Location	Elevation	Northing	Easting
S1	123.22	705777.32	8026543.19

RAMP	ITEM	VALUES	VALUES
		RAMP 1	RAMP 2
RAMP RUN 1	RUNNING SLOPE	3.8%	7.5%
	CROSS SLOPE	1.4%	0.0%
	GUTTER FLOW SLOPE	1.4%	1.4%
RAMP RUN 2	COUNTER SLOPE	4.0%	4.0%
	RAMP LENGTH	4.0 ft	5.6 ft
	RUNNING SLOPE	NA	NA
RAMP RUN 3	CROSS SLOPE	NA	NA
	RAMP LENGTH	NA	NA
	RUNNING SLOPE	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	1.4%	0.0%
	SLOPE Y	0.0%	1.4%


REVISIONS

NO.	DATE	

CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
**2023 ADA IMPROVEMENT PROJECT
UNION AND 5TH STREET - NE**
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.14
OF 60 SHEETS
JOB NO.
2023-003



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
	GUTTER FLOW SLOPE	4.0%
	COUNTER SLOPE	4.0%
RAMP RUN 2	RAMP LENGTH	4.7 ft
	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
RAMP RUN 3	RAMP LENGTH	6.6 ft
	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
TURNING	RAMP LENGTH	15.0 ft
	WIDTH X	5.0 ft
	LENGTH Y	6.5 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	131.99	131.74	705643.95	8026400.90
C2	131.89	131.54	705648.06	8026403.74
C3	131.69	131.34	705650.80	8026405.60
C4	131.45	131.34	705655.15	8026404.88
C5	131.41	131.41	705656.35	8026403.14
C6	131.89	131.89	705646.80	8026396.65
C7	131.94	131.94	705650.93	8026399.46

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
**2023 ADA IMPROVEMENT PROJECT
UNION AND 6TH PLACE - NW**
THE DALLES, OREGON

NAME TWS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.15
OF 60 SHEETS
JOB NO. 2023-003

UNION STREET



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.


- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
	GUTTER FLOW SLOPE	3.0%
RAMP RUN 2	COUNTER SLOPE	4.0%
	RAMP LENGTH	4.0 ft
	RUNNING SLOPE	7.5%
RAMP RUN 3	CROSS SLOPE	1.0%
	RAMP LENGTH	15.0 ft
	RUNNING SLOPE	4.5%
TURNING	CROSS SLOPE	1.0%
	RAMP LENGTH	10 ft
	WIDTH X	5.0 ft
	LENGTH Y	5.0 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

Location	Elevation	Northing	Easting
S1	132.22	705616.53	8026437.99
S2	132.00	705619.01	8026439.68
S3	131.95	705623.13	8026442.51
S4	131.77	705625.60	8026444.21


Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	133.04	132.47	705610.55	8026425.75
C2	132.60	132.10	705615.27	8026429.13
C3	132.10	131.85	705622.01	8026430.11
C4	131.75	131.75	705624.47	8026431.82
C5	131.60	131.60	705628.58	8026434.67
C6	131.67	131.42	705631.04	8026436.38
C7	131.26	130.84	705634.85	8026442.60

NO.	DATE	REVISIONS



A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
UNION AND 6TH PLACE - NE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.16
OF 60 SHEETS	
JOB NO.	2023-003



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	1.0%
RAMP RUN 2	COUNTER SLOPE	2.0%
	RAMP LENGTH	NA
	RAMP LENGTH	NA
RAMP RUN 3	RUNNING SLOPE	6.6%
	CROSS SLOPE	1.0%
	RAMP LENGTH	12.2 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	5.5 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	433.98	433.45	701279.13	8029385.13
C2	434.85	434.85	701271.67	8029398.85
C3	434.90	434.90	701271.76	8029405.23

REVISIONS


NO.	DATE	

CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 16TH PL AND E 18TH - NE
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.17
OF 60 SHEETS
JOB NO.
2023-003

VIEW COURT



E. 13TH PLACE

NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.


- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.5%
	COUNTER SLOPE	-4.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	6.9%
	CROSS SLOPE	1.0%
	RAMP LENGTH	13.4 ft
RAMP RUN 3	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	8.7 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	6.2 ft
	SLOPE X	0.6%
	SLOPE Y	0.8%

Location	Elevation	Northing	Easting
S1	298.28	702465.31	8030931.53
S2	297.69	702475.26	8030935.66
S3	298.30	702479.34	8030945.63

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	298.58	298.12	702460.30	8030926.46
C2	298.07	297.82	702469.34	8030926.41
C3	297.65	297.65	702476.48	8030928.17
C4	297.60	297.60	702482.76	8030934.54
C5	298.02	297.70	702484.42	8030941.49
C6	298.29	297.76	702484.40	8030946.05


NO.	DATE	REVISIONS



A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND VIEW CT - SE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.18
OF 60 SHEETS	
JOB NO.	2023-003

VIEW COURT



E. 13TH PLACE

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	297.21	296.71	702520.09	8030945.68
C2	297.01	296.66	702520.15	8030942.17
C3	296.55	296.55	702522.49	8030934.13
C4	296.48	296.48	702528.30	8030928.51
C5	296.67	296.26	702536.37	8030926.46
C6	296.71	296.21	702538.23	8030926.49

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C7	296.58	296.21	702541.30	8030926.53
C8	297.26	297.26	702525.08	8030945.81
C9	297.10	296.60	702527.67	8030937.29
C10	297.03	296.53	702531.35	8030933.94
C11	296.76	296.76	702538.16	8030932.04

NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	1.0%
	COUNTER SLOPE	-2.0%
RAMP RUN 2	RAMP LENGTH	NA
	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
RAMP RUN 3	RAMP LENGTH	8.9 ft
	RUNNING SLOPE	3.2%
	CROSS SLOPE	1.0%
TURNING	RAMP LENGTH	7.1 ft
	WIDTH X	5.0 ft
	LENGTH Y	5.7 ft
	SLOPE X	1.4%
	SLOPE Y	1.0%

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:

2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND VIEW CT - NE
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.19
OF 60 SHEETS
JOB NO.
2023-003



DRY HOLLOW RD

NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.9%
	COUNTER SLOPE	2.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	1.1%
	CROSS SLOPE	1.0%
	RAMP LENGTH	8.8 ft
RAMP RUN 3	RUNNING SLOPE	6.3%
	CROSS SLOPE	1.0%
	RAMP LENGTH	10.0 ft
TURNING	WIDTH X	11.1 ft
	LENGTH Y	9.4 ft
	SLOPE X	1.4%
	SLOPE Y	0.0%

E. 13TH PLACE

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	307.32	306.70	702516.78	8031359.56
C2	306.75	306.75	702516.72	8031369.56
C3	306.67	306.67	702520.16	8031378.05
C4	306.60	306.60	702526.34	8031381.40
C5	306.61	306.46	702528.57	8031381.64
C6	306.62	306.12	702533.99	8031381.71

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C7	307.38	307.38	702521.73	8031359.62
C8	307.47	307.06	702521.67	8031364.74
C9	307.36	306.84	702523.08	8031368.28
C10	307.25	306.75	702526.57	8031369.80
C11	306.85	306.85	702535.33	8031369.96

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND DRY HOLLOW NW
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET C7.20
OF 60 SHEETS
JOB NO. 2023-003

E. 13TH PLACE



DRY HOLLOW RD

NOTES:
1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.9%
	COUNTER SLOPE	-4.0%
RAMP RUN 2	RAMP LENGTH	NA
	RUNNING SLOPE	0.3%
	CROSS SLOPE	1.0%
	RAMP LENGTH	6.5 ft
RAMP RUN 3	RUNNING SLOPE	9.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	15.0 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	4.9 ft
	SLOPE X	0.0%
	SLOPE Y	1.4%

Location	Elevation	Northing	Easting
S1	308.42	702475.92	8031364.75
S2	308.44	702474.13	8031371.24
S3	309.87	702459.15	8031370.48

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	308.18	307.68	702480.97	8031358.28
C2	308.37	308.02	702480.92	8031364.79
C3	308.35	308.35	702480.88	8031371.29
C4	308.69	308.44	702476.44	8031379.66
C5	309.19	308.69	702470.31	8031381.46
C6	309.54	309.02	702461.73	8031381.20
C7	308.44	308.44	702474.09	8031376.24

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 13TH PL AND DRY HOLLOW SW
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.21
OF 60 SHEETS
JOB NO. 2023-003

DRY HOLLOW RD

E. 11TH STREET



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

- SIDEWALK
- TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES	
		RAMP 1	RAMP2
RAMP RUN 1	RUNNING SLOPE	0.5%	7.5%
	CROSS SLOPE	1.4%	0.0%
	GUTTER FLOW SLOPE	4.0%	0.0%
RAMP RUN 2	COUNTER SLOPE	4.0%	-4.0%
	RAMP LENGTH	6.5 ft	6.5 ft
	RUNNING SLOPE	11.7%	NA
RAMP RUN 3	CROSS SLOPE	1.4%	NA
	RAMP LENGTH	15.0 ft	NA
	RUNNING SLOPE	NA	NA
TURNING	WIDTH X	5.0 ft	5.0 ft
	LENGTH Y	5.0 ft	5.0 ft
	SLOPE X	1.4%	0.0%
	SLOPE Y	0.0%	1.4%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	261.90	261.40	703272.10	8031437.18
C2	261.35	260.85	703279.72	8031437.20
C3	260.65	260.65	703284.71	8031437.20
C4	260.67	260.42	703289.73	8031439.32
C5	260.20	260.20	703291.70	8031444.39
C6	260.20	260.20	703291.57	8031449.39

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C7	260.62	260.12	703291.43	8031454.38
C8	260.50	259.84	703291.18	8031463.50
C9	260.75	260.75	703279.71	8031444.19
C10	262.51	262.51	703264.70	8031449.07
C11	261.25	260.75	703279.70	8031449.19
C12	260.65	260.65	703286.40	8031455.97

REVISIONS	
NO.	DATE




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND DRY HOLLOW SE
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.22
OF 60 SHEETS
JOB NO.
2023-003

DRY HOLLOW RD



E. 11TH STREET



Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	258.82	258.46	703346.54	8031437.53
C2	259.00	258.50	703342.29	8031437.47
C3	259.00	258.70	703335.06	8031439.22
C4	258.75	258.75	703330.03	8031443.55
C5	259.05	258.80	703327.35	8031449.62
C6	259.08	258.74	703327.08	8031452.13

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C7	259.14	258.64	703326.99	8031456.41
C8	258.78	258.78	703335.34	8031444.65
C9	258.83	258.83	703330.39	8031449.69
C10	259.21	259.21	703342.41	8031449.60
C11	259.41	258.85	703335.39	8031449.65
C12	259.28	259.28	703335.22	8031456.64


NOTES:

- SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
- SLOPES HOLD OVER ELEVATIONS.
- SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING


RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	1.1%
	COUNTER SLOPE	2.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	6.1%
	CROSS SLOPE	1.0%
	RAMP LENGTH	7.0 ft
RAMP RUN 3	RUNNING SLOPE	5.1%
	CROSS SLOPE	1.0%
	RAMP LENGTH	7.0 ft
TURNING	WIDTH X	6.0 ft
	LENGTH Y	5.5 ft
	SLOPE X	1.4%
	SLOPE Y	0.7%

NO.	DATE	REVISIONS



A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND DRY HOLLOW NE
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.23
OF	60 SHEETS
JOB NO.	2023-003



E. 11TH STREET

Location	Elevation	Northing	Easting
S1	270.26	703325.08	8031923.24
S2	269.86	703324.98	8031928.64
S3	269.86	703326.10	8031929.83
S4	269.88	703331.08	8031931.50

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	269.81	296.60	703316.75	8031919.52
C2	270.18	269.68	703316.63	8031923.11
C3	269.78	269.78	703316.69	8031928.67
C4	269.82	269.82	703319.85	8031934.90
C5	269.78	269.78	703316.87	8031921.00
C6	269.82	269.40	703331.03	8031938.62
C7	269.59	269.03	703335.90	8031938.66

NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
2. SLOPES HOLD OVER ELEVATIONS.
3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

- MARKED OR INTENDED CROSSING LOCATION
- SIDEWALK
- TRANSITION SIDEWALK PANEL
(CROSS SLOPE CHANGE .5% PER FOOT)
- TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4'
(4' X 5' WHEN CONSTRAINED)
- TRUNCATED DOME
- CONCRETE PLANTER
- SLOPE 1.5% MAX. DESIGN
(MAX. 2.0% FINISHED SURFACE SLOPE)
- SLOPE 7.5% MAX. DESIGN
(MAX. 8.3% FINISHED SURFACE SLOPE)
- COUNTER SLOPE 4% MAX. DESIGN
(MAX. 5% FINISHED SURFACE SLOPE)
- STATION, OFFSET, ELEVATION POINT
- LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.5%
	COUNTER SLOPE	4.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	0.8%
	CROSS SLOPE	1.0%
	RAMP LENGTH	5.0 ft
RAMP RUN 3	RUNNING SLOPE	7.4%
	CROSS SLOPE	1.0%
	RAMP LENGTH	5.4 ft
TURNING	WIDTH X	5.9 ft
	LENGTH Y	5.9 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND OREGON AVE NW
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.24
OF 60 SHEETS
JOB NO.
2023-003

E. 11TH STREET



OREGON AVENUE

- NOTES:
- 1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - 2. SLOPES HOLD OVER ELEVATIONS.
 - 3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.7%
RAMP RUN 2	COUNTER SLOPE	4.0%
	RAMP LENGTH	NA
	RUNNING SLOPE	0.0%
RAMP RUN 3	CROSS SLOPE	1.0%
	RAMP LENGTH	6.0 ft
	RUNNING SLOPE	13.3%
TURNING	CROSS SLOPE	1.0%
	RAMP LENGTH	15.0 ft
	WIDTH X	4.5 ft
	LENGTH Y	5.5 ft
	SLOPE X	1.5%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	271.42	270.91	703281.19	8031919.23
C2	271.60	271.10	703281.10	8031923.49
C3	271.60	271.32	703281.03	8031926.55
C4	271.60	271.60	703280.35	8031930.30
C5	271.64	271.64	703277.95	8031934.33
C6	271.67	271.67	703274.19	8031937.13
C7	272.24	272.10	703269.05	8031938.30

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C8	272.51	272.31	703266.58	8031938.30
C9	273.75	273.25	703257.24	8031938.31
C10	271.65	271.65	703275.85	8031925.30
C11	272.01	271.65	703274.65	8031928.28
C12	272.52	271.72	703271.48	8031931.43
C13	273.05	272.55	703266.57	8031932.80
C14	273.79	273.79	703257.22	8031932.81

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 298-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
E 11TH ST AND OREGON AVE SW
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET C7.25
OF 60 SHEETS
JOB NO. 2023-003

COLUMBIA VIEW DRIVE



BRENTWOOD DRIVE



- NOTES:
- SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - SLOPES HOLD OVER ELEVATIONS.
 - SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.8%
	COUNTER SLOPE	2%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	0.2%
	CROSS SLOPE	1.0%
	RAMP LENGTH	6.2 ft
RAMP RUN 3	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	7.6 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	5.0 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	319.28	318.78	705452.28	8040023.64
C2	318.71	318.71	705461.62	8040019.63
C3	318.66	318.66	705466.28	8040014.95
C4	318.67	318.37	705469.82	8040007.47

NO.	DATE	REVISIONS




CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
COLUMBIA AND BRENTWOOD
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.26
OF 60 SHEETS
JOB NO. 2023-003

COLUMBIA VIEW DRIVE

BRENTWOOD DRIVE



- NOTES:**
- SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.
 - SLOPES HOLD OVER ELEVATIONS.
 - SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.
 - RELOCATE STOP SIGN TO BACK OF WALK TO MAINTAIN 4 FT MINIMUM PEDESTRIAN PATH AROUND POST.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.0%
	COUNTER SLOPE	-2.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	1.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	7.0 ft
RAMP RUN 3	RUNNING SLOPE	7.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	8.3 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	5.0 ft
	SLOPE X	1.0%
	SLOPE Y	1.0%

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	320.46	319.96	705452.44	8040058.25
C2	320.35	320.35	705460.98	8040062.03
C3	320.35	320.35	705465.69	8040066.71
C4	320.98	320.48	705469.83	8040077.01

REVISIONS


NO.	DATE	

CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
**2023 ADA IMPROVEMENT PROJECT
COLUMBIA AND BRENTWOOD**
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	1" = 5'
CHECKED	
SHEET	C7.27
OF	60 SHEETS
JOB NO.	2023-003

Location	Top of Curb Elev.	Flow Line Elev.	Northing	Easting
C1	329.55	329.05	705060.32	8040164.57
C2	329.25	329.25	705052.37	8040165.44
C3	329.25	329.25	705045.89	8040163.95
C4	329.64	329.14	705039.11	8040159.70



NOTES:

1. SEE SHEET C0.1 - C0.2 FOR GENERAL NOTES AND INFORMATION.

2. SLOPES HOLD OVER ELEVATIONS.

3. SEE SHEETS C9.1 - C9.3 FOR STANDARD DRAWINGS.

MARKED OR INTENDED CROSSING LOCATION

SIDEWALK

TRANSITION SIDEWALK PANEL (CROSS SLOPE CHANGE .5% PER FOOT)

TURNING SPACE - 2.0% MAX, MIN. AREA 4' X 4' (4' X 5' WHEN CONSTRAINED)

TRUNCATED DOME

CONCRETE PLANTER

SLOPE 1.5% MAX. DESIGN (MAX. 2.0% FINISHED SURFACE SLOPE)

SLOPE 7.5% MAX. DESIGN (MAX. 8.3% FINISHED SURFACE SLOPE)

COUNTER SLOPE 4% MAX. DESIGN (MAX. 5% FINISHED SURFACE SLOPE)

STATION, OFFSET, ELEVATION POINT

LANDSCAPING

RAMP	ITEM	VALUES
		RAMP 1
RAMP RUN 1	RUNNING SLOPE	NA
	CROSS SLOPE	NA
	GUTTER FLOW SLOPE	0.0%
	COUNTER SLOPE	2.0%
	RAMP LENGTH	NA
RAMP RUN 2	RUNNING SLOPE	5.0%
	CROSS SLOPE	1.0%
	RAMP LENGTH	6.0 ft
RAMP RUN 3	RUNNING SLOPE	6.5%
	CROSS SLOPE	1.0%
	RAMP LENGTH	6.0 ft
TURNING	WIDTH X	5.0 ft
	LENGTH Y	5.0 ft
	SLOPE X	0.0%
	SLOPE Y	1.0%





NO.	DATE	REVISIONS



CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A RAMP DETAIL SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
ROYAL CREST AND BRENTWOOD
THE DALLES, OREGON

NAME TMS
DATE 12/16/2022
SCALE 1" = 5'
CHECKED
SHEET
C7.28
OF 60 SHEETS
JOB NO. 2023-003







NO.	DATE	REVISIONS

CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

2023 ADA IMPROVEMENT PROJECT
THE DALLES, OREGON

NAME	TMS
DATE	12/16/2022
SCALE	AS NOTED
CHECKED	
SHEET	
C9.2	
OF 60 SHEETS	
JOB NO.	2023-003



REVISIONS

NO.	DATE	DESCRIPTION

CITY OF THE DALLES
PUBLIC WORKS DEPARTMENT
1215 West 1st Street
The Dalles, Oregon 97058
(541) 296-5401

A DETAIL DRAWING SHEET FOR:
2023 ADA IMPROVEMENT PROJECT
THE DALLES, OREGON

NAME: TMS
DATE: 12/16/2022
SCALE: AS NOTED
CHECKED:
SHEET:
C9.3
OF 60 SHEETS
JOB NO.: 2023-003