# Basin L Stormwater Treatment System Performance Verification Report

Kinder Morgan Port of Portland Terminal 4, Slip 3


## Prepared for:

# Kinder Morgan Bulk Terminals, Inc.

11040 North Lombard Street Portland, OR 97203 Multnomah County October 2, 2023 Project No. M1017.01.016

### Prepared by:

Maul Foster & Alongi, Inc. 3140 NE Broadway, Portland, OR 97232





# **Basin L Stormwater Treatment System Performance Verification Report**

# Kinder Morgan Port of Portland Terminal 4, Slip 3

The material and data in this report were prepared under the supervision and direction of the undersigned.

Maul Foster & Alongi, Inc.

Brooke Harmon. PE

Project Engineer

Krysta Krippaehne-Stein, EIT

Staff Engineer

# **Contents**

1	Intro	duction	1
		Purpose	
		Reporting Schedule	
	1.3	Site Background	1
		Stormwater Treatment System	
2	Inspe	ection and Maintenance Summary	2
3	Quar	ntitative Results	3
	3.1	Pollutant Reduction Rates	3
	3.2	Total Volume of Stormwater Treated	7
	3.3	Storm Events Exceeding Design Storm	8
4	Sumi	mary and Recommendations	8

# **Figures**

### In the Text

- 3-1: Kinder Morgan Stormwater Treatment System Effluent PAH Concentrations Compared to DEQ's PAHs in Stormwater Curve
- 3-2: Kinder Morgan Stormwater Treatment System Effluent Total Copper Concentrations Compared to DEQ's Total Copper in Stormwater Curve
- 3-3: Kinder Morgan Stormwater Treatment System Effluent Total Zinc Concentrations Compared to DEQ's Total Zinc in Stormwater Curve
- 3-4: Kinder Morgan Stormwater Treatment System Effluent TSS Concentrations Compared to DEQ's Total Suspended Solids in Stormwater Curve

### **Following the Report**

1-1 Site Location

### **Tables**

### In the Text

3-2 Storm Events Exceeding 1.08-Inch Design Storm

### **Following the Report**

3-1 Basin L Stormwater Treatment System Performance Monitoring Summary

Kinder Morgan Port of Portland Terminal 4, Slip 3 Basin L Stormwater Treatment System Performance Verification Report Contents (Continued)

# **Appendixes**

Appendix A

Inspection Records

Appendix B

Photo Log

# 1 Introduction

# 1.1 Purpose

Maul Foster & Alongi, Inc., has prepared this Basin L stormwater treatment system performance verification report on behalf of Kinder Morgan Bulk Terminals, Inc. (Kinder Morgan) consistent with the reporting requirements outlined in the June 8, 2022, Source Control Measures Work Plan.¹ The Source Control Measures Work Plan was approved by the Oregon Department of Environmental Quality (DEQ) on July 2, 2022. This performance verification report summarizes the performance monitoring of the Basin L stormwater treatment system for the 2022–2023 operating year (July 1, 2022, through June 30, 2023).

# 1.2 Reporting Schedule

The Source Control Measures Work Plan requires a performance verification report to be submitted to DEQ by October 1 following the end of the first year of the treatment system operations (the date of start-up through June 30 of the following year). The stormwater treatment system installation was completed in May 27, 2022, and this report discusses the operation of the system from start-up to June 30, 2023.

# 1.3 Site Background

The Kinder Morgan facility encompasses approximately 11.8 acres and is located at the Port of Portland Terminal 4 in section 02, township 1 north, range 1 west of the Willamette Meridian. Kinder Morgan is located at 11040 North Lombard Street in Portland, Oregon, and is bounded to the west by the Willamette River and to the east by North Terminal Road (see the figure) (the site). The site is owned by the Port of Portland (Port) and leased from the Port by Kinder Morgan.

The Kinder Morgan facility is a river-dependent active bulk storage and transfer site that primarily handles soda ash. Soda ash is delivered by rail from mines, then stored in the Soda Ash Building and loaded onto ships or railcars.

Basin L is within the Port's Slip 3 upland area with known historical soil and groundwater contamination. The Port entered into the DEQ's Voluntary Cleanup Program to address the historical contamination and implement source control measures to protect the Willamette River via an Agreement for Remedial Investigation, Source Control Measures, and Feasibility Study on December 4, 2003 (LQVC-NWR-03-18) (Environmental Cleanup Site Information No. 2356).

Stormwater runoff generated at Kinder Morgan's Basin L discharges to the Willamette River between river miles 4 and 5, consistent with the National Pollutant Discharge Elimination System Stormwater

<sup>&</sup>lt;sup>1</sup> MFA. 2022. Source Control Measures Work Plan, Kinder Morgan Terminal 4, Basin L Stormwater Treatment System. June 8.

Discharge Permit No. 1200-Z (1200-Z Permit) issued by the DEQ and administered by the City of Portland Bureau of Environmental Services.

The Basin L treatment system was designed to achieve source control goals and 1200-Z Permit benchmarks.

# 1.4 Stormwater Treatment System

The Basin L stormwater treatment system consists of a flow- and spill-control manhole, pump station, a pH adjustment system consisting of two aboveground reaction tanks, a carbon dioxide tank and a water quality skid that controls the carbon dioxide injection, a discharge and recirculation pump and valving, as well as two aboveground detention tanks, and a StormwateRx Aquip Model 400SXE filtration system.

Stormwater from Basin L is collected via 18 catch basins and a network of gravity pipes that discharge into a pump station that conveys the runoff into the reaction tanks where carbon dioxide is injected to reduce pH levels. The pH adjustment system is equipped with a recirculation system that is activated when the effluent pH is outside of the specified range; when activated, stormwater from the reaction tanks is discharged back into the pump station and routed through the pH adjustment system again until the effluent pH level drops to within the specified range. Stormwater is pumped from the reaction tanks to the detention tanks and filtered by the Aquip media filter prior to discharge to Wheeler Bay of the Willamette River.

# 2 Inspection and Maintenance Summary

Inspections of the Basin L stormwater treatment system are completed monthly to document site conditions and evaluate the need for system maintenance. Monthly inspection and maintenance reports are included in Appendix A. The following notable dates are associated with the first year of operation of the Basin L stormwater treatment system.

- October 25, 2022: Stormwater was observed to be ponding on top of the Aquip filter tarp cover. The tarp was installed to limit fugitive soda ash dust from entering the filter. The ponding did not affect the filter performance, but StormwateRx, LLC (StormwateRx) was notified.
- **November 9, 2022:** The tarp support bars were bent from the weight of stormwater ponding on the tarp.
- **November 15, 2022:** StormwateRx replaced two tarp support bars and tightened the tarp straps to prevent future ponding.
- **December 21, 2022:** StormwateRx added an additional support bar to prevent stormwater from ponding on the edges of the tarp cover.
- December 8, 2022: Black material accumulation was observed on the Aquip filter media surface.
   The surface of the media was scraped on December 16, 2022, and approximately 0.25 inches of accumulation was removed.

- March 13, 2023: Sediment accumulation was observed on the Aquip filter media surface. The surface of the media was scraped and the sediment was removed on March 29, 2023.
- May 16, 2023: Pump floats were observed to be tangled up, causing the pump to run when no stormwater was present (i.e., running dry). The pumps were shut off and the float cords were untangled. The system was turned on the following day after the pump was inspected by an electrician to ensure the long pump run time did not damage the motor. Kinder Morgan began evaluating preventive measures to avoid this issue in the future. These measures were implemented in August 2023 and will be discussed in detail in the 2023—2024 treatment system performance evaluation report.
- May 23, 2023: StormwateRx raised the overflow indicator pipe elevation to match the overflow pipe elevation inside the Aquip filter.

Relevant photographs of the stormwater treatment system are included in Appendix B.

# 3 Quantitative Results

Pollutant reduction rates, total volume of stormwater treated, and 24-hour rainfall data were analyzed consistent with the methodology outlined in the *Source Control Measures Work Plan*. The results of these analyses are summarized in the following sections.

# 3.1 Pollutant Reduction Rates

Four sampling events were conducted between July 1, 2022, and June 30, 2023. During each sampling event, stormwater samples were collected from the pump station, upstream of the filter (i.e., pre-filter), and downstream of the filter (i.e., post-filter), and analyzed for polycyclic aromatic hydrocarbons (PAHs), total copper, total zinc, and total suspended solids (TSS). The pump station samples represented untreated stormwater. The pre-filter samples represented stormwater quality downstream of the pH adjustment system. The post-filter samples consisted of the treated filter effluent.


Analytical results are presented in the attached stormwater treatment system performance monitoring table (Table 3-1). Pollutant reduction rates were calculated by comparing the pump station (untreated) and post-filter (treated) concentrations. The average PAH reduction rates ranged between 71 and 81 percent. The average reduction rate was 63 percent for total copper, 51 percent for total zinc, and 80 percent for TSS.

Consistent with the *Portland Harbor Joint Source Control Strategy* requirements,<sup>2</sup> concentrations should remain under the "knee of the curve" of the pollutant concentration charts published by DEQ and at concentrations less than 10 times the Portland Harbor screening level values (SLVs). Post-filter concentrations were over select PAH SLVs for the first three sampling evenings. However, aside from one non-detect copper result with a detection limit greater than the SLV, all post-filter concentrations were below 10 times the applicable SLVs for all sampling events. Additionally, the

<sup>&</sup>lt;sup>2</sup> United States Environmental Protection Agency and DEQ. 2005. *Portland Harbor Joint Source Control Strategy*. December.

post-filter concentrations from the fourth sampling event were under all SLVs. The post-filter sample concentrations for total PAHs, total copper, total zinc, and TSS were plotted on the respective *Portland Harbor Joint Source Control Strategy* chart shown in Figures 3-1, 3-2, 3-3, and 3-4 below. All post-filter sample concentrations were below the knee of the curve for each parameter plotted. Sampling results are further described below.

Figure 3-1: Kinder Morgan Stormwater Treatment System Effluent Total PAH Concentrations Compared to DEQ's PAHs in Stormwater Curve



### Notes


DEQ = Oregon Department of Environmental Quality.

PAH = polycyclic aromatic hydrocarbons.

ug/L = micrograms per liter.

The treatment system effluent total PAH concentrations fall below the knee of the curve, as shown in Figure 3-1, and are less than ten times the SLV, demonstrating that the Basin L stormwater treatment system is effective at reducing PAH concentrations in stormwater and achieving source control goals.

Figure 3-2: Kinder Morgan Stormwater Treatment System Effluent Total Copper Concentrations Compared to DEQ's Total Copper in Stormwater Curve




### **Notes**

DEQ = Oregon Department of Environmental Quality.

ug/L = micrograms per liter.

The treatment system effluent total copper concentrations fall below the knee of the curve, as shown in Figure 3-2. Two of the four sample results were below the SLV and the copper concentration in all four samples was less than ten times the SLV. Copper concentrations were also below the 1200-Z Permit benchmark for total copper. This demonstrates that the Basin L stormwater treatment system is effective at reducing copper concentrations in stormwater and achieving source control goals.

Figure 3-3: Kinder Morgan Stormwater Treatment System Effluent Total Zinc Concentrations Compared to DEQ's Total Zinc in Stormwater Curve




### Notes

DEQ = Oregon Department of Environmental Quality.

ug/L = micrograms per liter.

The treatment system effluent total zinc concentrations fall below the knee of the curve, as shown in Figure 3-3. The total zinc concentrations in all effluent samples were below the SLV. Zinc concentrations were also below the 1200-Z Permit benchmark for total zinc. This demonstrates that the Basin L stormwater treatment system is effective at reducing zinc concentrations in stormwater and achieving source control goals.

Figure 3-4: Kinder Morgan Stormwater Treatment System Effluent TSS Concentrations Compared to DEQ's Total Suspended Solids in Stormwater Curve



### Notes

DEQ = Oregon Department of Environmental Quality.

TSS = total suspended solids.

ug/L = micrograms per liter.

The treatment system effluent TSS concentrations fall below the knee of the curve, as shown on the above chart. The TSS concentration in all effluent samples was below the SLV. TSS concentrations were also below the 1200-Z Permit benchmark for TSS. This demonstrates that the Basin L stormwater treatment system is effective at reducing TSS concentrations in stormwater and achieving source control goals.

# 3.2 Total Volume of Stormwater Treated

The total volume of stormwater treated between July 1, 2022, and June 30, 2023, was 9.77 acrefeet or 3,183,564 gallons.

# 3.3 Storm Events Exceeding Design Storm

Continuous hourly rain gage data were retrieved from the City of Portland's HYDRA rain gage network at the nearby Shipyard Rain Gage to estimate the frequency of potential bypasses. There were four storm events between July 1, 2022, and June 30, 2023, that exceeded the 1.08-inch design storm, as shown in Table 3-2. These storm events may have resulted in a portion of the runoff bypassing the stormwater treatment system. It should be noted that typically, pollutant concentrations are diluted (lower) during large storm events and the combined treated and bypassed effluent quality was likely similar to the concentrations presented in this report.

Table 3-2: Storm Events Exceeding 1.08-Inch Design Storm

Date	Rainfall (inches)
November 4, 2022	2.34
December 26, 2022	2.90
March 13, 2023	1.21
April 10, 2023	1.19

# 4 Summary and Recommendations

Based on the available data presented in this report, the Basin L stormwater treatment system is operating effectively and as designed. The treatment system effluent pollutant concentrations were below the knee of their respective curves and either less than the SLVs or ten times the SLVs. Kinder Morgan proposes to discontinue source control sampling and continue to monitor and maintain the Basin L stormwater treatment system consistent with the requirements of the 1200-Z Permit.

# **Figure**



Site Address: 11040 North Lombard Street, Portland, Oregon Source: Taxlot obtained from Metro RLIS, US Geological Survey (1990) 7.5-minute topographic quadrangle: Linnton Section 2, Township 1 North, Range 1 West

# Figure 1-1 Site Location

Kinder Morgan Portland, Oregon



1,000 2,000 Feet



This product is for informational purposes and may not have been prepared for, or be suitable for legal, engineering, or surveying purposes. Users of this information should review or consult the primary data and information sources to ascertain the usability of the information.

# **Table**



# TABLE 3-1 BASIN L STORMWATER TREATMENT SYSTEM PERFORMANCE MONITORING SUMMARY KINDER MORGAN TERMINAL 4 PORTLAND, OREGON



Anglista	Portland Harbor	10 Times Portland	1200-Z Perm	enchmarks Surface Water				01/13/23 Sampling Event			02/13/23 Sampling Event			03/13/23 Sampling Event				Average			
Analyte	Screening Level Values	Harbor Screening Level Values	Benchmark		Pump Station	Pre-Filter	Post-Filter	Reduction	Pump Station	Pre-Filter	Post-Filter	Reduction	Pump Station	Pre-Filter	Post-Filter	Reduction	Pump Station	Pre-Filter	Post-Filter	Reduction	Reduction
Polycyclic Aromatic Hydroca	arbons (ug/L)	<del>!</del>		1											•					<u> </u>	
Naphthalene	0.2	2		12	<0.0190	<0.0200	<0.0194		<0.0208	<0.0200	0.0352 J		<0.0198 <sup>(a)</sup>	<0.0196 <sup>(a)</sup>	<0.0200 <sup>(a)</sup>		<0.0192	<0.0202	<0.0190		
2-Methylnaphthalene	0.2	2			<0.0190	<0.0200	<0.0194		<0.0208	<0.0200	0.0294 J		<0.0198 <sup>(a)</sup>	<0.0196 <sup>(a)</sup>	<0.0200 <sup>(a)</sup>		<0.0192	<0.0202	<0.0190		
Acenaphthylene	0.2	2			<0.00952	<0.0100	<0.00971		<0.0104	<0.0100	<0.00962		<0.00990 <sup>(a)</sup>	<0.00980 <sup>(a)</sup>	<0.0100 <sup>(a)</sup>		<0.00962	<0.0101	<0.00952		
Acenaphthene	0.2	2			<0.00952	<0.0100	<0.00971		<0.0104	<0.0100	<0.00962		<0.00990 <sup>(a)</sup>	<0.00980 <sup>(a)</sup>	<0.0100 <sup>(a)</sup>		<0.00962	<0.0101	<0.00952		
Fluorene	0.2	2			0.0100 J	<0.0100	<0.00971		<0.0104	<0.0100	<0.00962		<0.00990 <sup>(a)</sup>	<0.00980 <sup>(a)</sup>	<0.0100 <sup>(a)</sup>		<0.00962	<0.0101	<0.00952		
Phenanthrene	0.2	2			0.162	0.0954	0.0231	86%	0.0349	0.0435	<0.00962		0.113	0.118	0.0262	77%	0.129	0.0541	<0.00952		81%
Anthracene	0.2	2			0.0152 J	0.0142 J	<0.00971		0.0134 J	<0.0100	<0.00962		0.0237	0.0198	<0.0100		0.0130 J	<0.0101	<0.00952		
Fluoranthene	0.2	2			0.278	0.204	0.0507	82%	0.0438	0.0623	0.0179 J	59%	0.230	0.251	0.0483	79%	0.199	0.0874	0.0159 J	92%	78%
Pyrene	0.2	2			0.260	0.194	0.0467	82%	0.0420	0.0582	0.0170 J	60%	0.216	0.251	0.0441	80%	0.193	0.0854	0.0152 J	92%	78%
Benz(a)anthracene	0.018	0.18		0.0012	0.0951	0.0796	0.0185 J	81%	0.0171 J	0.0219 <sup>(b)</sup>	<0.00962		0.0687	0.0770	0.0150 J	78%	0.0675 <sup>(b)</sup>	0.0309 <sup>(b)</sup>	<0.00952		79%
Chrysene	0.018	0.18		0.0013	0.254	0.194	0.0494	81%	0.0393	0.0525	0.0165 J	58%	0.206	0.237	0.0454	78%	0.187	0.0851	0.0152 J	92%	77%
Benzo(b)fluoranthene	0.018	0.18		0.0012	0.261	0.233	0.0613	77%	0.0391	0.0529	0.0202	48%	0.248	0.300	0.0610	75%	0.185	0.0943	0.0119	94%	73%
Benzo(k)fluoranthene	0.018	0.18		0.0013	0.0834 <sup>(b)</sup>	0.0709 <sup>(b)</sup>	0.0167 J	80%	0.0129 J	0.0136 J	<0.00962		0.0798 <sup>(b)</sup>	0.0822 <sup>(b)</sup>	0.0178 J	78%	0.0669 <sup>(b)</sup>	0.0294 <sup>(b)</sup>	<0.00952		79%
Benzo(a)pyrene	0.018	0.18		0.00012	0.135	0.128	0.0284	79%	0.0186 J	0.0231	<0.00962		0.118	0.139	0.0238	80%	0.0999	0.0482	<0.00952		79%
Indeno(1,2,3-cd)pyrene	0.018	0.18		0.0012	0.131	0.124	0.0305	77%	0.0206 J	0.0273	0.0124 J	40%	0.121	0.137	0.0268	78%	0.0996	0.0498	0.0121 J	88%	71%
Dibenz(a,h)anthracene	0.018	0.18		0.00012	0.0267	0.0228	<0.00971		<0.0104	< 0.0100	<0.00962		0.0225	0.0264	<0.0100		0.0174 J	<0.0101	<0.00952		-
Benzo(g,h,i)perylene	0.2	2			0.131	0.116	0.0299	77%	0.0236	0.0284	0.0121 J	49%	0.114	0.127	0.0247	78%	0.101	0.0489	0.0106 J	90%	73%
Total PAHs <sup>(c)</sup>					1.84	1.48	0.355	81%	0.305	0.384	0.161	47%	1.56	1.77	0.333	79%	1.36	0.614	0.0809	94%	75%
Total Suspended Solids (mg/	L)																				
Total suspended solids			30		31.0	20.0	6.00	81%	<5.00	<5.00	<5.00		53.0	35.0	11.0	79%	21.0	7.00	<5.00		80%
Total Metals (mg/L)																			•		
Zinc	0.036	0.36	0.24	0.0365	0.0933	0.0898	0.0318	66%	0.0480	0.0503	0.0264	45%	0.228	<0.180 <sup>(d)</sup>	<0.180 <sup>(d)</sup>		0.0863	0.0596	0.0190	78%	63%
Copper	0.0027	0.027	0.015	0.00274	0.00588	0.00700	0.00353	40%	0.00696	0.00535	0.00282	59%	<0.0900 <sup>(d)</sup>	<0.0900 <sup>(d)</sup>	<0.0900 <sup>(d)</sup>		0.00488	0.00490	0.00226	54%	51%

### 140103

Samples were analyzed by EPA Method 8270E-SIM, EPA Method 200.8, and SM 2540D.

- -- = no value.
- < = not detected above listed method detection limit.

1200-Z Permit = National Pollutant Discharge Elimination System Stormwater Discharge Permit No. 1200-Z.

CUL = cleanup level.

EPA = U.S. Environmental Protection Agency.

J = result is an estimated concentration between the method detection limit and method reporting limit.

Kinder Morgan = Kinder Morgan Bulk Terminals, Inc.

mg/L = milligrams per liter.

PAH = polycyclic aromatic hydrocarbon.

Portland Harbor = Portland Harbor Superfund Site.

PS = pump station.

SLV = screening level value.

SM = Standard Methods for the Examination of Water and Wastewater.

ug/L = micrograms per liter.

(a) Indicates a Q-30 flag from the laboratory, where the recovery for laboratory control sample was below the lower control limit.

(b) Indicates a M-05 flag from the laboratory, where results are estimated due to peak separation for structural isomers being insufficient for accurate quantification.

<sup>(c)</sup>For total PAH calculations, non-detect values are multiplied by zero.

<sup>(d)</sup>Reporting levels elevated due to preparation and/or analytical dilution necessary for analysis.

# Appendix A

**Inspection Records** 



# STORMWATER TREATMENT SYSTEM INSPECTION AND MAINTENANCE REPORT

# Kinder Morgan Terminal 4 Portland, Oregon

Inspection Item (Y		
quip Filtration System	'es/No)	Additional Information  (e.g., Detailed Description, Source, Corrective Action and Implementation Date)
here evidence of significant solids and debris cumulation on top of the buffering media?	Jo	
there evidence of significant sediment or debris scumulation on the inlet distributor perforations (is after flow is uniform across the entire length of pe)?	No	
pes the media bed surface appear ittle/cracked?	No	
there evidence of significant sediment or debris ccumulation on the surface of the media bed?	No	
oes the top layer of the media require removal?	N2	
there ponded water above the media? If so, how nany inches?	ОИ	
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	) o	
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	JA.	
Is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	No	BE FINISHED, SCHEDULED FOR EARLY AUGUST
Detention Tanks		
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	No	
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	b	
	TASKS	AND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH

information, including the possibility of fines and imprisonment for knowing violations.

Scanned with CamScanner

Stormwater TREATMENT SYSTEM INSPECTION DATE AND TIME: 3/22/22 1400					
Treatment system must be inspected monthly to co	onfirm proper	r functioning and evaluate the need for maintenance.			
Inspection Item	(Yes/No)	Additional Information  (e.g., Detailed Description, Source, Corrective Action and Implementation Date)			
Aquip Filtration System					
ls there evidence of significant solids and debris accumulation on top of the buffering media?	No				
Is there evidence of significant sediment or debris accumulation on the inlet distributor perforations (is water flow is uniform across the entire length of pipe)?	Νa				
Does the media bed surface appear brittle/cracked?	No				
s there evidence of significant sediment or debris accumulation on the surface of the media bed?	No				
Does the top layer of the media require removal?	No				
s there ponded water above the media? If so, how many inches?	No				
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	No				
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	NR				
Is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	YES	Ø			
Detention Tanks					
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	No				
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	No				
and the second s	CE TASKS A	ND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH			
Fleeneign connecti	Jan V	DMILETED IN AUG 1222			
Inspected By: Blocke Halnon		Signature: Broshe fare			
personnel properly gather and evaluate the information sub-	mitted. Based or my knowledge ar	prepared under my direction or supervision in accordance with a system designed to assure that qualified in my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false itolations.			

# STORMWATER TREATMENT SYSTEM INSPECTION AND MAINTENANCE REPORT

Kinder Morgan Terminal 4
Portland, Oregon
BASIN L

Treatment system must be inspected monthly to co	onfirm prope	r functioning and evaluate the need for maintenance.
Inspection Item	(Yes/No)	Additional Information  (e.g., Detailed Description, Source, Corrective Action and Implementation Date)
Aquip Filtration System		
there evidence of significant solids and debris accumulation on top of the buffering media?	No	
there evidence of significant sediment or debris accumulation on the inlet distributor perforations (is vater flow is uniform across the entire length of sipe)?	No	
ooes the media bed surface appear orittle/cracked?	No	
there evidence of significant sediment or debris accumulation on the surface of the media bed?	No	
Ooes the top layer of the media require removal?	No	
s there ponded water above the media? If so, how nany inches?	No	
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	No	
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	NA	
Is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	Yes	Ø MIFT
Detention Tanks		
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	No	
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	No	
STORMWATER TREATMENT SYSTEM MAINTENAN	CE TASKS A	ND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH
HEED TO CHANGE UX	ILTS ON	J TOTALIZING FLOW METER
Inspected By: Brane Hyena		

I certify, under penalty of law, that this document and all attachments were prepared under my direction of supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.

BASIN L

Inspection Item	(Yes/No)	Additional Information  (e.g., Detailed Description, Source, Corrective Action and Implementation Date)
Aquip Filtration System		
s there evidence of significant solids and debris accumulation on top of the buffering media?	No	SUGHTEN MORE KLUMBLATTON ON EAST SIDE,
s there evidence of significant sediment or debris accumulation on the inlet distributor perforations (is water flow is uniform across the entire length of pipe)?	No	POSTIBLY MORE WATER FROW IND ON EAST POINTON OF FILTER- TALK TO STICK
Does the media bed surface appear poittle/cracked?	No	
is there evidence of significant sediment or debris accumulation on the surface of the media bed?	No	
Does the top layer of the media require removal?	No	
Is there ponded water above the media? If so, how many inches?	Юo	
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	No	
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	No	
is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	YES	0.21 ALRE FT - CHANGE UMTS
Detention Tanks		
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	No	
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	No	
STORMWATER TREATMENT SYSTEM MAINTENANG	CE TASKS A	ND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH
Some water ponded + See 14 7464	CHN	THEP COURT OF A QUIP - LET STEX KNOWN THE IT
Inspected By: Brook Harring		Signature: Brodo Harrer

Basin L

Stormwater TREATMENT SYSTEM INSPECT	Stormwater TREATMENT SYSTEM INSPECTION DATE AND TIME: November 9, 2022 10:30 AM					
Treatment system must be inspected monthly to co	onfirm prope	er functioning and evaluate the need for maintenance.				
Inspection Item	(Yes/No)	Additional Information (e.g., Detailed Description, Source, Corrective Action and Implementation Date)				
Aquip Filtration System						
Is there evidence of significant solids and debris accumulation on top of the buffering media?						
Is there evidence of significant sediment or debris accumulation on the inlet distributor perforations (is water flow is uniform across the entire length of pipe)?						
Does the media bed surface appear brittle/cracked?						
Is there evidence of significant sediment or debris accumulation on the surface of the media bed?						
Does the top layer of the media require removal?						
Is there ponded water above the media? If so, how many inches?						
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	No					
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	No					
Is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	Yes	2.26 acre feet				
Detention Tanks						
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	No					
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	No					
STORMWATER TREATMENT SYSTEM MAINTENAN	ICE TASKS	AND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH				
tightened the straps on the polyethylene co	over to pre ible to rem	cover from water ponding and bending the cover supports. They also event water from ponding on the cover again. They did not install the piece ove the cover to observe/inspect the Aquip filter media. I spoked with a part and install it once it arrives.				
Inspected By: Brooke Harmon		Signature: Brooks Harmon				
personnel properly gather and evaluate the information sub-	mitted. Based o	e prepared under my direction or supervision in accordance with a system designed to assure that qualified on my inquiry of the person or persons who manage the system, or those persons directly responsible for nowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting wing violations.				

Basin L

Stormwater TREATMENT SYSTEM INSPECTION DATE AND TIME:December 8, 2022 14:30				
Treatment system must be inspected monthly to co	onfirm prope	er functioning and evaluate the need for maintenance.		
Inspection Item	(Yes/No)	Additional Information (e.g., Detailed Description, Source, Corrective Action and Implementation Date)		
Aquip Filtration System				
Is there evidence of significant solids and debris accumulation on top of the buffering media?	NA			
Is there evidence of significant sediment or debris accumulation on the inlet distributor perforations (is water flow is uniform across the entire length of pipe)?	Yes	Manifold appears to be sloped to the east, with more accumulation on the eastern side of the filter. B Harmon will reach out to vendor about adjusting manifold.		
Does the media bed surface appear brittle/cracked?	No			
Is there evidence of significant sediment or debris accumulation on the surface of the media bed?	Yes	Black accumulation on media surface occluded filter, minor scrape without removing material allowed filter to drain. Filter needs surface scraping. B Harmon will coordinate vendor/sub for this month		
Does the top layer of the media require removal?	Yes	See comment above, scraping is warrented.		
Is there ponded water above the media? If so, how many inches?	No			
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	No			
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	No			
Is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	Yes	3.7 acre feet		
Detention Tanks				
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	NA	Detention tanks are green poly tanks and unable to see through/in		
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	No			
STORMWATER TREATMENT SYSTEM MAINTENAN	ICE TASKS	AND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH		
Interim surface scrape without removing mponded.	naterial alla	owed surface to drain on December 7, 2022, approximately 2 inches		
Surface scrape of Aquip conducted on Defrom the filter surface. Scraped material w		16, 2022. Approximately 0.25" of accumulation and clogged media removed d in covered roll off adjacent to filter.		
Inspected By: Brooke Harmon		Signature: Brooks Harmon		
personnel properly gather and evaluate the information sub-	mitted. Based o e best of my kr	e prepared under my direction or supervision in accordance with a system designed to assure that qualified on my inquiry of the person or persons who manage the system, or those persons directly responsible for nowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting wing violations.		

Basin L

Stormwater TREATMENT SYSTEM INSPECTION DATE AND TIME: January 10, 2023 11:00					
		er functioning and evaluate the need for maintenance.			
Inspection Item	(Yes/No)	Additional Information (e.g., Detailed Description, Source, Corrective Action and Implementation Date)			
Aquip Filtration System					
there evidence of significant solids and debris accumulation on top of the buffering media?	NA				
s there evidence of significant sediment or debris accumulation on the inlet distributor perforations ( vater flow is uniform across the entire length of pipe)?	is No	Flow appears uniform across the distribution manifold			
Ooes the media bed surface appear orittle/cracked?	No				
s there evidence of significant sediment or debris accumulation on the surface of the media bed?	No				
Ooes the top layer of the media require removal?	No				
s there ponded water above the media? If so, hor nany inches?	w Yes	Approximately 1-2 inches			
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and ralves?	No				
system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	Yes	417 gpm			
the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	Yes	5.77 acre feet			
Detention Tanks					
there evidence of significant sediment or debris accumulation in the detentation tanks?	NA	Detention tanks are green poly tanks - unable to see through/in			
are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead ttings?	No				
	NCE TASKS	AND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH			
Inspected By: Brooke Harmon		Signature: Brooks Harmon			
personnel properly gather and evaluate the information su	ıbmitted. Based i the best of my kı	re prepared under my direction or supervision in accordance with a system designed to assure that qualified on my inquiry of the person or persons who manage the system, or those persons directly responsible for nowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting			

Basin L

Stormwater TREATMENT SYSTEM INSPECTION DATE AND TIME: February 1, 2023 14:00						
Treatment system must be inspected monthly to co	onfirm prope	er functioning and evaluate the need for maintenance.				
Inspection Item	(Yes/No)	Additional Information (e.g., Detailed Description, Source, Corrective Action and Implementation Date)				
Aquip Filtration System						
ls there evidence of significant solids and debris accumulation on top of the buffering media?	NA					
Is there evidence of significant sediment or debris accumulation on the inlet distributor perforations (is water flow is uniform across the entire length of pipe)?	No					
Does the media bed surface appear brittle/cracked?	No					
Is there evidence of significant sediment or debris accumulation on the surface of the media bed?	No					
Does the top layer of the media require removal?	No					
Is there ponded water above the media? If so, how many inches?	No					
Are there leaks, cracks, breaks, or other evidence of damage in the influent and effluent piping and valves?	No					
If system is currently operating, is the flow rate exceeding 400 gpm? Record the flow rate.	No					
Is the flow totalizer functional? Record the volume on flow totalizer (influent to Aquip).	Yes	6.05 acre feet				
Detention Tanks						
Is there evidence of significant sediment or debris accumulation in the detentation tanks?	NA	Detention tanks are green poly tanks - unable to see through/in				
Are there any visible leaks, cracks, breaks, or other evidence of damage in the tanks or bulkhead fittings?	No					
	CE TASKS A	AND/OR CORRECTIVE ACTIONS IMPLEMENTED THIS MONTH				
Inspected By: Brooke Harmon		Signature: Broke Harmon				

I certify, under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.

### Stormwater Treatment System Inspection Record Kinder Morgan Bulk Terminals, Inc. Portland, Oregon

Inspection Date and Time: \_\_\_\_\_March 13, 2023 2:30 pm

Checklist Item	(Yes/No)	Additional Information (e.g., Location, Source, Detailed Description, Corrective Action Implemented [if applicable] and Implementation Date)
Pump Station Wet Well and Valve Vault		
Monthly. Are there any leaks, breaks, or evidence of damage in the piping, fittings and appurtenances within the wet well or valve vault?	No	
<b>Dry season.</b> Inspect for sediment accumulation, drain pump station if needed. If more than three inches of solids are observed in the wet well, pressure wash or vacuum the wet well and manage the wash water and solids consistent with applicable disposal regulations.	NA	
pH Adjustment System		
Monthly. Clean and calibrate process and effluent pH probes. Collect samples from each sampling port and measure pH using handheld meter. Compare system pH probe (programmable logic controller display) and handheld meter data (postcalibration). Download and review electronic pH data.	-	Conducted by MeasureTech
<b>Monthly.</b> Inspect recirculation pump and auto-actuated valves and verify proper operation.	Yes	
<b>Monthly.</b> Are there any visible cracks or leaks in the aboveground piping? Is the pipe insulation intact?	No Yes	
Aquip Filtration System		
<b>Monthly</b> . Is there evidence of excessive debris accumulated on the inlet distributor perforations? Is water flow uniform across the entire length of pipe?	No Yes	
Monthly. Does the media bed surface appear brittle or cracked?	No	
Monthly. Is there evidence of excessive accumulation of solids on the surface of the media bed? Is the accumulation evenly distributed and is there more sand visible than solids?	No Yes	
Monthly. Does the top layer of the media require removal?	Yes	media should be scrapped based on ponded water
Monthly. Is there ponded water above the media? If so, how many inches?	Yes	approx. 8 inches
<b>Monthly.</b> Are there any leaks, breaks, or evidence of damage in the influent or effluent piping and valves?	No	
Monthly. Is the system currently operating, is the flowrate exceeding 400 gpm? Record the flowrate.	Yes	397 gpm
<b>Monthly</b> . Is the flow totalizer functional? Record the total volume (influent to Aquip).	Yes	7.1 acre feet
Reaction/Detention Tanks		
Monthly. Are there any visible cracks or leaks in the aboveground tanks?	No	
<b>Monthly.</b> Do the inlets/outlets appear to be functioning as intended (i.e., is there any visible damage to the inlet/outlet pipes/structures)?	Yes	
<b>Dry season.</b> Inspect tanks for sediment accumulation, drain the tanks if needed. If more than three inches of solids are observed in either tank, pressure wash the tank and manage the wash water and solids consistent with applicable disposal regulations.	NA	
Stormwater System Maintenance: Note stormwater treatment system maintena	nce activi	ties and/or corrective actions implemented this month.
KM will procure drums to facilitate scraping of the top surface of the Aquip - completed on 3/29/23	media. M	FA will conduct surface scraping once drums are on site.
Inspected By: Brooke Harmon		Signature: Broke Harmon
I certify, under penalty of law, that this document and all attachments were prepared under my direc	tion or supervi	ision in accordance with a system designed to assure that qualified personnel properly

gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowledge or submitting false information.

### Stormwater Treatment System Inspection Record Kinder Morgan Bulk Terminals, Inc. Portland, Oregon

Inspection Date and Time: \_\_\_\_April 13, 2023 4 pm

inspection bate and time.			
Checklist Item	(Yes/No)	Additional Information (e.g., Location, Source, Detailed Description, Corrective Action Implemented [if applicable] and Implementation Date)	
Pump Station Wet Well and Valve Vault			
Monthly. Are there any leaks, breaks, or evidence of damage in the piping, fittings and appurtenances within the wet well or valve vault?	No		
<b>Dry season.</b> Inspect for sediment accumulation, drain pump station if needed. If more than three inches of solids are observed in the wet well, pressure wash or vacuum the wet well and manage the wash water and solids consistent with applicable disposal regulations.	NA		
pH Adjustment System			
Monthly. Clean and calibrate process and effluent pH probes. Collect samples from each sampling port and measure pH using handheld meter. Compare system pH probe (programmable logic controller display) and handheld meter data (postcalibration). Download and review electronic pH data.		Conducted by MeasureTech	
<b>Monthly.</b> Inspect recirculation pump and auto-actuated valves and verify proper operation.	Yes		
<b>Monthly</b> . Are there any visible cracks or leaks in the aboveground piping? Is the pipe insulation intact?	No Yes		
Aquip Filtration System			
<b>Monthly</b> . Is there evidence of excessive debris accumulated on the inlet distributor perforations? Is water flow uniform across the entire length of pipe?	No Yes		
Monthly. Does the media bed surface appear brittle or cracked?	No		
Monthly. Is there evidence of excessive accumulation of solids on the surface of the media bed? Is the accumulation evenly distributed and is there more sand visible than solids?	No Yes		
Monthly. Does the top layer of the media require removal?	No		
Monthly. Is there ponded water above the media? If so, how many inches?	No		
<b>Monthly.</b> Are there any leaks, breaks, or evidence of damage in the influent or effluent piping and valves?	No		
<b>Monthly</b> . Is the system currently operating, is the flowrate exceeding 400 gpm? Record the flowrate.	No		
Monthly. Is the flow totalizer functional? Record the total volume (influent to Aquip).	Yes	7.7 acre feet	
Reaction/Detention Tanks			
Monthly. Are there any visible cracks or leaks in the aboveground tanks?	No		
<b>Monthly</b> . Do the inlets/outlets appear to be functioning as intended (i.e., is there any visible damage to the inlet/outlet pipes/structures)?	Yes		
<b>Dry season.</b> Inspect tanks for sediment accumulation, drain the tanks if needed. If more than three inches of solids are observed in either tank, pressure wash the tank and manage the wash water and solids consistent with applicable disposal regulations.	NA		
Stormwater System Maintenance: Note stormwater treatment system maintena	nce activit	iles and/or corrective actions implemented this month.	
Inspected By: Brooke Harmon		Signature: Broke Harmon	
I certify, under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly			

I certify, under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.

### Stormwater Treatment System Inspection Record Kinder Morgan Bulk Terminals, Inc. Portland, Oregon

Inspection Date and Time: \_\_\_\_\_May 16, 2023 8:30 am

Checklist Item	(Yes/No)	Additional Information (e.g., Location, Source, Detailed Description, Corrective Action Implemented [if applicable] and Implementation Date)		
Pump Station Wet Well and Valve Vault	•			
Monthly. Are there any leaks, breaks, or evidence of damage in the piping, fittings and appurtenances within the wet well or valve vault?	No	pump floats were tangled/stuck and the pump was running dry; untangled cords and the pumps shut off.		
<b>Dry season.</b> Inspect for sediment accumulation, drain pump station if needed. If more than three inches of solids are observed in the wet well, pressure wash or vacuum the wet well and manage the wash water and solids consistent with applicable disposal regulations.	NA			
pH Adjustment System				
Monthly. Clean and calibrate process and effluent pH probes. Collect samples from each sampling port and measure pH using handheld meter. Compare system pH probe (programmable logic controller display) and handheld meter data (postcalibration). Download and review electronic pH data.	-	Conducted by MeasureTech		
<b>Monthly</b> . Inspect recirculation pump and auto-actuated valves and verify proper operation.	Yes			
Monthly. Are there any visible cracks or leaks in the aboveground piping? Is the pipe insulation intact?	No Yes			
Aquip Filtration System				
<b>Monthly</b> . Is there evidence of excessive debris accumulated on the inlet distributor perforations? Is water flow uniform across the entire length of pipe?	No Yes			
Monthly. Does the media bed surface appear brittle or cracked?	No			
<b>Monthly.</b> Is there evidence of excessive accumulation of solids on the surface of the media bed? Is the accumulation evenly distributed and is there more sand visible than solids?	No Yes			
Monthly. Does the top layer of the media require removal?	No			
Monthly. Is there ponded water above the media? If so, how many inches?	No			
<b>Monthly.</b> Are there any leaks, breaks, or evidence of damage in the influent or effluent piping and valves?	No			
<b>Monthly.</b> Is the system currently operating, is the flowrate exceeding 400 gpm? Record the flowrate.	No			
Monthly. Is the flow totalizer functional? Record the total volume (influent to Aquip).	Yes	9.7 acre feet		
Reaction/Detention Tanks				
Monthly. Are there any visible cracks or leaks in the aboveground tanks?	No			
<b>Monthly.</b> Do the inlets/outlets appear to be functioning as intended (i.e., is there any visible damage to the inlet/outlet pipes/structures)?	Yes			
<b>Dry season.</b> Inspect tanks for sediment accumulation, drain the tanks if needed. If more than three inches of solids are observed in either tank, pressure wash the tank and manage the wash water and solids consistent with applicable disposal regulations.	NA			
Stormwater System Maintenance: Note stormwater treatment system maintenance activities and/or corrective actions implemented this month.				
On May 23 StormwateRx raised overflow indicator pipe elevation to match the overflow pipe elevation inside the Aquip				
Inspected By: Brooke Harmon		Signature: Broke Harmon		
I certify, under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penaltiles for submitting false information, including the possibility of fines and imprisonment for knowing violations.				

### Stormwater Treatment System Inspection Record Kinder Morgan Bulk Terminals, Inc. Portland, Oregon

Inspection Date and Time: \_\_\_\_\_June 19, 2023 14:30

Checklist Item	(Yes/No)	Additional Information (e.g., Location, Source, Detailed Description, Corrective Action Implemented [if applicable] and Implementation Date)	
Pump Station Wet Well and Valve Vault			
Monthly. Are there any leaks, breaks, or evidence of damage in the piping, fittings and appurtenances within the wet well or valve vault?	No		
Dry season. Inspect for sediment accumulation, drain pump station if needed. If more than three inches of solids are observed in the wet well, pressure wash or vacuum the wet well and manage the wash water and solids consistent with applicable disposal regulations.	NA		
pH Adjustment System			
Monthly. Clean and calibrate process and effluent pH probes. Collect samples from each sampling port and measure pH using handheld meter. Compare system pH probe (programmable logic controller display) and handheld meter data (postcalibration). Download and review electronic pH data.		Conducted by MeasureTech	
<b>Monthly</b> . Inspect recirculation pump and auto-actuated valves and verify proper operation.	Yes		
Monthly. Are there any visible cracks or leaks in the aboveground piping? Is the pipe insulation intact?	No Yes		
Aquip Filtration System			
Monthly. Is there evidence of excessive debris accumulated on the inlet distributor perforations? Is water flow uniform across the entire length of pipe?	No NA		
Monthly. Does the media bed surface appear brittle or cracked?	No		
Monthly. Is there evidence of excessive accumulation of solids on the surface of the media bed? Is the accumulation evenly distributed and is there more sand visible than solids?	No Yes		
Monthly. Does the top layer of the media require removal?	No		
Monthly. Is there ponded water above the media? If so, how many inches?	No		
<b>Monthly.</b> Are there any leaks, breaks, or evidence of damage in the influent or effluent piping and valves?	No		
<b>Monthly</b> . Is the system currently operating, is the flowrate exceeding 400 gpm? Record the flowrate.	No		
<b>Monthly</b> . Is the flow totalizer functional? Record the total volume (influent to Aquip).	Yes	9.77 acre feet	
Reaction/Detention Tanks			
Monthly. Are there any visible cracks or leaks in the aboveground tanks?	No		
<b>Monthly</b> . Do the inlets/outlets appear to be functioning as intended (i.e., is there any visible damage to the inlet/outlet pipes/structures)?	Yes		
<b>Dry season</b> . Inspect tanks for sediment accumulation, drain the tanks if needed. If more than three inches of solids are observed in either tank, pressure wash the tank and manage the wash water and solids consistent with applicable disposal regulations.	NA		
Stormwater System Maintenance: Note stormwater treatment system maintena	nce activit	ties and/or corrective actions implemented this month.	
Inspected By: Brooke Harmon		Signature: Broke Harmon	
I certify, under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.			

L:\Projects\1017.01 Kinder Morgan\17\_On Call\Draft\SWPCP\Appendix B - Inspection Forms\Basin L Monthly Inspection & Maintenance Record.xlsx

# **Appendix B**

**Photo Log** 





# Photo No. 1. Description

Stormwater detention tanks

# **Photographs**

Project Name: Kinder Morgan Port of Portland Terminal 4, Slip 3,

Basin L

Project Number: M1017.01.016
Location: Portland, Oregon



# Photo No. 2. Description

Aquip filter, green detention tanks and white pH adjustment system reaction tanks in the background





# Photo No. 3. Description

Aquip filter media bed after filter installation

# **Photographs**

Project Name: Kinder Morgan Port of Portland Terminal 4, Slip 3,

Basin L

Project Number: M1017.01.016
Location: Portland, Oregon



# Photo No. 4. Description Stormwater ponding on the filter tarp cover





Photo No. 5. Description

Aquip filter in operation

# **Photographs**

Project Name: Kinder Morgan Port of Portland Terminal 4, Slip 3,

Basin L

Project Number: M1017.01.016
Location: Portland, Oregon



Photo No. 6. Description

Black material accumulated on the filter media surface prior to removal





# Photo No. 7. Description

Filter media surface after black material was scraped and removed

# **Photographs**

Project Name: Kinder Morgan Port of Portland Terminal 4, Slip 3,

Basin L

Project Number: M1017.01.016
Location: Portland, Oregon

