# PETROLEUM RELEASE FORM Please Check All That Apply

1-26-98e

	INCIDENT INFORMATION	
LOG NBR: 03-92-0125		REGULATED UST
UST FAC NBR: D	DATE REPORTED: 5 // / 9	□ NON-REGULATED UST
SITE NAME: MEADOW B	BROOK STORE	☐ HEATING OIL TANK
SITE ADDRESS: 16845 Hu	UY 211	
	TP: 97038	, FUNDING
SITE COUNTY: PHONE:		LUST HSRAF SINANCIAL ASST
		☐ INVOICE START ☐ INVOICE STOP ☐ NFA SENT
PROJECT MANAGER:		
	MAIL CONTACTS	
REPORTED BY	RESPONSIBLE PA	ARTY
NAME: Bob Monte	gonery NAME: 10	INI & JACK FRISON.
COMPANY:	COMPAN	00 0 1535 505
ADDRESS: PO BOX	ADDRESS:	FO (30X 0335 CRR
CITY: JANDY ZIP:		EBONNE ZIP: 97760
STATE:PHONE:	STATE:/	PHONE:
INVOICE CONTACT	OTHER CONTAC	T(S)
NAME:	NAME:	
COMPANY:	COMPANY:	
ADDRESS:		
	CITY:	ZIP:
STATE: PHONE:	STATE:	PHONE:
	SITE ASSESSMENT	
DATE DISCOVERED:	- ,30 ,92	☐ FUTHER CLEANUP REQ.
☐ EMERGENCY RESP.		□ NO FURTHER CLEANUP REQ.
□ ENFORCEMENT	11-711-98 X	☐ OFFSITE MIGRATION
	1 / 20 1001-	L.I.P.S. SCORE (Region)
CONFIRMATION:	DISCOVERY:	CAUSE:
☐ SI) STAFF	RM) ROUTINE MONITORING	TL) TANK LEAK
☐ LĎ) LAB: DEQ ☐ LR) LAB: RP	DC) DECOMMISSIONING CP) COMPLAINT	☐ PL) PIPE LEAK ☐ OF) OVERFILL
LO) LAB: OTHER RR) RP REPORT	☐ IC) INVENTORY CONTROL ☐ SA) SITE ASSESSMENT	☐ SS) SURFACE SPILL ☐ PV) PUMP/VALVE LEAK
CN) CONTRACTOR	☐ TT) TANK TEST ☐ OT) OTHER	OT) OTHER
1 I O I I O I I I L I		

С	CONTAMINANTS - IMPACTS-		
CONTAMINANTS:  UG) UNLEADED GASOLINE LG) LEADED GASOLINE MG) MISC. GASOLINE DS) DIESEL DFO) FUEL OIL WO) WASTE OIL LB) LUBRICANT	SV) SOLVENT  BF) BUNKER FUEL  OP) OTHER PET. DIST.  CH) CHEMICAL  HO) HEATING OIL  UN) UNKNOWN  OT) OTHER	MEDIA/IMPACT:  (SL) SOIL  (GW) GROUNDWATER  (SW) SURFACE WATER  (DW) DRINKING WATER  (FV) FACILITY (VAPOR)  (FP) FACILITY (FREE PROD.)	
release stopped: 4,30,92 Cleanup Started: 4,30,92	SITE - MANAGEMENT  FINAL REQUEST INVOICE	10 2	7
	NO FURTHER A	CTION:	8
	SOIL - MANAGEMENT		
SWLA PERMIT NUMBER:	DATE ISSUED: _		
AMOUNT OF SOIL (yds 3) TREATED ON SITE: AMOUNT OF SOIL (yds 3) TREATED OFF SITE:		TMENT METHOD: AREATION  THERMAL  BIOLOGICAL  OTHER	
AMOUNT OF SOIL (yds 3) DISPOSED OF:	TREATED	☐ UNTREATED	
FINAL DISPOSITION OF SOIL:	□ ONSITE □ LANDFILL	□ ROAD BASE □ OTHER	
NOTES/COMMENTS:			

This Space Provided For Regional Use

FILE NAME: Meadow Brook Grocery LOGNO.03 - 92 -121

### **NWR'S NFA TRACKING CHECKLIST** ROUTE **ACTIVITY** RESPONSIBLE DATE TO PERSON **COMPLETED** Draft NFA prepared by Project Manager (PM) Draft NFA approved by Rick Silverman (and/or Rich Reiter, if necessary) To Victor for Time Accounting/CR entries SEQUENT updated by Debi Smith (or Victor Beard) with final invoice request date and new ' green sheet information. ACCESS updated by Debi Smith (or Victor Beard) with final invoice request date and new green sheet information. **OPTIONAL STEP:** Expedited payment request by responsible party (RP) is handled by **OPTIONAL STEP:** Estimated Expedited Payment Amount given to RP by === Final invoice paid notice received from Business Office and PM informed by Andree Pollock Final NFA drafted and signed by PM (and Rich Reiter, if necessary) SEQUENT updated by Debi Smith (or Victor Beard) with filed closed information. ACCESS updated by Debi Smith (or Victor Beard) with file closed information. Proofreading letter and file closure activities by Victor Beard (or Debi Smith) Copies made and mailed by front desk receptionist

NFA PROCESS COMPLETE

3-42-125	*LUST FORM*	JE 12
12.05.15	INCIDENT INFORMATION	71.77
LUST Incident Nbr: 03-92-125		UST Facility ID: 1013
Date Received: 5/1/92	Medalowbyook Stove	Emergency Resp Taken: Y N
Tank Identification: File Name :	16845 HWY 211	
Street:		- Notes: see back-
	Lackamas Phone:	- TWWS-OUC VOUCIE
Incident Comments:	A1 X 2 N 4 X 3 X 3 X 3 X 3 X 3 X 3 X 3 X 3 X 3 X	The track of the service of the serv
	CONTACT & MAIL TYPES	THE MARKET WAS
Penarted By: 7 \ AA.al. com	LUST Contact:	Responsible Party DAN & MARGIE TUM
Reported By: Bob Montgomer	Name:	Name: MCADARA CANA CONTRACT
Company: Mantgoniery	Company:	Street: PO BOX 388
Street: PO Box 130   Zip: 9705	Street: Zip:	City: COLTON Zip: 97017
State: Phone: 668 4847	State: Phone:	State: OR Phone:
	The state of the property of the second to the second to the second to	
LUST Incident Nbr: (XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	SITE ASSESSMENT	
	Investigated By: Dem	C)Lab:RP D)Lab:Other ()RP) F)Other
Release Exists: Y N	Confirmation Method: A)Staff B)Lab:DEQ	
	Regulated Tank: (Y) N	Exposure Assessment: Y (B)
	Estimated Gallons Released:	Priority: 422
(Circle) Discovery Date: 4/30/92	Staff (vour in tials or stell	
	onitoring B)Inventory Control (C)Decom	missioning D)Site Assessment
How Discovered: A)Routine Mo (Circle) E)Complaint	F)Tank Test G)Other	
Material Released: A)Unleaded (	Gasoline B)Leaded Gasoline (C)Misc. Ga	soline 20 yd3 stockpile
Material Released: A)Unleaded ((Circle) D)Diesel	E)Fuel Oil F)Waste Oi	L COUL OVER TO
G)Lubricant	H)Solvent . I)Bunker F	Mill Hill Pride. 101
J)Other Pet	hist Kichemical Liunknown	cafety movered excavilla
Source of Release: (A)Tank Leak	B)Pipe Leak C)Overfill D)	surface spill plastic & filled w/vo
Source of Release: (Circle) (A)Tank Leak E)Pump/Valve	e Leak F)Other (G)Unknown	temporarily.
		2
Impacts: Soil (Circle) Groundwater	A letter (victor)	
Surface Water	er V	
Drinking Wa		7
Facility (V		7
Facility (F	ree Product) Y	2 ?
Site Assessment Comments:	o letter required	
orner lotter, etc.)	princes)	
LUST Incident Nbr: (XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	SITE MANAGEMENT	
Date Released Stopped: 413019	C . Carantol	Rogulaten Pank in
Cleanup Activity: Start Date:	Under Control Date:	
End Date:	.P. Cleanup Lead: RP SLW/TF	SLW/OTF
Cleanup Guideline: Matrix C.A (Circle)	OET (Circle) oninoide imposo	JEN, OTT
Free Product Disposal:	Soil Disposal:	24
Est. Gallons:	Est. Cu/Yds:	28
Resp. Party:	Resp. Party: Disposal Location:	Co Cde Agains
Disposal Location:  Removal Date:	Removal Date:	Carlo (15)
Enforcement Action: Y N		
(Circle)	Course of Cost Perovery	Pct. R.P.:
Cost Recovery Initiated: Y N	Source of Cost Recovery:	Pct. SLW/TF:
		Pct. SLW/OTF:
Estimations: Cost of Cleanup:	Staff Time On Project:	
Site Management Comments:		
once management comments:		[Version 102]

NWR UST CLEANUP SITE CHECKLIST (for regional use only)

RP

This site is:	(20)114	tonitJack Frison
440	0 ppm Matrix	Box/535 CRR
Rec	gulated Tank	Terrebonne, OR
Exe	empt Tank	(541)504-8751 97760
Oi:	l Heat Commission eligible	entropy and the second part of t
oth	ner was balagit savn)	A. K. (1997) A. (1998) 1994 1994 1994 1994 1994 1994 1994 199
Stransanal communication	(surface spill, non-petro	leum UST, etc.)
Assign site to:	To estimated callons Released:	The state of the s
Sta	aff (your initials or staff f	or major RP)
	assigned at this time atrix only, soil aeration not	anticipated)
	eds to be tracked (supervisor ason:	to assign)
Action:	Lenk Gyptrokeok Gyptrokeok Calover TUL	guege, or newsees Allens guege, or newsees Allens guege
Ser	nd Initial Letter (with rules	) Not (* :stason anound
Ser	nd Modified Letter (without r	ules)
Ser	nd <40 ppm Letter (without ru	les)
No	letter required (sending oth	er letter, etc.)
Regulated Tank Info	rmation (Y/N):	Control of the property of the control of the contr
Tai	nks registered ID No. # 70	073
	commissioning notice (30 day)	
3 (	day notice received	encitad inc
Fee	es current	Age = Softward larger
Nev	w tanks to be installed	100 100 120 A 110 MM 1 120 A 1
Misc. Notes:		

# OREGON DEPORTMENT OF ENVIRONMENTAL QUALITY UST INCIDENT PRIORITIZATION STEM Scoring Sheet

og Number: 03-92-125 Site Name: Newdow Brook Grocery
EQ Scorer Initials: Avc Consultant Name:
HUMAN HEALTH IMPACTS
Drinking Water *** NOTE: In this section, all (or none) of the criteria must be scored.
Difficulty in replacing the supply: Hard X Medium _ Easy _
Type of supply that may be impacted: Community Intermittent Private \(\private\)
Size of population served by the supply: Large Medium Small $\underline{\mathcal{X}}$
When is impact likely to occur: Current/In Use Imminent Current/Alt Possible
Toxic Vapor Impacts *** NOTE: In this section, all (or none) of the criteria must be scored.
Level of vapor present: High Low
Potential population exposed: Large Medium Small
ENVIRONMENTAL DAMAGES
*** NOTE: In this section, all (or none) of the criteria must be scored.
Type of environment that may be impacted: Type A _ Type B _ Type C _
Likelihood of impact: High Medium Low
RESOURCE DAMAGES
Non-Drinking Water Supply Impacts
Type of supply that may be impacted: Industrial Agricultural Non-use
If non-use supply, specify impact to: GroundwaterSurface Water
Utility Corridors: Presence Damage
TIEBREAKER
Potential for Transport *** NOTE: In this section, all (or none) of the criteria must be scored.
Mean Annual Rainfall: >45" (H) 20-45" (M) \( \sum < 20" (L)
Soil Permeability: High / Medium Low _
Type of Contaminant: Gasoline (G) V Diesel (D) Waste Oil (W) Crudes (C)
Magnitude of Release
Number of Gallons Lost: >5000 (V) _ 1000-5000 (L) _ 500-999 (M) \( \sqrt{100-499} \) (S) _ <100 (E) _
Potential Receptors  *** NOTE: In this section, all (or none) of the criteria must be scored.  Aquifer Depth: <25' (1) 25-50' (2) 51-100' (3) >100' (4)
Distance to surface water: <100 yds (N) _ 100-500 yds (M) _ >500 yds (F) \(  \)

422

# FAX TRANSMITTAL

Date and Time:	September 5, 2002	
To:	Henning Larsen	
Company:	DEQ	
Fax No.:	503 229-6945	
From:	Don Williams	
Company:	Meadowbrook Grocery	
Phone No.:	503 637-3055	
Fax No.:		
No. of Pages:	3, including cover	

Henning,

Here is the report from Coffey Labs on the well water.

Don



Report Date: September 5, 2002

Job Number: A20829AX

PWSID: 94658

PO Number: None Provided Project No: None Provided Project Name: None Provided

Margie Williams Meadow Brook Grocery P.O. Box 425 Eagle Creek, OR 97022

#### Sample Information

Laboratory Sample ID	Field Identification	Matrix	Collection Date	Collection Time
A20829AX-1	Kitchen Sink By Cash Register	Drinking Water	08/29/02	1515

Analytical results are on the following page(s).

Technical Services

Sincerely

The data submitted in this report is for the sole and exclusive use of the above-named client. All samples associated with the work order will be retained a maximum of 15 days from the report date or until the maximum holding time expires. All results pertain only to samples submitted.

Thank you for allowing Coffey Laboratories to be of service to you. If you have questions or need further assistance, please do not hesitate to call our Customer Services Department.

TS/atc



#### Analytical Data

Meadow Brook Grocery

Job Number: A20829AX Page Number: 2 of 2

Lab Sample ID: A20829AX-1

Field ID: Kitchen Sink By Cash Register

Date/Time: 08/29/02 1515 Matrix: Drinking Water

EPA Category: Volatile Organic Chemicals Analysis Performed: Volatile Organics by GC/MS.

Analysis Date: 09/03/02 Analyst: MRD

	Detection	Analytical	EPA	EPA
Parameter	Limit	Result	Limit	Code
Benzene	5,	ND		2990
Ethylbenzene	5.	ND		2992
Toluene	5.	ND		2991
m,p-Xylene	10.	ND		
o-Xylene	5.	ND		2995
Total Xylenes	10.	ND		2955
4-Bromofluorobenzene (Surr.)	20.	87%	,	
Dibromofluoromethane (Surr.)	20.	121%		
Toluene-d8 (Surr.)	20.	102%		

ND means none detected at or above the detection limit listed.

### State of Oregon

### Department of Environmental Quality

### Memorandum

To:

File

Date: October 8, 2002

From:

Henning Larsen

Hydrogeologist NWR Tanks Program

Subject:

Meadowbrook Grocery (DEQ File 03-92-0125)

Northwest Region Tanks Program Manager

On October 4, 2002, the DEQ received the results of monitoring well sampling recently conducted at the Meadowbrook Grocery. Although, the DEQ had not required sampling of the wells, the Department was interested in the results given the Department's recent site inspection and follow up to a complaint filed by PGE in 2000.

The results of the sampling have reaffirmed the Department's decision to not reopen this cleanup project. Consistent with the visual and olfactory observations made during an August 27<sup>th</sup>, 2002 site inspection, groundwater drawn from the wells contained low levels of gasoline contamination with benzene detected at a maximum concentration of 7.25 ppb. While several compounds were detected at concentrations exceeding their respective drinking water ingestion standards, the observed levels were of similar magnitude as to those detected at the time of closure in 1997. This suggests that conditions have not changed significantly since the time of closure and that there is no evidence of a recent, or on-going, release. At the time of closure it was acknowledged that the ingestion standards had not been met. However, the DEQ had determined that the impacts were tolerable since the groundwater contamination was localized within the shallow aquifer and repeated sampling had shown it was not affecting the on-site drinking water well.





C:/Warkith INFORMS/FAXCover.wpd

MARTIN S. BURCK ASSOCIATES, INC.

1832 W Cascade, Hood River, OR 9703 I Phone 541.387.4422 Portland 503.977.240 I

5413874813

MSBA

Geologic and Environmental Consulting Services

FACSIMILE	COV	EK PAGE	
To: Henning Larson, DEQ	Fax No	503-229 (A45	
J	Phone No_	1-800 452-4011	
From: Mortun S Burde Assoc. Inc	Fax No Phone No	541.387.4813 541.387.4422	
Total Pages: + Cover	Date:	10/4	2002
SUBJECT: Ground Wofer Monutarin	ig and Sair	upling-Oct 2002 - Mea	doudorode
COMMENTS:	J	J	
Please fund attached	0. 604	of subject report.	
Please call of pu I	han eng	guestox-	
Follow Up:			

1832 W Cascade, Hood River, OR 97031 Phone 541.387.4422 Portland 503.977.2401

5413874813

Geologic and Environmental Consulting Services



October 4, 2002

Mr. Don Williams 39801 S.E. Kitzmiller Eagle Creek, Oregon 97022

Subject:

Ground Water Monitoring and Sampling - October 2002

Meadowbrook Grocery 16845 S. Highway 211 Molalla, Oregon

Dear Mr. Williams:

This report presents the results of ground water monitoring and sampling activities performed at the Meadowbrook Grocery facility located at 16845 S. Highway 211, Molalla, Oregon in October 2002, by Martin S. Burck Associates Inc. (MSBA).

#### INTRODUCTION

The Meadowbrook Grocery site, owned by Don Williams, consists of an active automobile refueling station and grocery store. The legal description of the site location is Clackamas County, Tax Lot No. 800; Township 5S, Range 3E, Section 2. The site location is illustrated on Figure 1. The site features including a grocery store, pump island, former tanks, and three ground water monitoring wells are illustrated on Figure 2.

### GROUND WATER LEVEL MONITORING AND SAMPLING

The general scope of work consisted of measuring ground water levels in each of the monitoring wells (MW-1, MW-2, and MW-3) and collecting a ground water sample from each of the wells for laboratory analysis. Monitoring and sampling activities were performed in general accordance with the Field Methods and Procedures presented in Attachment A. The ground water monitoring and sampling activities were performed at the site on October 1, 2002.

### Ground Water Level Data Summary

The depth to ground water measured below the top of casing (TOC) in monitoring well MW-1 was 5.03 feet, MW-2 was 5.63 feet, and MW-3 was 5.92 feet. The depth to water measured in each of the wells is summarized in Table 1.

### Ground Water Analytical Data Summary

Ground water samples were collected from monitoring wells MW-1, MW-2, and MW-3 for laboratory analysis of benzene, toluene, ethylbenzene, xylenes, 1,2-dibromoethane (EDB), 1,2-dichloroethane (EDC), methyl tert-butyl ether (MTBE), naphthalene, 1,2,4-trimethylbenzene (124-TMB), 1,3,5-trimethylbenzene (135-TMB), isopropylbenzene (IPB), and n-propylbenzene (NPB) using EPA method 8260B. The ground water samples were also analyzed for dissolved lead using EPA method 6020. The ground water sample analytical data are summarized in Table 1 and are presented below.

Benzene was not detected in well MW-1 and was detected in wells MW-2 and MW-3 at concentrations of 7.25 parts per billion (ppb) and 0.79 ppb, respectively.

Toluene was not detected in wells MW-1 and MW-3 and was detected in well MW-2 at a concentration of 1.52 ppb.

Ethylbenzene was detected in wells MW-1, MW-2, and MW-3 at concentrations of 32.4 ppb, 98.9 ppb and 2.67 ppb, respectively.

Xylene was detected in wells MW-1, MW-2, and MW-3 at concentrations of 17.8 ppb, 282 ppb, and 1.90 ppb, respectively.

EDB, EDC, and MTBE were not detected in any of the wells.

Naphthalene was not detected in well MW-3 and was detected in wells MW-1 and MW-2 at concentrations of 27.2 ppb and 44.7 ppb, respectively.

124-TMB was detected in wells MW-1, MW-2, and MW-3 at concentrations of 77.2 ppb, 173 ppb, and 2.21 ppb, respectively.

135-TMB was detected in wells MW-1, MW-2, and MW-3 at concentrations of 44.9 ppb, 36.5 ppb, and 0.53 ppb, respectively.

IPB was not detected in well MW-3 and was detected in wells MW-1 and MW-2 at concentrations of 13.8 ppb and 15.1 ppb, respectively.

NPB was detected in wells MW-1, MW-2, and MW-3 at concentrations of 59.4 ppb, 35.9 ppb, and 2.28 ppb, respectively.

Dissolved lead was detected in wells MW-1, MW-2, and MW-3 at concentrations of 2.10 ppb, 1.11 ppb, and 1.10 ppb, respectively.

A copy of the ground water sample laboratory report is presented in Attachment 2 and copies of the ground water purge and sample data are presented in Attachment 3.

PAGE 04

#### REMARKS AND SIGNATURES

The information/conclusions/recommendations/proposals contained in this report were arrived at in accordance with currently accepted professional hydrogeologic and environmental practices at this time and location. No warranties are expressed or implied. This report was prepared solely for Mr. Don Williams and MSBA is not responsible for the independent conclusions or actions of others derived from the information presented herein.

Information and opinions presented in this report are based on the collection and review of data from limited portions of the site subsurface. MSBA is not responsible for conditions that may exist in portions of the site that were not investigated; for conditions that were not reported or properly presented to MSBA; and for future activities or investigations that may alter the current condition or understanding of the site.

Prepared by:

MARTIN S. BURCK ASSOCIATES, INC.

Michael Deely

Environmental Scientist

Reviewed By:

Martin S. Burck, RG

Registered Geologist

Date

C:\Workfile 0\R&C\Meadowbrook\Oct02gw.wpd

enc:

Figure 1:

Site Location Map

Figure 2:

Site Features and Well Location Map

Table 1:

Ground Water Sample Analytical Data and Depth to Water

Attachment 1:

Field Methods and Procedures

Attachment 2:

Ground Water Sample Laboratory Report

Attachment 3:

Ground Water Purge and Sample Data

Martin S. Burck Associates, Inc.


Meadowbrook Grocery

MSBA INC

Figures

Figure 1 Site Location Map
Figure 2 Site Features Map

5413874813



Scale 1:24,000 Contour Interval 20 Feet Dotted Lines Represent 10-Foot Contours National Geodetic Vertical Datum of 1929






FIGURE 1


SITE LOCATION MAP

Meadowbrook Grocery 16845 S. Highway 211 Molalla, Oregon



Adapted from Report Prepared by Others

Molu



### LEGEND

MW-1 ● Ground Water Monitoring Well and Label
Former Tank Location Outlines



### FIGURE 2

### SITE FEATURES MAP

Meadowbrook Grocery 16845 S. Highway 211, Molalla, Oregon

Table

Table 1 Ground Water Sample Analytical Data and Depth to Water

# TABLE 1 GROUND WATER SAMPLE ANALYTICAL DATA AND DEPTH TO WATER

Meadowbrook Grocery

16845 S. Highway 211, Molalla, Oregon

Well ID	Depth to Water a	Date	Benzene <sup>b</sup> (ppb) <sup>d</sup>	Taluene <sup>b</sup> (ppb)	Ethyl- benzene <sup>b</sup> (ppb)	Xylenes <sup>b</sup> (ppb)	EDB b	EDC <sup>b</sup> (ppb)	MTBE <sup>b</sup> (ppb)	124- TMB <sup>b</sup> (ppb)	135- TMB <sup>b</sup> (ppb)	IPB <sup>b</sup> (ppb)	NPB <sup>b</sup> (ppb)	Naph- thalene <sup>b</sup> (ppb)	Lead <sup>c</sup> (ppb)
MW-1	5.03	10/1/02	ND <sup>e</sup>	ND	32.4	17.8	ND	ND	ND	77.2	44.9	13.8	59.4	27.2	2.10
MW-2	5.63	10/1/02	7.25	1.52	98.9	282	ND	ND	ND	173	36.5	15.1	35.9	44.7	1.11
MW-3	5.92	10/1/02	.79	ND	2.67	1.90	ND	ND	ND	2.21	0.53	ND	2.28	ND	1.10

a Depth to ground water measured in feet from the top of each well casing to the ground water surface.

Benzene, toluene, ethylbenzene, xylenes, 1,2-dibromoethane (EDB), 1,2-dichloroethane (EDC), methyl tert-butyl ether (MTBE), 1,2,4-trimethylbenzene (124-TMB), 1,3,5-trimethylbenzene (135-TMB), isopropylbenzene (IPB), n-propylbenzene (NPB), and naphthalene analyzed using EPA method 8260B.

c Dissolved lead analyzed using EPA method 6020.

d Numeric analytical results reported in parts per billion (ppb).

Not detected (nd).

# Attachment 1

Field Methods and Procedures

### FIELD METHODS AND PROCEDURES

The following section presents the general field methods and procedures that were utilized to complete field activities. These activities included collecting and preserving ground water samples for laboratory analysis. Ground water samples were collected, preserved, transported, and analyzed in general accordance with DEQ methodology as presented in OAR 340-122-345 "Sample Collection Methods," and OAR 340-122-218 "Required Analytical Methods." If not specified by current DEQ regulations, sampling and analytical methods were implemented in general accordance with EPA protocol.

### Ground Water Level Monitoring

The top of each well casing is surveyed to within plus or minus (+/-) 0.01-foot relative to a common temporary benchmark. A temporary benchmark was designated with an assumed elevation relative to the approximate surface elevation above mean sea level (msl). The surveyed locations are marked on each casing for future reference and measuring. The purpose of the survey is to allow correlation of measured ground water levels between each of the wells at the site.

The depth to ground water (water level) was measured with an electronic, hand-held, water level indicator. The probe of the indicator is lowered in the well until contact with ground water completes a circuit causing a buzzer and light to activate. The depth to water, measured from the top of the well casing, is read directly from a graduated cord attached to the probe with marked increments of 0.01-foot.

### Ground Water Purging and Sampling

Prior to collecting the sample for laboratory analysis, ground water is purged from the well with a bailer. The well is purged to remove potentially stagnant ground water and allow the surrounding formation water to enter the well for sampling. Three to six well volumes are generally required to achieve this objective. The ground water temperature and conductivity were monitored after each well volume was purged. When the final readings were within ten percent of the previous readings for these parameters, following the removal of a minimum of three well volumes, the sample was collected for laboratory analyses.

After purging, a sample is collected when the water level in the well has recharged to within 85 percent of the initial static water level. If the desired amount of recharge is not achieved within a period of 60 minutes, the sample is collected and the water level is recorded.

The sample is collected from the well with a bailer designed to reduce the loss of volatile components. The water was collected from the well by lowering the bailer below the ground water interface and retrieving the bailer with the water contained inside. The water was transferred into two identical 40 mL glass VOA vials with septum lids provided by the laboratory. The glass jars contained 2-5 drops of dilute HCL as a preservative to increase the sample hold time to 14 days. The water was transferred to the glass jars with as little agitation as possible and immediately sealed with the Teflon-lined septum lids. The sample jars were filled so that no headspace was present at the time of collection to help prevent the potential loss of volatiles.

After the samples were properly sealed, they were placed immediately in an ice chest with ice and maintained at a temperature of 4 degrees C or 39 degrees F until being prepared by the laboratory for analysis.

### Chain-of-Custody and Labeling

The Chain-of-Custody (COC) is a form that documents the custody of a sample from the time of origin to the time of disposal or destruction. A COC was initiated in the field at the time the samples were collected. The sampler documents such information as the time, date, type of sample, requested analyses. Any individual in custody of the samples, including the laboratory, is required to document the transfer of custody (beginning with the sampler) by signing the COC (including date and time of transfer).

A label was affixed to each sample container designating the sample number, and other critical information including: project name, location, date, time, sampler name. After receiving the samples the laboratory assigns a unique number to each discrete sample for reference and verification.

### **Equipment Decontamination**

Equipment used to collect ground water samples such as: bailers, water level indicators, etc., are decontaminated prior to each use. Strict decontamination procedures are utilized to help eliminate the potential for cross-contamination between samples and sample locations. The decontamination procedure utilized at this site included a thorough washing in TSP or Alconox detergent followed by two rinses in tap water and a third and final rinse using deionized water. If time permitted, the sampling equipment was allowed to air dry.

Disposable latex gloves were worn during sampling to help eliminate the potential for cross-contamination by the sampler. The gloves were discarded after each sample event and a new pair was utilized for each subsequent sampling event.

Ground Water Sample Laboratory Report

5413874813 NCALABS. COM

MSBA INC

PAGE 14 P.02

Igamery, Suite B, Spokene, WA 99209-4776

#453-62.184 gamery, Sultra B, Spokene, WA 992CB-908-924-120 42 908-924-8280 9405 SW Nimbus Avenue, Bravanton, OR 97008-7132 503-906-9240 fex 503-906-9210 70332 Empire Avenue, Sultre F-1, Bend, OR 97761-5711 541-383-3310 fex 541-382-7988

Martin S. Burck Associates 1832 W. Cascade

Hood River, OR 97031

Project Meadowbrook

Project Number: none Project Manager: Marry Burck

Reported: 10/03/02 15:21

### ANALYTICAL REPORT FOR SAMPLES

		Matrix	Date Sampled	Date Heceived
Sample ID	Laboratory ID	17441714	100 100 11.20	10/01/02 13:05
3811411 A	P2J0039-01	Water	10/01/02 11:39	[0/01/02 13:03
MW-1	P230033-01		10/01/02 11:55	10/01/02 13:05
	P2J0039-02	Water		
MW-2		Water	10/01/02 11:26	10/01/02 13:05
MW-3	P2J0039-03	A Tfol		

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirely.



425.420.92 (425.420.321) (425. Spokera

Martin S. Burck Associates 1832 W. Cascade Hood River, OR 97031

Project: Meadowbrook

Project Number: none

Project Manager: Marty Burck

Reported: 10/03/02 15:21

# Dissolved Metals per EPA 6000/7000 Series Methods

North Creek Analytical - Portland

Result	Reporting Limit	Units	Dilution	Method	Prepared	Analyzed	Batch	Notos
				Samled: 10/0	1/02 Rece	ved: 10/01/	02	
		39		Suitpled. Two	11.42			
			, .	EDA 6020	10/02/02	10/03/02	2100076	
0.00210	0.00100	mg/l		ELY OOS				
				Sampled: 10/	11/02 Rece	ived: 10/01/	02	
				Sampled. 107	-			
				EDA 6020	10/02/02	10/03/02	2100076	
0.00111	0.00100	mg/I	1	EF 54 0020	.,			
••••								
				Campled: 10/	01/02 Reco	ived: 10/01	/02	100
		1000		Sampiag. 10	O IT VE	A PARTY PROPERTY OF THE PARTY O	1100	245
				PPA 6020	10/02/02	10/03/02	2100076	
0.00110	0.00100	ang/	1	El K GODE				
		0.00210 0.00100 0.00111 0.00100	Result Limit Units  0.00210 0.00100 mg/l  0.00111 0.00100 mg/l	Result   Limit Units Dilution	Result   Reporting   Units   Dilution   Method	Result   Reporting   Units   Dilution   Method   Prepared	Result   Reporting   Units   Dilution   Method   Prepared   Analyzed	Result   Climit Units   Dilution   Method   Prepared   Analyzed   Batch

North Creek Analytical - Portland

The results in this report apply to the samples analysed in accordance with the chain of custody document. This enclysical report must be reproduced in its entirety.

Philip Nerenberg, Laboratory Manager

North Crock Analytical, Inc. Environmental Laboratory Network Page 2 of 8



428.420.82 r 428.420.8210 p. Spokene, WA 89206-4776 p. Spokene, WA 892

Martin S. Burck Associates 1832 W. Cascade Hood River, OR 97031

Project Mesdowbrook Project Number: none

Reported: 10/03/02 15:21

Selected Volatile Organic Compounds per EPA Method 8260B

Project Manager: Marty Burck

North Creek Analytical - Portland

	Result	Reporting Limit	Units	Dilution	Method	Propered	Analyzed	Bench	Non			
Analyte	Sampled: 10/01/02 Received: 10/01/02											
MW-1 (P2J0039-01) Water		0.600	/1	1	EPA 8260B	10/02/02	10/02/02	2100054				
1,2-Dibromoethane	ND	0.500	ug/l			•		и				
1,2-Dichloroethane	ND	0.500				,,	ν					
Benzens	ND	0.500			•	u		Þ				
Toluene	ND	0.500	Y (1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		a	D	•	u				
Ethylbensens	32.4	0.500	_			<b>b</b>		×				
Xylenes (total)	17.8	1.00				·	u					
Methyl tert-butyl ether	ND	2.00						y "				
Naphthalese	27.2	2.00					37	n				
1,2,4-Trimethylbenzene	77.2	1.00				fr.		n				
1,3,5-Trimethylbenzene	44.9	0.\$00	**					н				
	13.8	2.00	u					fi fi				
Isopropylbenzene	59.4	0.500		4								
n-Propylbenzane	102 %	84.5.124	7 -									
Surr: 4-BFB	99.0 %	77.9-123										
Surr: 1.3-DCA-d4	100 %	83.5-119										
Surr: Dibromofluoromethane	101 %	84.1-116										
Surr: Tohiane-de	101 70						.:d. 10/01/	നാ				
MW-2 (P2J0039-02) Water					Sampled: 10/0	10/02/02	10/02/02	2100054				
1,2-Dibromosthane	ND	0.500	ug/l	1	EPA 8260B	1010202	"	н				
1,2-Dichlorosthane	ND	0.500	•					n				
	7.25	0.500	•	•				**				
Benzene	1.52	0.500				u						
Toluens	98.9	0.500	a	0								
Ethylbenzene	282	1.00	•	¥	14			"				
Xylenes (total)	ND	2,00	10		ь	и,		"				
A C. L. I have bright ofher			•					11 50				
Methyl terr-busyl ether	-	2.00										
Naphthalene	44.7	2.00	-		11		•					
Naphthalene 1,2,4-Trimethylbenzene	44.7 173	1.00	:		11		"	b				
Naphthalene	44.7 173 36.5	1.00 0.500	:			11 #	×	b "				
Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene 1sopropylbenzene	44.7 173 36.5 15.1	1.00 0.500 2.00	# #		u	-		b				
Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene	44.7 173 36.5 15.1 35.9	1.00 0.500 2.00 0.500			n n		×	b "				
Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene 1sopropyibenzene n-Propyibenzene	44.7 173 36.5 15.1 35.9	1.00 0.500 2.00 0.500 84,5-124			n n		×	b "				
Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene 1sopropylbenzene n-Propylbenzene Surr: 4-BFB	44.7 173 36.5 15.1 35.9 /02 %	1.00 0.500 2.00 0.500 84.5-124 77.9-123	/		n n		×	b "				
Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene 1sopropylbenzene n-Propylbenzene	44.7 173 36.5 15.1 35.9	1.00 0.500 2.00 0.500 84,5-124	/		n n		×	b "				

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirely.



gomery, Suite B, Spokane, WA 99206-4778 9x 508,824-9290

East 1111 (Spamery, Suita B, Spokenc, WA 99206-509.924.32) — 6x 505.924.9250 9405.5W Nimbus Avenue, Beaverton, OR 97008-7132 503.906.9200 fax 805.908.9210 2032 Empire Avenue, Suita F-1, Bend, OR 97701-5711 541.363.9310 fax 541.282.7588

Martin S. Burck Associates 1832 W. Cascade Hood River, OR 97031

Project: Meadowbrook

Project Number: none Project Manager: Marry Burck

Reported: 10/03/02 15:21

# Selected Volatile Organic Compounds per EPA Method 8260B

North Creek Analytical - Portland

Analyte	Rosult	Roporting Limit	Units	Diludon	Method	Prepared	Analyzed	Batch	Note
12-74-1		The state of the s			Sampled: 10/0	1/02 Reca	ived: 10/01/	02	
MW-3 (P2J0039-03) Water				,	EPA 8260B	10/02/02	10/02/02	2100054	
1,2-Dibrompethane	ND	0.500	wg∕1		Brx 8200B	, u	**	4	
2-Dichlorosthane	ND	0.500				11	14		
Benzene	0.790	0.500				, n	и	14	
Toluens	ND	0.500	-				· ·	17	
Echylbenzene	2.67	0.500	"				п		
(ylenes (total)	1.90	1.00					n —		
Methyl tert-butyl ether	ND	2.00			17	a			
Naphthalene	ND	2.00						N	
1,2,4-Trimethylbenzene	2.21	1.00		h			•		
1,3,5-Trimethylbenzene	0.530	0.500	11	u					
1,3,5- I FERENCE COMPANY	ND	2.00		•	-				
Isopropylbenzene a-Propylbenzene	2.28	0.500							
	102 %	84.9-124							
Surr: 4-BFB Surr: 1.2-DCA-d4	100 %	77.9-123							
Surr: Dibromofluoromethane	102 %	85.5-119							
Surr: Tolusne-d8	102 %	84.1-116							

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This enalytical report must be reproduced in its entirety.



Marrin S. Burok Associates

Hood River, OR 97031

1832 W. Cascade

Lend



Spokane Esst 11115 Omery, Suita B, Spokane, WA 99208-4776
508.924.9300
508.924.9390
0.005 SW Nimbus Avenue, Bosvertan, OR 97008-7132

Project: Meadowbrook

Project Number: none Project Manager: Marty Burck Reported: 10/03/02 15:21

Waster Strate Out States and house and the contract of North Creek Analytical - Portland RPD %REC Source Spike Noscs Reporting RPD Limit Limits %REC Result Lovel Limit Unite Result Analyto Batch 2100076 - EPA 200/3005 Diss Prepared: 10/02/02 Analyzed: 10/03/02 Blank (2100076-BLK1) mg/l 0.00100 סא Prepared: 10/02/02 Analyzed: 10/03/02 80-120 LCS (2100076-B\$1) 98.7 mg/ 0.100 0.00100 0.0987 Lead Prepared: 10/02/02 Analyzed: 10/03/02 Source: P2J0026-01 20 Duplicate (2100076-DUP1) mg/l 0.00100 ND Lead Prepared: 10/02/02 Analyzed: 10/03/02 Source: P2J0026-01 Matrix Spike (2100076-MS1) ND 0.100 mg/l 0.0976 0.00100 Load Prepared: 10/02/02 Analyzed: 10/03/02 Source: P210688-01 Matrix Spike (2100076-MS2) 75-125 ND 0.100 0.00100 0.0944

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirely.





k 423.420.9210 Igomary, Suite B, Spokane, WA 99266-4776 (ex 608.924.9280 Fest 1111 509.924.928 Sychene

9465 6W Nimbus Avenue, Beaverton, OR 97308-7132 9465 6W Nimbus Avenue, Beaverton, OR 97308-7132 903.996.9200 fax 503,996.9210 70332 Empire Avenue, Suite F-1, Bend, OR 97701-5711 341,383.9310 fax 541,392,7668 Portend

Martin S. Burck Associatos 1832 W. Casande Hood River, OR 97031

Project Meadowbrook

Project Number: none

Project Managor: Marry Burck

Reported: 10/03/02 15:21

	Nor	th Creek	MUSITA	Cay-20			WREC		RPD	
		Reporting		Spike	Source Result	%REC	Limits	RPD	Limit	Notes
Analyse	Result	Limit	Units	Lovel	POBULL	701000				
atch 2100054 - EPA 5030B										
llank (2100054-BLK1)				Prepared	& Analy	zed: 10/02	<u> 2002</u>			
2-Dibromoethane	ND	0,500	ug/i							
2-Dichlorosthans	NO	0.500	и							
Senzene	ND	0.500	•							
Coluene	ND	0.500	w							
	ND	0.500	н							
2thylberizene	ND	1.00	•							
cylenes (total)	ND	2.00								
Methyl tert-butyl ether	סא	2.00	n							
Vaphthalene	ND	1.00	×							
2.4-Trimethylbonzene	ND	0.500								
3,5-Trimothylbenzene	ND	2.00	Þ							
PoblobAlpeuzere	ND	0.500	,							
n-Propylbonzene				10.0		98.5	84.5-124			
Surr: 4-8FB	19.7			20.0		102	77.9-123			
Surr: 1,2-DCA-de	20.5			20.0		102	83.5-119			
Surv: Dibromefluoromuthane	20.4		d	200		102	84.1-116			
Surr: Toluens-d8	20.4									
TOR (CLOOPEL BCT)			71	Prepared & Analyzed: 10/02/02						
LCS (2100054-BS1) Benzene	19,4	0.500	ug/I	20.0		97.0	80-125			
	19.3	0.500	q	20.0		96.5	80-125			
Tolusne	19.0	0.500		20.0		95.0	80-123			
Sthylbenzene	57.8	1.00		60.0		96.3	80-129			
Xylenes (total)	19.6		D	20.0		98.0	84.5-124			
Surr: 4-BFB	19.6 20.4			20.0		102	77.9-125			
Surr: 1,2-DCA-44				20.0		104	83.5-119			
Surr. Dibromofluoromethane	20.9			20.0		104	84.1-116			
Surr: Toluene-di	20.7						00/00			
Marrix Spike (2100054-MS1)	S	ource: P2J00	15-01			lyzed: 10/	02/02			
	20.6	0.500	ug/I	20.0	סא	104	80-125			
Ben2ane Tolumb	20.8	0.500	•	20.0	ND	104	80-125			
Toluche	20.9	0.500		20.0	מא	104	80-125			
Ethylbenzene	63.8	1.00		60.0	ND	106	80-125			
Xylencs (total)	19.7			20.0		98.5	84.5-124	1		
Surr: 4-BFB	•			20.0		102	77.9-123	1		
Surr: 1,2-DCA-d4	20.4			20.0		106	83.5-118	)		
Surr: Dibramofluoromethane	21.3 20.6			20.0		/03	84.1-110	s		

North Creek Analytical - Fortland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirely.





425.420.821 F 425.420.8210 F 425.420.8210 S 309.421.8200 F 425.420.8200 F 425.420.8200 F 425.420.8200 F 425.420.8200 F 425.420.8200 F 425.4200 F 425.4200

203924.8200 TRX DUB944.82091 9408 SW Nimbus Avenue, Bearvarton, OR 97008-7132 501.968.9200 fax 303.908.8210 20332 Empire Avenue, Sulte F-1, Bend, OR 97701-5711 541.383.8310 fax 541.382,7588 Portland

102

84.1-116

Martin S. Burck Associates 1832 W. Cascade Hood River, OR 97031

Surr: Dioromofluoromethene

Surr: Toluene-d8

Project: Mesdowbrook

Project Number: none

20.3

Project Manager: Marry Burck

Reported: 10/03/02 15:21

		th Creek Reporting		Spike	Source Result	%REC	%REC	RPD	RPD Limit	Notes
Analyte	Result	Limit	Units	Level	Acoust	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				
Batch 2100054 - EPA 5030B	A A									
	So	urce: P2J001	5-01	Prepare	d & Analy		2/02	9.03	25	
Matrix Spike Dup (2100054-MSD1)	20.2	0.500	ug/l	20.0	ND	101	80-125	293		
Benzeré	20.0	0.500		20,0	ND	100	80-125	3.92	24	
Toluena	A 10-10-10	0.500		20.0	MD	102	80-125	2.42	25	
Brhylbenzona	20.4		*1	60.0	ND	105	80-125	1.42	25	
Xylenes (total)	62.9	1.00				98.5	B4.5-124			
Sur: 4-BFB	19.7			20.0						
- 100 - 100	20.7		**	20.0		104	77.9-123			
Sur: 1,2-DCA-d4	20.8		, p	20.0		104	63.5-119			
Sure: Dinramofluoromathane	20.0					103	DA I TIA			

20.0

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analysical roport must be reproduced in its ensirely.



425.420.92 Past 11115 S09.924.9200 Tex 509.924.9280

200326.2000 lipx 80%.324.02.200 9405 5W Nimbus Avenue, Beaverton, DR 97008-7132 503.905.5200 lax 903.905.9210 20032 Empire Avenue, Suits F-1, Bend, QR 97701-9711 541.383.6310 lax 541.382.7583

Martin S. Burck Associates 1832 W. Cescade Hood River, OR 97031

Project: Meadowbrook

Project Number: none Project Manager: Marty Burck

Reported 10/03/02 15:21

### Notes and Definitions

Analyse DETECTED DET

Analyte NOT DETECTED at or above the reporting limit ND

Not Reported NR

Sample results reported on a dry weight basis. MRLs are adjusted if %Solids are less than 50% dry

Sample results reported on a wet weight basis (as received) West

Relative Percent Difference RPD

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of ouslody document. This analytical report must be reproduced in its entirely.





Issas 11115 Montgomery, Suite B, Spolume, WA 99206-4776
9405 S. W. Ninchus Avenue, Bezverton, OR 97008-1132
20332 Empire Avenue, Suite F-1, Bend, OR 97701-5711

(509) 924-920**0** (503) 906-9200 FAX 924-9290 FAX 906-9210

(503) 906-9200 FAX 906-9210 (541) 383-9310 FAX 382-7588

Work Order #: CHAIN OF CUSTODY REPORT TURNAROUND REQUEST in Business Days INVOICETO: MSBA CLENT: MSBA Organic & Inorganic Analysics 4 (SAME) REPORTTO MARTY BURCK ADDRESS: 1832 W. CASE AND ANE 15:31 STD. Hood River, OR 97031 FAX: 54 -387 - 4613 PO, NUMBER: MEADOW BLOOK PHONE: 541-387-4472 REQUESTED ANALYSES PHOJECT NAME MEADON brook OTHER PROJECT NUMBER: Sibraroannal liberary in less them them transfered men paren Facts Charges. SAMPLED RY M DEELS MATRIX # OF SAMPLING CLIENT SAMPLE COMMENTS CONT (W.S.O) DATE/TIME IDENTIFICATION W 10/1/02 X 1139 1-60M 5 W x 11 55 MW-2 W 1120 MW-3 DATE DATE ( 1 02 RECEIVED B) DATE: 12 DAGE THE 12 23 FIRM MSBA PRINT NAME MICHAEL DERCH THE L'S KELINUUISHED DY: TIME 17 Q MRM: 10-10-2 ADDITEDNAL REMARKS

TOTAL P. 10

(LOT, RPM 763)

Attachment 3
Ground Water Purge and Sample Data

10/04/2002 19:50

# MARTIN S. BURCK ASSOCIATES, INC

1832 W. Cascade Ave, Hood River, OR 97031 Phone: (541) 387-4422, Ptld: (503) 977-2401



# GROUND WATER LEVEL DATA

Meadowbrook Grocery, 16845 S. HWY 211, Molalla, OR

out the table type	a ar			60	
Vell No.	Time		/ DTW	Elev	
MW-3	1009	NA	5.92		
Mw-1	10 10	NA	5.03		
v (u - Z	1012	NA	5.63		
, y , z					
1					
- 1	4 2				
- , ,					
· , i		N 25 1 1			
	4				

MARTIN S. BURCK ASSOCIATES, INC

1832 W. Cascade Ave, Hood River, OR 97031 Phone: (541) 387-4422, Ptld: (503) 977-2401

# MSBA

## GROUND WATER PURGE & SAMPLE DATA

Project: Date:	1. 102	ook Grocery, Sampl					
			ITORING W		ORMATI	ON	
Well Numb	er MW	-1 G	eneral Loca	ntion: ಀೕ	u Box	UNDER	2' sq Dian. plate
Well Diame	eter (in)					Denth	to Ground r (ft)
Wetted Cas _ength (ft)	sing 8.97	One Volu	Well me (gals)	Oll NA7 II	1.52	16	" Well = 0.66 gal/foot
No. of Well o Purge							5 7 ~ 4 . 5
		WELL DEV					
Time	Depth to Water	Gallons Purged	Cumulative Total		С	рН	Comments
10 46	5.03	0	٥				STARTED PURGE
10 49		1.5	1.5	64.2	2009		were vor.
10 53		1.5	3.0	64.1	2900		Well VOL
10 5.7	4.85	1.5	4.5	63.8	2890		WELL VOL STOPPED PUR
11 39	5.06	0	4.5	Slight	PHC	ODOR	COLLECTED SAMPLE
Comments	: ≥ 85% statio	water colum	in≤6.371	feet depth	to wate	r	
		GROUN	O WATER S		lear ·		nal Fice Chest & Ice
Collection T	ime //	39	_ Appearar		oudy orbid	Therr Prese	ervation Other
Containers	(3) 40 ml VO.	Preserved		) 500 ml P		quested alyses:	☐ EPA 8021B ☐ EPA 8260B ☐ OTHER
Comments	HCL HCL	□ HC	slight	PHC.	ODOR		

# MARTIN S. BURCK ASSOCIATES, INC

1832 W. Cascade Ave, Hood River, OR 97031 Phone: (541) 387-4422, Ptld: (503) 977-2401



# GROUND WATER PURGE & SAMPLE DATA

	Meadowbro	ook Grocery	16845 S H\	WY 211.	Molalla.	OR	Sample Order ( 5
Project:	Meadowbic	- Charles	10040 0.11		1010101101		
Date: 10	1/02	Sampl	led By:		MPD		
		MON	IITORING W	ELL INF	ORMATI	ON	
Well Numb	er MW-	·2 G	eneral Locat	ion:	~ PARE	SPOT	NEXT TO STORE
	ter (in)2		tal Depth (ft)	15		Depth Wate	to Ground r (ft)5-63
Wetted Cas Length (ft)	9.3	One 7 Volu	e Well ume (gals) _	1	1.59		" Well = 0.66 gal/foot
No. of Well to Purge	volumes		_ Total Pu	rge Volu	me (gals)	<u> </u>	.78 N 5
		WELL DEV	ELOPMENT	/PURGII	NG INFO	RMATIO	N
Time	Depth to Water	Gallons Purged	Cumulative Total	7	С	рΗ	Comments
1102	5.63	0	0				STARTED PURGE
1106		1.5	1.5	63	2540		well vol
11 09		1.5	3.0	62.9	2380		well vol
11 13	8.20	2.0	5.0	63	2460		well us (STOPPED PURGE
1155	5.45	0	5.0	slight	PHC 0	<b>DOR</b>	COLLECTED SAMPLE
		i j					
Comments	: ≥ 85% static	water colun	nn≤7.03fe	eet deptl	to water		
		GROUN	D WATER S		INFORMA lear		nal     Ice Chest & Ice
Collection T	ime	55	_ Appearan	′□ c	loudy urbid		ervation Other
Containers	(3) 40 ml VO	As ( )1 lite		500 ml F		uested lyses:	☐ EPA 8021B ☐ EPA 8260B ☐ PAHS(Pb) ☐ OTHER
Comments		5/19	nt PHC	ODOR			

## MARTIN S. BURCK ASSOCIATES, INC

MSBA INC

1832 W. Cascade Ave, Hood River, OR 97031 Phone: (541) 387-4422, Ptld: (503) 977-2401



# GROUND WATER PURGE & SAMPLE DATA

Project:	Meadowbro	ook Grocery,	16845 S. H	WY 211,	Molalla	, OR	Sample Order ( )
Date:	10/1/02	Sampl	led By:	MPD			
		MON	IITORING W	ELL INF	ORMAT	TION	
Well Number	er MW-	.3 G	eneral Locat	ion: Nu	U ENTR	NE	ar util pole
Well Diame	ter (in) 2	To	tal Depth (ft)	15		Depti _ Wate	n to Ground r (ft)
Wetted Cas Length (ft)	ing 9.08	One Volu	e Well ume (gals)	2" Well =	1 ·54 = 0.17 gs	al/foot 4	" Well = 0.66 gal/foot
No. of Well			_ Total Pu				
		WELL DEV	ELOPMENT	/PURGII	NG INFO	DRMATIC	ON .
Time	Depth to Water	Gallons Purged	Cumulative Total	T	С	рН	Comments
10 25	5.92	•	0				STARTED PURGE
10 29		1.5	1.5	62	1760		well vol
10 32		1.5	3.0	45	1880		well vol
10 37	7.85	2.0	5.0	66	1920		well vol (STOPPES PURGE
11 20	5.98	0	5.0	slight	PHC	ODOR	COLLECTED SAMPLE
Comments	≥ 85% static	water colum	n < 7 2 % fe	et denti	to wate	er	
		GROUN	D WATER S	AMPLE	INFORM lear loudy	MATION Therr	The second secon
Collection T  Containers		As ( )1 lite	-	500 ml F		Prese quested alyses:	Ervation Other  EPA 8021B EPA 8260B  PAHS PO OTHER
Comments		Sligh		ODOR	_		



07594

Lynn Green



### PETROLEUM RELEASE FORM Please Check All That Apply

-INCIDENT INFORMATION--LOG NBR: (Dept. use only) \_\_\_ RECEIVED BY: (Dept. use only) \_\_\_ DATE REPORTED: (today's date) // Doctor NON-REGULATED UST Thomason SITE ADDRESS: REGULATED UST & FAC NBR:\_\_\_\_\_ HEATING OIL TANK PHONE: SITE COUNTY: MAIL CONTACTS RESPONSIBLE PARTY (person responsible for remedial action) REPORTED BY (person reporting this release to the Dept.) NAME. \_\_ NAME: Lynn Green COMPANY: \_ COMPANY: Tanks-A-Lot, Inc ADDRESS: \_\_\_ ADDRESS: PO Box 80747 ZIP: 97280 CITY: Portland STATE: \_\_\_\_PHONE: \_\_ PHONE: 503-452-5561 STATE: OR Lynng@easystreet.com EMAIL:\_\_\_ OTHER CONTACT(S) (not required) INVOICE CONTACT (required, may be same as responsible party) NAME: \_ NAME: COMPANY: -SITE ASSESSMENT-DATE TANK IS EMPTY: \_\_\_\_/\_ DATE DISCOVERED: \_\_\_/\_\_\_ CAUSE: DISCOVERY: TL) TANK LEAK CONFIRMATION: RM) ROUTINE MONITORING SI) STAFF: DEQ PL) PIPE LEAK DC) DECOMMISSIONING OF) OVERFILL LD) LAB: DEQ CP) COMPLAINT SS) SURFACE SPILL LR) LAB: RP IC) INVENTORY CONTROL PV) PUMP/VALVE LEAK LO) LAB: OTHER SA) SITE ASSESSMENT RR) RP REPORT OT) OTHER TT) TANK TEST UN) UNKNOWN CN) CONTRACTOR OT) OTHER OT) OTHER CONTAMINANTS-OP) OTHER PET. DIST\_ WO) WASTE OIL UG) UNLEADED GASOLINE CH) CHEMICAL\_ HO) HEATING OIL LG) LEADED GASOLINE OT) OTHER LB) LUBRICANT UN) UNKNOWN MG) MISC. GASOLINE SV) SOLVENT DS) DIESEL (motor fuel) -IMPACTS--SW) SURFACE WATER DW) DRINKING WATER GWI GROUNDWATER SL) SOIL FP) FACILITY OR BUILDING (FREE PRODUCT.) FV) FACILITY OR BUILDING (VAPOR) -SITE-MANAGEMENT (THIS SECTION DEPT. USE ONLY)— FINAL REQUEST INVOICE DATE: \_\_\_\_\_/\_\_\_\_ RELEASE STOPPED: \_\_\_\_\_/\_\_\_/ NO FURTHER ACTION: NOTES/COMMENTS: TO1849

## State of Oregon

## Department of Environmental Quality

## Memorandum

To:

File 03-92-0125

Date: September 11, 2002

NW Region Tanks Program

From:

Henning Larsen

**NWR Tanks Program** 

Subject:

File Status

Hand written notes at the bottom of a March 3, 2000 pollution complaint form found in the file indicate the project had been reopened by the DEQ based on the complaint and the involvement of SML Associates in the project. This is incorrect, the project status has not changed since it was closed in January 26, 1998. Re-opening the project was to be based on discussions with the property owners, a review of file information, and a site visit. After doing these tasks, the DEQ ultimately decided not to re-open the project



#### State of Oregon

## Department of Environmental Quality

Memorandum

To:

Andree Pollock

Date: September 3, 2002

Northwest Region Tanks Program Manager

From:

Henning Larsen

Hydrogeologist NWR Tanks Program

Subject:

Meadowbrook Grocery (DEQ File 03-92-0125)

#### **Background:**

In March 2000, the DEQ was notified by Lolita Carter (PGE Environmental Affairs) that a PGE construction crew had observed gasoline contamination in groundwater during the installation of a utility pole at the intersection of Highway 211 and Beaver Creek Road. This utility pole is located in right-of-way immediately west of the Meadowbrook store (UST Facility No. 7673). The facility has had historical releases of gasoline that were first discovered in 1989. A second release was discovered in 1992 during the decommissioning of three USTs located in the northwest corner of the property. 35 tons of contaminated soil were excavated and treated onsite. Confirmation sampling indicated that soil with gasoline contamination as high as 4,900 ppm remained after finishing the excavation work. Following the decommissioning work, three monitoring wells were installed to evaluate the extent of the groundwater contamination. The results of the monitoring indicated low levels of gasoline constituents were present in shallow groundwater. These levels eventually declined to levels below the 5 ppb drinking water standard. In addition, repeated sampling of an on-site public water supply well did not detect the presence of any petroleum contamination. The site was eventually closed in January 1998.

On August 27, 2002, I made a visit to the Meadowbrook store and met with its owner, Don Williams. I discussed with Mr. Williams the notice we had received from PGE, and asked him to show me around the station. Mr. Williams gave me a tour of the UST system which he indicated was "state of the art" with double-walled piping and tanks, line leak detectors, properly sloped trenches, sealed sumps with sensors, secondarty containment beneath the pump islands, and an ATG that performed tightness tests monthly. Mr. Williams indicated his wife reconciled the sales, deliveries, and inventory statistics monthly and had no indication of product losses. I inspected tightness tests printouts from the last four months which indicated the tanks were tight. I consulted with Greg Toran (NWR Compliance) and Greg concurred that the readouts indicated the tanks were tight, but he also pointed out that the paperwork only represented four separate tests of three individual tanks.

During my visit I inspected two of the three groundwater monitoring wells that had been constructed during a previous investigation. The third well was not visible and may have been paved over during the station upgrade. I used a disposable bailer and removed five full bailers of water from each well making visual and olfactory observations of the water quality. MW-3, located due north of the tank nest did not have any observable sheen or petroleum odor and appeared free of contamination. MW-2, located along the east wall of the former tank nest, did

not have a sheen, but did have a slight petroleum odor. A review of historical groundwater monitoring data indicates low levels of BTEX persisted in the well at the time of closure. My observations were consistent with what was reported in SML (Harold Slavik) reports.

Land use around the station, is residential and agricultural. A house is located immediately north of the station property and is owned by the station owner, Don Williams. To the east is a small Christmas tree farm, also owned by Mr. Williams. To the south is a large Christmas tree farm of 30 acres and to the west is a small farm/ranch that looks to be on the order of five to ten acres in size. The nearest structures, aside from the Williams rental home, appears to be approximately five hundred feet from the station property.

Domestic water in the area is supplied from groundwater wells. The Williams use an on-site well to supply the station and the adjacent house. Mr. Williams did not know any details of the construction of his well. The next nearest well appears to be at least five hundred feet to the west.

I reviewed results of previous water sampling of the William's well contained in the DEQ file. Three separate analyses did not detect the presence of petroleum contamination. In addition, I requested that Mr. Williams perform another test on the well which he has done since my site visit. Mr. Williams called on September 4, 2002 to tell me that Coffey Laboratories had verbally indicated the results were non-detect for petroleum contamination.

#### **Overall Assessment**

The observations of the PGE crew indicate the extent of contamination is greater than what had been reported during earlier investigations. The area by the utility pole had not been sampled previously. In general, the extent of soil contamination had never been fully delineated. However, the location of the utility pole is approximately 30 feet from the former tank nest, thus it is not unexpected that residual contamination remains in this area and it is not necessarily evidence that the previous release is significantly more extensive than had been reported or that a new release has occurred.

The monitoring well network shows little evidence of contamination in groundwater. Although, the network is not downgradient of the historical source of contamination at all times of the year it is close in proximity, and is downgradient of the source for the majority of the time. The fact that it is not showing signs of significant contamination suggests the extent of the remaining contamination is very limited.

While the groundwater monitoring at the site was conducted by Harold Slavik, who has since been convicted of falsifying data by the Multnomah DA, my observations were consistent with the conditions reported by Mr. Slavik.

There does not appear to be any evidence that the active UST system is leaking.

There does not appear to be any receptors for the contamination in downgradient areas, and the on-site water well does not appear vulnerable.

#### Recommendations

I recommend that we do not reopen the file without further evidence of a contamination problem. I have discussed the facility with Greg Toran and he indicated that he may put it on his list of facilities to inspect.



Comp	annt
Comp	uiiii

Monday, March 06, 2000 09:08:36 AM

Page 1 of 1

Complaint Number:	NWR-2000-0182	Co	unty: CLACKAMAS					
Date/Time Recv'd:	03/03/2000 11:5	50:00 AM	By: Dan Murphy					
Observed:	03/03/2000 @ 09:5	0						
Source:	Unknown							
Pollution Location:	NW corner of HWY 211 and Meadow Brook Grocery							
	Molalla	99999-						
Description:		ransmission line and	g HWY 211 near Molalla to chor when the backhoe					
Referred to:	Andree Pollock, Ta	nks						
Program:	WMC/T <b>Pro</b>	gram Contact: A	ndree Pollock					
Potential Resp. Party:	Unknown NW corner of HWY Molalla	Y 211 and Meadow OR 99999						
Complainant :	Lolita Carter, PGE'	s Envirn Aff	Confidential? $\Box$					
	OR		Anonymous?					
Phone:	Home:	Work:	(503) 464-8520					
Action Taken:								
Contact Date:		1.0	/1					
Site Visit Date:		Inspector: LA						
Resolution Date:		Resol. Days:	0 Staff Hours: 0					
NON Issue Date:		Enforcement Refe	erral Date:					
Permit No:		Facility/Site ID:						
Entered By:	Dan Murphy	03/06/2000 09:00:	17 AM					
Last Updated By:	Dan Murphy	03/06/2000 09:08:2						
H NOTE: Retur	reved Archive	d files, sid	se reopened, shi u	s en!				
Consi	ultent, pass	ed on to Her	ining Carsen					

3/3/00 @ 11:50 hrs

DEQ Duty Officer contacted by Lolita Carter of PGE's Environmental Affairs Group.

Lolita Carter 464-8520 (possibly also Terry Whorl at 464-8519)

PGE crew was excavating a hole along Highway 211 near Molalla to construct a power transmission line anchor when the backhoe operator encountered gasoline odors. (encountered at 9:50 this morning)

The property easement where the excavation was located is owned by a telephone utility (176 Grange Street; 829-1100).

PGE was excavating an 8 ft x 6 ft x 10 ft deep hole to construct an 8 ft x 6 ft x 10 ft concrete anchor for a power transmission line.

The lower 2 feet of the excavation encountered river rock. Gasoline odors were released when the river rock was exposed.

Site is near the Northwest corner of Hwy 211 and the Meadow Brook Grocery: Grocery is located across Hwy 211.

16835 S Hwy 211, Molalla.

Property is a Christmas Tree farm; Grocery store may have had gasoline tanks.


55 25 13

4/29/92 Gasamo

property owner >

otests 829-9165 "meadowlorook Grocery & Deli 16845 Sthuy 211 Molalla 97238 Utility Company Molalla Telephone Co.

hearby 03-92-0125, close > JAn 1998 f 7673



LUST INCIDENT DATABASE SYSTEM BASIC INCIDENT INFORMATION +----+ To Access the LUST Cost Recovery System, Press ESC-8 LUST Incident Number: 3706 LUST Log Nbr: 03-92-0125 Date Received: 01-MAY-1992 Lead Staff Initials: JEM Facility Number: 7673 Geo Location ID: 23197 Emergency Response? N Regulated Tank? Y Admin Closure? N Petroleum Tank? Heat/Oil Tank? MEADOWBROOK GROCERY Site Name: 16845 Quadrant: SW Street Nbr: Street Name: HWY 211 Street Type: HWY Address: 16845 SW HWY 211 Zip: 97038 Phone: (503)829-9165 | City: MOLALLA County: 03 (CLACKAMAS ) Date Updated: 27-JAN-1998 Updated By: ( OPS\$DXS ) | First two digits of log number are the county code of the release site. <List><Replace> Count: 23

UST Compliance Query
------ Facility ------

Facility ID 7673 SIC LUST facility Y

Facility Name MEADOWBROOK GROCERY Facility Address 16845 SW HWY 211

City, ST Zip MOLALLA OR 97038

Comments

----- Tanks

Tank ID 1 Contents:
Tank Status REMOVED Empty

Date Decomm. 29APR1992 Petroleum GASOLINE

Permit # FFEC Haz. Material

Permit Status TERMINATED Unknown

Lestalled Construction STEEL External Prot PAINTED

Overfill
Leak Detect

Count: 2 v <Replace>

UST Compliance Query

Facility ID 7673 SIC LUST facility Y

Facility Name MEADOWBROOK GROCERY Facility Address 16845 SW HWY 211

City, ST Zip MOLALLA OR 97038

Comments

----- Tanks -----

Tank ID 1A Contents:
Tank Status ACTIVE Empty

Tank Status ACTIVE Empty
Date Decomm. Petroleum GASOLINE

Permit # BEKDE Haz. Material

Permit Status ACTIVE Unknown

Installed 25JUL1997 Construction STEEL lons 12000 External Prot FRP Overfill YES

Overfill YES
Leak Detect BETWEEN WALLS,

Count: 2 ^ v <Replace>

UST Compliance Query
----- Facility -----

Facility ID 7673 SIC LUST facility Y

Facility Name MEADOWBROOK GROCERY Facility Address 16845 SW HWY 211

City, ST Zip MOLALLA OR 97038

Comments

----- Tanks -----

Tank ID 2 Contents: Tank Status REMOVED Empty

Date Decomm. 29APR1992 Petroleum GASOLINE

Permit # FFED Haz. Material

Permit Status TERMINATED Unknown

Installed Construction STEEL Lons 1000 External Prot PAINTED

Overfill Leak Detect

Count: 3 ^ v < Replace>

UST Compliance Query
----- Facility -----

Facility ID 7673 SIC LUST facility Y

Facility Name MEADOWBROOK GROCERY Facility Address 16845 SW HWY 211

City, ST Zip MOLALLA OR 97038

Comments

----- Tanks -----

Tank ID 2A Contents:
Tank Status ACTIVE Empty

Date Decomm. Petroleum GASOLINE

Permit # BEKDF Haz. Material

Permit Status ACTIVE Unknown

Lestalled 25JUL1997 Construction STEEL lons 6000 External Prot FRP YES

Leak Detect BETWEEN WALLS,

Count: 4 ^ v <Replace>

UST Compliance Query
----- Facility

Facility ID 7673 SIC LUST facility Y Facility Name MEADOWBROOK GROCERY

Facility Address 16845 SW HWY 211

City, ST Zip MOLALLA OR 97038

Comments

----- Tanks -----

Tank ID 2B Contents:
Tank Status ACTIVE Empty

Date Decomm. Petroleum DIESEL

Permit # BEKDG Haz. Material

Permit Status ACTIVE Unknown

Installed 25JUL1997 Construction STEEL External Prot FRP

Overfill YES

Leak Detect BETWEEN WALLS,

Count: 5 ^ v <Replace>

UST Compliance Query ----- Facility -----

LUST facility Y Facility ID 7673 SIC

Facility Name MEADOWBROOK GROCERY Facility Address 16845 SW HWY 211

City, ST Zip MOLALLA OR 97038

Comments

. , . . .

----- Tanks -----

Contents: Tank ID Tank Status REMOVED Empty Petroleum

Date Decomm. 29APR1992 GASOLINE


Haz. Material Permit # FFEE

Permit Status TERMINATED Unknown


Installed Construction STEEL 550 External Prot PAINTED llons

Overfill Leak Detect

<Replace> Count: \*6



Owner :Low Joseph T & Zola L Site :\*No Site Address\* Parcel :01084533 Ref Par :R52E02A 00100 Mail :20006 S Unger Rd Beavercreek Or 97004
Use :640 Vacant, Forest Land Xferd : Tot AV :\$11,180 MapGrid: Price: Bedrm: Bth: YearBlt:1900 BldgSF: Acres:30.15 \*----: MetroScan / Clackamas :-----\* Owner :Molalla Telephone Co
Site :\*No Site Address\*
Mail :PO Box 360 Molalla Or 97038 Parcel :01084542 Ref Par :R52E02A 00200 Xferd :
Tot AV : :003 Misc, Centrally Assessed Price : Acres: MapGrid : Price :\$136,800 ,475 Acres:4.57 MapGrid : Bth:2.00 YearBlt:1993 BldgSF:1,475 Bedrm: 3



MetroScan / Clackamas

 Gwner:
 :Hart Arlen & Mary
 Parcel
 :01603429

 Site
 :16789 S Union Mills Rd Mulino 97042
 Ref Par
 :R42E35 02704

 Mail
 :PO Box 1234 Canby Or 97013
 Xferd
 :11/01/1990

 Use
 :641 For, Forest Land, Improved
 Tot AV
 :\$175,560

 MapGrid
 Price
 :\$195,000

 Bedrm:
 Bth:2.00
 YearBlt:1993
 BldgSF:2,463
 Acres:8.95

```
*-----*
Owner . :Bue Robert L Trustee

Parcel .01083856
                                                      Parcel :01083856
Ref Par :R52E01B 00100
Xferd :12/12/1997
Tot AV :$840
Price :
  Site :*No Site Address*
  Mail :
Use :640 Vacant, Forest Land
  MapGrid :
                                               Parcel :01083865
Ref Par :R52E01B 00200
  Owner : Monroe William A & Beverly J
  Site
         :*No Site Address*
                                                      Xferd :09/12/1997
7 Mail
                                                      Tot AV :$34,440
  Use :100 Vacant, Residential Land
                                                      Price :$70,000
  MapGrid :
  Bedrm: Bth: YearBlt:1900 BldgSF:
                                                             Acres:2.37
  *----: MetroScan / Clackamas :-----
Owner :Monroe Douglas P & Geraldine L Parcel :01083874
Site :17217 S Monroe Ln Mulino 97042 Ref Par :R52E01B 00300

Mail :17217 S Monroe Ln Mulino Or 97042 Xferd :02/29/1996
Use :401 Tract,Tract Land,Improved Tot AV :$409,480
                                                      Price :
  MapGrid :
  Bedrm: 4 Bth: 3.50 YearBlt: 1997 BldgSF: 3,856 Acres: 4.99
  *-----* MetroScan / Clackamas :------*
  Owner : Conn Steven E & Lollie J
                                               Parcel :01083883
  Mail :17109 S Highway 211 Molalla Or 97038 Xferd :09/01/1997
Use :101 Res,Residential Land,Improved Tot AV :$18,320
MapGrid :
Bedrm: R+h.
  Owner :Alford Dorman Otto & Haruko Parcel :01083892
Site :17200 S Monroe Ln Mulino 97042 Ref Par :R52E01B 003
Mail :17200 S Monroe Ln Mulino Or 97042 Xferd :12/01/1991
Use :101 Res,Residential Land,Improved Tot AV :$240,420
                                                     Ref Par :R52E01B 00302
  MapGrid :
                                                      Price :
  Bedrm:3 Bth:2.00 YearBlt:1995 BldgSF:1,654 Acres:1.15
*----: MetroScan / Clackamas :-----
  Parcel :01083918
Ref Par :R52E01B 00500
  Owner :Robertson David S
Site :*No Site Address*
  Mail :17053 S Highway 211 Molalla Or 97038
Use :100 Vacant, Residential Land
                                                      Xferd :05/01/1995
Tot AV :$17,630
Price :$19,000
Acres:2.01
  MapGrid :
  Bedrm: Bth: YearBlt:1900 BldgSF: Acres:2.01

*-----: MetroScan / Clackamas :-----*
  Parcel :01083936
   Owner :Hines Teresa
  Ref Par :R52E01B 00601
```

```
*----- MetroScan / Clackamas
Owner : Hopkins Larry M & Martha O
Site :17100 S Monroe Ln Mulino 97042
                                                               Parcel :01083945
                                                              Ref Par :R52E01B 00602
Mail :17100 S Monroe Ln Mulino 9/042
Use :101 Res, Residential Land, Improved
                                                               Xferd :02/28/1996
Tot AV :$92,930
Price :$127,000
24 Acres:1.46
 MapGrid :
                                YearBlt:1990 BldgSF:924
 Bedrm:
                Bth:
 *----: MetroScan / Clackamas :-----*
                                                              Parcel :01083954
Ref Par :R52E01B 00603
 Owner : Holman Paul B Trustee
 Site
         :*No Site Address*
 Mail
                                                               Xferd :04/09/1998
         :101 Res, Residential Land, Improved
                                                               Tot AV
                                                                         :$10,020
Use
                                                               Price
 MapGrid :
                                                                         :
                                YearBlt:1900 BldgSF:
                                                                        Acres:1.91
 Bedrm:
 *-----: MetroScan / Clackamas :------
                                                            Parcel :01083963
 Owner :Lehman James W & Evelyn
 Site :*No Site Address* Ref Par :R
Mail :30000 S Beavercreek Rd Mulino Or 97042 Xferd :
Use :101 Res,Residential Land,Improved Tot AV :$
                                                               Ref Par :R52E01B 00700
                                                               Tot AV :$5,370
                                                               Price :
 MapGrid :
 Owner :Country Ch Inc Nondenomintl Parcel :01083972
Site :16915 S Highway 211 Molalla 97038 Ref Par :R52E01B 00'
Mail :16915 S Highway 211 Molalla Or 97038 Xferd :09/08/1995
Use :100 Vacant, Residential Land Tot AV :$47,110
                                                             Ref Par :R52E01B 00701
 MapGrid :807 J6
                                                               Price :$85,000
 Acres:1.02
 Owner :Hess Martin A & June M Parcel :01083981
Site :29900 S Beavercreek Rd Mulino 97042 Ref Par :R52E01B 007
Mail :29900 S Beavercreek Rd Mulino Or 97042 Xferd :07/01/1989
Use :101 Res,Residential Land,Improved Tot AV :$146,270
                                                              Ref Par :R52E01B 00702
 Mail :29900 S Beavercreek Rd Mulino Or 97042
Use :101 Res, Residential Land, Improved
 MapGrid:

Bedrm: 2 Bth: 1.00 YearBlt: 1970 BldgSF: 1,560 Acres: .76

*-----: MetroScan / Clackamas :------*
                                                        Parcel :01083990
Ref Par :R52E01B 00703
 Owner :Hess Martin A & June M
         :*No Site Address*
 Site
 Site :*No Site Address*
Mail :29900 S Beavercreek Rd Mulino Or 97042
Use :100 Vacant, Residential Land
                                                              Xferd :07/01/1989
Tot AV :$15,970
 MapGrid:

Bedrm: Bth: YearBlt:1900 BldgSF: Acres:1.65

*----: MetroScan / Clackamas :------
 Owner :Monroe Douglas P/Geraldine L Parcel :01084007
Site :17173 S Monroe Ln Mulino 97042 Ref Par :R52E01B 00704
 Mail :17217 S Monroe Ln Mulino Or 97042
Use :401 Tract, Tract Land, Improved
                                                               Xferd :04/05/1999
Tot AV :$138,860
                                                                         :$138,860
 Parcel :01084016
 Owner :Lehman James W & Evelyn
 Site :*No Site Address*
Mail :30000 S Beavercreek Rd Mulino Or 97042
Use :101 Res, Residential Land, Improved
                                                               Ref Par :R52E01B 00705
                                                              Xferd
                                                              Tot AV :$19,930
 MapGrid :
 Owner :The Country Church Inc Parcel :01084025
Site :16975 S Highway 211 Molalla 97038 Ref Par :R52E01B 00706
Mail :16975 S Highway 211 Molalla Or 97038 Xferd :
Use :401 Tract, Tract Land, Improved Tot AV :$1,139,740
 MapGrid :
                                                              Price :
                         YearBlt:1976 BldgSF:
                                                                        Acres:6.12
```

Bedrm:

Bth:

```
*----- MetroScan / Clackamas
Owner : :Berget Antoinette

Site :29970 S Beavercreek Rd Mulino 97042 Ref Par :KDZEUID CO
Mail :29970 S Beavercreek Rd Mulino Or 97042 Xferd :05/31/1996
Use :101 Res,Residential Land,Improved Tot AV :$130,260

MapGrid : Price :$145,900

Acres:1.25
. Owner . :Berget Antoinette
                                                         Ref Par :R52E01B 00707
 *-----: MetroScan / Clackamas :------
 Owner :Lehman James W & Evelyn
                                                      Parcel :01084052
 Site :*No Site Address*
                                                           Ref Par :R52E01B 00708
 Mail :30000 S Beavercreek Rd Mulino Or 97042
Use :101 Res, Residential Land, Improved
                                                           Xferd
         :101 Res, Residential Land, Improved
                                                                   :$1,770
                                                           Tot AV
                                                           Price :
 MapGrid :
 Bedrm: Bth: YearBlt:1900 BldgSF:
                                                                   Acres:.19
 *----: MetroScan / Clackamas :------
 Owner : Taylor Teddi A Trustee
                                                   Parcel :01084061
 Site :17270 S Hallbacka Ln Mulino 97042
                                                           Ref Par :R52E01B 00710
 Mail :PO Box 1163 Mulino Or 97042
Use :101 Res, Residential Land, Improved
                                                           Xferd :03/01/1995
                                                                  :$73,310
                                                           Tot AV
                                                           Price
 MapGrid :
                                                                  Acres:
                       YearBlt:1900 BldgSF:
 Bedrm: Bth:
 *-----: MetroScan / Clackamas :-----*
                                                        Parcel :01084070
 Owner :Ellington Carol E
Site :17050 S Monroe Ln Mulino 97042

Mail :17050 S Monroe Ln Mulino Or 97042

Use :101 Res, Residential Land, Improved
                                                           Ref Par :R52E01B 00713
                                                           Xferd :02/15/1996
                                                           Tot AV :$77,260
                                                           Price :$95,000
 MapGrid :
 Bedrm: Bth:
 Owner :Williams D L & Marjorie M
Site :16845 S Highway 211 Molalla 97038
                                                          Parcel :01084089
                                                          Ref Par :R52E01B 00800
 Mail :16845 S Highway 211 Molalla Or 97038
Use :201 Com, Commercial Land, Improved
                                                          Xferd :05/01/1997
Tot AV :$275,740
 MapGrid :807 J6
                                                           Price :$345,000
                             YearBlt:1957 BldgSF:
                                                                   Acres:1.32
 Bedrm: Bth:
 *----: MetroScan / Clackamas :-----
         :30000 S Beavercreek Rd Mulino 97042 Ref Par . P52F01P C
 Owner :Lehman James W & Evelyn P
                                                          Ref Par :R52E01B 00801
                                                      Xferd
 Mail :30000 S Beavercreek Rd Mulino Or 97042
Use :101 Res, Residential Land, Improved
                                                          Tot AV :$152,400
 MapGrid: Price: Bedrm:3 Bth:1.00 YearBlt:1971 BldgSF:1,320 Acres:.71
                                                          Price :
 *----: MetroScan / Clackamas :-----
                                                    Parcel :01084105
Ref Par :R52E01B 00900
 Owner : Holman Paul B & Reina V
         :17045 S Highway 211 Molalla 97038
 Site
 Mail :17045 S Highway 211 Molalla 9/038

Use :101 Res, Residential Land, Improved

MapGrid :
                                                           Tot AV .s
                                                                    :$167,520
                                                           Price : Acres:1.60
 MapGrid: Price: Bedrm:3 Bth:2.00 YearBlt:1970 BldgSF:1,658 Acres:1.60 *-----: MetroScan / Clackamas :------*
 Owner :Robertson David S & Carole A
Site :17053 S Highway 211 Molalla 97038
Mail :17053 S Highway 211 Molalla Or 97038
Use :101 Res,Residential Land,Improved
 Owner : Robertson David S & Carole A
                                                   Parcel :01084114
                                                       Ref Par :R52E01B 01000
                                                          Xferd :05/15/1992
Tot AV :$167,520
                                                          Price :$4,000
2,752 Acres:1.87
 MapGrid :
 Bedrm: 3
 Owner :Krupicka Joseph F & Virginia Mae Parcel :01084132
Site :17105 S Highway 211 Molalla 97038 Ref Par :R52E01B 01200
Mail :17105 S Hwy #211 Molalla Or 97038 Xferd :
Use :101 Res,Residential Land.Improved
                                                         Ref Par :R52E01B 01200
                                                          Price :
 MapGrid :
           Bth:1.00 YearBlt:1948 BldgSF:1,420 Acres:.50
```

Bedrm: 3

```
*---: MetroScan / Clackamas
Owner . :Conn Steven E & Lollie J
 Owner : Conn Steven E & Lollie J Parcel
Site :17109 S Highway 211 Molalla 97038 Ref Par
Mail :17109 S Highway 211 Molalla Or 97038 Xferd
Use :101 Res,Residential Land,Improved Tot AV
                                                                        Parcel :01084141
                                                                     Ref Par :R52E01B 01300
                                                                                    :09/10/1997
                                                                        Tot AV :$112,230
                                                                        Tot A.
Price :
Acres:.78
 MapGrid:
Bedrm:1 Bth:1.00
  Owner :Alford Dorman O & Haruko Parcel :01084169
Site :17115 S Highway 211 Molalla 97038 Ref Par :R52E01B 01500
Mail :17200 S Monroe Ln Mulino Or 97042 Xferd :05/01/1994
Use :101 Res,Residential Land,Improved Tot AV :$100,440
MapGrid : Price :$53.000
 Owner :Hutchinson William Trustee
Site :17129 S Highway 211 Molalla 97038 Ref Par :K5ZE01D 01
Mail :PO Box 591 Molalla Or 97038 Xferd :02/01/1999
101 Res,Residential Land,Improved Tot AV :$152,250
Price :
Acres:1.00
                                                                        Ref Par :R52E01B 01600
 Bedrm: 2 Bth: 1.00 YearBlt: 1964 BldgSF: 1,618 Acres: 1.00
  *-----: MetroScan / Clackamas :-----*
 Owner :Morris Athalie Parcel :01084187
Site :17135 S Highway 211 Molalla 97038 Ref Par :R52E01B 01700
Mail :17135 S Highway 211 Molalla Or 97038 Xferd :
Use :101 Res,Residential Land,Improved Tot AV :$159,820
MapGrid : Price :
 Bedrm: 4 Bth: 1.50 YearBlt: 1961 BldgSF: 1,920 Acres: 1.90
  *----: MetroScan / Clackamas :-----

      Owner
      :Donnell Larry R & Lois E
      Parcel
      :01084196

      Site
      :17165 S Highway 211 Molalla 97038
      Ref Par
      :R52E01B 01800

      Mail
      :17165 S Highway 211 Molalla Or 97038
      Xferd
      :12/01/1979

      Use
      :101 Res, Residential Land, Improved
      Tot AV
      :$110,030

 Owner :Bohlander John E Trustee
Site :*No Site Address*
Mail :1326 Oppek St NE Salem Or 97303
Use :100 Vacant, Residential Land
                                                                        Parcel :01084203
Ref Par :R52E01B 01900
                                                                        Xferd :12/01/1992
Tot AV :$54,830
 Price :$26,000
Acres:1.83
 Site :17245 S Highway 211 Molalla 97038 Ref Par :R52E01B 02000 Mail :17245 S Hwy #211 Molalla Or 97038 Xferd : 101 Res, Residential Land, Improved Tot AV :$101,950 MapGrid :
 Owner :Bue Robert L Trustee Parcel :01084230
Site :17400 S Highway 211 Molalla 97038 Ref Par :R52E01B 02100

Mail :17400 S Highway 211 Molalla Or 97038 Xferd :12/12/1997
Use :641 For, Forest Land, Improved Tot AV :$70,720
                                                                         Price :
  MapGrid :
                  Bth:1.00 YearBlt:1956 BldgSF:864 Acres:11.08
```

Bedrm: 2

MetroScan / Clackamas

\*----: MetroScan / 0
Owner :Schiewe Rosalee & William P
Site :17399 S Highway 211 Molalla 97038
Mail :17445 S Highway 211 Molalla Or 97038
Use :641 For, Forest Land, Improved

Parcel :01084249 Ref Par :R52E01B 02200 :11/01/1987 Xferd

Tot AV :\$6,870 Price :\$10,000 Acres:3.27

MapGrid :

Bedrm:

YearBlt:1900 Bth:

BldgSF:



January 26, 1998

TONI AND JACK FRISON BOX 1535 CRR TERREBONNE OREGON 97760 DEPARTMENT OF ENVIRONMENTAL

QUALITY

NORTHWEST REGION

Re: Meadow Brook Grocery

File No. 03-92-0125 Facility ID. No. 7636

Dear Toni and Jack:

The Department of Environmental Quality has completed its review of the information submitted to date concerning the underground storage tank (UST) decommissioning and cleanup conducted at 16845 Highway 211 in Molalla, Oregon. The Department has determined that the cleanup appears to have met the requirements of Oregon Administrative Rules (OAR) 340-122-205 through 340-122-360 and that no further action is required at this time.

This determination is a result of our evaluation and judgment based on the regulations and facts as we now understand them, including:

- 1. A 550, a 1,000 and a 2,000 gallon UST were decommissioned at this location. The tanks were recycled at Schnitzer Steel Products in Portland, Oregon.
- 2. Gasoline contamination was discovered during the decommissioning. Approximately 38 tons of contaminated soil were excavated and treated onsite. After treatment was complete, no gasoline was detected remaining in the soil. The soil was spread out onsite and covered with clean fill.
- 3. After excavation of contaminated soil was complete, up to 4,900 parts per million (ppm) gasoline was detected remaining in the soil. In addition, gasoline constituents were detected in the groundwater.
- 4. To address the remaining soil and groundwater contamination, three monitoring wells were installed. Benzene was the only contaminant of concern to be detected in the groundwater above its cleanup standard (5 parts per billion (ppb)). The maximum concentration of Governor benzene detected in the wells was 64 ppb.
- 5. Four consecutive quarters of compliance monitoring have been conducted pursuant to OAR 340-122-242. During these last four quarters of sampling, a maximum of 4 ppb benzene was detected.

2020 SW Fourth Avenue Suite 400 Portland, OR 97201-4987 (503) 229-5263 Voice TTY (503) 229-5471

DEQ-1

Toni and Jack Frison January 26, 1998 Page 2

The Department's approval to leave soil contamination is based on the site conditions described in the report as they exist today. Should any contaminated soil be excavated in the future, the Department must be notified and the soil taken to an permitted treatment or disposal facility. You are also responsible for notifying potential purchasers of the property about this remaining contamination.

The Department's determination will not be applicable if new or undisclosed facts show that the cleanup does not comply with the referenced rules. The Department's determination also does not apply to any conditions at the site other than the release of the petroleum product specifically addressed in the report(s).

Please note that pursuant to OAR 340-122-360(2), a copy of your report must be retained until ten (10) years after the first transfer of the property. We recommend that a copy of this information be kept with the permanent facility records.

Your efforts to comply with the regulations to ensure that your facility has been adequately cleaned up have been appreciated. If you have any questions, please feel free to contact me at (503) 229-5474.

Sincerely,

Andree Pollock

UST Cleanup Specialist

el Pollack

cc:

Don and Margie Williams Meadow Brook Grocery P.O. Box 388 Colton, Oregon 97017

(avp:AVP)

#### SML Associates Inc.

CCB # 120112 1774 Sunset Ave. West Linn, Oregon 97068 (503) 656-3625 Fax: 656-3627 DEPT OF ENVIRONMENTAL QUALITY RECEIVED

OCT 0 8 1997.

NORTHWEST REGION

October 7, 1997

Mr. Rick Silverman Oregon Department of Environmental Quality Northwest Region, UST Section 2000 SW Fourth Ave., Suite 400 Portland, Oregon 97201 (503) 229-5477

Re: Quarterly groundwater monitoring, Meadowbrook Grocery, 16845 S. Hwy. 211, Molalla, Oregon. DEQ file #03-92-125

Dear Mr. Silverman:

This letter and the accompanying documents presents the results of the most recent groundwater monitoring for the above named property, as outlined in the modified CAP.

#### Background

Prior to sampling the total depth and depth to groundwater was measured in each well using a Solinst 100 interface probe. This information was recorded on a sampling event data sheet, one of which was recorded for each well. Copies of the data sheets are attached. The probe was decontaminated before and between each measurement by washing in tap water and Alconox, a biodegradable laboratory cleaner and degreaser, and rinsing in fresh tap water.

#### Sample Collection

The measurements obtained were used to calculate the well volume so that at least three volumes were purged prior to sampling. Purging was accomplished utilizing an ES-60 Purger submersible pump. Purged water was placed in individual, dedicated 55 gallon, DOT approved drums. Each drum was labeled with the monitoring well number and stored in a secured area between the store and the Frison home. The pump and tubing were decontaminated before and between sample events by submergence in a tap water and Alconox solution and flushing approximately five gallons through the pump and tubing. They were then flushed with approximately five gallons of tap water. The flushed water and Alconox solutions were placed in the appropriate 55 gallon drum.

The samples were collected in three laboratory supplied 40 ml VOA bottles. The samples were immediately refrigerated, information recorded on a chain of custody and hand delivered to the laboratory within 24 hours. Copies of the chain of custody and the analytical results are attached.

#### Groundwater Flow Direction

On August 12, 1995 the wells were surveyed by a registered surveyor. A copy of his survey was submitted with the first monitoring report. Utilizing the information from the survey and the measurement data collected during sampling, the groundwater flow direction for this sampling event has been determined to be to the northwest, specifically N. 56° W. A copy of the determination is attached.

#### Analytical Results and Recommendations

The results of the current and previous sampling are presented in Table 1. Results indicate levels in all three wells have continued below regulatory compliance limits for a full hydrogeological cycle. Very slight fluctuations in constituents, we believe, may be the result of seasonal high groundwater encountering a very small residual pocket of hydrocarbons. Groundwater flow direction, as will be seen in previous reports, is generally to the north-northwest. Reversals in flow direction, we believe, may be due to groundwater usage at a nearby Christmas tree farm. A groundwater reversal has occurred on three occasions during the nine quarters we have been monitoring.

The dissolved lead levels during the first monitoring event were well below the drinking water standards. Therefore, with your verbal approval, we have discontinued the lead analysis. Based upon the foregoing, on behalf of the Frison's we respectfully request a letter of No Further Action be issued. When the letter is received we will proceed with well abandonment according to Department of Water Resources regulation.

Sincerely,

SML Associates, Inc.

Harold J. Slavik, Jr., PG

President

for

Toni Frison


encs.

Table 1

#### Groundwater Analytical Results Meadowbrook Grocery 16845 So. Highway 211 Molalla, Oregon

Results are presented, in parts per billion (ppb), as benzene / toluene / ethylbenzene / xylenes. ND means below instrument detection limits (<2 ppb).

Sample Date	MW-1	MW-2	MW-3
July 26, 1995	7 / 4 / 98 / 190	26 / 36 / 110 / 390	ND/ND/2/5
November 1, 1995	7 / 7 / 120 / 220	64 / 220 / 520 /2200	6 / 15 / 36 / 150
February 15, 1996	14 / 13 / 140 / 260	25 / 35 / 150 / 1000	10 / 8 / 29 / 150
May 11, 1996	7 / 4 / 47 / 45	10 / 7 / 47 / 94	ND / ND / ND /ND
September 4, 1996	4/3/14/16	7/4/9/16	ND / ND / ND/ ND
December 6, 1996	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND
March 6, 1997	ND/ ND/ 32/ 35	4/ 7/ 56/ 160	ND/ ND/ ND/ ND
June 14, 1997	ND/ ND/ ND/ ND	2/ ND/ 15/ 23	ND/ ND/ 22/ 21
September 21, 1997	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND



# SAMPLING EVENT DATA SHEET (fill out completely)

WELL OR LOCATION MW-/

95-044 PROJECT Meadow	brook EV	ENT Oth	/y SAMP	LER <u>H</u>	Slavi.	L DATE 9/	21/97
Well / Hy	drologic statist	1	Actio	on	Time	Pump rate	IWL (low yield)
	Wellty	MW MW	Start pump	/ Begin	1230	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
	(MW, E	W, etc.)		7	e deservice		
				2 8			
	d (diamet	ver $\frac{2^{11}}{0.16^3}$ gal/ft. casing					
	diamete					1 1 1 no	
(if above screen)			ing				
		$\sim$	Stop		1240		
packer intake bailer depth (circle one)			Sampled		1245		
bailer depth (circle one)		TOP	(Final IWL)				
		TOP	0,163 avri	. 9,36	Purge ca	B gals x 3 = 4	59 gals.
SWL			1 1 -	WL to BOF	$\sim$		e volume-
(if in screen)			Р	acker to BO	OP volu		casings
		ВОР		Head pu	irge calcu	ulation (Airlift	only)
measured 14,54		T.D. (as built)	gal/	ft. *	ft. =	gals.	
T.D. <u>17,37</u>		1.D. (as built)	1 -	packer to	SWL		
Equipment Used / San	npling Method / D	escription of Ev	rent:	Actual g	allons pur	ged <u>5</u>	
See A	$1\omega-3$	sheet		Actual vo	olumes pu	rged $\frac{3}{}$	<u>+</u>
				Well yiel			
				coc	# _		
						Analysis	Lab
Additional comments:		- XY - X					
					_		
				-	<u> </u>		
Gallons purged *	TEMP °C / °F (circle one)	EC (µs / cm)	PH	TURBIC (NTU			
1.		e w					
2.							
3.			3.7				
4.							
5.							
* Take measurement at approximately each casing volume purged.	⊕ <u>HY-</u> Minimal W.L. drop		luring one sitting ng pump rate or		to purge 3 es by retur or next day.	ning una	mal recharge - ble to purge olumes.

# SAMPLING EVENT DATA SHEET

(fill out completely)

WELL OR LOCATION MW-2

PROJECT Meadow brook EVENT Otrly SAMPLER H. Slavik DATE 9/21/97								
	drologic statistic		Actio	ח	Time	Pump rate	IWL (low yield)	
	Well type (MW, EV	y, etc.)	Start pump	/ Begin	1150			
SWL (if above screen)	- d - { diamete	7.163 gal/ft. casing	Stop		1210.			
packer intake bailer depth) 5,47 ft.			Sampled (Final IWL)	14 14 14 14 14 14 14 14 14 14 14 14 14 1	1215			
SWL————————————————————————————————————		OP	Purge calculation  0.163 gal/ft. • 7.8   ft. = 1.27 gals x 3 = 3.8   gals.  SWL to BOP or one purge volume- packer to BOP volume 3 casings					
measured <u>13,28</u> T.D.		C.D. (as built)	gal/		ft. =			
Equipment Used / Sam				Actual gallons purged 5				
See 1	1	Actual volumes purged 3, 3  Well yield ① (see below)						
				COC Sample		Analysis	Lab	
Additional comments:								
Gallons purged *	TEMP °C /°F (circle one)	EC (µs / cm)	PH	TURBII (NT				
1.								
2.								
3.			· ·	N 1			ar ve	
4.*								
5.				A 2 2				
* Take measurement at approximately each casing volume purged.	⊕ <u>HY-</u> Minimal W.L. drop	MY - WL drop - ab volumes duri by reducing p cycling pump	ng one sitting oump rate or	volur	to purge 3 nes by retu or next day	irning un	nimal recharge - able to purge rolumes.	

## SAMPLING EVENT DATA SHEET

(fill out completely) WELL OR LOCATION MW-3 PROJECT\_Meadowbrook EVENT Otale SAMPLER H. Slavik DATE IWL Pump rate Time Action Well / Hydrologic statistics (low yield) Well type MW (MW, EW, etc.) Start pump / Begin 1110 diameter  $2^{\prime}$ (if above screen) 1130 Stop Sampled packer (Final IWL) intake bailer depth (circle one) Purge calculation 0.163 gal/tt. • 7.69 ft. = 1.25 gals x 3 = 3.75 gals. purge volume-SWL to BOP or one packer to BOP volume 3 casings (if in screen) Head purge calculation (Airlift only) - BOP gal/ft. \* \_\_\_\_\_ft. = \_\_\_\_\_gals. measured /3,49 packer to SWL Equipment Used / Sampling Method / Description of Event: Actual gallons purged ES-60 purser pump disposable deflon bailers 100' Soliust probe Actual volumes purged  $\oplus$ Well yield (see below) COC # Lab Sample I.D. Analysis Additional comments: TEMP °C /°F TURBIDITY PH EC Gallons purged \* (NTU) (circle one) (µs / cm) 1. 2. 1 3. 4. 5. VLY - Minimal recharge -LY - Able to purge 3 MY - WL drop - able to purge 3 ⊕ HY- Minimal Take measurement at unable to purge volumes by returning volumes during one sitting W.L. drop 3 volumes. approximately each 'later or next day. by reducing pump rate or

cycling pump.

casing volume purged.

Meadowbrook Groc.

Sampling GW Flow

Calculation 9/21/97

$$-6.78 \text{ Low}(A)$$

$$MW-3$$

$$(-0.98)$$

$$N$$

$$-6.61 \text{ High}(B)$$

$$MW-2$$

$$(-1.14)$$

$$-6.69 \text{ Med}(c)$$

$$med-low = \frac{BE}{AB}$$

$$(-6.69)-(-6.78) = \frac{K}{22.87}$$

$$(-6.61)-(-6.78) = \frac{K}{22.87}$$

$$0.53(22.87) = 12.12$$

요즘 아이들이 얼마를 가는 것이 되었다.	
Oregon 14855 S.W. Old Scholls Ferry Rd.  Analytical Beaverton, Oregon 97007 (503) 590-5300  FAX (503) 590-1404	CHAIN OF CUSTODY RECORD NO 5272 Page of LABORATORY ANALYSIS REQUEST
Company Meadowbrook Grocery Contact Toni Frison	Project Name Mealow brook Groc, Sampler's Name Harold Slavik
Contact Youi Frison	Project Number 95-044 Signature N. S. Slavet For,
Contact 1801 171300	P.O. Number Sampling Date
Address OX 1555 CTT	Comments Send / Fox copy results Provide Verbal Results 1 Yes No
Phone # (541) 504-875/ FAX # (503) 656-362	P.O. Number  Comments Send Fox cap results  Provide Verbal Results  Provide FAX Results  Yes No  Provide FAX Results  ANALYSES
Priorie # (3 77) 507 6727 1700 (303) 450	ANALISES NI / 2 minutes
Sample Identification Date Time OAL#	Soil  Water Other (Note in Remarks)  Volatiles 624/8260 (circle) All Aromatic Halogenated Semivolatiles 625/8270 (circle) All Aromatic Halogenated Semivolatiles 625/8270 (circle) All PAHSIM) Phenol Phthalate Organochlorinateds 608/8080 All PCB Pesticide (circle) Chlorinated Herbicides 8150 TPH-HCID OR-DEQ Quantification (circle) G D 418.1M 418.1 G D 418.1M 418.1  BTEX 602/8020 TCLP Metals As Ba Cd Cr Pb Hg Se Ag TCLP Organics (circle) Vol Semivol Pest Herb Netals Dissolved DTotal List  AT T  West Herb Se Ag Semivol Pest Herb Semivol Pest Herb Semivol Pest Herb Semivol Pest Herb Semivol Semivol Pest Herb Semivol Semivol Dissolved DTotal Semivol Semivol Pest Herb Semivol Semivol Pest Herb Semivol Semivol Pest Herb Semivol Semivol Dissolved DTotal Semivol Semivol Pest Herb Semivol Semivol Dissolved DTotal Semivol Semivol Dissolved DTotal Semivol Semivol Pest Herb Semivol S
1 MW 3-9 1/35 13532-1	3 × M
2 MW 2-9 / 215 -2	3 ×
3 MW 1-9 1235 -3	3 X V
4	
5	
6	
7	
10	
Company L Associates, Tuc,  Signature  Signature  Signature	Received @ °C  Appropriate Containers Yes \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
Print Name	Name India Hogon 12:35 Glass Bottles other





Sample ID	Lab#	Matrix		Sampled	Received
MW 3-9	L3532-1	water		09/21/97 11:35	09/22/97
MW 2-9	L3532-2	water		09/21/97 11:35	09/22/97
MW 1-9	L3532-3	water		09/21/97 11:35	09/22/97

# **Definition of Terms**

ND Analytical result was below the reporting limit.



Client: Meadowbrook Grocery

Contact: Toni Frison

Printed on recycled paper

# **BTEX** by EPA 8020

Sample ID	Matrix					Lab Number
Analyte	e	Result	Reporting Limit	Units (ppb)	Comment	1 1
					Sampled: 09/21/97	
MW 3-9	Water				Analyzed: 09/25/97	L3532-1
Benzen	e	ND	2.	μg/L		
Ethylbe	nzene	ND	2.	μg/L		
	9		2.	μg/L		
Total Xy	ylenes	ND	2.	μg/L		
		Surrogate			Recovery Limit	
		Bromofluorobenze	ene		90.% 50 150.	

MW 2-9	) Water						d: 09/21/97 d: 09/25/97	L3532-2
	Benzene		ND	2.	μg/L			
	Ethylbenzene			2.	μg/L			
	Toluene.		ND	2.	μg/L			
	Total Xylenes		ND	2.	µg/L			
		Surrogate Bromofluoro	benzene			Recovery 98.%	Limit 50 150.	

MW 1-9 Water				Sampled: Analyzed:		L3532-3
Benzene	ND	2.	μg/L			
Ethylbenzene	ND	2.	μg/L			
	ND	2.	μg/L			
Total Xylenes	ND	2.	µg/L			
Surrogate Bromofluorob	enzene			Recovery 99.%	Limit 50 150.	

### OREGON ANALYTICAL LABORATORY

#### SML Associates Inc.

CCB # 120112 1774 Sunset Ave. West Linn, Oregon 97068 (503) 656-3625 Fax: 656-3627

DEPT OF ENVIRONMENTAL QUALITY RECEIVED

JUN 2 3 1997

June 18, 1997

NORTHWEST REGION

Mr. Rick Silverman
Oregon Department of Environmental Quality
Northwest Region, UST Section
2000 SW Fourth Ave., Suite 400
Portland, Oregon 97201
(503) 229-5477

Re: Quarterly groundwater monitoring, Meadowbrook Grocery, 16845 S. Hwy. 211, Molalla, Oregon. DEQ file #03-92-125

Dear Mr. Silverman:

This letter and the accompanying documents presents the results of the most recent groundwater monitoring for the above named property, as outlined in the modified CAP.

# **Background**

Prior to sampling the total depth and depth to groundwater was measured in each well using a Solinst 100 interface probe. This information was recorded on a sampling event data sheet, one of which was recorded for each well. Copies of the data sheets are attached. The probe was decontaminated before and between each measurement by washing in tap water and Alconox, a biodegradable laboratory cleaner and degreaser, and rinsing in fresh tap water.

## Sample Collection

The measurements obtained were used to calculate the well volume so that at least three volumes were purged prior to sampling. Purging was accomplished utilizing an ES-60 Purger submersible pump. Purged water was placed in individual, dedicated 55 gallon, DOT approved drums. Each drum was labeled with the monitoring well number and stored in a secured area between the store and the Frison home. The pump and tubing were decontaminated before and between sample events by submergence in a tap water and Alconox solution and flushing approximately five gallons through the pump and tubing. They were then flushed with approximately five gallons of tap water. The flushed water and Alconox solutions were placed in the appropriate 55 gallon drum.

The samples were collected in three laboratory supplied 40 ml VOA bottles. The samples were immediately refrigerated, information recorded on a chain of custody and hand delivered to the laboratory within 24 hours. Copies of the chain of custody and the analytical results are attached.

# Groundwater Flow Direction

On August 12, 1995 the wells were surveyed by a registered surveyor. A copy of his survey was submitted with the first monitoring report. Utilizing the information from the survey and the measurement data collected during sampling, the groundwater flow direction for this sampling event has been determined to be to the northwest, specifically N. 9° W. A copy of the determination is attached.

## Analytical Results and Recommendations

The results of the current and previous sampling are presented in Table 1. Results indicate levels in all three wells continue below regulatory compliance limits. Very slight fluctuations in constituents, we believe, may be the result of seasonal high groundwater encountering a very small residual pocket of hydrocarbons. Groundwater flow direction, as will be seen in previous reports, is generally to the north-northwest. Reversals in flow direction, we believe, may be due to groundwater usage at a nearby Christmas tree farm. A groundwater reversal has occurred on three occasions during the eight quarters we have been monitoring.

The dissolved lead levels during the first monitoring event were well below the drinking water standards. Therefore, with your verbal approval, we have discontinued the lead analysis. The next sampling is scheduled for September 1997.

GEOLOGIS

Sincerely,

SML Associates, Inc.

Harold J. Slavik, Jr., PG

President

for

Toni Frison


encs.


Table 1

# Groundwater Analytical Results Meadowbrook Grocery 16845 So. Highway 211 Molalla, Oregon

Results are presented, in parts per billion (ppb), as benzene / toluene / ethylbenzene / xylenes. ND means below instrument detection limits (<2 ppb).

Sample Date MW-1		MW-2	MW-3
July 26, 1995	7 / 4 / 98 / 190	26 / 36 / 110 / 390	ND/ND/2/5
November 1, 1995	7 / 7 / 120 / 220	64 / 220 / 520 /2200	6 / 15 / 36 / 150
February 15, 1996	14 / 13 / 140 / 260	25 / 35 / 150 / 1000	10 / 8 / 29 / 150
May 11, 1996	7 / 4 / 47 / 45	10 / 7 / 47 / 94	ND/ND/ND/ND
September 4, 1996	4/3/14/16	7/4/9/16	ND / ND / ND/ ND
December 6, 1996	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND
March 6, 1997	ND/ ND/ 32/ 35	4/ 7/ 56/ 160	ND/ ND/ ND/ ND
June 14, 1997	ND/ ND/ ND/ ND	2/ ND/ 15/ 23	ND/ ND/ 22/ 21





39.26 MW-1 (-1,51) 6.38

High (B)

# SAMPLING EVENT DATA SHEET

(fill out completely)

WELL OR LOCATION MW-3

PROJECT Meadow	brook Graev	ENT 94/4 M	lonit SAMF	PLER H.	Slavik	_ DATE	14/97
Well / H	ydrologic statist		Actio	on	Time	Pump rate	IWL (low yield)
5	Well ty	De MW	Start pump	/ Begin			
	(MW, E	EW, etc.)			i		
			- 49				
	d (diamet	er 2"		<del></del>			
swL		0,163 gal/ft. casir			1 m. P		,
(if above screen)	( equals.	gal/ft. casir					
packer )			Stop		1110	disciplination of the second	
lintaka ( ft.			(Final IWL)		1140		
bailer depth (circle one)		ТОР			Purge ca	culation	
5-54	1 1	12.11	. 0,163 gal/fi	. 7.93			87 gals.
SWL 5,54		3	1 A -	WL to BOP	<b>-</b> ~~	_	e volume-
(if in screen)				acker to BC			casings
		ВОР		Head pu	rge calcu	lation (Airlift o	only)
measured 13,47		T.D. (as built)	gai/	ft. *	ft. =	_gals.	
1.D. ———		T.D. (as built)		packer to S	SWL		
Equipment Used / San	npling Method / D	ent:	Actual ga	allons purg	ed 5		
-F6 60 -	202	. la marci	Res		1	2	+
- ES 60 Pu	ingt.	R	ump	Actual vo	lumes pur	ged	1
i		V	0	Well yield		<u>H</u>	<u>Y</u>
- Solinst	100 Pr	obe		(see belo		/	
	0 6	Ola Tof	100	coc		1574	
- Timeo	disposa	61E /E)	bailer		1.D		Lab OAL
Additional comments:				10100	<u> </u>	DILK.	UNL
Additional comments:							
	*					*	
Gallons purged *	TEMP °C /°F	EC	PH	TURBID			
	(circle one)	(µs / cm)		(NTU	)		
1.	- A					3.5	
2.	260			1 1 2 2		· ×	
3.	1						
4.			te"			,	
5.		1 1 1 2 2 3 3 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4				w'	E A E E E
* Take measurement at		MY - WL drop - a		LY - Able			mal recharge -
approximately each casing volume purged.	W.L. drop		iring one sitting g pump rate or		es by return or next day.		ble to purge plumes.



(fill out completely)

WELL OR LOCATION MW-2

PROJECT Meadow brook Grac, EVENT OHLY M	PROJECT Meadow brook Grac, EVENT OHLY MONT, SAMPLER H. Slavik DATE 6/14/97											
Well / Hydrologic statistics	Actio	n	Time	Pump rate	IWL (low yield)							
Well type(MW, EW, etc.)	Start pump	/ Begin										
d   diameter   diame	Stop Sampled (Final IWL)		/2(0	alculation								
SWL 5,3 (if in screen)	, s	gal/ft. * 8,97 ft. = 1,46 gals x 3 = 4  SWL to BOP or one pure packer to BOP volume 3  Head purge calculation (Airlift gal/ft. * gal/s.										
T.D. (as built)	gav	packer to S	************	gais.								
Equipment Used / Sampling Method / Description of Ever	1	Actual vo	# _	rged 3 // /	Lab							
Additional comments:		MWZ	1.D. 2-8	Analysis  BTEX	OAL							
Gallons purged * TEMP °C / °F EC (circle one) (us / cm)	PH	TURBIC (NTU										
1.												
2.	de la											
4.												
* Take measurement at # HY- Minimal WY - WL drop - all volumes du	ring one sitting pump rate or	volum	to purge 3 les by retu or next day	rning una	imal recharge - able to purge olumes.							



(fill out completely)

PROJECT Meadoub	PROJECT Meadon brook Graz EVENT Otly Mont, SAMPLER H. Slavik DATE 6/14/97											
Well / Hy	drologic statistic	\ \ \	Actio	on.	Time	Pump rate	<u>IWL</u> (low yield)					
	Well typ (MW, E	w, etc.)	Start pump	/ Begin								
SWL 4,87 (if above screen)	- d - { diamete	or $\frac{2^{1/2}}{0.1663}$				`						
packer intake bailer depth (circle one)		гор	Stop Sampled (Final IWL)									
SWL————————————————————————————————————			⊥ s	SWL to BOP	t. = 1,58 or one		gals. e volume- casings					
measured <u>/4,54</u> T.D.		T.D. (as built)		The second second second second	rge calc	ulation (Airlift)						
Equipment Used / Sam	pling Method / De	escription of Event	:	Actual ga		ged						
				Actual vo	lumes pu	urged 37	<u> </u>					
				Well yield		MY	<u>/</u>					
				COC Sample	I.D.	1574 Analysis BTEX	Lab OAL					
Additional comments:			- X-									
Gallons purged *	TEMP °C / °F (circle one)	EC (µs / cm)	РН	TURBIC (NTU								
1.				e jest (								
2.												
3.												
<b>4. 5.</b>												
* Take measurement at approximately each casing volume purged.	W.L. drop	MY - WL drop - abi volumes durii by reducing p	ng one sitting oump rate or		to purge 3 les by retu or next day	rning una	imal recharge - able to purge olumes.					



MEADOWBROOK GROCERY 16845 S. HIGHWAY 211 MOLALLA, OR 97038 ANALYST REVIEW BY: WS

DATE: 6-18-97

DATA PACK REVIEW BY:

DATE: 6/18/77

TONI FRISON (503)829-9165/FX 829-9079 P/N:95-044

# BTEX BY EPA 602/8020/8021 OR 624/8240

SAMPLE ID:	MW3-8	MW2-8	MW1-8
OAL ID: 25-J251-	59614	59615	59616
SAMPLE DATE:	6/14/97	6/14/97	6/14/97
MATRIX:	WATER	WATER	WATER
EXTRACTION DATE:	NA	NA	NA
ANALYSIS DATE:	6/17/97	6/17/97	6/17/97
BENZENE PPB	ND	2.	ND
TOLUENE PPB	ND	ND	ND
ETHYLBENZENE PPB	סא	15.	22.
XYLENES PPB	ND	23.	21.
SURR.RECOVERY %	95.	100.	98.
ANALYST:	WB	WB	WB

BROMOFLUOROBENZENE WAS USED AS THE SURROGATE

PPB = UG/KG, SOLIDS PPB = UG/L, LIQUIDS

NA = NOT ANALYZED

MI = MATRIX INTERFERENCE WITH SURROGATE RECOVERY.

ND - NOT DETECTED


REPORTING LIMITS:	WATER	SOIL
BENZENE	<2.0	<2.0
TOLUENE	<2.0	<2.0
ETHYLBENZENE	<2.0	<2.0
XYLENES	<2.0	<2.0

#### OREGON ANALYTICAL LABORATORY

A Division of Portland General Electric

14855 S.W. Old Scholls Ferry Road, Beoverton, OR 97007

Phone 503-590-5300 • Fax 503 590 1404



	-12	<i></i>	_																		
OAI Oregon Analytical Laboratory	- EAV 45	Oragon 97007 503  590-5300		L		AIN (								Т	N	ō		15	74	Page /	of <u>/</u>
Company Mealowbrook (-rocery Contact Von; Frison Address To Lawrie Robinson 35018 5. Wall St. Cotton, OR 97017 Phone # FAX# 656-3627				Project Name Mealow brook Grod Project Number 95-044  P.O. Number Fort & Comments Send Copy results to SML Associates						2C, S	Sampler's Name Havold Slavik Signature H. Slavik Sampling Date 6/14/97  Provide Verbal Results   Yes   No Provide FAX Results   Yes   No										
3 Mw1-8 4 5 6 7	9/1/9/1140	0AL# 25.J251. 59614 59616	S S Containers	X X Water	Other (Note in Remarks)	All Alogensted Survivals SSS 200 (circle) Survivals(like SSS) 8250 (circle) All Patrician All Patrician Statement Survivals(like) Survivals(li	Organodiversations 608/8080 AR PC8 Pesticide (circle)	Chloringted Herbiddes 8150	Quantity? TY## TNo	D 418.1M 418.1	8TEX 602/8020 Z	Organica (orcle)	Vol Semivol Pest Horb	i				S R	- 2 wee - 1 wee - Rush - Other	ek .	
10																					
Signature  Print Name  Company  Associates  Signature  Print Name  Company  Company	13	Signatu 10 Signatu Print Na Compar	ame	מצי		Rec	alved 153	211		eta	5/9	7		Rec	eived	iate C		iners Soz. Vial	°C Ye Jars Is ttles	delivere	-d

SML Associates Inc.

CCB # 120112 1774 Sunset Ave. West Linn, Oregon 97068 (503) 656-3625 Fax: 656-3627 DEPT OF ENVIRONMENTAL QUALITY
RECEIVED

MAR 1 4 1997

NORTHWEST REGION

March 13, 1997

Mr. Rick Silverman Oregon Department of Environmental Quality Northwest Region, UST Section 2000 SW Fourth Ave., Suite 400 Portland, Oregon 97201 (503) 229-5477

Re: Quarterly groundwater monitoring, Meadowbrook Grocery, 16845 S. Hwy. 211, Molalla, Oregon. DEQ file #03-92-125

Dear Mr. Silverman:

This letter and the accompanying documents presents the results of the most recent groundwater monitoring for the above named property, as outlined in the modified CAP.

#### Background

Prior to sampling the total depth and depth to groundwater was measured in each well using a Solinst 100 interface probe. This information was recorded on a sampling event data sheet, one of which was recorded for each well. Copies of the data sheets are attached. The probe was decontaminated before and between each measurement by washing in tap water and Alconox, a biodegradable laboratory cleaner and degreaser, and rinsing in fresh tap water.

### Sample Collection

The measurements obtained were used to calculate the well volume so that at least three volumes were purged prior to sampling. Purging was accomplished utilizing an ES-60 Purger submersible pump. Purged water was placed in individual, dedicated 55 gallon, DOT approved drums. Each drum was labeled with the monitoring well number and stored in a secured area between the store and the Frison home. The pump and tubing were decontaminated before and between sample events by submergence in a tap water and Alconox solution and flushing approximately five gallons through the pump and tubing. They were then flushed with approximately five gallons of tap water. The flushed water and Alconox solutions were placed in the appropriate 55 gallon drum.

The samples were collected in three laboratory supplied 40 ml VOA bottles. The samples were immediately refrigerated, information recorded on a chain of custody and hand delivered to the laboratory within 24 hours. Copies of the chain of custody and the analytical results are attached.

#### Groundwater Flow Direction

On August 12, 1995 the wells were surveyed by a registered surveyor. A copy of his survey was submitted with the first monitoring report. Utilizing the information from the survey and the measurement data collected during sampling, the groundwater flow direction for this sampling event has been determined to be to the northeast, specifically N. 82° E. A copy of the determination is attached.

#### Analytical Results and Recommendations

The results of the current and previous sampling are presented in Table 1. Results indicate levels in all three wells continue below regulatory compliance limits. The very slight increase in MW-2 we believe may be the result of seasonal high groundwater encountering a very small residual pocket of hydrocarbons. Groundwater flow direction, as will be seen in previous reports, is generally to the north-northwest. A reversal in flow direction, we believe, may be due to groundwater usage at a nearby Christmas tree farm. A groundwater reversal has occurred on at least three occasions during the seven quarters we have been monitoring.

The dissolved lead levels during the first monitoring event were well below the drinking water standards. Therefore, with you verbal approval, we have discontinued the lead analysis. The next sampling is scheduled for early June, 1997.

HAROLD J. SLAVIK, JR

Sincerely,

SML Associates, Inc.

Harold J. Slavik, Jr., PG

President

for

Toni Frison, Owner Meadowbrook Grocery


encs.

Table 1

Groundwater Analytical Results Meadowbrook Grocery 16845 So. Highway 211 Molalla, Oregon

Results are presented, in parts per billion (ppb), as benzene / toluene / ethylbenzene / xylenes. ND means below instrument detection limits (<2 ppb).

Sample Date	MW-1	MW-2	MW-3
July 26, 1995	7/4/98/190	26 / 36 / 110 / 390	ND/ND/2/5
November 1, 1995	7 / 7 / 120 / 220	64 / 220 / 520 /2200	6 / 15 / 36 / 150
February 15, 1996	14 / 13 / 140 / 260	25 / 35 / 150 / 1000	10 / 8 / 29 / 150
May 11, 1996	7/4/47/45	10 / 7 / 47 / 94	ND/ND/ND/ND
September 4, 1996	4/3/14/16	7/4/9/16	ND/ND/ND/ND
December 6, 1996	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND
March 6, 1997	ND/ ND/ 32/ 35	4/ 7/ 56/ 160	ND/ ND/ ND/ ND
3.			



Site Location



MEADOWBROOK GROCERY 16845 S. HIGHWAY 211 MOLALLA, OR 97038 ANALYST REVIEW BY: RT DATE: 3/11/97

DATA PACK REVIEW BY:

DATE: 3/11/97

TONI FRISON (503)829-9165/FX 829-9079 P/N:95-044

BTEX
BY EPA 602/8020/8021 OR 624/8240

SAMPLE ID:	MW3-7	MW2-7	MW1-7
OAL ID: 25-J251-	56351	56352	56353
SAMPLE DATE:	3/6/97	3/6/97	3/6/97
MATRIX:	WATER	WATER	WATER
EXTRACTION DATE:	NA	, NA	NA NA
ANALYSIS DATE:	3/10/97	3/10/97	3/10/97
BENZENE PPB	ND	4.	ND
TOLUENE PPB	ND	7.	ND
ETHYLBENZENE PPB	מא	56.	32.
XYLENES PPB	ND	160.	35.
SURR. RECOVERY %	96.	103.	95.
ANALYST:	RJ	RJ	RJ

BROHOFLUOROBENZENE WAS USED AS THE SURROGATE WATER MATRIX UNITS ARE UG/L (PPB)
SOLIDS MATRIX UNITS ARE UG/KG (PPB)

NA = NOT ANALYZED

MI = MATRIX INTERFERENCE WITH SURROGATE RECOVERY.

NO . NOT DETECTED

al an annual of manor 193

 REPORTING LIMITS:
 WATER
 SOIL

 BENZENE
 <2.0</td>
 <2.0</td>

 TOLUENE
 <2.0</td>
 <2.0</td>

 ETHYLBENZENE
 <2.0</td>
 <2.0</td>

 XYLENES
 <2.0</td>
 <2.0</td>

OREGON ANALYTICAL LABORATORY

A Division of Portland Genetal Electric 14855 S.W. Old Scholls Ferry Road Beaverton, OR 97007

1 aboratory	14855 S.W. Old Scholle Ferry Rd. (U. ) Wesvertoo: Oregon 97007   1503  590-5300   1	CHAIN OF CUSTODY RECORD DABORATORY ANALYSIS REQUES	ST Nº 3870 Page / of /
Company Ton: Fris Contact Harold 51 Address 16845 So.	Javik 211	Project Name <u>Meadowbrook</u> Gro Project Number <u>95-044</u> P.O. Number Comments <u>Report Recults</u> to SML Associates, Inc. Fax: 636	Signature
Sample Identification	DATE TIME OAL #	O O O O O O O O O O O O O O O O O O O	N-2 weeks S-1 week R-Rush O-Other  REMIARKS
1 MW3-7. 2 MW2-7. 3 MW1-7.	3/6/91 0950 5635 1 1°35 5635 1 110 5635	2 3 X X X	
8 9 10 Refinance by		Relinquished	O Dalivered
Harold Slavik	Time; 800  Tes, Inc.,	Print Name  Time  Company  Beceived  Signatura  Date  Print Name  Company	Shipped Via Hand Solivered  Received @ °C  Appropriate Containers X Yes  No  40z./80z. Jars  VOA Vials  Plastic Bottles  Glass Bottles  other

# SAMPLING EVENT DATA SHEET

(fill out completely)

WELL OR LOCATION  $M\omega - I$ 

Well / H	ydrologic statisti	CS	Ac	tion	Time	Pump rate	(low yield)
	Well ty; (MW, E	ew, etc.)	Start pur	np / Begin	1100		
_swL 3., 38	d — d diamet	er 2 1 / 0 / 16 3 / 16 gal/ft. casi	ng				
(if above screen)  packer intake bailer depth (circle one)			Stop Sampled (Final IW	L)	1110		
— SWL———————————————————————————————————		TOP	0,16 <sup>3</sup> ga	SWL to BOR packer to Bo	or one		gals. ge volume- casings
measured / 4,54 T.D.		BOP T.D. (as built)			rge calc	ulation (Airlift	
Equipment Used / Sar	mpling Method / D	escription of Ev	ent:	Actual q	allons pui	rged $Z+$	
Same ac	MW-=	3		X -	olumes p	2	<b>H</b>
					ld ⊕	4	
					1.D.	3870 Analysis BTEX	Lab OAL
Additional comments:							
Gallons purged *	TEMP °C /°F (circle one)	EC (µs / cm)	PH	TURBIC (NTU			
1.		2 - 1		<u>.</u>	· _		
2.				12 th			- L
3.							
4.							
5.							
* Take measurement at approximately each casing volume purged.	W.L. drop		uring one sitting g pump rate or	volun	to purge 3 nes by retu or next day	irning una	imal recharge able to purge olumes.

# SAMPLING EVENT DATA SHEET

(fill out completely)

WELL OR LOCATION MW-2

PROJECT Gro	brook L. EVI	ENT Z+hMW	Sampling SAMF	LER #	, Slav,	K DATE 3	6/97
Well / Hy	drologic statisti	, n	Actio	on.	Time	Pump rate	IWL (low yield)
	Well typ (MW, E	W, etc.)	Start pump	o / Begin	1018		
SWL 4,50	d diamete	er <u>2</u> 0,163 0,163 0,163					
packer intake bailer depth (circle one)			Stop Sampled (Final IWL)		1030		
SWL—(if in screen)		TOP		SWL to BOF	or one	gals x 3 = 4	gals. ge volume- casings
measured 14,28		T.D. (as built)	gai	Head pu /ft. * packer to	ft. =	ulation (Airlift) gals.	only)
Equipment Used / San	npling Method / D	escription of Ever	nt:	Actual g	allons pur	ged <u>5</u>	<u> </u>
See Mi	N-3 D	ada Il	cel	Actual vo	olumes pu	$\frac{3}{7}$	<del></del>
				Well yiel	d ⊕ ow)	+/)	<u></u>
				COC Sample	1.D.	3870 Analysis BTEX	Lab OA4
Additional comments:	,						
Gallons purged *	TEMP °C /°F (circle one)	EC (µs / cm)	PH	TURBIC (NTU			
1.					;		
2.							
3.			•				
<b>4. 5.</b>							
* Take measurement at approximately each casing volume purged.	⊕ <u>HY-</u> Minimal W.L. drop	MY - WL drop - ab volumes dur by reducing cycling pump	ing one sitting pump rate or	volum	to purge 3 nes by retu or next day	rning una	mal recharge - able to purge olumes.

# SAMPLING EVENT DATA SHEET (fill out completely)

WELL OR LOCATION MW-3

PROJECT Gro	brook CEV	ENT TMU	Say SAM	PLER _	, Slav	L DATE 3	6/97
Well / H	ydrologic statist	lcs	Act	ion	Time	Pump rate	IWL (low yield)
	Well ty	pe MW	Start pur	np / Begin	0931		
	(MW, E	EW, etc.)					
		.,					
	d ( diamet	er 2					
_ swL	equals	0.163 gal/ft. casi	ng		¥ 12.		<u> </u>
(if above screen)	l (oqual	943111 0401	Stop		0946		
packer )			Sampled		0948		
intake (circle one)	:		(Final IWI	_)	1		
bailer depth (circle one)		ТОР	0, 163 gal	nt. • 9,26	Purge c	alculation gals x 3 = 4	(53 gals.
(if in screen)			<b>1</b>	SWL to BOR	or one		ge volume- casings
		ВОР		Head by	irde calc	ulation (Airlift	only)
measured <u>13,47</u> T.D.		T.D. (as built)	ga	packer to	ft. =	etroticocotico de rodico de la	
Equipment Used / Sar	mpling Method / D	escription of Ev	ent:	Actual o	allons pur	ged 5	
Solinst 1	00' prob	be		_	olumes pu	24	
ES60 pudisposable	inger pl	ing 6.1	0	Well yie	d ⊕	1/1	_
115008abl	e 1-0/10	on call		COC	#	3870	
	V					Analysis	Lab
						BTEX	OAL
Additional comments:							
Gallons purged *	TEMP °C / °F (circle one)	EC (µs / cm)	PH	TURBIC (NTU			
1.							
2.							
3.							
4.							
5.	. 787 C						
* Take measurement at approximately each casing volume purged.	⊕ <u>HY-</u> Minimal W.L. drop		uring one sitting g pump rate or	volum	to purge 3 nes by retu or next day	rning una	imal recharge - able to purge olumes.

Meadowbrook Groc.

Musampling/GW Flow calculation 3/6/97

1"=10'

(-0,98) -4.21 bgs -5.19 Med C 14,50 bgs MW-2 (-1.14) (5.64) 39.29 med-low BE Digh-low AB MW-1 -3.38 bgs (-1.51)  $\frac{(-5.19) - (-5.64)}{(-4.89) - (-5.64)} = \frac{BE}{39.26}$  $39.26\left(\frac{0.45}{0.75}\right) = B\bar{E} = 23,56$ 

۲.

#### SML Associates Inc.

6920 SW 92nd Avenue, Unit 10 Portland, Oregon 97223 (503) 768-4512 Fax: 768-3902

December 27, 1996

DEPT OF ENVIRONMENTAL QUALITY RECEIVED

DEC 3 1 1996

NORTHWEST REGION

Mr. Rick Silverman
Oregon Department of Environmental Quality
Northwest Region, UST Section
2000 SW Fourth Ave., Suite 400
Portland, Oregon 97201
(503) 229-5477

Re: Quarterly groundwater monitoring, Meadowbrook Grocery, 16845 S. Hwy. 211, Molalla, Oregon. DEQ file #03-92-125

Dear Mr. Silverman:

This letter and the accompanying documents presents the results of the most recent groundwater monitoring for the above named property, as outlined in the modified CAP.

#### **Background**

Prior to sampling the total depth and depth to groundwater was measured in each well using a Solinst 100 interface probe. This information was recorded on a sampling event data sheet, one of which was recorded for each well. Copies of the data sheets are attached. The probe was decontaminated before and between each measurement by washing in tap water and Alconox, a biodegradable laboratory cleaner and degreaser, and rinsing in fresh tap water.

# Sample Collection

The measurements obtained were used to calculate the well volume so that at least three volumes were purged prior to sampling. Purging was accomplished utilizing an ES-60 Purger submersible pump. Purged water was placed in individual, dedicated 55 gallon, DOT approved drums. Each drum was labeled with the monitoring well number and stored in a secured area between the store and the Frison home. The pump and tubing were decontaminated before and between sample events by submergence in a tap water and Alconox solution and flushing approximately five gallons through the pump and tubing. They were then flushed with approximately five gallons of tap water. The flushed water and Alconox solutions were placed in the appropriate 55 gallon drum.

The samples were collected in three laboratory supplied 40 ml VOA bottles. The samples were immediately refrigerated, information recorded on a chain of custody and hand delivered to the laboratory within 24 hours. Copies of the chain of custody and the analytical results are attached.

#### Groundwater Flow Direction

On August 12, 1995 the wells were surveyed by a registered surveyor. A copy of his survey was submitted with the first monitoring report. Utilizing the information from the survey and the measurement data collected during sampling, the groundwater flow direction for this sampling event has been determined to be to the southeast, specifically S. 13° E. A copy of the determination is attached.

#### Analytical Results and Recommendations

The results of the current and previous sampling are presented in Table 1. Results indicate continuing decrease in all three wells. Groundwater flow direction, as will be seen in previous reports, is to the north-northwest. The reversal in flow direction, we believe, may be due to groundwater usage at a nearby Christmas tree farm. A groundwater reversal has occurred on at least two other occasions during the last year and one half.

The dissolved lead levels during the first monitoring event were well below the drinking water standards. Therefore, with you verbal approval, we have discontinued the lead analysis. The next sampling is scheduled for early March, 1997.

OREGON HAROLD J. SLAVIK

Sincerely,

SML Associates, Inc.

Harold J. Slavik, Jr., PG

President

for

Toni Frison, Owner Meadowbrook Grocery


encs.

Table 1

# Groundwater Analytical Results Meadowbrook Grocery 16845 So. Highway 211 Molalla, Oregon

Results are presented, in parts per billion (ppb), as benzene / toluene / ethylbenzene / xylenes. ND means below instrument detection limits (<2 ppb).

Sample Date	MW-1	MW-2	MW-3
July 26, 1995	7 / 4 / 98 / 190	26 / 36 / 110 / 390	ND/ND/2/5
November 1, 1995	7 / 7 / 120 / 220	64 / 220 / 520 /2200	6 / 15 / 36 / 150
February 15, 1996	14 / 13 / 140 / 260	25 / 35 / 150 / 1000	10 / 8 / 29 / 150
May 11, 1996	7 / 4 / 47 / 45	10 / 7 / 47 / 94	ND / ND / ND /ND
September 4, 1996	4/3/14/16	7/4/9/16	ND / ND / ND/ ND
December 27, 1996	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND	ND/ ND/ ND/ ND



Site Location



MEADOWBROOK GROCERY 16845 S. HIGHWAY 211 MOLALLA, OR 97038

ANALYST REVIEW BY: DATE: 12-12 96

DATA PACK REVIEW BY: SL DATE: 12/12/96

TONI FRISON (503)829-8609/FX 768-3902 PN:95-044

> BTEX BY EPA 602/8020/8021 OR 624/8240

SAMPLE ID:	MW1-5	MW2-5	MW3-5
OAL ID: 25-J251-	54019	54020	54021
SAMPLE DATE:	12/6/96	12/6/96	12/6/96
MATRIX:	WATER	WATER	WATER
EXTRACTION DATE:	NA	NA	NA
ANALYSIS DATE:	12/10/96	12/11/96	12/10/96
BENZENE PPB	ND	ND	ND
TOLUENE PPB	ND	ND	ND
ETHYLBENZENE PPB	ND	ND	ND
XYLENES PPB	ND	ND	ND
SURR.RECOVERY %	109.	106.	91.
ANALYST:	WB	WB	WB

BROMOFLUOROBENZENE WAS USED AS THE SURROGATE WATER MATRIX UNITS ARE UG/L (PPB) SOLIDS MATRIX UNITS ARE UG/KG (PPB)

NA = NOT ANALYZED

MI = MATRIX INTERFERENCE WITH SURROGATE RECOVERY.

ND = NOT DETECTED

RE	PORTING LIMITS:	WATER	SOIL
	BENZENE	<2.0	<2.0
	TOLUENE	<2.0	<2.0
	ETHYLBENZENE	<2.0	<2.0
	XYLENES	<2.0	<2.0

#### OREGON ANALYTICAL LABORATORY

A Division of Portland General Electric 14855 S.W. Old Scholls Ferry Road, Beaverton, OR 97007 Phone 503-590-5300 • Fax 503-590-1404



والمراج والمتعادي والمساور والمتعاد والمت والمتعاد والمتعاد والمتعاد والمتعاد والمتعاد والمتعاد والمتع		And building the state of the s		-										-		-	-	Marking Street Co.	and the same of his bridge beauti
Oregon Analytical Laboratory	4. 1.	Cholis Ferry Rd. Oregon 97007 503) 590-5300 503) 590-1404				AIN O							Т	Nο		38	75	Pa	ge <u>/</u> of <u>/</u>
Company Meadow be Contact Joni F. Address 10845 S. Molalla, Phone # 829-3609  SAMPLE IDENTIFICATION	rison Hwy OR	#211 97038 68-390	2  3	Project P.O. I Comm	Number Nu	nber _ er _ Rep	6/8080   Gridel	500.	19	175	Cd Cr Pb Hg Se Ag 33 Sanits	emivol Pest Herb	Si Sa [	gnature impling Provi	s Name g Date _ de Verl de FA)	bal R X Res X Res	$\frac{1}{2}$ - $\frac{1}{6}$	- 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90	Yes   No
1 MW1-5 2 MW2-5	12-6 3:36	T	) jo #	Soil	Other	Semivol All PAP	Organoc All P	Chlorina TPH-HC	TPH Qu	3	As Be	Vol S	ž <b>i</b>			Turna		KE	MARKS
3 MW 3-5	4:41		3	X						3 3						Y	/		
7													· · · · · · · · · · · · · · · · · · ·	The second secon		And the second s			
9					400											Town Williams and American	_		
Relinquisher  Signature  Print Name  M. L.C. ISing Ext  Company  M. ASSICICIT  Signature  Signature	Time	0.2	unasyro  Int founce  Ornorry  Onature	1, C	1	Sla Sla		<u> </u>	I	10			Re	ceived	@ ate Con 40z	taine z./80z	rs 🔊		// venzo
Pint Name / Slavik	Time	322	int Name	Do	ug	MCK C)A		710	7	DE0	200				Pla	iss Bo	ottles		

## SAMPLING EVENT DATA SHEET

(fill out completely)

WELL OR LOCATION MW-1 PROJECT Meadow brook EVENT 5th art SAMPLER M. Boyer DATE 12-6-96 IWL Time Pump rate Action Well / Hydrologic statistics (low yield) Well type \_\_\_\_\_\_(MW, EW, etc.) 3:02 Start pump / Begin equals 0,16 3 gal/ft. casing (if above screen) Stop packer Sampled intake 3:36 (Final IWL) bailer depth (circle one) - TOP Purge calculation 0.163 gal/tt. 13.08tt. = 2.13 gals x3 = 6.4 gals. SWL-SWL to BOP or purge volume-(if in screen) packer to BOP volume 3 casings BOP Head purge calculation (Airlift only) measured 14,53 gal/ft.\* ft. = \_\_\_\_gals. T.D. (as built) T.D. packer to SWL Equipment Used / Sampling Method / Description of Event: Actual gallons purged Solinst 100 interprote ES 60 purger pump Actual volumes purged Well yield  $\oplus$ (see below) COC # Lab Sample I.D. Analysis BIEX Additional comments: TEMP °C /°F EC PH TURBIDITY Gallons purged \* (circle one) (us / cm) (NTU) 1. 2. 3. 4. VLY - Minimal recharge -LY - Able to purge 3 MY - WL drop - able to purge 3 ⊕ HY- Minimal Take measurement at unable to purge W.L. drop volumes during one sitting volumes by returning approximately each 3 volumes. by reducing pump rate or later or next day. casing volume purged. cycling pump.

i stor

# SAMPLING EVENT DATA SHEET (fill out completely)

	npletely)	WEL	L OR LO	CATION	1W-2
ROJECT Menelandrook EVENT 5th q	Mr_SAMPL	er _	1, Boje	_ DATE	-6-96
Well / Hydrologic statistics	Action	n	Time	Pump rate	IWL (low yield)
(MW, EW, etc.)	Start pump	/ Begin	4:10		
-SWL 1.74 diameter 2" equals 0,163 equals gal/ft. casir				W. Jan.	,
(if above screen)	Stop Sampled				
ntake pailer depth (circle one)	(Final IWL)		4:41	leulation.	
pailer depth) (click sho)	1 A -		ft. = 2,0	gals x 3 =	And the second s
(if in screen)	S P	acker to BO		me 3	ge volume- casings
measured 14.27 — BOP — T.D. (as built)	gal/		ft. =		
equipment Used / Sampling Method / Description of Ev	ent:	T	allons pur	ged <u>6</u>	1 <u>3</u> †
Solinst 100 interpor prop	be	γ-	olumes po		17
es 60 purger pump		Well yie	low)		
	*	COC Sampl MW2-	e I.D.	Analysis  **BTEX	Lab OAL
Additional comments:	***	10f	3 :		
		30	3		
0.00					
Gallons purged • TEMP °C / °F EC (us / cm)	PH	TURB (NT	DITY บ)		
1.					
2.		+			
3.					
4.	0 12	-			
5.	¥				inimal rechar

## SAMPLING EVENT DATA SHEET

(fill out completely)

WELL OR LOCATION MW-3 SAMPLER M. Boyer DATE 12-6.96 PROJECT Mendowbrook EVENT\_ 5th got Pump rate Action Time Well / Hydrologic statistics (low yield) Well type \_\_\_\_\_\_ (MW, EW, etc.) Start pump / Begin 7:40 equals 0, 163 (if above screen) Stop Sampled packer intake (Final IWL) 4:06 bailer depth (circle one) TOP Purge calculation 0,163 gal/ft. · 12.55 ft. = 2.05 gals x 3 = SWL-SWL to BOP or purge volume-(if in screen) packer to BOP volume 3 casings BOP Head purge calculation (Airlift only) measured 44 gal/ft. \* \_\_\_\_ ft. = \_\_\_\_ gals. T.D. (as built) T.D. packer to SWL Actual gallons purged 6.20 # Equipment Used / Sampling Method / Description of Event: Solinst 100 interprobe Es 60 purgar pump Actual volumes purged Well yield  $\oplus$ (see below) COC # Lab **Analysis** Sample I.D. BIEX QA1\_ MW3-5 1073 : Additional comments: TEMP °C /°F PH TURBIDITY EC Gallons purged \* (circle one) (us / cm) (NTU) 1. 3. 4. VLY - Minimal recharge -LY - Able to purge 3 MY - WL drop - able to purge 3 ⊕ HY- Minimal Take measurement at unable to purge volumes by returning volumes during one sitting W.L. drop approximately each 3 volumes. later or next day. by reducing pump rate or casing volume purged.

cycling pump.

