### QUARTERLY REPORT JULY 1999

# GROUNDWATER MONITORING "Flying J – Milwaukie #2" DEQ Site No. 03-93-0008

Delco Petroleum Company, LLC 17873 S.E. McLoughlin Boulevard Milwaukie, Oregon 97267

August 4, 1999

Prepared For:

Delco Petroleum Company, LLC

14 Long Leaf Drive Hamilton, New Jersey 08690 through NW Envirocon, Vancouver, WA

DEPT OF ENVIRONMENTAL QUALITY
RECEIVED

AUG 04 1999

NORTHWEST REGION

Prepared By:

Richard C. Kent, R.G. GeoPro Geologic Services Post Office Box 26 Battle Ground, WA 98604



Project Number 990621

# QUARTERLY REPORT JULY 1999

# GROUNDWATER MONITORING "Flying J – Milwaukie #2" DEQ Site No. 03-93-0008

# Delco Petroleum Company, LLC 17873 S.E. McLoughlin Boulevard Milwaukie, Oregon 97267

August 4, 1999

Prepared For:

#### Delco Petroleum Company, LLC

14 Long Leaf Drive Hamilton, New Jersey 08690 through NW Envirocon, Vancouver, WA

DEPT OF ENVIRONMENTAL QUALITY
RECEIVED

AUG 04 1999

**NORTHWEST REGION** 

Prepared By:

Richard C. Kent, R.G. GeoPro Geologic Services Post Office Box 26 Battle Ground, WA 98604



Project Number 990621

#### TABLE OF CONTENTS

	Page
1. INTRODUCTION	4
1.1. PURPOSE AND SCOPE OF WORK	4
1.2. LOCATION	
2. PREVIOUS WORK	5
2.1. PREVIOUS REPORTS	5
2.2. ENVIRONMENTAL ASSESSMENTS	
2.3. CLEANUP STANDARD EVALUATION REPORT	
2.4. SUMMARY REPORT	
2.5. QUARTERLY REPORTS	
2.6. FREE PRODUCT	
2.7. MONITOR WELL INSTALLATIONS	
2.8. PREVIOUS GROUNDWATER LEVELS	
2.10. PREVIOUS GROUNDWATER GRADIENT ESTIMATES	
3. JULY 1999 GROUNDWATER SAMPLING	
3.1. GEOLOGY AND HYDROGEOLOGY	
3.2. GROUNDWATER GRADIENTS	
3.3. GROUNDWATER SAMPLING METHODOLOGY	
3.4. LABORATORY ANALYSES	17
4. INTERPRETATIONS AND CONCLUSIONS	
4.1. DEQ NOTICE OF VIOLATION	
4.2. GROUNDWATER MONITORING	
4.2.1. Previous Groundwater Sampling	
4.2.2. July 1999 Groundwater Sampling	
5. RECOMMENDATIONS	20
5.1. FURTHER WORK	20
6. LIMITATIONS	21

#### Table of Contents - continued

#### **TABLES**

Table 1 – PHASE III SOIL SAMPLING ANALYTICAL RESULTS	
Table 2 – SUMMARY OF QUARTERLY REPORTS	
Table 3 – MONITOR WELL INSTALLATION SUMMARY	
Table 4 – PREVIOUS GROUNDWATER LEVELS (feet)	
Table 5 – SUMMARY OF PREVIOUSLY REPORTED GROUNDWATER GRADIENTS	
Table 6 – PREVIOUS GROUNDWATER SAMPLING ANALYSES (µg/l)	
Table 7 – MONITOR WELL ELEVATIONS AND STATIC WATER LEVELS	
Table 8 – GROUNDWATER ANALYSIS RESULTS	17
FIGURES	
FIGURES	
Figure 1 – LOCATION MAP	22
Figure 2 – SITE MAP	
Figure 3 – GROUNDWATER, GRADIENT MAP: JULY 1999	24
CHARTS	
Chart 1 – PREVIOUS GROUNDWATER LEVELS	
Chart 2 – PREVIOUS GROUNDWATER ANALYSES (SELECTED WELLS)	
Chart 3 – JULY 1999 STATIC WATER ELEVATIONS	16
APPENDICES	
Appendix A – JULY 1999 LABORATORY REPORT	
Appendix B – JULY 1999 WATER SAMPLE FIELD LOGS	
Appendix C – MONITOR WELL LOGS (MW-1 THROUGH MW-13)	
Appendix D – DEQ NOTICE OF CIVIL PENALTY (JUNE 7, 1999)	
Appendix E – WELL SURVEY SUMMARY BY BARBIERI & ASSOCIATES	

#### 1. INTRODUCTION

#### 1.1. PURPOSE AND SCOPE OF WORK

The purpose of this report is to summarize analysis of groundwater samples collected on July 23<sup>rd</sup>, 24<sup>th</sup>, and 25<sup>th</sup>, 1999 from ten (10) monitor wells and an on-site petroleum hydrocarbon separator treatment facility. Richard C. Kent, Registered Geologist of GeoPro Geologic Services ("Consultant"), was authorized by Delco Petroleum Company, LLC, 14 Long Leaf Drive, Hamilton, New Jersey 08690 ("Client" and "Landowner") to begin work on July 1, 1999.

This report has been prepared in partial response to a Notice of Violation, Department Order, and Assessment of Civil Penalty No. WMC/T-NWR-99-064 Clackamas County in the Matter of Devinder Dhillon and Delco Petroleum Co., LLC before the Environmental Quality Commission of the State of Oregon ("Order"). The resumption of quarterly groundwater sampling and reporting is required as stated in a cover letter to the Order by Certified Mail Z 440 760 423 dated June 7, 1999 from Mr. Langdon Marsh, Director of the Oregon Department of Environmental Quality ("DEQ") to Mr. Devinder Dhillon (see Appendix D).

Previous work is summarized in this report to allow convenient reference to prior investigation data. However, such summary information is not a replacement for work by others.

#### 1.2. LOCATION

The Delco Petroleum Company, LLC service station at 17873 SE McLoughlin Boulevard, Milwaukie, Oregon 97267 ("Site") is a commercial property surrounded by other commercial properties within the SE/4 of the SW/4, Section 18, Township 2 South, Range 2 East (WM) in Clackamas County, Oregon (see Figure 1 - "Location Map"). The Site is Tax Lot 1700 adjacent to "Ed's Mufflers and Brakes" to the north and "Busters Restaurant" to the south on the west side of McLoughlin Boulevard (Oregon State Highway 99) (see Figure 2 - "Site Map"). The Site has also been referenced as "Milwaukie Fuel Stop", "Delco Company", and/or "Flying J". The Willamette River flows northerly approximately one-half mile west of the Site.

The Site is an active service station which is understood to contain one (1) abandoned diesel underground storage tank ("UST") with a nominal capacity of 8,000-gallons, and three (3) active gasoline UST's each with a nominal capacity of 12,000-gallons in a 'tank field' located in the north-central portion of the Site. The Site also contains a building with office and three (3) service bays for auto lubrication and oil changing, and, three (3) gasoline pump islands. Initial analysis of soil and groundwater samples collected from borings and monitor wells indicated groundwater contamination that exceeded cleanup levels due to apparent gasoline and/or diesel leakage from the UST's, piping, and/or associated facilities.

Apparently, three (3) or five (5) lube-oil USTs, removed during, or prior to, 1993, were located immediately north of existing Monitor Well MW-6. Groundwater for a pump treatment system is produced from Monitor Wells MW-7 and MW-8, located east and west, respectively, of the tank field. Sampling of the treatment system is done under a National Pollutant Discharge Elimination System ("NPDES") Permit No. 1500A, dated August 24, 1995 and expiring June 30, 2000.

#### 2. PREVIOUS WORK

#### 2.1. PREVIOUS REPORTS

Previous Site work has been summarized in the following available reports:

- "Phase III Environmental Assessment Report", for Jiffy Lube, Milwaukie, OR, by Delta Environmental Consultants, Inc., Bellevue, WA, undated, 6pp., Figures, Tables, and Appendices.
- "Cleanup Standards for Benzene, Toluene, Ethylbenzene, Xylene, and TPH per EPA Guidance Document EPA 910/9-91-036", for Eclipse Environmental Consulting, Richland, WA, by Columbia Energy & Environmental Services, Inc., Richland, WA, June 15, 1994, 5pp. and Tables.
- "Third Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, June 15, 1995, 6pp. and Appendices.
- "Fourth Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, June 22, 1995, 7pp. and Appendices.
- "Fifth Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, October 18, 1995, 7pp. and Appendices.
- "Delco Project Summary Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, December 20, 1995, 6pp. and Appendices.
- "Sixth Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, February 15, 1996, 7pp. and Appendices.
- "Seventh Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, May 15, 1996, 7pp. and Appendices.
- "Ground Water Monitoring Report", for Delco Company, by Northwest Envirocon, Inc., Vancouver, WA, September 30, 1996, 10pp. and data information.
- "Eighth Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, November 8, 1996, 8pp. and Appendices.
- "Ninth Quarterly Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, February 21, 1997, 8pp. and Appendices.
- "First Quarter 1998 Ground Water Monitoring Report", for Delco Company (formerly Flying J), by Northwest Envirocon, Inc., Vancouver, WA, February 12, 1998, 8pp. and Appendices.

#### 2.2. ENVIRONMENTAL ASSESSMENTS

"Phase I" and "Phase II" Environmental Assessments were completed by Delta Environmental Consultants Inc. ("Delta"), 3150 Richards Road, Suite 100, Bellevue, Washington 98005 between May 12 and May 27, 1993. Phase I was completed to asses the historical and potential environmental impacts to the Site. Phase II involved drilling five soil borings to collect and analyze soil samples. The Site was known as "Jiffy Lube International Store #1012", located at 17869 SE McLoughlin Boulevard, Milwaukie, Oregon.

Between June 18 and June 21, 1993, Delta performed a "Phase III" Environmental Assessment as summarized in an undated report by Patricia A. Crump and Daniel S. Whitman of Delta. Phase III involved the drilling and installation of six-(6) groundwater monitoring wells: MW-1, MW-2, MW-3, MW-4, MW-5, and MW-6. Soil samples from the borings for the monitor wells were analyzed for BTEX and TPH. Groundwater samples collected from each monitor well were analyzed for BTEX, TPH, and TPH-G.

During Phase III, petroleum hydrocarbons were detected in soil samples from MW-1 through MW-4 at unknown depths and MW-5 at 5- to 6.5-feet. Benzene was detected in groundwater samples from wells MW-1 through MW-5. Toluene was detected in water samples from MW-1, MW-3, and MW-4. Ethylbenzene and xylenes were detected in all groundwater samples, but apparently exceeded DEQ action levels only in well MW-3. Apparently no constituents were detected in the water sample from well MW-6. Initial soil analytical results are summarized below in Table 1 – "Phase III Soil Sampling Analytical Results".

Table 1 – PHASE III SOIL SAMPLING ANALYTICAL RESULTS

						A	analytical Tes	st Results,	mg/kg (ppn	1)		1
Boring	Sample	Depth	Date	TPH- G	TPH-D	TPH-ID Gasoline	TPH-ID Diesel	TPH	В	T	E	X
MW-1	S-2	unk (5-6.5 ft?)	6/23/93	87	550	>20	<50	110	510	44	150	1,050
MW-2	S-1	unk (2.5-4 ft?)	6/23/93	29	1,200	>20	>50	1,100	23,000	320	9,800	40,470
MW-3	S-2	unk (5-6.5 ft?)	6/23/93	62	180	>20	>50	680	3,800	49,000	51,000	289,000
MW-4	S-2	unk(5-65. ft?)	6/23/93	<10		>20	>50	120	4,600	520	6,000	10,500
MW-5	S-2	5-6.5 ft	6/23/93	13		>20	<50	210	2,900	84	1,300	3,250
MW-6	S-2	7.5-9 ft	6/23/93	<10	23	>20	>50	160	<30	<30	<30	<30

Notes: "<" = Below Reporting Limit of laboratory, and may be accepted as practically non-detectable, or very low concentration and not; ND = Not

Detected at or above reporting limit; TPH = Total Petroleum Hydrocarbons, TPH-G = gasoline-range hydrocarbons, TPH-D = diesel-range
hydrocarbons, B=benzene, T=toluene, E=ethylbenzene, X=total xylenes; blank boxes = not analyzed.

Delta concluded from water level measurements taken during Phase III that the groundwater gradient was approximately 0.001-feet/foot between MW-1 and MW-5 in a west to northwest direction. Groundwater was encountered at approximately seven (7)-feet below ground surface during the drilling of the monitor wells. Silty sands essentially underlie the Site, with silty clay occurring at shallow depths.

#### 2.3. CLEANUP STANDARD EVALUATION REPORT

The report titled "Cleanup Standards for Benzene, Toluene, Ethylbenzene, Xylene, and TPH per EPA Guidance Document EPA 910/9-91-036", competed by Columbia Energy & Environmental Services, Inc. ("Columbia") on June 15, 1994, concluded that "benzene groundwater concentration was the only compound to average above the EPA and Oregon cleanup levels". The calculations for groundwater risk exposures

apparently used "soil cleanup standards". Columbia infers that average TPH values "showed Oregon compliance" but "specific locations ... need to be addressed for cleanup".

Because the basis for concluding that benzene is the only compound of interest may be outdated guidance documents that may not be currently used by DEQ, this report by Columbia will not been further evaluated.

#### 2.4. SUMMARY REPORT

A report was prepared by Northwest Envirocon, Inc. ("NWE") titled "Delco Project Summary Report" dated December 20, 1995. The purpose of the report was to summarize Site remediation activities from May 1993 through December 1995. The report notes that free product was recovered from July 1994 to January 1995, presumably from recovery wells MW-7 and MW-8, and was not observed at the treatment facility after January 1995. The report concludes that from June to December 1995, BTEX concentrations increased in monitor wells MW-1 and MW-5, while decreasing in other monitor wells.

#### 2.5. QUARTERLY REPORTS

The following Table 2 - "Summary of Quarterly Reports" is a list of available prior monitoring reports.

Table 2 – SUMMARY OF QUARTERLY REPORTS

Report Title	Date of Report	Date of Groundwater Sampling	Monitor Wells Sampled
First Quarterly Ground Water Monitoring Report	August 14, 1994	July 18-19, 1994	MW-1 through MW-6
Third Quarterly Ground Water Monitoring Report	June 15, 1995	January 24, 1995	MW-1 through MW-6
Fourth Quarterly Ground Water Monitoring Report	June 22, 1995	June 20, 1995	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9
Fifth Quarterly Ground Water Monitoring Report	October 18, 1995	September 29, 1995	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9
Sixth Quarterly Ground Water Monitoring Report	February 15, 1996	February 15, 1996	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9
Seventh Quarterly Ground Water Monitoring Report	May 15, 1996	April 26, 1996	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9
Ground Water Monitoring Report	September 30, 1996	September 17-18, 1996	MW-11 through MW-13
Eighth Quarterly Ground Water Monitoring Report	November 8, 1996	October 29, 1996	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9 through MW-13
Ninth Quarterly Ground Water Monitoring Report	February 21, 1997	January 15, 1997	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9 through MW-13
First Quarter 1998 Ground Water Monitoring Report	February 12, 1998	January 27, 1998	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9 through MW-13

#### 2.6. FREE PRODUCT

As reported in the "Third Quarterly Ground Water Monitoring Report" by NWE dated June 15, 1995, free product was observed only in Monitor Well MW-3 during sampling on January 24, 1995. As stated in the report: "Manual removal of free product from MW-3 was conducted on a weekly basis from July 19, 1994 to October 30, 1994; and biweekly from November 6, 1994 until January 24, 1995." The free product "smelled like gasoline, was dark brown-black in color", and was one (1)-inch thick in MW-3 on July 19, 1994. No measurable layer of free product was observed during sampling of MW-3 on October 2, 1994, after which "residue" was observed in the bailer during subsequent sampling events.

As reported in the "Fourth Quarterly Ground Water Monitoring Report" by NWE dated June 22, 1995, free product was observed only in Monitor Well MW-7 during sampling on June 20, 1995. As stated in the report: "The bailed free product and ground water from MW-7 is stored in a 55-gallon drum on the site."

No free product was reportedly observed in any monitor wells on and after September 29, 1995 (see Fifth Quarterly Ground Water Monitoring Report by NWE).

#### 2.7. MONITOR WELL INSTALLATIONS

Thirteen (13) groundwater monitor wells have been installed in response to potential impact by petroleum hydrocarbons to groundwater following the initial Environmental Assessment Phases I through III as described above. Ten (10) monitoring wells are currently accessible for obtaining groundwater samples. Available well logs are included in Appendix C – "Monitor Well Logs (MW-1 through MW-13)".

Monitoring Well MW-3 was decommissioned on February 20, 1995 by Geo-Tech Explorations, Inc., Tualatin, Oregon as summarized in a letter to DEQ by Martin S. Burck, R.G. on March 24, 1995. The decommissioning was caused by site characterization excavation activities (apparently a backhoe or similar) which removed soil around MW-3 to a depth of four (4)- to five (5)-feet and destroyed the annular seal. The well was reportedly decommissioned by overdrilling and backfilling with bentonite per Oregon Department of Water Resources procedures. Monitor Well MW-7 was previously installed on January 27, 1995 as an anticipated monitoring location replacement for well MW-3.

Also on January 27, 1995, monitor wells MW-8 and MW-9 were installed at the Site. MW-7 and MW-8 are constructed with four (4)-inch PVC as production wells for the treatment facility. All other monitor wells are constructed with two (2)-inch PVC. One monitoring well, MW-11, was installed off-site in a downgradient direction on August 17, 1996, to the northwest, on the "Ed's Muffler & Brakes" property.

The following Table 3 – "Monitor Well Installation Summary" includes reported well installation methods.

**Table 3 - MONITOR WELL INSTALLATION SUMMARY** 

Monitor Well	Date Installed	Elevation (ft)	Total Depth (ft bgs)	SWL When Drilled	Casing & Screen Size	Screened Interval	Filter Pack	Annular Seal Bottom	General Lithology
MW-1	6/18/93	99.67	15.0	5.02	2-inch PVC	5-15 ft	10/20 4-15 ft	4 ft	clay
MW-2	6/18/93	98.79	14.0	4.2	2-inch PVC	4-14 ft	10/20: 3-14 ft	3 ft	clay
MW-3	6/18/93	98.57	15.0	4.0	2-inch PVC	5-15 ft	10/20: 4-15 ft	4.ft	clay, sandy silt
MW-4	6/18/93	99.30	15.0	4.76	2-inch PVC	5-15 ft	10/20: 4-15 ft	4 ft	clay, fn sand
MW-5	6/19/93	100.66	15.0	6.14	2-inch PVC	5-15 ft	10/20: 4-15 ft	4 ft	clay, fn sand
MW-6	6/19/93	100.29	14.5	5.71	2-inch PVC	5-14.5 ft	10/20: 3.5- 14.5ft	3.5 ft	silty fn sand
MW-7	1/27/95	98.96	19.0	unk	4-inch PVC	4-19 ft	10/20: 3-19 ft	unk (13?)	clayey silt, silty sand
MW-8	1/27/95	99.63	20.0	unk	4-inch PVC	5-20 ft	10/20: 3-20 ft	unk (14.5?)	clayey silt, silty sand
MW-9	1/27/95	99.72	15.0	unk	2-inch PVC	5-15 ft	10/20: 3-15 ft	unk (10?)	clayey silt
MW-10	8/12/96	98.77	15.0	9.0	2-inch PVC	10-15 ft	10/20: 8-15 ft	8 ft	gray clay
MW-11	8/12/96	99.98	15.0	9.0	2-inch PVC	10-15 ft	10/20: 8-15 ft	8 ft	gray clay
MW-12	8/12/96	100.54	15.0	9.0	2-inch PVC	10-15 ft	10/20: 8-15 ft	8 ft	gray clay
MW-13	8/12/96	100.11	15.0	9.0	2-inch PVC	10-15 ft	10/20: 8-15 ft	8 ft	gray clay

#### **Notes:**

Elevations are from report titled "Eighth Quarterly Ground Water Monitoring Report" dated November 8, 1996 by NWE for Delco. "SWL when drilled" for MW-1 through MW-6 was calculated from elevation shown on Delta construction well log minus water level measured two or three days after installation. "Annular seal bottom" in MW-1 through MW-6 calculated from top of PVC casing depth shown on well construction logs by Delta. First encounter of groundwater for MW-7 through MW-9 not recorded on available geologic logs by Martin S. Burck, OR R.G.. Data for MW-10 through MW-13 from driller's well report since geologic logs are unavailable or missing.

#### 2.8. PREVIOUS GROUNDWATER LEVELS


Groundwater levels appear to fluctuate as indicated in the following Table 4 – "Previous Groundwater Levels" and accompanying Chart 1 - "Previous Groundwater Levels".

Table 4 – PREVIOUS GROUNDWATER LEVELS (feet)

Monitor Well	Date	SWL Below Casing	SWL Elevation	Monitor Well	Date	SWL Below Casing	SWL Elevation
MW-1	6/21/93	nr	94.65	MW-6	6/21/93	nr	94.58
Ju.	1/24/95	3.97	95.70		1/24/95	4.75	95.54
	6/20/95	4.67	95.00		6/20/95	5.28	95.01
	9/29/95	6.91	92.76		9/29/95	7.38	92.99
	2/15/96	3.00	96.67		2/15/96	3.17	97.12
	4/26/96	3.74	95.93		4/26/96	4.27	96.02
	10/29/96	5.82	93.85		10/29/96	6.47	93.82
	1/15/97	2.74	96.93		1/15/97	3.33	96.96
	1/27/98	4.51	95.16		1/27/98	5.01	95.28
MW-2	6/21/93	nr	94.59	MW-7	6/20/95	4.61	94.34
	1/24/95	2.97	95.82	MW-8	6/20/95	4.68	94.94
	6/20/95	3.77	95.02	MW-9	6/20/95	4.88	94.83
	9/29/95	6.48	92.31		9/29/95	6.73	92.99
	2/15/96	1.87	96.92		2/15/96	3.39	96.32
	4/26/96	3.16	95.63		4/26/96	4.42	95.30
97	10/29/96	5.00	93.79		10/29/96	5.66	94.06
A STATE OF THE PARTY OF THE PAR	1/15/97	2.23	96.56		1/15/97	2.34	97.38
	1/27/98	3.75	95.04		1/27/98	4.91	94.81
MW-3	6/21/93	nr	94.57	MW-10	9/18/96	5.18	93.59
	1/24/95	2.89	95.68		10/29/96	4.94	93.83
MW-4	6/21/93	nr	94.54		1/15/97	2.03	96.74
2	1/24/95	3.56	95.74		1/27/98	3.61	95.16
	6/20/95	4.28	95.02	MW-11	9/18/96	6.54	93.44
	9/29/95	7.20	92.10		10/29/96	6.37	93.61
	2/15/96	2.57	96.73		1/15/97	4.38	95.60
	4/26/96	3.75	95.55		1/27/98	5.66	94.32
	10/29/96	5.55	93.75	MW-12	9/18/96	7.19	93.35
	1/15/97	2.75	96.55		10/29/96	6.68	93.86
	1/27/98	4.26	95.04		1/15/97	4.72	95.82
MW-5	6/21/93	nr	94.52		1/27/98	4.96	95.58
and the same of	1/24/95	4.94	95.72	MW-13	9/18/96	5.19	94.92
	6/20/95	5.63	95.03		10/29/96	6.29	93.82
	9/29/95	8.22	92.44		1/15/97	3.13	96.98
	2/15/96	3.77	96.89		1/27/98	4.86	95.25
TEN Y	4/26/96	5.00	95.66	- 1			2
	10/29/96	6.95	93.71	14 b) 2' 5			
	1/15/97	4.02	96.64				
	1/27/98	5.62	95.04	, a			

Notes: SWL in feet below top of casing. Elevations from data in quarterly reports (not Barbieri survey of 7/27/99)."nr" = not reported.

#### **Chart 1 - PREVIOUS GROUNDWATER LEVELS**



#### 2.9. PREVIOUS GROUNDWATER GRADIENT ESTIMATES

Previous groundwater gradient maps in quarterly reports indicate that the direction of groundwater flow may be variable as indicated in Chart 1 above and summarized in the following Table 5 – "Summary of Previously Reported Groundwater Gradients".

Table 5 – SUMMARY OF PREVIOUSLY REPORTED GROUNDWATER GRADIENTS

Report Title	Date of Report	Date of Groundwater Measurement	Monitor Wells Measured	Reported Groundwater Flow Direction
First Quarterly Ground Water Monitoring Report	August 14, 1994	apparently July 18-19, 1994	apparently MW-1 through MW-6	not reported
Third Quarterly Ground Water Monitoring Report	June 15, 1995	January 24, 1995	MW-1 through MW-6	"virtually flat"
Fourth Quarterly Ground Water Monitoring Report	June 22, 1995	June 20, 1995	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9	southeast
Fifth Quarterly Ground Water Monitoring Report	October 18, 1995	September 29, 1995	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9	northwest
Sixth Quarterly Ground Water Monitoring Report	February 15, 1996	February 15, 1996	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9	east and west
Seventh Quarterly Ground Water Monitoring Report	May 15, 1996	April 26, 1996	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9	north and southeast
Ground Water Monitoring Report	September 30, 1996	September 17-18, 1996	MW-11 through MW-13	southeast
<b>Eighth</b> Quarterly Ground Water Monitoring Report	November 8, 1996	October 29, 1996	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9 through MW-13	northwest
Ninth Quarterly Ground Water Monitoring Report	February 21, 1997	January 15, 1997	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9 through MW-13	northwest
First Quarter 1998 Ground Water Monitoring Report	February 12, 1998	January 27, 1998	MW-1, MW-2, MW-4, MW-5, MW-6, MW-9 through MW-13	north

#### Notes:

Initial flow directions as reported in Environmental Assessment Phase III report are west-northwest.

#### 2.10. PREVIOUS GROUNDWATER SAMPLING RESULTS


The results of previous groundwater sampling analyses are shown below in the Table 6 – "Previous Groundwater Sampling Analyses" and in Chart 2 – "Previous Groundwater Analyses (Selected Wells)".

Table 6 - PREVIOUS GROUNDWATER SAMPLING ANALYSES (µg/l)

Monitor Well	Date Sampled	В	T	E	X	TPH Gas	Monitor Well	Date Sampled	В	T	Е	X	TPH Gas
MW-1	6/22/93	910	1,300	470	2,090		MW-6	7/18/94	14	7	7	26	
	7/18/94	770	14	264	272			10/28/94	ND	ND	ND	ND	
	10/28/94	729	16	269	145			1/24/95	ND	ND	ND	ND	1
	1/24/95	62	29	349	315			6/20/95	ND	ND	ND	ND	
	6/20/95	619	10	66	377			9/29/95	ND	ND	ND	ND	
	9/29/95	3,700	43	1,050	895			2/15/96	ND	ND	ND	ND	
	2/15/96	727	8	92	261			4/26/96	ND	ND	ND	ND	
	4/26/96	497	17	180	159			10/29/96	ND	ND	ND	ND	
	10/29/96	231	5	18	15			1/15/97	ND	ND	ND	ND	
	1/15/97	83	ND	9	13			1/27/98	ND	ND	ND	ND	
	1/27/98	411	11	66	82		MW-7	6/20/95	4,230	6,410	11,700	16,700	
MW-2	6/22/93	140	13	20	75			9/29/95	540	4	117	74	
	7/18/94	25	ND	ND	187		<	2/15/96	117	26	13	629	
	10/28/94	53	ND	4	4			4/26/96	276	31	70	309	1.51
	1/24/95	108	ND	6	8			10/29/96	298	5	16	55	
	6/20/95	240	ND	ND	4			1/15/97	258	50	60	225	
	9/29/95	208	ND	ND	ND			1/27/98	309	121	315	1,560	14
	2/15/96	26	ND	ND .	ND		MW-8	6/20/95	2,830	312	253	2,830	
	4/26/96	56	ND	ND	ND			9/29/95	1,164	70	211	290	
	10/29/96	54	ND	ND	ND			2/15/96	384	38	111	496	
	1/15/97	9	ND	ND	ND			4/26/96	163	ND	41	208	
	1/27/98	34	ND	ND	ND		- F	10/29/96	ND	ND	ND	ND	
MW-3	6/22/93	1,600	3,800	1,900	10,100	3/		1/15/97	944	153	130	1,690	1-11
	7/18/94	226	141	58	286	F - 1		1/27/98	522	63	230	469	
	10/28/94	18,400	17,400	3,200	20,200		MW-9	6/20/95	ND	ND	ND	2	¥ E
	1/24/95	19,900	21,200	6,170	31,500		The second	9/29/95	ND	ND	ND	ND	
MW-4	6/22/93	3,500	1,500	420	2,360		11, 12, 14, 14, 14, 14, 14, 14, 14, 14, 14, 14	2/15/96	ND	ND	ND	ND	15 often
	7/18/94	7,460	134	2,730	8,120		a test	4/26/96	71	ND	12	9	7420
	10/28/94	8,400	161	5,320	4,724			10/29/96	ND	ND	ND	ND	THE R. L.
	1/24/95	14,900	4,200	1,630	7,500			1/15/97	55	ND	10	15	1 14
	6/20/95	5,130	281	3,150	16,400			1/27/98	ND	ND	ND	ND	L 30 5
	9/29/95	12,900	70	2,090	733		MW-10	9/18/96	ND	ND	ND	ND	ND
	2/15/96	4,490	522	1,500	2,390			10/29/96	ND	ND	ND	ND	
	4/26/96	4,330	257	1,160	3,320			1/15/97	ND	ND	ND	ND	
	10/29/96	490	15	123	442		27	1/27/98	ND	ND	ND	ND	
	1/15/97	4,540	149	739	2,210		MW-11	9/18/96	ND	ND	ND	ND	ND
	1/27/98	2,960	133	513	1,070			10/29/96	ND	ND	ND	ND	
MW-5	6/22/93	500	750	180	1,090			1/15/97	ND	ND	ND	ND	X 100
	7/18/94	237	24	ND	187	- 20	F = \$1 02	1/27/98	ND	ND	ND	ND	
513 ° - W	10/28/94	141	ND	28	35	Q ·	MW-12	9/18/96	ND	ND	ND	ND	ND
- Land	1/24/95	726	10	36	125		- T	10/29/96	ND	ND	ND	ND	Tally 1
Territoria	6/20/95	150	18	4	70			1/15/97	ND	ND	ND	ND	
	9/29/95	386	3	75	63			1/27/98	ND	ND	ND	ND	
	2/15/96	23	ND	ND	9		MW-13	9/18/96	ND	ND	ND	ND	ND
	4/26/96	310	ND	34	30			10/29/96	ND	ND	ND	ND	
	10/29/96	350	2	23	49		111111111111111111111111111111111111111	1/15/97	ND	ND	ND	ND	
	1/15/97	33	ND	2	5	314.0	, , to , , , , , , , , , , , , , , , , ,	1/27/98	ND	ND	ND	ND	
	1/27/98	901	5	17	60	7			500				1

Notes: ND = Not Detected at or above reporting limit; TPH-Gas = gasoline-range hydrocarbons, B=benzene, T=toluene, E=ethylbenzene, X=total xylenes; blank boxes = not analyzed. Lab Report date of 10/28/94 included in "Delco Project Summary Report" dated December 20, 1995 for Delco Company by Northwest Envirocon. Apparently this data was included in a "First" Ouarterly report which is unavailable or missing.

Chart 2 – PREVIOUS GROUNDWATER ANALYSES (Selected Wells)



#### 3. JULY 1999 GROUNDWATER SAMPLING

#### 3.1. GEOLOGY AND HYDROGEOLOGY

The Site is within Pleistocene fine-grained facies of coarse sand to silt deposited by catastrophic floods. The finer sediments are predominantly quartz and feldspar and also contain white mica. The coarser sediments are predominantly Columbia River Basalt fragments. Poorly defined beds of 1- to 3-feet thick have complex layering. Soil development commonly introduces significant clay in the upper 6- to 15-feet. The fine sediments are locally thick and extend upslope to elevation 300- to 350-feet. Local variations to shallow groundwater flow directions may occur due to changes in lithology and thickness of beds.

The northwest trending Oatfield Fault to the north and the sub-parallel Concord Fault to the south bound the Site. The faults are mapped (*ibid.*) as cutting through the youngest sediments, including the Pleistocene fine-grained facies.

The Site is generally at approximate elevation 100-feet mean sea level ("msl"). It is surrounded by gently sloping terrain toward the Willamette River, which flows northerly approximately one-half mile to the west. Wells within one-mile of the Site to the west include two monitoring wells, one industrial well, ten domestic wells (about 42-feet average depth), and one unused well (U.S. Geological Survey Water Resource Division). Most wells develop from basalt aquifers.<sup>2</sup>

#### 3.2. GROUNDWATER GRADIENTS

A survey by Barbieri & Associates, Inc., 7017 NE Hwy 99, Suite 204, Vancouver, WA 98665 of selected monitor well PVC casing tops was completed on July 27, 1999 as reported July 30, 1999 (see Appendix E – "Well Survey Summary by Barbieri & Associates"). The survey was completed based on relative elevations and X-Y coordinates. A survey was completed because the "top of riser elevations" listed for the monitor wells in Appendix D of the report titled "Eighth Quarterly Ground Water Monitoring Report" dated November 8, 1996 by NWE for Delco cannot be verified (no reference to a completed survey in reports or attached documentation). An accurate survey of relative elevations is necessary to estimate groundwater flow and directions.

The groundwater flow direction is estimated to be north-northwesterly based on July 1999 static water level measurements (see Figure 3 – "Groundwater Gradient Map: July 1999"). The inferred groundwater gradient from Monitor Well MW-13 (4884.4892N, 5056.2117E) to Monitor Well MW-11 (5035.1486N, 4984.8006E) is approximately 0.63-feetV per 150.7-feetH, or 0.0042-feet per foot.

An isolated high groundwater peak occurs in the vicinity of Monitor Well MW-5. The cause of this high groundwater is unknown, however a zone of low permeability, such as, a clay lense could cause it. Others causes could be related to the tank field approximately twenty (20)-feet north of the well serving as a sump area; a leak in a water supply pipe; or possibly the well encountered a perched groundwater zone and is screened in multiple groundwater-bearing intervals.

<sup>&</sup>lt;sup>1</sup> "Geologic Map of the Lake Oswego Quadrangle, Clackamas, Multnomah, and Washington Counties, Oregon", M.H. Beeson and Others, State of Oregon Department of Geology and Mineral Industries GMS-59, 1989, 1 Plate.

<sup>&</sup>lt;sup>2</sup> NWE memo dated June 30, 1994.


The following Table 7 – "Monitor Well Elevations and Static Water Levels" and Chart 3 – "July 1999 Static Water Elevations" summarize monitor well relative elevations at the top of the PVC casings and static water levels measured in July 1999.

Table 7 - MONITOR WELL ELEVATIONS AND STATIC WATER LEVELS

Surveyed by Barbieri & Associated, July 27, 1999

Monitor Well	Top of Casing	Date	SWL	SWL Elevation
	Elevation (ft)		Feet BGS	(ft)
MW-1	99.37	7/24/99	5.66	93.71
MW-2	98.51	7/24/99	5.18	93.32
MW-3	decommissioned			
MW-4	99.00	7/25/99	5.57	93.43
MW-5	100.41	7/25/99	5.99	94.42
MW-6	100.01	7/24/99	6.25	93.76
MW-7	recovery well			
MW-8	recovery well		72	
MW-9	99.42	7/23/99	5.64	93.78
MW-10	98.50	7/23/99	4.82	93.68
MW-11	99.64	7/24/99	6.42	93.22
MW-12	100.26	7/24/99	6.88	93.38
MW-13	99.85	7/23/99	6.00	93.85

Chart 3 – JULY 1999 STATIC WATER ELEVATIONS



#### 3.3. GROUNDWATER SAMPLING METHODOLOGY

Prior to purging, the static water level was measured in each well. The monitor wells were purged of stagnant water in the casing and filter pack by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized, or approximately three well volumes were evacuated (see Appendix B - "Water Sample Field Logs"). Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging.

Water samples were placed in clear 40-milliliter vials (volatile organic analysis-VOA) and 1-liter amber glass containers. All sample containers were new (except containing a preservative prepared by the laboratory). Separate vials were used for water samples to be analyzed for gasoline and gasoline constituents (e.g. BTEX). Disposable latex gloves were used at all times during sampling. Closure of each sample container was accomplished with a plastic screw cap onto a Teflon faced septum, which was used to seal the bottle without headspace. Each sample bottle was then inverted and tapped to test for air bubbles. The bottles were labeled and placed in an ice chest with blu-ice for transport to the laboratory. All samples were accompanied from the field to laboratory by a signed and dated chain-of-custody and request for analysis. Two (2) VOA's and one (1) liter bottles were filled with groundwater from each monitor well and the treatment facility spigot for analysis.

#### 3.4. LABORATORY ANALYSES

The following Table summarizes laboratory analysis for groundwater samples collected on July 23-25, 1999. The laboratory report is included in Appendix A - "July 1999 Laboratory Report". Analyses performed were at the request of DEQ.

Monitor Well NWTPH-Gx NWTPH-Dx Benzene (µg/l) Toluene (µg/I) **Ethyl Benzene** Total Xylenes MTBE (µg/I)  $(\mu g/I)$ (mg/I) $(\mu g/I)$  $(\mu g/I)$ MW-1 2,330 ND 340 4.29 9.60 ND 112 MW-2 ND ND 1.54 ND ND ND 113 MW-4 10,300 2,910 ND 109 ND ND  $2.57^{3}$ MW-5 118 ND 35.7 ND ND ND ND ND MW-6 ND ND ND ND ND ND MW-9 ND ND ND ND ND ND ND MW-10 ND ND ND ND ND ND ND MW-11 ND 0.542 ND ND ND ND ND MW-12 ND ND ND ND ND ND ND MW-13 ND ND ND ND ND ND ND ND Treatment ND ND ND ND ND ND

**Table 8 - GROUNDWATER ANALYSIS RESULTS** 

 $\underline{\underline{Notes}: ND = Not\ Detected\ at\ or\ above\ reporting\ limit;\ NWTPH-Gx = gasoline-range\ hydrocarbons,\ NWTPH-Dx = diesel-range\ hydrocarbons,\ B=benzene,\ T=toluene,\ E=ethylbenzene,\ X=total\ xylenes,\ MTBE = methyl\ tert-butyl\ ether(typical\ gasoline\ additive);\ blank\ boxes = not\ analyzed.$ 

Gasoline hydrocarbons were analyzed per NWTPH-Gx Method and BTEX/MTBE were analyzed per EPA Method 8020A. Diesel and Heavy Range Hydrocarbons were analyzed per NWTPH-Dx Method. Total xylenes include m,p- and o-xylenes.

<sup>&</sup>lt;sup>3</sup> MW-4 Heavy Oil Hydrocarbons detected at 0.627 mg/l. All other well samples were ND for Heavy Oil Hydrocarbons.

Moderate sheen and diesel odors were observed during the sample collection at Monitor Well MW-4. No free product was observed during purging or sampling of any of the monitor wells.

#### 4. INTERPRETATIONS AND CONCLUSIONS

#### 4.1. DEQ NOTICE OF VIOLATION

This report has been prepared in partial response to a Notice of Violation, Department Order, and Assessment of Civil Penalty No. WMC/T-NWR-99-064 Clackamas County in the Matter of Devinder Dhillon and Delco Petroleum Co., LLC before the Environmental Quality Commission of the State of Oregon ("Order"). This report is the resumption of quarterly groundwater sampling and reporting as requested in a cover letter to the Order by Certified Mail Z 440 760 423 dated June 7, 1999 from Mr. Langdon Marsh, Director of the Oregon Department of Environmental Quality ("DEQ") to Mr. Devinder Dhillon.

#### 4.2. GROUNDWATER MONITORING

#### 4.2.1. Previous Groundwater Sampling

Nine (9) quarterly monitoring reports and three (3) supplemental reports were briefly reviewed and summarized in this report. The reports on prior investigations include sampling events from July 18, 1994 through January 27, 1998.

Thirteen (13) groundwater monitor wells have been installed in response to potential impact by petroleum hydrocarbons to groundwater following initial Environmental Assessment Phases I through III. Ten (10) monitoring wells are currently accessible for obtaining groundwater samples from a shallow groundwater horizon (15 to 20-feet total depth bgs). Monitoring Well MW-3 was decommissioned on February 20, 1995.

On January 27, 1995, monitor wells MW-7 and MW-8 were installed and constructed with four (4)-inch PVC as production wells for the on-Site treatment facility. All other monitor wells are constructed with two (2)-inch PVC. One monitoring well, MW-11, was installed off-site in a down-gradient direction on August 17, 1996, to the northwest, on the "Ed's Muffler & Brakes" property.

The monitor wells are essentially in a configuration representing five (5) upgradient (MW-1, MW-6, MW-9, MW-10, and MW-13), and two (2) downgradient locations (MW-11, MW-12) relative to the suspected contaminant release location at or near the existing USTs. Monitor wells MW-2, MW-4, MW-5, MW-7 and MW-8 are basically located within the suspected contaminant release location of the existing USTs.

No free product was reported in any monitor wells on and after September 29, 1995 (Fifth Quarterly Ground Water Monitoring Report by NWE).

Based on previous reports, groundwater levels have fluctuated approximately four (4)-feet. The groundwater gradient direction has been variable, but generally in a north to northwest direction.

Previous groundwater sampling had detected high concentrations of gasoline constituents BTEX in wells MW-1, MW-2, MW-4, MW-5, MW-7, and MW-8; all of which, except MW-1, are located in the proximity of the suspected contaminant release location. Previous groundwater sampling had detected lower concentrations of BTEX in monitor wells MW-6 (only at time of installation) and MW-9. BTEX had not been detected in monitor wells MW-10, MW-11, MW-12 or MW-13.

#### 4.2.2. July 1999 Groundwater Sampling

Static water levels vary over a foot within the Site, but are generally within one-half foot. The groundwater direction of flow is estimated to be north-northwesterly based on July 1999 static water level measurements. The inferred groundwater gradient from Monitor Well MW-13 (upgradient) to Monitor Well MW-11 (downgradient) is approximately 0.0042-feet per foot.

A groundwater high peak occurs in the vicinity of Monitor Well MW-5. The cause of the high groundwater is unknown, however a zone of low permeability, such as, a clay lense could cause it. Others causes could be related to the tank field approximately twenty (20)-feet north of the well serving as a sump area; a leak in a water supply pipe; or possibly the well encountered a perched groundwater zone and is screened in multiple groundwater-bearing intervals.

The July 1999 groundwater sampling event resulted in gasoline-range hydrocarbons being detected in samples from monitor wells MW-1, MW-2, MW-4, and MW-5. MTBE, a typical gasoline additive, was detected in samples from MW-1 and MW-2. Concentrations of benzene above 5  $\mu$ g/l (ppb) were detected in samples from MW-1, MW-2, MW-4, and MW-5. Toluene was detected in a sample from one (1) monitor well (MW-1) at 4.29  $\mu$ g/l. Ethylbenzene was detected in two (2) well samples: 9.60  $\mu$ g/l (MW-1) and 109  $\mu$ g/l (MW-4). Total xylenes were not detected in any well samples.

A low concentration of diesel-range hydrocarbons (2.57 mg/l) was detected in the groundwater sample from monitor well MW-4. Moderate sheen and diesel odors were observed during the sample collection of Monitor Well MW-4. No free product or sheen was observed during purging or sampling of any other monitor wells.

The results of analyzing groundwater samples from MW-2, MW-4, and MW-5 in July 1999 indicate that previous leakage from the gasoline USTs, pipelines, or associated facilities, and possibly the diesel UST, are potential sources of contamination to shallow groundwater.

The potential source of contaminants detected in the groundwater sample from the upgradient monitor well MW-1 cannot be identified. The analysis of groundwater samples collected from monitor well MW-13, located approximately thirty (30)-feet southwest of MW-1, has resulted in non-detection since September 18, 1996.

#### 5. RECOMMENDATIONS

#### 5.1. FURTHER WORK

It is recommended that further quarterly groundwater sampling work be performed following a DEQ review of this report and accompanying documentation. It is recommended that a meeting be sought with DEQ representatives as soon as feasible to discuss the interpretations and conclusions of this report.

It is recommended that future groundwater sampling of monitor well MW-6 not be performed because no analyzed constituents have been detected since July 18, 1994. The purpose or location is redundant with respect to adjacent monitor well MW-13 which is located nearby in an upgradient direction to the potential source of contamination .

It is planned to excavate the gasoline and diesel USTs in the near future. After excavation, the purpose of Monitor Wells MW-4, MW-7 and MW-8 should be reviewed since the source of potential contamination will be removed.

#### 6. LIMITATIONS

This report is restricted to an investigation which has included the review of previous work involving underground storage tanks which contained known or suspected hazardous products identified either by the property owner(s), historical records, or previous reports. Such records and investigations have been relied upon in good faith, however, no responsibility is accepted for errors or omissions of previous work. Drilling services were performed under separate agreement with the landowner and Consultant makes no claim of responsibility for services provided by drilling services or others.

It is possible that exploration or sampling by others failed to reveal the presence of hazardous materials at areas where hazardous materials were assumed, suspected or expected to exist. Client understands that third-party failures to discover contaminated or hazardous materials through appropriate and mutually agreed-upon sampling techniques does not guarantee that such materials do not exist at the Site. Similarly, a Site which in fact is unaffected by contaminated or hazardous materials at the time of exploration or sampling, may later, due to natural causes or human intervention, become contaminated. Consultant is not responsible for failing to locate groundwater monitoring wells which have not discovered hazardous materials at the time of this report or in the future.

This report should not be construed as presenting a value to the Site nor the condition as to construction capabilities. In the event of changes in future development plans as understood at the time of this report, the conclusions and recommendations made herein shall be invalid until given the opportunity to review and modify this report in writing.


Services were performed, findings obtained, and recommendations prepared in a manner generally exercised by members of the profession under similar conditions at the time services were rendered. This warranty is in lieu of all other warranties, either expressed or implied. Findings apply only to present conditions, and opinions expressed are subject to revision when additional or new information is submitted in writing. This report has been prepared for the landowner(s) or landowner's agents and Consultant shall not accept liability or responsibility for detachment, partial use or separation by third parties and such use shall be at user's sole risk.


Portions of an Agreement to perform professional services for the Client may or may not be disclosed in this report. Final approval of environmental investigations and remediation is authorized only by appropriate governmental agencies.

Respectfully submitted,

Richard C. Kent, R.G. Professional Geologist

Figure 1 - LOCATION MAP
Source: U.S.G.S. Topographic Map, Gladstone Quadrangle, 1:24,000







GeoPro Geologic Services Battle Ground, WA

August 4, 1999

Project No. 990621

Legend

Monitor Well Location

MW-13

APPROXIMATE SCALE


0 40

1 inch = 40 feet

#### SITE MAP

DELCO PETROLEUM CO. LLC 17873 SE McLoughlin Blvd. Milwaukie, OR

Figure 3 – GROUNDWATER GRADIENT MAP: JULY 1999



 $<sup>^{1}</sup>$  Grid used in Figure 3 from Barbieri survey; relative elevations.

# **APPENDIX A**

# JULY 1999 LABORATORY REPORT

www.ncalabs.com

Portland 9/405 Avoi 16x 506,079,0790 9/405 AV Nimbus Avonue, Beaverton, OR 97008-7132 503,006,9700 fax 503,906 9710 9/332 (hiptor Avenue, Sulfe F-1, Band, OB 97701-5711 541,383,9310 fax 541,382,7588

Goolira P.O. Box 26

Battle Ground, WA 98604

Project: Delco Groundwater

Project Number: 990621

Project Manager: Richard Kent

Sampled: 7/23/99 to 7/25/99

Received: 7/26/99 Reported: 8/4/99 10:03

#### ANALYTICAL REPORT FOR SAMPLES:

Sample Description	Laboratory Sample Number	Sample Matrix	Date Sampled
MW-1	P907456-01	Water	7/24/99
MW-2	1907456-02	Water	7/25/99
MW-1	P907456-03	Water	7/25/99
MW-5	1907456-04	Water	7/25/99
MW-6	P907456-05	Water	7/24/99
MW-7/8 Separator	P907456-06	Water	7/25/99
MW-9	1907456-07	Water	7/23/99
MW-10	1907456-08	Water	7/23/99
MW-11	P907456-09	Water	7/24/99
MW-12	P907456-10	Water	7/24/99
MW-13	P907456-11	Water	7/23/99

North Creek Analytical - Portland

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Seattle 18939-120th Avenue Nr. Suite 101, Bothell, WA 98011-9508

425 420 9200 Tox 425 420 9210

Spokane Tast 11136 Montgomery, Spite B, Spokane, WA 99206-4776
509 924 9200 fax 509 924 9290

Portland

500 624.0200 148 files 824.9290 9405 5W Ninthins Avenue, Beaverton, OR 97008 7132 503.906 9200 fax 503.906.9210 20332 Empite Avenue, State E.1, Bend, OR 97701-6713 541.303.9316 fax 541.362 7588

GeoPro

P.O. Box 26

Battle Ground, WA 98604

Project: Delco Groundwater

Project Number: 990621

Project Manager: Richard Kent

Sampled: 7/23/99 to 7/25/99

Received: 7/26/99 Reported: 8/4/99 10:03

Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX/MTBE per EPA Method 8020A North Creek Analytical - Portland

	Batch	Date	Date	Surrogate	Reporting			
Analyte	Number	Propared	Analyzed	Limits	Limit	Result	Units	Notes*
MW-1			P9074	<u>56-01</u>			Water	
Benzene	0790809	7/29/99	7/29/99		2.50	340	ug/I	
Toluenc	n	31	n		2.50	4.29	Ar .	
Ethylbenzene	u .	n	н		2.50	9.60		
Xylenes (total)	и.	**	п		5.00	ND	п	
Methyl tert-butyl ether	и	11	u		10.0	112	lt .	2
Gasoline Range Hydrocarbons	h	н	n		400	2330	ĮI.	
Surrogate: 4-BFB (FID)	"	"	"	50.0-150		108	%	
Surrogate: 4-BFB (PID)	n	n	"	75. <b>0</b> -125		105	"	
1			P9074	56-02			Water	
<u>MW-2</u>	0790749	7/28/99	7/28/99	20.02	80.0	ND	ug/l	
Gasoline Range Hydrocurbons	0/90/49	1120/79	11 20/77	50.0-150	7010	113	%	
Surrogate: 4-BFB (FID)	0790809	7/29/99	7/29/99	50.0-150	1.00	1.54	ug/J	
Benzene	0/90809	ルングラン	1129199		1.00	ND	11	
Toluene	u u	11	H		1.00	ND	P	
Ethylbenzene	n	11	U		2.00	ND	U	
Xylenes (total)	"	,,	D .	7 'T	4.00	113	ur.	2.
Methyl tert-butyl ether	"	"	,,	75 () 175	4.00	96.2	%	-
Surrogate: 4-BFB (PJD)	"	"	"	75.0-125		90.2	70	
MW-4			P9074	56-03			Water	
Benzene	0890002	8/2/99	8/2/99		25.0	2910	пñ\J	
Toluene	- и	11	H		25.0	ND	D.	
Ethylbenzene	II	AT .	11		25.0	109	п	
Xylenes (total)	11	n	n		50.0	ND	O .	
Methyl tert-butyl ether	н	N .	n		100	ND	u .	
Gasoline Range Hydrocarbons	n	16			4000	10300	11	
Surrogate: 4-BFR (FID)	#	н	11	50.0-150		96.2	%	
Surrogate: 4-BFB (P1D)	"	"	н	75.0-125		101	"	

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

Sara McClurg, Project Manager

North Creek Analytical, Inc. **Environmental Laboratory Network**  Page 2 of 11

18939 120th Avenue Nt., Suite 101, Bothell, WA 98011-9508 Seattle

425.476.9200 tox 425.420.9210 Fast 11116 Montgonery, Suite B, Spokane, WA 99206-4776 509.994.9200 fox 509.924.9290

Spakane

9405 SW Nimbus Avenue, Beaverton, UR 97008 7132 Postland

503,906 9200 Tax 503,906,9210

20332 Empire Avenue, Sulle 1-1, Hend, UR 97701-5711

541 383 9310 Tox 541.882.7588

GcoPro Delco Groundwater Sampled: 7/23/99 to 7/25/99 Project Number: 990621 Received: 7/26/99 P.O. Box 26 Reported: 8/4/99 10:03 Battle Ground, WA 98604 Project Manager: Richard Kent

#### Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX/MTBE per EPA Method 8020A North Creek Analytical - Portland

	Batch	Date	Date	Surrogate	Reporting			
Analyte	Number	Prepared	Analyzed	Limits	Limit	Result	Units	Notes
MW-5			P9074:	56-04			Water	
Benzene	0790809	7/29/99	7/29/99		0.500	35.7	ug/l	
Foluene	0720802	1122122	11		0.500	ND	ug/i	
Sthylbenzene	n	n .	10		0.500	ND	)r	
Xylenes (total)	n	1r	r		1.00	ND	ļi.	
Methyl tert-butyl ether	n	11	n		2.00	ND	ti.	
	n	11	n		80.0	118	ır	
Gasoline Range Hydrocarbons	"	н	"	50.0-150	<b>6</b> V.V	92.6	%	
Surrogate: 4-BFB (FID)	n,	,,	,,	75.0-125		93.6	70 "	
Surragate: 4-BFB (P1D)	-			75.0-125		93.0		
MW-6			P9074	56-05			Water	
Benzene	0790749	7/28/99	7/28/99		0.500	ND	ug/I	
l'oluene	b	U	11		0.500	ND	н	
Ethylbenzene	II.	11	11		0.500	ND	ь	
Xylenes (total)	ш	n	10		1.00	ND	п	
Methyl tert-butyl other	n	н	11		2.00	ND	н	
iasoline Range Hydrocarbons	п	н	н		80.0	ND	h	
Surrogate: 4-BFR (FID)	"	"	"	50.0-150		103	36	
Surrogate: 4-BFB (PID)	"	"	"	75.0-125		86.2	"	
MW-7/8 Separator			P9074:	56-06			Water	
Benzene	0790749	7/28/99	7/28/99		0.500	ND	ug/I	
l'oluene	"	0	11		0.500	ND	IF.	
Sthylbenzene	п	11	n		0.500	ND	14	
Xylenes (total)	h	n	u		1.00	ND	14	
Methyl tert-butyl ether	u	п	U		2.00	ND	n	
Gasoline Range Hydrocarbons	п	н	n		80.0	ND	- h	
Surrogate: 4-BFR (FID)	"	n	"	50.0-150	1317.17	104	%	
Surrogate: 4-BFB (PID)	n	"	11	75.0-125		87.8	"	
MW-9			P90743	56 N7			Water	
Benzene	0790749	7/28/99	7/28/99	EMEN (	0.500	ND	ug/l	
	0/90/49	//26/99	1126/99		0.500	ND	ug/i	
Foluene	11	11	11		0.500	ND	п	
(thylbenzene		11	0		1.00		0	
Xylenes (total)	"	,,	0			ND	, i	
Methyl tert-butyl ether	"	,, D			2.00	ND	"	
Gasoline Range Hydrocarbons	"	"	"		80.0	ND		
Surrogate: 4-BFB (FID)				50.0-150		96.8	%	
Surrogate: 4-BFB (PID)	n	и	"	75.0-125		83.0	n	

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

Sará McClurg, Project Mauager

Seattle 18939 120th Avenue NL, Suite 101, Botten, WA 98011-9508 425, 420,9700 1ax 425, 420,9710 1ax 11115 Montgonery, Saite II, Spekane, WA 90206 4776 509,974 9790 (ax 509,974 9790)

Portland 9405 SW Nimbus Avenue, Beaverlon, OR 97005 7132 503.901.9200 fox 503.906.9210 20302 Empire Avenue, Soite I-1, Bond, OR 97704-5713 541.383.0319 fax.541.382.7588



7/23/99 to 7/25/99 Sampled: Project: Delco Groundwater Geoliro 7/26/99 Received: 990621 Project Number: P.O. Box 26 Reported: 8/4/99 10:03 Richard Kent Project Manager: Baule Ground, WA 98604

#### Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX/MTBE per EPA Method 8020A North Creek Analytical - Portland

	Batch	Date	Date	Surrogate	Reporting			
Analyte	Number	Prepared	Analyzed	Limits	Limit	Result	Units	Notes*
							Water	
<u>MW</u> -10		1.010	P9074:	<u>56-08</u>	0.500	ND	Water	
Benzene	0790749	7/28/99	7/28/99		0.500		ug/l	
l'oluene	п	N .	н		0.500	ND	"	
Ethylbenzene	11	ır	п		0.500	ND		
Xylenes (total)	11	н	10		1.00	ND	н	
Methyl tert-butyl other	Ü.	п	U		2.00	ND	II.	
Gasoline Runge Hydrocarbons	α	o.	9		0.08	ND	11	
Surrogate: 4-BFB (FID)	#	11	"	50.0-150		102	%	
Surrogale: 4-BFB (PID)	"	n	п	75.0 125		87.6	"	
MW-11			P9074	56-09			Water	
	0790749	7/28/99	7/28/99		0.500	ND	ug/l	
Benzene	0/30/49	0	11		0.500	ND	0	
Toluene	п	n	u .		0.500	ND	11	
Ethylbenzenc	tt	11	п		1.00	ND		
Xylenes (total)	11	R	10 E.		2.00	ND	IP.	
Methyl tert-butyl other	11	н	19		80.0	ND	н	
Gasoline Range Hydrocarbons	"	,,	"	50.0-150	60.0	108	%	
Surrogate: 4-BFB (FID)	"	"	"			90.6	"	
Surrogate: 4-BFB (PID)	"	"		75.0-125		<b>9</b> 17.17		
MW-12			<u>1'9074</u>	56-10			Water	
Велиене	0790809	7/29/99	7/29/99		0.500	ND	ug/l	
Toluene	Н =	n	п		0.500	ND	11	
Ethylbenzene	D	0	ei .		0.500	ND	11	
Xylenes (total)	D	п	11		1.00	ND	п	
Methyl tert-butyl other	U	u	a .		2.00	ND	**	
Gasoline Range Hydrocarbons	n	11	U	*	0.08	ND	n .	
Surrogate: 4-BFB (FID)	"	n	<i>"</i>	50.0-150		95.8	%	
Surrogate: 4-BFB (PID)	11	n	n	75.0-125		95.0	n	
BASS/ 12			P9074	156-11			Water	
MW-13	0790749	7/28/99	7/28/99		0,500	ND	ug/l	
Benzene	0/90/49	11 20199	н		0.500	ND	u .	
Toluene	u u	II.	ri .		0.500	ND	41	
Ethylbenzene	II .	н	11		1.00	ND	н	
Xylenes (total)		" 11	n		2.00	ND		
Methyl tert-butyl ether	11	u u	n n		80.0	ND	n	
Gasoline Range Hydrocarbons		n	"	00 150	80.0			
Surrogate: 4-BFB (FID)	u			50.0 150		107	%	
Surrogate: 4-BFB (PID)	"	"	11	75.0-125		92.2	"	

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

Sara McClury, Project Manager

Scattle 10939 120th Avenue NL, Spite 101, Bothell, WA 98011-9508

109.0 1200 Avenue W. 120.9210 125.121115 Montgomery, Suite B. Spokana, WA 99206-4776 509.924.9200 Grx 509.924.9290 9405 SW Nindus Avenue, Resverton, OR 97008-7132 Spokano

Portland

503 309 9200 fax 503.006.0910 20332 Empire Avenue, Suon E-1, Hand, GR 97701-5711 541.303.9310 fax 541 382 7688

GeoPro

P.O. Box 26

Battle Ground, WA 98604

Project: Delco Groundwater

Project Number: 990621

Project Manager: Richard Kent

7/23/99 to 7/25/99 Sampled:

7/26/99 Received: 8/4/99 10:03 Reported:

#### Diesel and Heavy Range Hydrocarbons per NWTPH-Dx Method North Creek Analytical - Portland

	Batch	Date	Date	Surrogate	Reporting			green and
Analyte	Number	Prepared	Analyzed	Limits	Limit	Result	Units	Notes'
MW-1			<u>P9074</u>	<u>56-01</u>			Water	
Diesel Range Organies	0790712	7/27/99	7/28/99		0.250	ND	mg/l	
Icavy Oil Runge Hydrocarbons	н	n	11		0.500	ND		
Surrogate: I-Chlorovetudecane	"	11	"	50.0-150		84.5	%6	
MW-2			P9074	<u>56-02</u>			Water	
Diesel Range Organies	0790821	7/29/99	7/29/99		0.250	ND	mg/l	
leavy Oil Range Hydrocarbons	и	п	D		0.500	ND	н	
Surrogate: 1-Chlorooctadecane	11	n	"	50.0-150		81.0	%	
							***	
M <u>W-4</u>			P9074	<u>56-03</u>		4	Water	
Diesel Range Organics	0790821	7/29/99	7/29/99		0.250	2.57	mg/l	3
Heavy Oil Range Hydrocarbons	D.	0	10		0.500	0.627		
Surrogate: 1-Chlorooctadecane	11	"	"	50.0-150		104	%	
•				±			Water	
MW-5			P9074	<u>56-04</u>	0.050	NIA		
Diesel Range Organies	0790821	7/29/99	7/29/99		0.250	ND	mg/l	
Heavy Oil Range Hydrocarbons	н	II.	11		0.500	ND		
Surrogate: 1-Chlorooctadecane		"	"	50.0-150		105	%	
and the second s			P9074	EG 05			Water	
<u>MW-6</u>		B/08/00	7/28/99	20-02	0.250	ND	mg/l	
Diesel Range Organics	0790712	7/27/99	1120199		0.500	ND	11	,
Heavy Oil Range Hydrocarbons		"	 11	50.0-150	0.500	94.6	%	
Surrogate: 1-Chlorooctadecane	"	. "		30.0-130		24.0	70	
- 4111 - E10 G			P9074	156- <u>06</u>			Water	
MW-7/8 Separator	0790821	7/29/99	7/29/99	<u></u>	0.250	ND	mg/I	
Diesel Range Organics	0/90621	1127177	11		0.500	ND		
Heavy Oil Range Hydrocarbons	"	n 2	11	50.0-150		105	96	
Surrogate: 1-Chlorooctadecane				,70.0-150				
MW-9			P9074	<u>156-07</u>			Water	
Diesel Range Organics	0790712	7/27/99	7/28/99	The state of	0.250	ND	mg/l	
	0790712	11	11 20,77		0.500	ND	н	
Heavy Oil Range Hydrocarbons Surrogate: 1-Chlorooctadecana	<i>n</i> .	#1	"	50.0-150		49.5	%	4
Surrogate: 1-Cntoroocuaecane				- 11.15				
MW-10			P9074	456-08			Water	
Diesel Range Organics	0790712	7/27/99	7/28/99		0,250	ND	mg/l	
Heavy Oil Range Hydrocarbons	H	11	н		0.500	ND	**	
	n - n	ır.	**	50.0-150		99.6	%	
Surrogate: 1-Chlorovetadevane				20.0 100				

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

Sara McClurg, Project Manager

North Creek Analytical, Inc. **Environmental Laboratory Network**  Page 5 of 11

www.ncalabs.com

Seattle 10909 120th Avenue NIII, Suite 101, Bothell, WA 98011 9608

425,420,9200 fax 425,420,9210 Last 11115 Muntgoneery, Sulte B, Spokann, WA 99206-4776

Spokane 509 924 9200 fax 509 924 9290

9405 SW Nimbus Avenue, Desverton, Olt 97000-7132 503,906,9200 fax 503,906,9210 Portland

20339 Umpire Avenue, Saite F. 1. Bend. OR 97701 5711 541 383 9310 Tax 541 382 7586

GeoPro

Project: Delco Groundwater

Sampled:

7/23/99 to 7/25/99

P.O. Box 26 Battle Ground, WA 98604 Project Number: 990621

Project Manager: Richard Kent

Received:

7/26/99 Reported: 8/4/99 10:03

#### Diesel and Heavy Range Hydrocarbons per NWTPH-Dx Method North Creek Analytical - Portland

	Batch	Date	Date	Surrogate	Reporting	···		
Analyte	Number	Prepared	Analyzed	Limits	Limit	Result	Units	Notes*
MW-11			P9074	56- <u>09</u>			Water	
Diesel Range Organics	0790712	7/27/99	7/28/99		0.250	0.542	mg/l	5
Heavy Oil Range Hydrocarbons	п	н	M		0.500	ND		
Surrogate: I-Chlorooctadecane	"	"	"	50.0-150		95.5	%	
MW-12			P9074:	56-10			Water	
Diesel Range Organies	0790712	7/27/99	7/28/99		0.250	ND	mg/l	
Heavy Oil Range Hydrocarbons	H	li .	и		0.500	ND	11	
Surrogate: 1-Chlorooctadecane		"	n.	50.0-150		99.0	%	
MW-13			P9074	<u> </u>			Water	
Diesel Range Organics	0790712	7/27/99	7/28/99		0.250	ND	mg/l	
Heavy Oil Range Hydrocarbons	16	11:	11		0.500	ND	11	
Surragate: 1-Chlorooctadecane	u .	"	11	50.0-150		111	%	

www.ncalabs.com

Seattle 18939 120th Avenue NI., Suite 101, Bothell, WA 98011 9908 426 A20 9200 fax 475.470.9210 Fast 11115 Montgomery, Suite B, Spokane, WA 99206 4776 509.924.9200 fax 509.924.9290 Fast 1110 Proceedings of the State of State of

509 524.5200 for 509 HZ4 MZ40 9A65 SW Nimbus Avenue, Deaverton, Off 97008 7132 503.906,9200 for 503.906.9210 20332 Lippins Avenue, Suite F 1, Bend, DR 97701-5711 541 383.9310 for 541.382.7588

GeoPro P.O. Box 26

Battle Ground, WA 98604

Project: Deleo Groundwater

Project Number: 990621 Project Manager: Richard Kent Sampled: 7/23/99 to 7/25/99

Received: 7/26/99 Reported: 8/4/99 10:03

#### Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX/MTBE per EPA Method 8020A/Quality Control North Creek Analytical - Portland

	Date	Spike	Sample	QC	I, - Me	Reporting Limit		RPD	RPD	
Analyte	Analyzed	Level	Result	Result	Units	Recov. Limits	%	Limit	%	Notes*
D4U. 0700740	Date Prepa	red: 7/29/	)()		Extrac	tion Method: EP.	A 5030			
Butch: 0790749	0790749-BI		<u> </u>		,,,,,,,,					
Blank	7/28/99	<u> </u>		ND	սջ/1	0.500				
Benzene	1120177			ND	10	0.500				
Tolucne	ıı			ND		0.500				
Ethylbenzene	п			ND	TI.	1.00				
Xylencs (total)	9			ND	11	2.00				
Methyl tert-butyl other				ND	11	80.0				
Gasoline Range Hydrocarbons	,,	E0.0		50. I	"	50.0-150	100			
Surrogate: 4-BFB (FID)		50.0			N	75,0-125	81.4			
Surrogate: 4-BFB (PID)	н	50.0		40.7		73,U-123	N1.4			
LCS	0790749-В	51								
Gasoline Range Hydrocarbons	7/28/99	1250		1150	սջ/1	50.0-150	92.0			
Surrogate: 4-BFB (FID)	"	50.0		62.1	"	50,0-150	124			
LCS	0790749-BS	52								
Renzene	7/28/99	20.0		17.0	ug/l	69.0-138	85.0			
Toluene	10	20.0		17.6	0	61.0-141	88.0			
Ethylbenzene		20.0		18.4	II .	53.0-151	92.0			
Xylenes (total)	n	60.0		56.5	H	62.0-144	94.2			
Mothyl tert-hutyl ether	ш	20.0		18.2	*1	60.0-140	91.0			
Surrogate: 4-BFB (PID)	"	50.0		44.7	"	75.0-125	89.4			
Duplicate	079 <b>0749-</b> D	UP1 P	907456-01							
Gasoline Range Hydrocarbons	7/28/99		2210	2140	ug/l			50.0	3.22	
Surrogate: 4-BFR (FID)	"	30.0		99.2	"	50.0-150	198			
Duplicate	079 <u>0749-D</u>	UP2 P	907456-02							
Gasoline Range Hydrocarbons	7/28/99		ND	ND	ug/I			50.0		
	"	50.0	112	52.0	"	50.0-150	104			
Surrogate: 4-BFB (FID)		30.0		52.17		27.0 22.0				
Matrix Spike	0790749-M		90745 <u>6-03</u>							
Benzene	7/28/99	20.0	1620	1140	ug/l	67.0-130				6,
Toluenc	II .	20.0	22.5	46.4	11	76.0-124				
Dihylbenzene	n	20.0	119	122	н	75.0-126				
Xylenes (total)	н	60.0	68.1	123	TI.	75,0-126	91.5			
Surrogate: 4-BFB (PID)	"	50.0		77,2	n	75.0-125	154			

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

North Creek Analytical, Inc. **Environmental Laboratory Network**  Page 7 of 11

www.ncalahs.com

18930 120th Avenue NF, Suita 101, Bothell, WA 98011-9506 425,420 9200 fax 426,420,9210 Last 11115 Montgomery, Suita B, Spokana, WA 99206 4776 509 924 9200 fax 509,924,9290

Spokane

940h SW Nimbes Avenue, Beavertos, UR 97008 7132 503.806.9200 fax 503.906.9210 20332 [mpite Avenue, Suite L.1, Bend, UR 97701-5711 Portland

541 383 9310 Tax 641 382 7688

7/23/99 to 7/25/99 Geol'ro Project: Deleo Groundwater Sampled: P.O. Box 26 Project Number: 990621 Received: 7/26/99

8/4/99 10:03 Battle Ground, WA 98604 Project Manager: Richard Kent Reported:

#### Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX/MTBE per EPA Method 8020A/Quality Control North Creek Analytical - Portland

	Date	Spike	Sample	QC		Reporting Limit	Reçov.	RPD	RPD	
Analyte	Analyzed	Level	Result	Result	Units	Recov. Limits	%	Limit	%	Notes*
1,414.4				,						
Matrix Spike Dup	<u>0790749-M</u>		907456-03	44.50		<b></b>		15.6		
Benzene	7/28/99	20.0	1620	1150	ug/l	67.0-130	NR	13.0		6,E
Toluene	11	20.0	22.5	40.1		76.0-124	88.0	15.0	30.8	7
Ethylbenzene	n.	20.0	119	126	+1	75.0-126	35.0	13.0	80.0	6
Xylenes (total)	li	60.0	68.1	120	11	75.0-126	86.5	13.0	5.62	
Surrogate: 4-BFB (PID)	"	50.0		85.0	"	75.0-125	170			1
Batch: 0790809	Date Prepa	red: 7/29/5	<u>)9</u>		Extrac	tion Method: EP.	A 5030			
Blank	0790809-BI	.K1								
Benzene	7/29/99			ND	ug/l	0.500				
Toluene	11			ND	U	0.500				
Ethylbenzene	н			ND	U	0.500				
Xylenes (total)	D .			ND	tr.	1.00				
Methyl tert-butyl ether	п			NĐ	11	2.00				
Gasoline Range Hydrocarbons	н			ND	11	80.0				
Surrogate: 4-BFB (FID)	ш	50.0		48.0	n	50.0-150	96.0			
Surrogate: 4-BFB (PID)	11	50.0		48.1	n	75.0-125	96.2			
marrigate. 4-101 12 (1-10)		21111								
LCS	0790809-B5	<u>31</u>								
Gasoline Range Hydrocarbons	7/29/99	1250		1160	ug/I	50.0-150	92.8			
Surrogate: 4-BFB (FID)	"	50.0		61.3	"	50.0-150	123			
1.CS	0790809-BS	§2								
Benzene	7/29/99	20.0		19.3	ug/I	69.0-138	96.5			
Toluenc	11	20.0		19.1	"	61,0-141	95.5			
Inhylbenzene	*1	20.0		19.2	17	53.0-151	96.0			
Xylenes (total)	n	60.0		58.6	0	62.0-144	97.7			
Methyl tert-butyl ether	н	20.0		17.8	o	60.0-140	89.0			
Surrogate: 4-BFB (PID)	a	50.0		49.4	n	75.0-125	98.8			
Batch: 0890002	Date Prepa	red · 8/2/0	D		Extract	tion Method: EP.	A 5030			
Blank	0890002-B1		_				- 11717			
Benzene	8/2/99	713.L		ND	ug/I	0.500				
Toluene	11			ND	ug/1	0.500				
	41			ND ND	11	0.500				
Ethylbenzene					11					
Xylenes (total)	i i			ND	11	1.00				
Methyl tert-butyl ether	n h			ND	11	2.00				
Gasoline Range Hydrocarbons		• • • •		ND		80.0				
Surrogate: 4-BFB (FID)		50.0		48.5	"	50.0-150	97.0			

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

Sara McClurg, Project Manager

www.ncalabs.com

Seattle 10939 (Wender W., Sindi 101, Donica, vac soor 1 3556 425 420 9200 fax 425 420,9210 4x 509 924 6290 509.924,9200 fax 509 924 6290 Portland 940,5 W Norther Avenue, Beaverton, 0lt 97008 713? Portland

503 005 9200 Los 503 905 9210 20332 Linpure Avenue, Suite I-1, Bend, OR 97701-6711 541,363,9310 fox 541,382,7588

GcoPro P.D. Box 26 Battle Ground, WA 98604 Project: Deleo Groundwater

Project Number: 990621 Project Manager: Richard Kent Sampled: 7/23/99 to 7/25/99

Received: 7/26/99 Reported: 8/4/99 10:03

#### Gasoline Hydrocarbons per NW TPB-Gx Method and BTEX/MTBE per EPA Method 8020A/Quality Control North Creek Analytical - Portland

	Date	Spike	Sample	QC		Reporting Limit	Recov.	RPD	RPD
Analyte	Analyzed	Level	Result	Result	Units	Recov. Limits	%	Limit	% Notes*
Blank (continued) Surrogate: 4-BFB (PH)	<u>0890002-B</u> 1 8/2/99	<u>LK1</u> 50.0		50.7	ug/l	75.0-125	101		
LCS Gasoline Range Hydrocarbons Surrogate: 4-BFB (FID)	<u>089000<b>2-B</b>:</u> 8/2/99 "	8 <u>1</u> 1250 <i>50.0</i>		1320 63.8	ug/l	50.0-150 50.0-150	106 128		
LCS	0890002-B	<u>S2</u>							
Benzene	8/2/99	20.0		19.9	ug/1	69.0-138	99.5		
Toluene	н	20.0		19.4	11	61.0-141	97.0		
Ethylbenzene	и	20.0		20,2	lf.	53.0-151	101		
Xylenes (total)	ir	60.0		61.2	11	62.0-144	102		
Methyl tert-butyl ether	11	20.0		18.7	н	60.0-140	93.5		
Surrogate: 4-BFB (PID)	"	50.0		51.2	n	75.0-125	102		

North Creek Analytical - Portland

\*Refer to end of report for text of notes and definitions.

Sará McClurg, Project Mapager

North Creek Analytical, Inc. Environmental Laboratory Network Page 9 of 11

18939 120H; Avenue W., Shan But, Bollich, WA 9801 (1900) Scattle

425 420 9200 tax 425,420 9210

 Spokane
 Last 11115 Montgomery, Sulfn B, Spokane, WA 99206-4776

 509.924.9200 Tex 509.924.9290

 Portland
 9405 SW Nimbus Avenire, Beaverton, OR 97006-7132

 503.006 B200 Tex 503.906.9210

20332 i mpire Avenue, Suile F.1, Bend, OR 97701-5711 541,363 9310 fax 541,382 7688

www.ncalabs.com

GeoPro P.O. Box 26 Battle Ground, WA 98604 Project: Delco Groundwater

Project Number: 990621 Project Manager: Richard Kent Sampled:

7/23/99 to 7/25/99

Received: 7/26/99 8/4/99 10:03 Reported:

#### Diesel and Heavy Range Hydrocarbons per NWTPH-Dx Method/Quality Control North Creek Analytical - Portland

	Date	Spike	Sample	QC		Reporting Limit	Recov.	RPD	RPD	
Analyte	Analyzed	Level	Result	Result	Units	Recov. Limits	%	Limit	%	Notes*
	Data Darra		30		Extract	tion Method: TP	H-D Ext	action		
Batch: 0790712	Date Prepa		7.7		PARTIE HE	non Pictrotta				
Blank	0790712-B)	abet		ND	mg/l	0.250				
Diesel Range Organics	7/28/99				ng/i	0.500				
Heavy Oil Runge Hydrocarbons				ND	"		109			
Surrogate: 1-Chlorooctadecane	"	0.100		0.109		50.0-150	109			
LCS	0790712-B	51								
Diesel Range Organics	7/28/99	2.51		2.03	mg/l	50.0-150	80.9			
Heavy Oil Range Hydrocarbons	n	1.03		1.07	11	50.0-150	104			
Surrogate: I-Chlorooctadecane	"	0.100		0.0840	"	50.0-150	84.0			
1.CS Dup	0790712-B	SD1								
Diesel Range Organics	7/27/99	2,51		2.61	mg/I	50.0-150	104	50.0	25.0	
Heavy Oil Range Hydrocarbons	0	1.03		1.25	ıı .	50.0-150	121	50.0	15.1	
Surrogate: 1-Chloroovladveane	"	0.100		0.0975	"	50.0-150	97.5			
Batch: 0790821	Date Prepa	red: 7/29/	99		Extrac	tion Method: TP	H-D Ext	raction		
Blank	0790821-B									
Diesel Runge Organics	7/29/99			ND	mg/l	0.250				
Heavy Oil Range Hydrocarbons	H			ND	*1	0.500				
Surrogate: 1-Chlorooctadecane	"	0.100		0.0915	"	50.0-150	91.5			
1.00	079 <b>0821<u>-1</u>3</b>	<b>C</b> 1								
<u>LCS</u> Diesel Range Organics	7/29/99	2.57		1.93	mg/J	50,0-150	75.1			
	11	1.02		0.830	11	50,0-150				
Heavy Oil Runge Hydrocarbons Surrogate: 1-Chlorocetadecane	п	0.100		0.0985	"	50.0 150	98.5			
LCS Dup	0790821-B				- 0		<b>55.0</b>	#A A	0.50	
Diesel Range Organics	7/29/99	2.57		2.00	mg/l	50.0-150		50.0	3.53	
Heavy Oil Range Hydrocarbons	D.	1.02		0.865	14	50.0-150		50.0	4.09	•
Surrogate: 1-Chlorooctadecane	u	0.100		0.0980	"	50.0-150	98.0			

North Creck Analytical - Portland

\*Refer to end of report for text of notes and definitions.

7/23/99 to 7/25/99

Seattle 18939 120th Avenue NI., Salte 101, Bothell, WA 98011-9508

Sampled:

425,420,9200 Tax 425,420,9210

Fast 11115 Montgomery, Suite B. Spokanc, WA 99266 4776 509 924 9200 fax 509,924,9290

1999,08-04

9405 SW Nimbus Avenue, Beaverlon, OR 97008 7182 Portland

503 806 9200 fax 503,906,9210 20302 (Impite Avenue, Suite I-1, Bond, OR 97701-5711

541.383.9310 Tax 541.382.7588

www.ncalabs.com

GcoPro Project: Delco Groundwater

P.O. Box 26 Project Number: Project Manager: Richard Kent Battle Ground, WA 98604


990621 7/26/99 Received: Reported: 8/4/99 10:03

#### Notes and Definitions


Note E Estimated value. The reported value exceeds the calibration range of the analysis. The surrogate recovery for this sample cannot be accurately quantified due to interference from cocluting organic compounds 1 present in the sample. Analyte hit confirmed by GC/MS. 2 Detected hydrocarbons appear to be due to overlap of gasoline as well as some late diesel-range hydrocarbons that may be from 3 biogenic interference. Surrogate recovery is outside control limits due to matrix interference. 4 Detected hydrocarbons in the diesel range do not have a distinct diesel pattern and may be due to heavily weathered diesel or 5 possibly bingenic interference. The RPD and/or percent recovery for this QC spike sample cannot be accurately calculated due to the high concentration of analyte already present in the sample. The spike recovery, and or RPD, for this QC sample is outside of established control limits. Review of associated batch QC 7 indicates the recovery for this analyte does not represent an out-of-control condition for the batch. DET Analyte DETECTED ND Analyte NOT DETECTED at or above the reporting limit NR Not Reported Sample results reported on a dry weight basis dry Recovery Recov. Relative Percent Difference RPD

North Creek Analytical - Portland

Page 11 of 11



Data File Name Operator Instrument : DUAL FID2 Vial Number : 71 Sample Name : 907456-2 Injection Number: 1 Run Time Bar Code: Sequence Line : 1 : 29 Jul 99 08:05 PM Instrument Method: ENWTPHD.MTH Acquired on Report Created on: 29 Jul 99 08:46 PM Analysis Method : ENWTPHDR.MTH Last Recalib on : 23 JUL 99 05:16 PM Sample Amount : 0 ISTD Amount Multiplier





Coc 99723

8939 T20th Avenue N.E., Suite 101, Bothell, WA 98011-9508
East 11115 Montgomery, Suite B, Spokane, WA 98206-4776
9405 S.W. Nimbus Avenue, Beaverton, OR 97008-7132
20332 Empire Avenue, Suite F-1, Bend, OR 97701-5711

(425) 420-9200 FAX 420-9210 (509) 924-9200 FAX 924-9290 (503) 906-9200 FAX 906-9210 (541) 383-9310 FAX 382-7588



#### **CHAIN OF CUSTODY REPORT**

#### Work Order #:

CLIENT: GEOPR	O GEOLOGIC	SE	RVI	CES	INVO	ICE TO	: De	ELCC	PE	TRO	LEU	m C	D., LL	C	TURN	IAROUNI	O REQUEST in I	Business [	ays*
REPORT TO: ATTN: RICHARD KENT			17873 SE MCLOUGHLIN BLVD.						- 1	Organic & Inorganic Analyses  10 7 5 4 3 2 1 < 1									
ADDRESS: P.O.	BOX 26				1	MIL									10	5	4 3	2 1	< 1
BATT	BOX 26 LE GROWD, WA	49	860	04	1. 1	4	503	-6.	54-	981	2				STD.		um Hydrocarbon An		7
PHONE: 360-666.	1465 FAX:				P.O. N						St	mp	LING	-	2	Marie	3 2	1 <1	7
PROJECT NAME: DELC		\$	J	T		REC	QUEST	ED ANA	ALYSE I	S		T	Т		ST		Please Spe	ecify	
PROJECT NUMBER: 990	621	10 %	Š													OTH	ER		_
SAMPLED BY: rck		4	XO-HOLLIN	I							-			L	*Turnar	ound Requests	less than standard may	incur Rush Ch	arges.
CLIENT SAMPLE	SAMPLING	NWT BTFX/	E	0										l	MATRIX	# OF			NCA WO
IDENTIFICATION	DATE/TIME	2 %	NK				1,46					-,71			(W, S, O)	CONT.	COMME	NTS	ID
1. MW-1	7/24/99:1350	X	X	m <sup>22</sup> h 1											W	3	2 VOA	,14	
2. MW-2	7/24/99: 1545	X	Ϋ́												W	3			
3. MW-4	7/25/99: 1440	X	X							iti ki					W	3			,
4. MW-5	7/25/99: 1330	X	X							- 5					W	3			= "
5. MW-6	7/24/99: 1235	X	X												W	3			1
6. MW-7/8 Separator	7/25/99: 1517	X	X	X	11.5	25 07			T 9		V XI				W	3		-	
7. MW-9	7/23/99: 1845	X	X			7.1-					L		1.	3 14 2	W	3		4	
8. WW-10	7/23/99: 1530	X	X			S. p.r		Ι,		2				Stagen.	W	3			
	7/24/99: 1745	X	X		Tyre:			1					. 2		W	3			
10. MW-12	7/24/99: 1650	X	X												W	3			
11. MW-13	7/23/99: 1605	X	X	150	1 P	12.1									$\sim$	3	V		
12.						Sur T								ir .					
13.																			
14.													7						
15.				- 1		,	F												
RELINQUISHED BY:					DATE:	7/20	1999	RECEI	VED B	Y: /		775	l i i				Andrews Area and Property and Area and	DATE:	
PRINT NAME: RICHARD	KENT FIRM: 6	EOF	20	111	TIME:	125	-2	PRINT	NAME	: (-		//	1.600		FIRM:			TIME:	1 18
RELINQUISHED BY:					DATE:			RECEI	VED B	Y:			2					DATE:	
PRINT NAME:	FIRM:			je uč	TIME:			PRINT	NAME	:	***************************************				FIRM:	***		TIME:	
ADDITIONAL REMARKS:							*										TEMP:		
COC REV 3/99																		PAGE	OF

# **APPENDIX B**

# JULY 1999 WATER SAMPLE FIELD LOGS

August 4, 1999 APPENDIX

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/24/99	WELL NO.: MW-1				
Time Sample Collected: 1350	SAMPLE NO.: MW-1				
COC/RFA Number: 99723	Sampler: rck				
Well as-built depth (ft): 15	Well depth when sampled (ft): 15				
Well install date: 6/18/93	Depth to bottom of aquifer seal (ft): 1.8				
Casing inside diameter (inches): 2	Elevation: 99.37				
WELL PURGE INFORMATION					
Pre-purge static water level (ft): 5.66	Pre-purge volume of water in casing & annulus (gals): 5.7				
Filter pack thickness (inches): 6	Total amount purged (gals): 7.5				
No. of 55-gal drums used for purged water: <1	☑ Purge by bailer ☐ Purge by pump				

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: traffic box seal loose, water in traffic box, moderately slow recharge, traffic cover ID 54772.

SWL at time of sample collection: 7.28 ft.	Other:
Sample temperature: 68.9 °F	Sample color: It gray
Sample conductance: 4.87×10 <sup>-2</sup>	Sample turbidity: slight
Sample pH: 7.66	Sample odor: none

#### Analysis Requested:

NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1325	1.40	70.6	4.65	7.63	v. slight	lt gray
15	1330	4.20	66.6	4.51	7.40	v. slight	lt gray ·
25	1339	7.00	66.3	4.32	7.77	slight	lt gray
29	1340	7.50		-			

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft × 0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 9.34 ft below seal  $\times$  0.163 gals/ft + [annulus] 9.34 ft. below seal  $\times$  0.45 gals/ft = 5.725 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/24/99		WELL NO.: MW-2				
Time Sample Collected: 1445	SAMPLE NO.: MW-2					
COC/RFA Number: 99723	Sampler: rck					
Well as-built depth (ft): 14	Well depth when sampled (ft): 14					
Well install date: 6/18/93	Depth to bottom of aquifer seal (ft): 3.5					
Casing inside diameter (inches): 2		Elevation: 98.51				
WELL PURGE INFORMATION						
Pre-purge static water level (ft): 5.18	Pre-p	e-purge volume of water in casing & annulus (gals): 5.41				
Filter pack thickness (inches): 6	Tota	otal amount purged (gals): 8				
No. of 55-gal drums used for purged water: <1	Purge by bailer 🗖 Purge by pump					

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: water in traffic box; top of PVC cut at angle

SWL at time of sample collection: 5.28 ft.	Other:
Sample temperature: 64.6 °F	Sample color: v. lt gray
Sample conductance: 2.89 ×10 <sup>-2</sup>	Sample turbidity: v. slight
Sample pH: 7.87	Sample odor: none

#### Analysis Requested:

NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1521	1.40	68.0	3.67	7.75	v. slight	lt gray
15	1527	4.20	64.8	3.20	7.84	v. slight	lt gray
25	1535	7.00	64.8	3.06	7.94	v. slight	lt gray
30		8.00	64.6	2.87	7.87	v. slight	lt gray

#### **Purged Volume Example**

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft  $\times$  0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 8.82 ft below seal × 0.163 gals/ft + [annulus] 8.82 ft. below seal × 0.45 gals/ft = 5.41 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ½ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling

Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/25/99	WELL NO.: MW-4				
Time Sample Collected: 1440	SAMPLE NO.: MW-4				
COC/RFA Number: 99723	Sampler: rck				
Well as-built depth (ft): 15	Well depth when sampled (ft): 15				
Well install date: 6/18/93	Depth to bottom of aquifer seal (ft): 3.5				
Casing inside diameter (inches): 2	Elevation: 99.00				
WELL PURGE INFORMATION					
Pre-purge static water level (ft): 5.571	Pre-purge volume of water in casing & annulus (gals): 5.78				
Filter pack thickness (inches): 6	Total amount purged (gals): 8				
No. of 55-gal drums used for purged water: <1	Purge by bailer ☐ Purge by pump				

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: sheen on purge water after first bail; strong diesel odor from wellhead; no free product visible; water in traffic box

SWL at time of sample collection: 5.826 ft.	Other:
Sample temperature: 69.1 °F	Sample color: It gray
Sample conductance: 3.19 ×10 <sup>-2</sup>	Sample turbidity: slight
Sample pH: 3.21	Sample odor: moderate diesel

#### Analysis Requested:

NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1407	1.40	74.2	3.37	8.74	v. slight	lt gray, diesel odor
15	1417	4.20	74.1	3.47	8.86	v. slight	lt gray, diesel odor
25	1425	7.00	70.3	3.26	9.01	v. slight	lt gray, diesel odor
30	1429	8.00	68.6	3.10	8.89	v. slight	lt gray, diesel odor

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft  $\times$  0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 9.429 ft below seal × 0.163 gals/ft + [annulus] 9.429 ft. below seal × 0.45 gals/ft = 5.78 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/25/99	WELL NO.: MW-5					
Time Sample Collected: 1330	SAMPLE NO.: MW-5					
COC/RFA Number: 99723	Sampler: rck					
Well as-built depth (ft): 15	Well depth when sampled (ft): 15					
Well install date: 6/19/93	Depth to bottom of aquifer seal (ft): 3.5					
Casing inside diameter (inches): 2	Elevation: 100.41					
WELL PURGE INFORMATION						
Pre-purge static water level (ft): 5.99	Pre-purge volume of water in casing & annulus (gals): 5.5					
Filter pack thickness (inches): 6	Total amount purged (gals): 7					
No. of 55-gal drums used for purged water: <1	☐ Purge by bailer ☐ Purge by pump					

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: OR WRD ID metal tag in traffic box: 54776; water in traffic box

SWL at time of sample collection: 6.915 ft.	Other:
Sample temperature: 70.9 °F	Sample color: It gray
Sample conductance: 2.56 ×10 <sup>-2</sup>	Sample turbidity: v. slight
Sample pH: 8.76	Sample odor: none

#### Analysis Requested:

#### NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1249	1.40	71.5	2.22	8.42	clear	
15	1258	4.20	69.3	2.07	8.61	clear	
25	1316	7.00	69.7	2.11	8.84	v. slight	lt gray

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft × 0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 9.01 ft below seal  $\times$  0.163 gals/ft + [annulus] 9.01 ft. below seal  $\times$  0.45 gals/ft = 5.5 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling

Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/24/99	WELL NO.: MW-6		
Time Sample Collected: 1235	SAMPLE NO.: MW-6		
COC/RFA Number: 99723	Sampler: rck		
Well as-built depth (ft): 14.5	Well depth when sampled (ft): 14.5		
Well install date: 6/19/93	Depth to bottom of aquifer seal (ft): 3.5		
Casing inside diameter (inches): 2	Elevation: 100.01		
WELL PURGE INFORMATION			
Pre-purge static water level (ft): 6.251	Pre-purge volume of water in casing & annulus (gals): 5.01		
Filter pack thickness (inches): 6	Total amount purged (gals): 7.0		
No. of 55-gal drums used for purged water: <1	■ Purge by bailer □ Purge by pump		

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: traffic cover full of water

SWL at time of sample collection: 7.391 ft.	Other:
Sample temperature: 63.1 °F	Sample color: med gray
Sample conductance: 2.16 ×10 <sup>-2</sup>	Sample turbidity: moderate
Sample pH: 7.24	Sample odor: none

#### **Analysis Requested:**

#### NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1220	1.40	67.9	2.48	7.47	v. slight	yel brn
15	1225	4.20	63.5	2.36	7.13	moderate	gray
25	1231	7.00	63.3	2.23	7.35	moderate	gray

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft × 0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 8.749 ft below seal  $\times$  0.163 gals/ft + [annulus] 8.749 ft. below seal  $\times$  0.45 gals/ft = 5.01 gals.

#### Bailer Volume Example

Bailer dimensions are  $1.5^{\circ}$  ID x 36" long.  $1.5^{\circ}$  = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/23/99	WELL NO.: MW-9
Time Sample Collected: 1845	SAMPLE NO.: MW-9
COC/RFA Number: 99723	Sampler: rck
Well as-built depth (ft): 15	Well depth when sampled (ft): 15
Well install date: 1/27/95	Depth to bottom of aquifer seal (ft): 3
Casing inside diameter (inches): 2	Elevation: 99.42
WELL PURGE INFORMATION	
Pre-purge static water level (ft): 5.641	Pre-purge volume of water in casing & annulus (gals): 5.74
Filter pack thickness (inches): 6	Total amount purged (gals): 8.5
No. of 55-gal drums used for purged water: <1	☑ Purge by bailer ☐ Purge by pump

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: traffic box filled with bentonite, cleaned out; very slow recharge

SWL at time of sample collection: 10.91 ft.	Other:
Sample temperature: 68.2 °F	Sample color: med. gray
Sample conductance: 2.82 ×10 <sup>-2</sup>	Sample turbidity: moderate
Sample pH: 8.18	Sample odor: none

#### **Analysis Requested:**

#### NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1637	1.40	68.9	3.64	7.93	clear	
15	1643	4.20	66.2	3.36	7.95	clear	
25	1654	7.00	67.0	3.34	7.90	slight	med gray
31		8.5	1		-	-	

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft  $\times$  0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] =  $9.36\,$  ft below seal  $\times\,0.163\,$  gals/ft + [annulus]  $9.36\,$  ft. below seal  $\times\,0.45\,$  gals/ft =  $5.74\,$  gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/23/99	WELL NO.: MW-10
Time Sample Collected: 1530	SAMPLE NO.: MW-10
COC/RFA Number: 99723	Sampler: rck
Well as-built depth (ft): 15	Well depth when sampled (ft): 15
Well install date: 8/12/96	Depth to bottom of aquifer seal (ft): 8
Casing inside diameter (inches): 2	Elevation: 98.50
WELL PURGE INFORMATION	
Pre-purge static water level (ft): 4.821	Pre-purge volume of water in casing & annulus (gals): 4.89
Filter pack thickness (inches): 8	Total amount purged (gals): 9.8
No. of 55-gal drums used for purged water: <1	☑ Purge by bailer ☐ Purge by pump

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: OR WRD No. L04479 metal tag in traffic box; water in traffic box; traffic box stamped ID 90055

SWL at time of sample collection: 5.14 ft.	Other:	
Sample temperature: 72.3 °F	Sample color: v. lt yellow brn	
Sample conductance: 2.31 ×10 <sup>-2</sup>	Sample turbidity: v. slight	
Sample pH: 9.18	Sample odor: none	100

#### Analysis Requested:

#### NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1504	1.40	74.2	2.48	9.57	slight	lt gray
15	1511	4.20	79.8	2.31	9.09	v. slight	lt gray
25	1515	7.00	78.0	2.26	9.39	moderate	lt gray
35	1524	9.80	71.9	2.44	9.16	slight	lt gray

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft × 0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 3.72 ft above seal  $\times 0.163$  gals/ft = 0.6 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 7 ft below seal × 0.163 gals/ft + [annulus] 7 ft. below seal × 0.45 gals/ft = 4.89 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/24/99	,	WELL NO.: MW-11		
Time Sample Collected: 1745	5	SAMPLE NO.: MW-11		
COC/RFA Number: 99723	5	Sampler: rck		
Well as-built depth (ft): 15	7	Well depth when sampled (ft): 15		
Well install date: 8/12/96	I	Depth to bottom of aquifer seal (ft): 8		
Casing inside diameter (inches): 2	I	Elevation: 99.64		
WELL PURGE INFORMATION				
Pre-purge static water level (ft): 6.421 Pre-		e-purge volume of water in casing & annulus (gals): 4.3		
Filter pack thickness (inches): 8 Total		amount purged (gals): 7.0		
No. of 55-gal drums used for purged water: <1	⊠ Pur	ge by bailer 🗖 Purge by pump		

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: traffic cover stamped MW 11 90056; metal tag in traffic box OR DWR ID L04488; very slow reacharge

SWL at time of sample collection: 11.16 ft.	Other:
Sample temperature: 65.1 °F	Sample color: v. lt yel brn
Sample conductance: 3.22 ×10 <sup>-2</sup>	Sample turbidity: slight
Sample pH: 8.10	Sample odor: none

#### **Analysis Requested:**

NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1727	1.40	66.5	3.30	8.24	slight	yel brn
15	1734	4.20	64.3	3.22	7.97	slight	yel brn
25	1738	7.00	64.0	3.24	8.05	slight	yel brn

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft  $\times$  0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

 $\underline{\mathbf{2"DATA}}$ : ABOVE SEAL: Volume in 2" PVC in 8" hole = 1.58 ft above seal × 0.163 gals/ft = 0.257 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 7 ft below seal  $\times$  0.163 gals/ft + [annulus] 7 ft. below seal  $\times$  0.45 gals/ft = 4.29 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ½ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/24/99	WELL NO.: MW-12
Time Sample Collected: 1650	SAMPLE NO.: MW-12
COC/RFA Number: 99723	Sampler: rck
Well as-built depth (ft): 15	Well depth when sampled (ft): 15
Well install date: 8/12/96	Depth to bottom of aquifer seal (ft): 8
Casing inside diameter (inches): 2	Elevation: 100.26
WELL PURGE INFORMATION	
Pre-purge static water level (ft): 6.88	Pre-purge volume of water in casing & annulus (gals): 4.47
Filter pack thickness (inches): 8	Total amount purged (gals): 7.0
No. of 55-gal drums used for purged water: <1	☑ Purge by bailer ☐ Purge by pump

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: OR DWR metal tag in traffic box ID L04489; traffic box dry; very slow reacharge

SWL at time of sample collection: 8.56 ft.	Other:
Sample temperature: 65.1 °F	Sample color: v. pale yel brn
Sample conductance: 2.76 ×10 <sup>-2</sup>	Sample turbidity: v. slight
Sample pH: 8.24	Sample odor: none

#### **Analysis Requested:**

#### NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1628	1.40	65.7	2.73	8.29	moderate	yel brn
15	1634	4.20	62.9	2.64	8.13	slight mod.	yel brn
25	1638	7.00	62.2	2.67	8.11	v. slight	yel brn

#### Purged Volume Example

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft  $\times$  0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 1.12 ft above seal × 0.163 gals/ft = 0.18 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 7 ft below seal × 0.163 gals/ft + [annulus] 7 ft. below seal × 0.45 gals/ft = 4.47 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

Post Office Box 26 Battle Ground, WA 98604 (360) 666-1465

#### WATER SAMPLE FIELD LOG

Project Name: Delco Petroleum Groundwater Sampling

Project Number: 990621

Project Location: 17873 SE McLoughlin Blvd., Milwaukie, Oregon 97267

Client: Delco Petroleum Co., LLC

DATE: 7/23/99	WELL NO.: MW-13
Time Sample Collected: 1605	SAMPLE NO.: MW-13
COC/RFA Number: 99723	Sampler: rck
Well as-built depth (ft): 15	Well depth when sampled (ft): 15
Well install date: 8/12/96	Depth to bottom of aquifer seal (ft): 8
Casing inside diameter (inches): 2	Elevation: 99.85
WELL PURGE INFORMATION	
Pre-purge static water level (ft): 6.00	Pre-purge volume of water in casing & annulus (gals): 5.52
Filter pack thickness (inches): 8	Total amount purged (gals): 7.0
No. of 55-gal drums used for purged water: <1	☑ Purge by bailer ☐ Purge by pump

#### SAMPLE COLLECTION INFORMATION

#### Sample Collection Method:

The monitor well was purged of stagnant water in the casing and filter by hand bailing with a disposable bailer until the temperature, conductivity and pH reasonably stabilized or approximately three well volumes were evacuated. Samples were collected with a disposable PVC bailer lowered below the water level which had reached approximately 80% of the static level as recorded prior to purging. Water samples were placed in septum-capped 40-milliliter vials (volatile organic analysis-VOA) and/or 1 or ½-liter amber glass containers. The containers were filled to prevent air-entrapment, sealed with Teflon septums as appropriate, labeled, and placed in an ice chest with blu-ice for transport to the laboratory.

Other Comments: OR DWR ID metal tag in traffic boc L04487; top of traffic box stamped MW-13 90058

SWL at time of sample collection: 6.14 ft.	Other:
Sample temperature: 68.8 °F	Sample color: clear
Sample conductance: 2.58 ×10 <sup>-2</sup>	Sample turbidity: v. slight
Sample pH: 8.28	Sample odor: none

#### **Analysis Requested:**

NWTPH-Gx/BTEX/MTBE, NWTPH-Dx

#### FIELD DATA

Bail No.	Time	Gals. Purged	Temp °F	Cond ×10 <sup>-2</sup>	pН	Turbidity	Comment
5	1747	1.40	82.1	2.91	8.40	slight	yel brn
15	1752	4.20	71.7	2.72	8.40	slight	reddish brn
25	1759	7.00	69.8	2.59	8.31	clear	

#### **Purged Volume Example**

One purged volume is the water contained within the filter pack (annulus) and the casing ("standing water"). Bail approximately 3 purged volumes of water prior to collecting a sample. For example, calculate one purged volume using the following conversions:

2" Sch-40 PVC casing = 0.163 gallons per foot (4" casing is 0.653 gallons per foot). Assume filter pack w/6" annulus (8" hole) has 30% porosity, then 1.5 gals/ft  $\times$  0.30 = 0.45 gals/ft in annulus. A 4" PVC in 10.25" hole, annulus of 6.25", is 1.55 gals/ft.

2" DATA: ABOVE SEAL: Volume in 2" PVC in 8" hole = 0 ft above seal × 0.163 gals/ft = 0 gals.

BELOW SEAL: Volume [in 2" PVC in 8" hole] = 9 ft below seal  $\times$  0.163 gals/ft + [annulus] 9 ft. below seal  $\times$  0.45 gals/ft = 5.52 gals.

#### Bailer Volume Example

Bailer dimensions are 1.5" ID x 36" long. 1.5" = 0.092 gals/ft. 3 ft bailer = 0.28 gals/bail, or about ¼ gal/bail. e.g. 10 ft of water in monitor well x 0.363 gals/ft = 3.63 gallons per volume (assume no water above aquifer seal). 3.63 x 3 = 11 gals. = 3 purged volumes. 11 gals. x 1 bail/0.28 gals = about 40 bails (excluding water above aquifer seal).

# APPENDIX C

# MONITOR WELL LOGS (MW-1 through MW-13)

August 4, 1999 APPENDIX

	ROJECT 1	NАМЕ/LO	CATION:		Project Number	43-93-011	Boring Number	MW-1	
Jiffy Lube Internation Store #1012 17869 S.E.McLoughlin Boulevard			Con- tractor	Geotech Explorations	Drilling Method	6 1/4" Hollow St	em Auger		
Milwaul					Driller	Mike Reneker	Drilling Rig	B-61	
					Start	8:36 a.m. 06/18/93	Completed	9:16 a.m. 06/18/	/93
Landow	ner:	Flying 1	Corpor	ration	Surface Elev.		Logged By	Mark Underhill	
Sar	nple		San	nple	Depth			Observa	ations
Туре	No.	Blow Count	Interval (ft)	Recovery (in.)	Scale 1" = 4'	Descriptions of Materials and Conditions	5	Instrument: hNu Units: ppm	Comments
					0 <u> </u>	— Asphalt Concrete and Gravel Base			
SS	1	4 9 8	2.5-4.0	6	2 - 3 - 4 - 4	GRAVELY SILT; dark grey, damp			
SS	2	1 1	5.0-6.5	6	5	GRAVELY SILT; dark grey, damp	<u>-</u>	0	
SS	3	3 6 7	7.5-9.0	6	7 – 8 – 9 –	MEDIUM GREY CLAY; trace silt.	damp -	0	
SS	4	3 3 5	10.0- 11.5	6	10 -	DARK GREY CLAY; trace silt, dan	np -	0	
SS	5	0 2 4	12.5- 14.0	6	12 <u>-</u> 13 <u>-</u> 14 <u>-</u>	DARK GREY CLAY; trace silt, day		0	
SS	6	5 9 12	15.0- 16.5	6	15 <u> </u>	DARK GREY FINE-MEDIUM SAI	ND; wet —	0	
					17 - 18 - 19 - 20 - 21 - 22 - 23 - VEL DATA	End of Soil Boring at 16.5 feet belo surface. Monitoring Well MW-1 in	w ground — stalled		

	BOREHOLE WATER	R LEVEL DATA
Date	06/18/93	
Time	9:25 a.m.	
GWL	7.0 feet	
Casing Depth	15.0 feet	



Sheet 1 of 1

Project Jiffy Lube International Monitoring Well No.

MW-1

17869 S.E. McLoughlin Blvd.

Elevations:

99.67


Delta No.

43-92-011

Milwaukie, OR

Ground Level:

Top of Riser:



L1	=		FT
L2	= _	2.8	FT
L3	=	10.0	FT
L4	= _	16.5	FT

Installation Completed

Date: 06/18/93

Time: 9:25 a.m.

Date	Time	Water Level*
06/21/93	5:58 p.m.	94.65 feet
9		

Manitoring Wall Water Lavel Mangurements

Measure Point Top of casing

Delta
Consideres, Inc.

Р	ROJECT N	NAME/LO	CATION:	.	Project Number	43-93-011	Boring Number	MW-2	
	be Intern .E. McL				Con- tractor	Geotech Exploration	Drilling Method	6 1/4" Hollow Sta	em Auger
Milwauk	kie, OR				Driller	Mike Reneker	Drilling Rig	B-61	
					Start	10:23 a.m. 06/18/93	Completed	11:16 p.m. 06/18	8/93
Landow	ner:	Flying .	Ј Согро	ration	Surface Elev.		Logged By	Mark Underhill	
Sample Sample		Depth			Observa	ations			
Туре	No.	Blow	Interval (ft)	Recovery (in.)	Scale 1" = 4'	Descriptions of Materia and Conditions	ıls	Instrument: hNu Units: ppm	Comments
					0 -	Asphalt Concrete and Gravel Base			Comments
					1 -			-	
ss	1	2	2.5-4.0	6	2 -	SILTY CLAY, dada	_	30	
33		2 5 6	2.3-4.0	0	3	SILTY CLAY; dark grey, damp	_		
					4	_		_	
SS	2	1 3	5.0-6.5	6	5 -	CLAY; trace silt, dark grey, damp		0	
		1			6 -	_	_	_	
ss	3	<u>2</u> 6	7.5-9	6	7 -	CLAY; trace silt, medium grey, m		0	
		6 8			8				
0.0					9 -		_		
SS	4	2	10.0- 11.0	6	10 -	CLAY; trace silt, dark grey, moist	_	0	
		3	y v		11 -		_	_	
SS	5	2 3	12.5- 14.0	6	13 -	CLAY; trace organics, moist	_	0	
		6	14.0		14 -		_		
ss	6	N/A	15.0-	6	15 -	3" heave-no sample recovered	_		
			16.5		16 -	End of horing at 16.5 feet below g	round surface.		
					17 -	Monitoring Well MW-2 installed.	-		
					18 -		-		
				<i>a</i> –	19 -		-		
					20 -		_		
		8 B			21 -			F	
					22 -		<u>-</u>		
					23 -		·		

	BOREHOLE WATER	LEVEL DATA	
Date	06/18/93		
Time	11:25 a.m.		
GWL	7.0 feet		
Casing Depth	14.0 feet		



Jiffy Lube International Project

Monitoring Well No.

MW-2

17869 S.E. McLoughlin Blvd.

Elevations:


Milwaukie, OR

Top of Riser: 98.79

Delta No.

43-92-011

Ground Level:



L1	=		FT
L2	=	4.5	FT
L3	=	10.0	FT
L4	=	15.5	FT

Installation Completed

Date: 06/18/93 Time: 11:25 a.m.



Well Water Level M	easurements
Time	Water Level*
6:17 p.m.	94.59 feet
	Time

Measure Point Top of casing

F	PROJECT 1	NAME/LO	CATION:		Project Number	43-93-011	Boring Number	MW-3	
Jiffy Lube International Store #1012 17869 S.E. McLoughlin Boulevard				Con- tractor	Geotech Exploration	Drilling Method	6 1/4" Hollow Sta	em Auger	
Milwau	kie, OR				Driller	Mike Reneker	Drilling Rig	B-61	
					Start	10:58a.m. 05/27/93	Completed	11:25 p.m. 05/2	7/93
Landow	ner:	Flying J	Ј Согро	ration	Surface Elev.		Logged By	Mark Underhill	
Sa	ınple	5.1	Sar	nple	Depth		2	Observa	itions
Турс	No.	Blow Count	Interval (ft)	Recovery (in.)	Scale 1" = 4'	Descriptions of Material and Conditions	S	Instrument: hNu. Units: ppm	Comments
					0 -	Asphalt Concrete and Gravel Base			***************************************
					1 -			-	
SS	1	1	2.5-4.0	6	2 –	SANDY SILT; medium grey, damp	_	173 ppm	
		3 2			3 –	-	_		
	2	_	5065		4		_	- 050	
SS	2	3 2 4	5.0-6.5	6	5 <b>-</b> 6 <b>-</b>	CLAYEY SILT; dark grey, moist		259 ppm	
		7			7 -		_		
SS	3	1 2 1	7.5-9.0	6	8 –	CLAY; trace silt, medium grey, dan	- - - np -	57 ppm	
		1			9 _		_	_	
SS	4	l	10.0-	6	10 -	CLAY; trace silt, dark grey, damp	_	0 1	
		2	11.0		11 -	<u> </u>	_		
SS	5	6	12.5-		12 –	SANDY SUT. Jode	_		
33	J	9 46	14.0	6	13 –	SANDY SILT; dark grey, wet	-	0	
		40			14 –		_		
SS	6	6 4	15.0- 16.5	6	15 —	SAND; dark grey, fine-medium san	d, wet —	0	
		7			16 –	End of boring at 16.5 feet below grammer. Monitoring Well MW-3 installed.	ound surface.—		
					17 –		-		
					18 <u> </u>		_		
					20 -	E			
					21 -	<u> </u>		_	
5					22 _	_	-		
					23 –		_		
		L			/EL DATA	<del> </del>	,	±	

	BOREHOLE WATER LEVEL DATA			
Date	06/18/93			
Time	1:55 p.m.			
GWL	7.0 feet			
Casing Depth	15.0 feet			



Sheet 1 of 1

Project Jiffy Lube International

Monitoring Well No.

MW-3

17869 S.E. McLoughlin Blvd.

Elevations:

98.57


Delta No.

43-92-011

Milwaukie, OR

Ground Level: --

Top of Riser:



L1	=		_ FT
L2	=	4.5	_ FT
L3	=	10.0	_ FT
L4	=	16.5	_ FT

Installation Completed

Date: 06/18/93

Time: 1:55 p.m.

Date	Time	Water Level*
06/21/93	5:13 p.m.	94.57 feet

\* Measure Point Top of casing



Р	ROJECT	NAME/LO	CATION	:	Project Number	43-93-011	Boring Number	MW-4	
Jiffy Lu 17869 S	be Intern .E.McL	nation Sto	re #101 Soulevard	2	Con- tractor	Geotech Explorations	Drilling Method	6 1/4" Hollow Sta	em Auger
Milwauk	cie, OR				Driller	Mike	Drilling Rig	B-61	
			*****		Start	2:45 p.m. 06/18/93	Completed	3:23 p.m. 06/18/	/93
Landow	ner:	Flying.	Ј Согро	ration	Surface Elev.		Logged By	Mark Underhill	102
Sample Sample		Depth			Observa	itions			
Туре	No.	Blow	Interval (ft)	Recovery (in.)	. Scale 1" = 4'	Descriptions of Materi and Conditions	als .	Instrument: hNu Units: ppm	Comment
					0 –	Asphalt Concrete and Gravel Base		_	Commen
SS	. 1	6 5 3	2.5-4.0	6	1 — 2 — 3 — 4 —	SILTY CLAY; dark grey, damp		33 ·ppm	
SS	2	4 3 1	5.0-6.5	6	5	CLAYEY SILT; dark grey, moist	- - -	83 ppm	
SS	3	2 4 5	7.5-9.0	6	7 — 8 — 9 —	CLAY; trace silt with organies, m	edium grey, -	2.5 ppin	
SS	4	3 4 5	10.0- 11.0	6	10 _	CLAY; trace silt, dark grey, mois	- - -	0	
SS	5	6 4 5	12.5- 14.0	6	12 <u> </u>	FINE-MEDIUM SAND; dark gre	/, wct	0	
SS	6	3 5 8	15.0- 16.5	6	15 — 16 — 17 —	FINE-MEDIUM SAND; dark green  End of Soil Boring at 16.5 feet be surface. Monitoring Well MW-4	low ground -	0	
		e e e e e e e e e e e e e e e e e e e			18 — 19 — 20 — 21 — 22 — 23 —	surface. Monitoring Well MW-4	installed.		

	BOREHOLE WATER LEVE	L DATA
Date	06/18/93	
Time	3:35 p.m.	
GWL	7.0 feet	
Casing Depth	15.0 feet	



Project Jiffy Lube International

Monitoring Well No.

MW-4

17869 S.E. McLoughlin Blvd.

Elevations:

Delta No.


Milwaukie, OR

Top of Riser:

99.30

43-92-011

Ground Level:



L1	=		FT
L2	=	4.5	FT
L3	=	10.0	FT
L4	=	16.5	FT

Installation Completed

Date: 06/18/93 Time: 3:35 p.m.



Date	Well Water Level Me Time	Water Level*
06/21/93	5:09 p.m.	94.54 feet
	·	

Measure Point Top of casing

PROJECT NAME/LOCATION:			Project Number	43-93-011	Boring Number	MW-5			
Jiffy Lube International Store #1012 17869 S.E. McLoughlin Boulevard					Con-	Geotech Exploration	Drilling Method	6 1/4" Hollow St	em Auger
Milwau	kie, OR				Driller	Mike Reneker	Drilling Rig	B-61	
					Start	9:00 a.m. 06/19/93	Completed	9:37 a.m. 06/19/	/93
Landov	/ner:	Flying .	J Corpoi	ration	Surface Elev.	<u></u> 2	Logged By	Mark Underhill	
Sa	mple		Sar	nple	Depth			Observa	ations
Туре	No.	Blow	Interval (ft)	Recovery (in.)	Scale 1" = 4'	Descriptions of Mate: and Conditions	ials	Instrument: hNu Units: ppm	Comments
					0 –	Asphalt Concrete and Gravel Bas	: -		Comments
# # # # # # # # # # # # # # # # # # #					1 —			_	
SS	1	5	2.5-4.0	6	2 - 3 -	SILT; trace clay, dark grey, dain	p -	0	
		5	1 2		3 — 4 —		-	-	
ss	2	2 3	5.0-6.5	6 .	5 _	CLAYEY SILT; dark grey, dain	oist -	0	
		5	,		6 —		_		
SS	3	2	7.5-9.0	6	7 — 8 —	SILTY CLAY; medium grey, me	ist _	0	
		4	= _		9 _		_	_	
SS	4	5 5 5	10.0- 11.0	6	10 -	CLAY; trace silt, dark grey, moi	st -	0	
					12 _				
SS	5	2 5 10	12.5- 14.0	6	13 —	FINE-MEDIUM SAND; trace or grey/brown, wet	ganies, dark -	0	
					14 —				
SS	6	5 7	15.0- 16.5	6	15 —	- FINE-MEDIUM SAND; dark gre	y, wet	0	
		4	in the second		16 — 17 —	<ul> <li>End of boring at 16.5 feet below</li> <li>Monitoring Well MW-5 installed.</li> </ul>	ground surface.—		
					18 _				
7.2					19 _	_			
					20 _		-	_	
					21 _				
					22 _			_	
					23;			_	

	BOREHOLE WATE	ER LEVEL DATA
Date	06/19/93	
Time	9:45 a.m.	
GWL	7.0 feet	
Casing Depth	15.0 feet	



Project

Jiffy Lube International

Monitoring Well No.

MW-5

17869 S.E. McLoughlin Blvd.

Elevations:

100.66


Delta No.

43-92-011

Milwaukie, OR

Ground Level:

Top of Riser:




L1	=		_ FT
L2	=	4.5	_ FT
L3	=	10.0	_ FT
L4	=	16.5	_ FT

Installation Completed

Date: 06/19/93

Time: 9:45 a.m.

Date .	Time	Water Level*
06/21/93	5:05 p.m.	94.52 feet





P	ROJECT	NАМЕ/LO	CATION:		Project Number	43-93-011	Boring Number	MW-6	
Jiffy Lube International Store #1012 17869 S.E. McLoughlin Boulevard			Con-	Geotech Exploration	Drilling Method	6 1/4" Hollow St	em Auger		
Milwauk					Driller	Mike Reneker	Drilling Rig	B-61	
					Start	11:05 a.m. 06/19/93	Completed	11:56 a.m. 06/1	9/93
Landown	ner:	Flying .	Ј Согро	ration	Surface Elev.		Logged By	Mark Underhill	
San	nple	Diam	Sar	nple	Depth	Davidai a CM as i		Observe	ations
Туре	No.	Blow Count	Interval (ft)	Recovery (in.)	Scale 1" = 4'	Descriptions of Materia and Conditions	1s	Instrument: hNu Units: ppm	Comments
SS	1	4 6 18	2.5-4.0	6	0 1 2 3 4 5 6	Asphalt Concrete and Gravel Base  SANDY SILT; dark grey, damp		0	
SS	2	3 5 6	7.5-9.0	6	7 – 8 – 9 –	SILT CLAY; trace organics, medic	in grey, dainp	0	
SS	3	2 4 5	10.0- 11.0	6	10 -	SILTY SAND; medium grey, mois	-	0	
SS	4	3 7 10	12.5- 14.0	6	12 -	FINE-MEDIUM SAND: dark grey	, wet	0	
SS	5	3 21 3	15.0- 16.5	6	14 — 15 — 16 — 17 — 18 — 19 — 20 — 21 — 22 — 23 —	FINE-MEDIUM SAND; dark grey  End of boring at 16.5 feet below gr Monitoring Well MW-6 installed.		- 0	

	BORLHOLL WATE	CR CETCE DATA	
Date	06/19/93		
Time	12:05 p.m.		
GWL	7.0 feet		
Casing Depth	14.5 feet	*	



Project Jiffy Lube International

Monitoring Well No.

MW-6

17869 S.E. McLoughlin Blvd.

Elevations:

100.29


Delta No.

43-92-011

Milwaukie, OR

Ground Level: ---

Top of Riser:



L1	=		FT
L2	=	4.5	FT
L3	=	10.0	FT
L4	=	15.5	FT
lo.	-+-1	lation Completed	


Installation Completed


Date: 06/19/93 Time: 12:05 p.m.

Date	Time	Water Level*
06/21/93	5:53 p.m.	94.58 feet



\* Measure Point Top of casing






	THE PARTY OF THE P	CANADA DE LA CANADA DEL CANADA DE LA CANADA DEL CANADA DE LA CANADA DELA CANADA DE LA CANADA DE LA CANADA DE LA CANADA DE LA CANADA DE			I Daging Alumbag	
			G LOG A		Boring Number  MW-9	Page Number 1 of 1
DEL OO O					Drilling Contractor  Tank - Liners, Inc.	Drilling Method Hollow-Stem-Auger
	178	73 S.E.	McLoughl	105.00	Start (Date - Time) 1/27/95 - 14:00	Finish (Date - Time) 1/27/95 - 14:53
	IVI	iiwauikie	e, Oregon		Elevation (Surface / Top of Well Casing)  not available	Logged By  Martin S. Burck R.G.
Sample Number	Blow Count (per 6 inches)	Sample Recovery (inches)	Depth (feet) Sample Interval	Samp	le Description and Subsurface Conditions	Monitoring Well Construction Diagram
			0 +			SurfaceCover— Well Plug
				- Asphalt	and Gravel Base	- J
, 18 j				Silty Grands brown, n	avelly Sand, (Fill Material) dark noist, pebbles, cobbles and s, (SW)	Concrete
MW- 9-5	3 for 24"	18	5	- Clayey \$	Silt, dark brown, moist-wet, (ML)	Sand Natrive Soil Bentonite
MW- 9-10	7 for 24"	18	10	Clayey S	Silt, dark brown, saturated, (ML)	0 Slot Screened Casing
MW- 9-15	6 for 24"	24	15	Clayey S	Silt, grey/tan, saturated, (ML)	
					Total Depth 15 feet	<del>-</del>
Comment	S: * B		20		OREGON MATTIN S. BURCK GIRLS GEOLOGIST	Auger Dimensions: 8" O.D., 4.25" I.D. Casing: 2" I.D., Sched. 40 PVC

I





(1) OWNER/PROJECT: WELL NO. M(N.//)	(6) LOCATION OF WELL By legal description
NAME DESCRIPTION THOUSAND MANNER	Well Location: County Clara
Address 4/ LONG LONF DIN	Township 25 (N or S) Range E (E or W) Section
City 1 ten Mon qual state NJ. Zio 08610	1. 5 1/4 of 5 1/4 of above section, 2. Street address of well location 17873 SE 106/04/11
(2) TYPE OF WORK:	2. Street address of well location 118/3 32 116/100/11/11
New construction Repair Recondition	3. Tax lot number of well location
Conversion Deepening Abandonment 2019	4. ATTACH MAP WITH LOCATION IDENTIFIED.
(3) DRILLING METHOD	(7) STATIC WATER LEVEL:
Rotary Air Rotary Mud Cable flamoil 198	Only William Program Pland surface 1 100 yr Date 25/2-56
nollow Staff Auger Unter	Artesian Pressureioysq. in. Date
(4) BORE HOLE CONSTRUCTION: stem selled, sacte, hollow stem and case and ca	
Yes Wo	(8) WATER BEARING ZONES:
	The Depth at which water was first found
Land surface	SWL 400 2 (2005) Sakon of July to anomaly south for the second of July to anomaly south for the second of July to anomaly south for the second of July to anomaly second of the second o
Vault Pose (O of All VV point)	how to a manage but named but named and an arranged
ft.  TO  Surface flush vault	if odt de a to the a grisse for age, given a manifigation?
TO Surface flush vault	Seconds Develor by the of section the Line 1.
ft. Locking cap. Dow	Complete all blanks et apperiget de l'unter et des l'apper
Casing	(9) WELL LOG: Ground elevation dguords
diameter 9	in.
material or Quick	
A V V Signature of the control to th	
Seal Liner	
diameter	in. Byruns gay Clay 51 15' 9'
material	Glord Constant to and an indicate the control of the control of
	fixore. Section fine the tenenther
ft. Well scal:	A Constitution of the Cons
Material DO	Hyp contact.
Amount 4 SA	of the state of th
Borehole diameter de	to the state of th
	light on the state of the state
Bentonite plug at lea	St Z II. thick
Screen Screen	For the Country of th
Filter material PUC	
interval(s):	
From 10 Note To 1	<del></del>
Slot size_OlO	
Material Alica S	
Size /(/2()_in.	Date started 8-12-96 Completed 8-12-96
And the state of t	(unbonded) Moritor Well Constructor Certification: 0 200
(5) WELL TEST: 1 2 3 4 1 10 m with mode, and near smooth flow to see	가 어느 어느 어느 어느 아이들은 얼굴이 가는 아이들이 아니는 아니는 아니는 아이들이 아이들이 아니는
Pump Bailer Air Air Plowing Artes	standards. Materials used and information reported above are true to the best
PermeabilityYieldGPM	knowledge and belief.
ConductivityPH	Signed Nick DM Challe Date 8-1896
Temperature of water°F/C Depth artesian flow found	·····································
Was water analysis done? Yes No	(bonded) Monitor Well Constructor Certification:  I accept responsibility for the construction, alteration, or abandonment
By whom?	work performed on this well during the construction dates reported above. All
Remarks:	work performed during this time is in compliance with Oregon well construction
	standards. This report is true to the best of my knowledge and belief.  MWC Number 1005/
Name of supervising Geologist/Engineer Peter Trabusine	Signed Date Date
D D	

STATE OF OREGON
MONITORING WELL REPORT
(as required by ORS 537.765 & OAR 690-240-095)

	ance	
Start Card #	9/// > 6	
Start Calum_	1000	

(1) OWNER/PROJECT: WELL NO. M. W //	(6) LOCATION OF WELL By legal description
INING WILL REPORT CHILLON OF SHORE	Well Location: County CARCATTAS
City Hery lot Sough State NT Zip 08690	Township 25 (N or S) Range (E or W) Section / S  1. SE 1/4 of SW 1/4 of above section.
f	1. Steet address of well location 1/3/3 5.6 12 Goughlin
(2) TYPE OF WORK:	11/11/21/Kin CM 972/67
New construction Repair Recondition Conversion Deepening Abandonment 1999 (1999)	3. Tax lot number of well location  2. Particle and after the control of the cont
(3) DRILLING METHOD	
A South	(7) STATIC WATER LEVEL: 100 0 10 003 17 0 0
Hollow Stem Auger Other	Artesian Pressurelb/sq. in. Date
tary mud, cable, hollow stem aNOITOURTENOO ALOH AROB (4)	(3) Drill methods: Mark the cornect box: rotary air, ro
Yes Ng	(8) WATER BEARING ZONES:
Special Standards Depth of completed well ft.	Depth at which water was first found and address (1)
Land surface Land the Water Resources Department.	AWZ If speciate work trails to the court of self-or hult descriptions of s
Vanit ( )	For tuli descriptions of seaffice head of the following th
Surface thich visualty	Casing lines to cold type of desires and
'Y   Y   24	2 Trong Comment of the Comment of the top
ft. Locking cap. burns and	dayord
Casing diameter 2 in.	(9) WELL LOG: Ground elevation.dguord:
1 10 material	JWC OF) Vell more to the learning to the SWL
aron Welded, Threaded, Glued	Migh Rin Hollow supposite 6'
Seal Liner Liner	े व स्मिन्नित्तर है जा कराज कर कि जिल्हा है के ति है।
diameterin.	Brown gla Char 6 65 9
material Welded Threaded Glued	Indicate the focuser of the former of the fo
्य locamin, with a clear 🚧 ा के 🤍 े	fiture. Section, 1th 1 the main Paper of The
Well seal of the s	indicated. I defend the component of a second of the secon
Material 1) Cont / 1/C	CONDS.
Amount 4 Rigs	Yang di ang
Borehole diameter	that if the second of the state of the second of the secon
in.	I phicate are a contracted
Bentonite plug at least 2 ft.	thick (8) (8)
to ever sens that a country Second 10740	(8) YERF 3030 III / CHES - 10 - 1 depte - 1 to 10 III   1
Filter Screen material P.V.C.	Managada
pack   material / mate	.0.3.19 1304 101 10 10 10 10 10 10 10 10 10 10 10 10
ft. From 10 interval(s) in interval(	
70   From the state of the stat	
ft. Filter pack:	40.31 46.316. 11. 11. 11. 11. 11. 11. 11. 11. 11.
Material Silica SANC	Date started 8-17-76 Completed 8-12-64-66
Size 0/0-76n.	
(E) TATELY MINOR	(unbonded) Monitor Well Constructor Certification 50 301
	it certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction
	standards. Materials used and information reported above are true to the best
Permeability Yield GPM	knowledge and belief.  MWC Number/1376
Conductivity PH  Temperature of water°F/C Depth artesian flow found ft.	Signed SiCCIIII (DVICC Date Signed
Was water analysis done? Yes No	(bonded) Monitor Well Constructor Certification:
By whom?	I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All
Depth of strata to be analyzed. Fromft. toft.	work performed during this time is in compliance with Oregon well construction
Remarks:	standards. This report is true to the best of my knowledge and belief.
Name of supervising Geologist/Engineer Peta Jachusmin	Signed MWC Number Date 9
traine of substatistic decions and the substation of the substatio	

(as required by ORS 537.765 & OAR 690-240-095)	STATE OF OREGON MONITORING WELL REPORT as required by ORS 537.765 & OAR 690-240-095)	
--	--	--

		-
. \ 1	(100 -	
Start Card #	9/1//	
Start Caru #	100 3 1	

(1) OWNER/PROJECT: WELL NO. M. W. 12	(6) LOCATION OF WELL By legal description
	Well Location County Chacks mas
City Herry Source State N.J. Zip 08490	Township (N or S) Range (E or W) Section
- A	1. SE 1/4 of SW 1/4 of above section.  2. Street address of well location 1737 3 SE Millinghly
(2) TYPE OF WORK:	milusulties On 91261
New construction Repair Recondition Conversion Deepening Abandonment	3. Tax lot number of well location
	4. ATTACH MAP WITH LOCATION IDENTIFIED.
(3) DRILLING METHOD	(7) STATIC WATER LEVEL: HEAW TO CAPET (12)
	Anna Fribelow land surface through Date 10/1/54
Hollow Stem Auger Other	Artesian Pressurelb/sq. in. Date
(4) BORE HOLE CONSTRUCTION: mottew steem cables, cables, cables, build yardy notes with the cables and cables and cables are cables are cables and cables are cables and cables are cables	
Yes No	(8) WATER BEARING ZONES:
Depth of completed well fr. w b.	
Land surface	For full descriptions (1 200 house) U.F. 684
TO THE ME IN THE PROPERTY OF T	10 0 A TORIO TRIBANTILLE IN LOCALIST COMMINIC
and account of the	National State of the State of
.Mu / [9]	
ft. And no (A. not was a substance of the property of	
Casing	(9) WELL LOG: Ground elevation dguords
diameterin.	ONE SERVICEMATERIAL CONTROL AND SERVICE SWILL SERVICE SWILL
Of Jaizonn Welded Threaded Glued	
v v v Q poor Loed the affect of the feat	· · · · · · · · · · · · · · · · · · ·
Scal Liner diameter in.	Remark 11 16 51 151 61
ft. material material	Brownsh Shan Clay 5 5 15
Welded Threaded Glued	fdicate the toxyoto of toxyoto and toxyoto
The first transfer of	Lature, Section, 174-174-7 constays, Pacing of the analysis of the analysis of the section of th
	1.6 (60.03)
Material Bent Aug.	
Borchole diameter	The second production of the second of the s
	and quarter to accommon the seconds.
Bentonite plug at least 2 ft. th	hick
ele an estimate of flow rate,	the state of the s
	that I have been also as a minimum of the
Filter pack material P.V.C. interval(s): (10/12)	and the same and t
ft. From / To /5"	grade demonstration of the property of the
To To Trom To Trom	Elesenhoths and matter matter with the second
5 ft. Slot size O/O in.	apd aquifer when There should be restricted
Filter pack:	<i>,</i>
Material Sur A SAV	Date started 8-12-96 Completed 8-12-96
in the control of the control of the state o	
the date of well construction, alteration of a said of the first (5)	(unbonded) Monitor Well Constructor Certification:
Pump Bailer Air 2019/ Flowing Artesian	abandonment of this well is in compliance with Oregon well construction
PermeabilityYieldGPM	standards. Materials used and information reported above are true to the best
	knowledge and belief.  MWC Number 10376
ConductivityPH	Signed Rid Man Date Signed Rid Date
Temperature of water°F/C Depth artesian flow foundft.  Was water analysis done? Yes No	(bonded) Monitor Well Constructor Certification:
By whom?	I accept responsibility for the construction, alteration, or abandonment
Depth of strata to be analyzed. Fromft. toft.	work performed on this well during the construction dates reported above. All
Remarks:	work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
	in the second se
Name of supervising Geologist/Engineer Later Tralmonn	Signed Date C-151-316

# STATE OF OREGON MONITORING WELL REPORT (as required by ORS 537.765 & OAR 690-240-095)

$\overline{}$	GAACC		
Start Card #	10038	•	

(1) OWNER/PROJECT: WELL NO. M.W /7	(6) LOCATION OF WELL By legal description
Name Owencer Phillon THOSTAR HAW DATAGE	
Address / Y Long LATE DR	Township 25 (N or S) Range 2E (E or W) Section 18
City Merciella Squar State NJ Zio 08690	1. $SE$ 1/4 of $SU$ 1/4 of above section.
(2) TYPE OF WORK:	2. Street address of well location 17873 SE MC/ach/In
New construction Repair Recondition	3. Tax lot number of well location
Conversion Deepening Abandonment Springer	4. ATTACH MAP WITH LOCATION IDENTIFIED.
(3) DRILLING METHOD	(7) STATIC WATER LEVEL: Blow to ST 19 //
Rotary Air Rotary Mud Cable Cable 190011	21 1010010 Grow-Fr. below land surface 1101000 Date 127 24 5
M Hollow Staff Auget Office	Altesian Flessureioysq. in
(4) BORE HOLE CONSTRUCTION: more wollon, edder, burn by	
Yes No	(8) WATER BEARING ZONES:
	has deep Depth at which water was first found many aladema (A)  From the Application of the SWL  SWL
Land surface	-00. Figure 1. F
Yami ( iii iii iii ii ii ii ii ii ii ii ii	To son which the state of the all and the state of the son which the state of the stat
(1970a)	A 3 SE SEASON SEED AND A SECURITION OF SECUR
ft.	
Casing	(9) WELL LOG: Ground elevation deposition
diameterin	Material second of world gFrom 119 W (To SWL)
Welded Threaded Glue	
	J Bell Brains Comment
Seal Liner	0 19 01 -1 15
diameterir	Shownest Jaling (Pag.
Welded Threaded Glue	d (Artis)
aulo babeard bablew and clear with the control of t	Rum. Sec ion 2 <sup>th</sup> 12 th a strip, forgon at 12 th
Well seals	to discount and the control of the state of
Material Boot Hu	De tropical and a second secon
Borehole diameter,	30 1 1/2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	्यात क्रमण्य वे व्यावस्थान वहार व्यवस्था विकास होता
Bentonite plug at least 2 f	it. thick
we explored to 30 to 20	The state of the second st
Filter Screen PIC	About A Line Control of the Control
pack material interval(s):	10 1 10 10 10 10 10 10 10 10 10 10 10 10
ft.   From 10 To 15	as in the community of the community and yes
To To	- " seeing the principle of the color of the
ft. Slot size 0/0	sed squifer littled. Here we are governed to an ini-
Filter pack: Material SIINA SANG	
Size 10/10_in.	Date started 8-17-96 Completed 8-12-96
MANUFACTURE TO THE PARTY OF THE	(unbonded) Monitor Well Constructor Certification: 0 5dT
(5) WELL TEST: message a mark large a manufacture Hose he each a	in the construction, alteration, or
Pump Bailer Air Flowing Artesian	abandonment of this well is in compliance with Oregon well construction standards. Majorials used and information reported above are true to the best
PermeabilityYieldGPM	knowledge and belief.
ConductivityPH	MWC Number OS/O
Temperature of water°F/C Depth artesian flow foundft.	
Was water analysis done? Yes No	(bonded) Monitor Well Constructor Certification:
By whom?	I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All
Depth of strata to be analyzed. Fromft. toft.  Remarks:	work performed during this time is in compliance with Oregon well construction
Achiaiks,	standards. This report is true to the best of my knowledge and belief.
Name of supervising Geologist/Enginee Potan Jun fousing	Signed
That of supervising Octobals deligned 1 1/1/1/19	

## APPENDIX D

# DEQ NOTICE OF CIVIL PENALTY (JUNE 7, 1999)

August 4, 1999 APPENDIX



DEPARTMENT OF ENVIRONMENTAL QUALITY

#### CERTIFIED MAIL Z 440 760 423

June 7, 1999

Devinder Dhillon
Delco Petroleum Co., LLC
14 Long Leaf Drive
Hamilton, NJ 08690

Re: Notice of Assessment of Civil Penalty No. WMC/T-NWR-99-064 Clackamas County

Dear Mr. Dhillon:

In March of 1995 you registered as the permittee of underground storage tanks (USTs) located at 17873 S.E. McLaughlin Boulevard in Milwaukie, Oregon, although you had been associated with the site through Delco Petroleum for the preceding year. At that time, the tanks were known to have released gasoline, contaminating groundwater at the site. Oregon law requires quarterly groundwater sampling, analysis, and reporting at sites with known groundwater contamination. In June 1994, your contractor Northwest Envirocon installed groundwater monitoring wells at the site and began sampling the wells. The first three sampling events took place on schedule. However, no sampling was done in April 1995, or July 1996. Between October 1996 and April 1999 each of the wells should have been sampled eleven times. Only three out of the eleven required sampling events were actually performed.

As the permittee of the tanks you are legally responsible, along with Delco Petroleum as owner and operator, for investigating groundwater contamination from your tanks. Quarterly sampling is required to protect human health and the environment by assessing the nature and extent of contamination and monitoring the movement of contaminated groundwater.

You are liable for a civil penalty assessment because you violated Oregon environmental law. In the enclosed Notice, I have assessed a civil penalty of \$32,087 against you and Delco, together. In determining the amount of the penalty, I used the procedures set forth in Oregon Administrative Rule (OAR) 340-12-045. The Department's findings and civil penalty determination are attached to the Notice as Exhibit 1. The majority of the penalty is the economic benefit you gained by not paying for the required monitoring.

811 SW Sixth Avenue Portland, OR 97204-1390 (503) 229-5696 TDD (503) 229-6993 DEQ-1 Devinder Dhillon Case No. WMC/T-NWR-99-064 Page 2

In addition to the civil penalty, the enclosed Order requires you to do the following:

- · Resume quarterly groundwater sampling and reporting
- · Submit a Corrective Action Plan for the site
- If you plan to upgrade the site, submit a work plan for the upgrade.

Appeal procedures are outlined in Section VI of the Notice. If you fail to either pay or appeal the penalty within twenty (20) days, a Default Order will be entered against you and the Order will become final and enforceable.

If you wish to discuss this matter, or if you believe there are mitigating factors which the Department might not have considered in assessing the civil penalty, you may request an informal discussion by attaching your request to your appeal. Your request to discuss this matter with the Department will not waive your right to a contested case hearing.

I look forward to your cooperation in complying with Oregon environmental law in the future. However, if any additional violations occur, you may be assessed additional civil penalties.

Copies of referenced rules are enclosed. Also enclosed is a copy of the Department's internal management directive regarding civil penalty mitigation for Supplemental Environmental Projects (SEPs). If you are interested in having a portion of the civil penalty fund an SEP, you should review the enclosed SEP directive. Exceptional pollution prevention could result in partial penalty mitigation.

If you have any questions about this action, please contact Roger Dilts with the Department's Enforcement Section in Portland at 229-5692 or toll-free at 1-800-452-4011, enforcement extension 5692.

Sincerely,

Langdon Marsh

Director

e:\winword\delco\dhillon\cvrltrdhillon

Enclosures

cc: Robert Williams, Northwest Region, DEQ
Waste Management and Cleanup Division, DEQ
Oregon Department of Justice
U.S. Environmental Protection Agency
Environmental Quality Commission
Clackamas County District Attorney

#### BEFORE THE ENVIRONMENTAL QUALITY COMMISSION

#### OF THE STATE OF OREGON

NOTICE OF VIOLATION,
IN THE MATTER OF:
DEVINDER DHILLON
and DELCO PETROLEUM CO., LLC,
Respondents.

NOTICE OF VIOLATION,
DEPARTMENT ORDER, AND
ASSESSMENT OF CIVIL
PENALTY
No. WMC/T-NWR-99-064
CLACKAMAS COUNTY

#### I. AUTHORITY

This Notice of Violation, Department Order, and Assessment of Civil Penalty (Notice and Order) is issued by the Department of Environmental Quality (Department or DEQ) pursuant to Oregon Revised Statutes (ORS) 466.810, ORS Chapter 183, and Oregon Administrative Rules (OAR) Chapter 340, Divisions 11 and 12.

#### II. FINDINGS

- 1. Respondent Devinder Dhillon (Dhillon) was the permittee of underground storage tank systems (USTs) storing petroleum, a regulated substance, located at 17873 S.E. McLoughlin Boulevard, Milwaukie, Oregon, (the site), between March 30, 1995, and December 23, 1998, and has been the permittee of such USTs since January 20, 1999.
- 2. Respondent Delco Petroleum Co., LLC, (Delco) is and at all relevant times was, an Oregon limited liability company.
- 3. During or about May 1994 Respondent Delco became the owner of the site and owned the site at all relevant times.
- 4. During or about May 1994 Respondent Delco began operating a retail service station at the site, under the name "Milwaukie Fuel Stop," and operated the station at all relevant times.
- 5. In January 1993 the previous owners discovered gasoline contamination of the subsurface at the site. During site assessment in July 1993, gasoline contamination of groundwater at the site was discovered.

Page 1 - NOTICE OF VIOLATION, DEPARTMENT ORDER, AND ASSESSMENT OF CIVIL PENALTY

WMC/T-NWR-99-064

e:\winword\delco\dhillon\cpo

6

3

9

14

20

18

- 6. Monitoring wells showed that groundwater was contaminated by gasoline beyond the confines of the tank excavation.
  - 7. The site is a "facility" as defined at ORS 465.200(12).
- 8 Pursuant to OAR 340-122-0240, Respondent Dhillon, as the permittee, had and continues to have, the responsibility for conducting an investigation of the nature, magnitude, and extent of groundwater contamination at the site. OAR 340-122-0240(2)(c)(A) requires quarterly groundwater monitoring for such investigations.
- 9. Pursuant to OAR 340-122-0240, Respondent Delco, as the owner and operator of the site, had and continues to have, the responsibility for conducting an investigation of the nature, magnitude, and extent of groundwater contamination at the site. OAR 340-122-0240(2)(c)(A) requires quarterly groundwater monitoring for such investigations.
- Respondent Dhillon failed to sample, analyze, and report results for required quarterly groundwater monitoring events for April 1995, July 1996, April 1997, July 1997, October 1997, April 1998, July 1998, October 1998, January 1999, and April 1999.
- Respondent Delco failed to sample, analyze, and report results for required 11. quarterly groundwater monitoring events for April 1995, July 1996, April 1997, July 1997, October 1997, April 1998, July 1998, October 1998, January 1999, and April 1999.

#### III. VIOLATION

Based upon the Findings above, Respondents each violated Oregon's laws and rules as follows:

Respondents violated OAR 340-122-0240 by failing to investigate the nature, magnitude, and extent of groundwater contamination according to OAR 340-122-0242, now at OAR 340-122-0240(2)(c)(A). Specifically, Respondents failed to monitor groundwater contamination on a quarterly basis and submit the results to the Department. This is a Class I violation pursuant to OAR 340-012-0067(1)(e).

111 111

> Page 2 - NOTICE OF VIOLATION, DEPARTMENT ORDER, AND ASSESSMENT OF CIVIL PENALTY WMC/T-NWR-99-064 c:\winword\delco\dhillon\cpo

6

9

27

90

25

#### IV. DEPARTMENT ORDER

Based upon the foregoing FINDINGS AND VIOLATIONS, Respondents are hereby ORDERED TO:

- Immediately initiate actions necessary to correct all of the above cited violations 1 and come into full compliance with Oregon's laws and rules.
- Within thirty days of receipt of this Order, resume collection, analysis, and 2. reporting of groundwater monitoring samples from all groundwater monitoring wells at the site (including any off-site wells installed for the purpose of investigating the site) and continue such monitoring on a quarterly basis until informed in writing by the Department that the schedule may be modified. The wells must be sampled for benzene, toluene, ethylbenzene, and xylene, and analyzed by approved methods. Each quarterly report must include a determination of the groundwater flow direction, and data used in making such determination.
- Within sixty days of receipt of this Order, submit a written Corrective Action Plan (CAP) that meets the requirements of OAR 340-122-0250.
- If Respondents plan to upgrade the site, Respondents must submit a written work 4 plan for excavation, upgrade, and contaminated soil removal at least thirty days before work begins. The work plan must include a discussion of how groundwater remediation will proceed following over-excavation of the tank cavity, as well as a map of proper scale showing the proposed excavation area and the groundwater contamination area.

#### V. ASSESSMENT OF CIVIL PENALTIES

The Department imposes a penalty of \$32,087 upon Respondents Devinder Dhillon and Delco Petroleum Co., LLC, for the violation in Section III, above.

The findings and determination of Respondents' civil penalty pursuant to OAR 340-012-045 are attached and incorporated as Exhibit No. 1.

#### VI. OPPORTUNITY FOR CONTESTED CASE HEARING

This Notice and Order shall become final unless Respondents request, in writing, a hearing before the Environmental Quality Commission. The request must be received by the

Page 3 - NOTICE OF VIOLATION, DEPARTMENT ORDER, AND ASSESSMENT OF CIVIL PENALTY e:\winword\delco\dhillon\cpo WMC/T-NWR-99-064

Department's Rules Coordinator within 20 days from the date Respondents receive this Notice and Order, and must be accompanied by a written "Answer" to the allegations contained in this Notice and Order.

In the written Answer, Respondents shall admit or deny each allegation of fact contained in this notice, and shall affirmatively allege any and all affirmative claims or defenses to violations and assessment of any civil penalty that Respondents may have and the reasoning in support thereof. Except for good cause shown:

- 1. Factual matters not controverted shall be presumed admitted;
- 2. Failure to raise a claim or defense shall be presumed to be a waiver of such claim or defense;
- 3. New matters alleged in the Answer shall be presumed to be denied unless admitted in subsequent pleading or stipulation by the Department or Commission.

Send the request for hearing and Answer to: **DEQ Rules Coordinator**, Office of the Director, 811 S.W. Sixth Avenue, Portland, Oregon 97204. Following receipt of a request for hearing and an Answer, Respondents will be notified of the date, time and place of the hearing.

If Respondents fail to file a timely request for hearing and Answer, the Notice and Order shall become a final and enforceable Order of the Environmental Quality Commission by operation of law without any further action or proceeding. If the Order becomes final by operation of law, the right to judicial review, if any, is outlined within ORS 183.480.

Failure to appear at a scheduled hearing or meet a required deadline may result in a dismissal of the request for hearing and also an entry of a Default Order.

The Department's case file at the time the Notice and Order was issued may serve as the record for purposes of entering the Default Order.

#### VII. OPPORTUNITY FOR INFORMAL DISCUSSION

In addition to filing a request for a contested case hearing, Respondents may also request an informal discussion with the Department by attaching a written request to the hearing request and Answer.

Page 4 - NOTICE OF VIOLATION, DEPARTMENT ORDER, AND ASSESSMENT OF CIVIL PENALTY
WMC/T-NWR-99-064
e:\winword\delco\dhillon\cpo

#### VIII. PAYMENT OF CIVIL PENALTY

The civil penalty is due and payable ten (10) days after the Order imposing the civil penalty becomes final by operation of law or on appeal. Respondents may pay the penalty before that time. Respondents' check or money order in the amount of \$32,087 should be made payable to "State Treasurer, State of Oregon" and sent to the Business Office, Department of Environmental Quality, 811 S.W. Sixth Avenue, Portland, Oregon 97204.

6-7-99	nonsan Waal	
Date	Langdon Marsh, Director	A Property of the Control of the Con

1 111

Page 5 - NOTICE OF VIOLATION, DEPARTMENT ORDER, AND ASSESSMENT OF CIVIL PENALTY
WMC/T-NWR-99-064
e;\winword\delco\dhillon\cpo

#### EXHIBIT 1 WMC/T-NWR-99-064

# FINDINGS AND DETERMINATION OF RESPONDENT'S CIVIL PENALTY PURSUANT TO OREGON ADMINISTRATIVE RULE (OAR) 340-12-045

VIOLATION:

Failure to conduct and submit reports of quarterly groundwater monitoring.

CLASSIFICATION:

This is a Class I violation pursuant to OAR 340-012-0067(1)(e).

MAGNITUDE:

The magnitude of the violation is moderate, pursuant to OAR 340-012-0045(1)(a)(B), because there is no selected magnitude for this violation.

CIVIL PENALTY FORMULA:

The formula for determining the amount of penalty of each violation is:

 $BP + [(0.1 \times BP) \times (P + H + O + R + C)] + EB$ 

"BP" is the base penalty which is \$3,000 for a Class I, moderate magnitude violation in the matrix listed in OAR 340-12-042(1).

"P" is Respondent's prior significant action(s) and receives a value of 0, because Respondent has no prior significant actions.

"H" is the past history of Respondent in taking all feasible steps or procedures necessary to correct any prior significant action(s) and receives a value of 0, because Respondent has no prior significant actions.

"O" is whether or not the violation was a single occurrence or was repeated or continuous during the period of the violation and receives a value of 2, because the violation was repeated.

"R" is the cause of the violation and receives a value of 2, because Respondents' failure to conduct groundwater monitoring was negligent. The Department issued a Notice of Noncompliance to Respondents on October 15, 1997, for failing to submit quarterly groundwater monitoring reports and requesting that quarterly monitoring resume. Respondents conducted a sampling on January 27, 1998, then failed to conduct further sampling. Respondents failed to take reasonable action to ensure that quarterly groundwater monitoring was done.

"C" is Respondent's cooperativeness in correcting the violation and receives a value of 2, because Respondents did not take reasonable efforts to correct the violation.

"EB" is the approximate dollar sum of the economic benefit that the Respondents gained through noncompliance, and receives a value of \$27,287. Respondents avoided the costs of sampling, analyzing, and reporting the results of ten quarterly groundwater monitoring events. The total cost avoided is estimated to be \$38,880. The economic benefit realized by Respondents, as calculated by the EPA BEN computer model pursuant to OAR 340-012-0045(1)(c)(F)(iii), is \$27,287.

D

#### PENALTY CALCULATION:

Penalty

 $= BP + [(0.1 \times BP) \times (P + H + O + R + C)] + EB$   $= \$3.000 + [(0.1 \times \$3.000) \times (0 + O + 2 + 2 + 2 + 2)] + EB$ 

=  $$3,000 + [(0.1 \times $3,000) \times (0 + 0 + 2 + 2 + 2)] + $27,287$ =  $$3,000 + [$300 \times 6] + $27,287$ 

= \$3,000 + \$1,800 + \$27,287

= \$32,087

Pursuant to OAR 340-012-0045(1)(c)(F)(iv), for purposes of determining the maximum penalty allowed, where a violation has extended over more than one day, the Department may treat the violation as extending over as many days as necessary to recover the economic benefit of noncompliance. In this case, the Department treats the violation as extending over the quarterly sampling events that were due in April, July, and October 1998, and January 1999.

D

# APPENDIX E

# WELL SURVEY SUMMARY BY BARBIERI & ASSOCIATES

August 4, 1999 APPENDIX

BARBIERI & ASSOCIATES, INC. 7017 NE HWY 99 SUITE 204 VANCOUVER, WA. 98665 360-695-1001 Fri Jul 30 14:17:25 1999

PROJECT: C:\PRO\JIFF.pro

Point Co	oordinates Lis North	ting East E	lev Name
1	5000.0000	5000.0000	100.00 MAG WEST
2	5000.0000	5155.5700 4928.3490	99.09 MAG EAST
3			*
100		5155.5740	
101	4985.931/	4957.8054	100.51 MW12 RIM
102	4985.9264	4957.7929 4984.7244	100.26 MW12 PVC
103 104			99.80 MW11 RIM 99.64 MW11 PVC
105		4984.8006 5023.3084	100.75 MW5 RIM
106	4961.6531 4961.3219	5023.3794	100.41 MW5 PVC
107	4996.5026	5029.1640	99.65 MW8 S. RIM
108	4990.0388	5034.2069	99.50 MW4 RIM
109	4990.2710	5034.4790	99.00 MW4 PVC
110	4884.2271	5014.6438	100.28 MW6 RIM
111	4884.6778	5014.8186	100.01 MW6 PVC
112	4882.4065	5155.4990	99.90 MW9 RIM
113	4882.8403	5155.4990 5155.4432	99.42 MW9 PVC
114	4951.5571	5142.8629	99.15 MW10 RIM
115	4951.8577	5142.8029 5142.9787 5117.7147	98.50 MW10 PVC
116	4991.8741	5117.7147	98.81 MW2 RIM
117	4992.2711	5117.6229	98.51 MW2 PVC
118	5000.7117		
119	4947.5015 4950.1359	4979.3594 5047.6845	101.16 BLD 101.20 BLD
120 121	5000.0000	4999.9960	100.00 CKBS
122	4884.4892	5056.1585	99.99 MW13 RIM
123	4884.8889	5056.2117	
124	4903.3638	5078.9954	99.99 MW1 RIM
125	4903.1689	5079.4649	
126	5000.0000	4999.9879	
127	4993.5840	5143.8186	98.05 CB
128	4885.6397	5139.2591	98.97 CB
129	4920.3333	5122.9234	99.68 PUMP ILNS
130	4919.9110	5122.9234 5111.6408 5103.9790	99.79 PUMP ILNS
131			
132	4919.0961	5090.5965	99.99 PUMP ILNS
133	4919.0961 4945.0011	5089.5648 5102.8827	99.72 PUMP ILNS
134 135	4945.4619	3102.0021	
136	4946.2725	5110.5543 5121.8965	99.59 PUMP ILNS 99.44 PUMP ILNS
137	4972.1976	5120.8638	99.20 PUMP ILNS
138	4971.7217	5109.5914	99.27 PUMP ILNS
139	4971.4617	5101.7954	99.38 PUMP ILNS
141	5009.2147	5043.9798	100.41 VENT TUBS
142	5011.8025	5043.1874	100.37 ED MUFF.WALL
143	5009.9629	5124.5200	99.18 ED MUFF BLD CC
144	5007.4654	5152.6002	98.60 5/8"IR
145	4912.9467	5054.1351	100.62 PK
146	5000.0000	5155.5700	99.11 CKBS
147	4917.7346	5048.9604	101.38 BLD
148	4915.0700	4980.6164	100.99 BLD
149	4870.9168	4968.5950	98.70 5/8" IR
150	4867.5422	5158.0749	97.69 5/8" IR