

#### **Eugene Office**

32986 Roberts Court Coburg, Oregon 97408

P.O. Box 71158 Eugene, Oregon 97401

> (541) 484-9484 Fax (541) 484-4188

# **Portland Office**

25195 SW Parkway Ave., Suite 207 Wilsonville, Oregon 97070

> (503) 570-9484 Fax (503) 570-0384

www.bergeson-boese.com



Bergeson-Boese & Associates, Inc. Comprehensive Environmental Services

# INVESTIGATION FOR MAGNITUDE AND EXTENT OF CONTAMINATION, AND CONCEPTUAL SITE MODEL

Tillamook Creamery Association 4185 Highway 101 North Tillamook, Oregon LUST 29-08-0695

#### Report Prepared For:

Oregon Department of Environmental Quality Northwestern Region Office 2020 SW 4th, Suite 400 Portland, Oregon 97201

#### On behalf of:

Mr. Shawn Reiersgaard Tillamook Creamery P.O. Box 313 Tillamook, Oregon 97141

# Report Prepared By:

Bergeson-Boese & Associates, Inc. 25195 SW Parkway Ave; Suite 207 Wilsonville, Oregon 97070 (503) 570-9484 DEPT OF ENVIRONMENTAL QUALITY RECEIVED

JUL 3 1 2008

NORTHWEST REGION

# **TABLE OF CONTENTS**

|  | <u>Pag</u>   | <u>je</u>  |
|--|--|--|
| 1.1<br>1.2                             | Initial Discovery and Immediate Actions  | 1  |
| 2.1<br>2.2<br>2.3<br>2.4               | Site Location Current Use and Improvements Surrounding Land Use Utility Information  | 5<br>6<br>6  |
| <b>REGION</b> 3.1 3.2 3.3 3.4          | Regional Hydrogeology Local Hydrogeology Groundwater Occurrence - Water Well Query Potential for Inter-Aquifer Connection  | . 7<br>. 7<br>. 8  |
| 4.1<br>4.2<br>4.3                      | SITE CHARACTERIZATION Soil and Water Sampling Results Reporting  | 11<br>11   |
| <b>SUBSUR</b> 5.1 5.2 5.3              | Prace Investigation Push Probe Installations, Sampling, Analysis Soil Sample Analytical Results Discussion of Analytical Results - Soil  | 13<br>15   |
| <b>GROUN</b><br>6.1<br>6.2<br>6.3      | Temporary Well Installation and Groundwater Sampling   | 17<br>18<br>21   |
| 7.1<br>7.2<br>7.3<br>7.4<br>7.5<br>7.6 | Summary of Previous CSM (LUST 29-00-0859)  Risk-Based Concentrations  Evaluation of Applicable Exposure Pathways  Contaminants-of-Potential-Concern (CoPCs)  Extent of Soil and Groundwater Contamination  Evaluation of Applicable Exposure Pathways  7.6.1 Vapor Intrusion of Soil Contaminants to Indoor Air  7.6.2 Volatilization of Soil Contaminants to Outdoor Air  7.6.3 Incidental Ingestion, Inhalation, and Dermal Contact of Soil  7.6.4 Leachate of Soil Contaminants to Groundwater  7.6.5 Volatilization of Groundwater Contaminants to Indoor Air  7.6.6 Volatilization of Groundwater Contaminants to Outdoor Air  7.6.7 Ingestion of and Inhalation from Tap Water  7.6.8 Incidental Ingestion, Inhalation, and Dermal | 22<br>22<br>23<br>23<br>24<br>24<br>24<br>25<br>25<br>26   |
|  | 1.1<br>1.2<br>SITE DE<br>2.1<br>2.2<br>2.3<br>2.4<br>REGION<br>3.1<br>3.2<br>3.3<br>3.4<br>INITIAL S<br>4.1<br>4.2<br>4.3<br>SUBSUR<br>5.1<br>5.2<br>5.3<br>GROUN<br>6.1<br>6.2<br>6.3<br>CONCEP<br>7.1<br>7.2<br>7.3<br>7.4<br>7.5  | INTRODUCTION  1.1 Initial Discovery and Immediate Actions  1.2 Background  SITE DESCRIPTION  2.1 Site Location 2.2 Current Use and Improvements 2.3 Surrounding Land Use 2.4 Utility Information  REGIONAL AND LOCAL GEOLOGY AND HYDROGEOLOGY 3.1 Regional Hydrogeology 3.2 Local Hydrogeology 3.3 Groundwater Occurrence - Water Well Query 3.4 Potential for Inter-Aquifer Connection  INITIAL SITE CHARACTERIZATION 4.1 Soil and Water Sampling 4.2 Results 4.3 Reporting  SUBSURFACE INVESTIGATION 5.1 Push Probe Installations, Sampling, Analysis 5.2 Soil Sample Analytical Results - Soil 5.3 Discussion of Analytical Results - Soil  GROUNDWATER INVESTIGATION 6.1 Temporary Well Installation and Groundwater Sampling 6.2 Groundwater Analytical Results 6.3 Results Discussion - Groundwater  CONCEPTUAL SITE MODEL 7.1 Summary of Previous CSM (LUST 29-00-0859) 7.2 Risk-Based Concentrations 7.3 Evaluation of Applicable Exposure Pathways 7.4 Contaminants-of-Potential-Concern (COPCs) 7.5 Extent of Soil and Groundwater Contamination 7.6 Evaluation of Applicable Exposure Pathways 7.6.1 Vapor Intrusion of Soil Contaminants to Indoor Air 7.6.2 Volatilization of Soil Contaminants to Indoor Air 7.6.3 Incidental Ingestion, Inhalation, and Dermal Contact of Soil 7.6.5 Volatilization of Groundwater Contaminants to Indoor Air 7.6.6 Volatilization of Groundwater Contaminants to Indoor Air 7.6.7 Ingestion of and Inhalation from Tap Water  7.6.7 Ingestion of and Inhalation from Tap Water |

| 7.7   | Risk-Based Concentrations for Applicable Exposure Pathways  |
|---|---|
| 7.8   | Summary of Soil and Groundwater Evaluation  |
| 8.0 CONCLUS<br>8.1<br>8.2   | SIONS AND RECOMMENDATIONS   |
| 9.0 LIMITATI  | ONS   |
|   | LIST OF FIGURES   |
| Figure 2 - Site<br>Figure 3 - Wa<br>Figure 4 - Ana                      | e Location Map  |
|   | LIST OF TABLES  |
| Table 2. Soil A<br>Table 3. Grou<br>Table 4. Sum<br>Table 5. Com        | I Site Characterization Measures  |
|   | APPENDICES  |
| Appendix A: Appendix B: Appendix C: Appendix D: Appendix E: Appendix F: | Fluid Disposal and Tank Recycling Receipts Zoning Information Oregon Water Resources Department Well Query Report Laboratory Reports and Chain-of-Custody Records Push Probe and Monitoring Well Completion Logs Historical Groundwater Data Tables |

# 1.0 INTRODUCTION


This report presents the results of an Investigation of Magnitude and Extent of Contamination associated with an abandoned underground storage tank (UST) discovered at the Tillamook Co. Creamery Association, located at 4185 Highway 101 North in Tillamook, Oregon (see **Figure 1 for Site Location Map**). The unregistered UST was encountered by the City of Bay City Public Works Department while installing a new water main along the north side of Latimer Road. The UST was found adjacent to former LUST site 29-00-0859, which received a "No Further Action" designation from the Oregon Department of Environmental Quality (DEQ). Initial Site Characterization activities were completed and are presented in a Twenty-Day Report dated June 27, 2008. This report presents a progress summary of assessment activities and a description of site conditions. This report also includes a Conceptual Site Model (CSM) for evaluating residual concentrations of gasoline range total petroleum hydrocarbons (TPH) and constituents in soil and groundwater beneath the site. The results are evaluated and recommendations for site closure are presented in accordance with DEQ guidance for the assessment and cleanup of petroleum-contaminated sites.

#### 1.1 Initial Discovery and Immediate Actions

An approximately 500-gallon abandoned UST containing a mixture of water and petroleum fuel was discovered on March 31, 2008 by utility workers while installing a new eight (8) inch water main near the southeast entrance to the Tillamook Creamery facility. The UST was encountered at a depth of approximately 36 inches below land surface (BLS) within a pea gravel backfill material. Surrounding native soils consisted primarily of clayey silts, and silty sands. Upon discovery of the UST, a capped two (2) inch diameter fill pipe was found attached to the tank, however no dispensers were observed in the area of the tank. Initial inspection of the tank area indicated no evidence of any prior releases around the fill pipe.

The tank was discovered when the bucket of a backhoe inadvertently punctured the top of the tank leaving an approximately 12-inch hole in the top of the tank. According to witnesses, less than one (1) gallon of watery fluid was released into soils immediately surrounding the exposed tank. Trench work was immediately halted and the area was inspected for fire and explosion hazards.

Prior to removal, a total of 598 gallons of fluids were pumped from the tank and the tank was triple rinsed by Zwald Industrial Services of Tillamook, Oregon. The interior of the tank was monitored for the presence of combustible gases and removed from the trench using a backhoe. Upon removal, standing water was observed in the pit at approximately five (5) feet BLS. The tank was constructed of single-wall steel and measured 45 inches in diameter by approximately six (6) feet long. Inspection of the tank revealed no evidence of heavy corrosion pits, holes, or cracked weld seams in the walls of the tank.



The contents of the UST and used wash water was transported to Pacific Power Vac in Portland, Oregon for disposal. The tank was transported off-site for recycling on April 2, 2008 to Don Averil Recycling, located at 1315 Eckloff Road in Tillamook, Oregon. A copy of the receipt for disposed water is included in **Appendix A**. A copy of the tank recycling receipt is included in **Appendix B**. The location of the abandoned UST is illustrated on the Site Map presented on **Figure 2**.

The release was reported to the DEQ on June 11, 2008 and issued DEQ case number LUST 29-08-0695. A Twenty-Day Report presenting the initial discovery of the UST and initial abatement measures was submitted to the DEQ on June 27, 2008.

#### 1.2 Background


On July 27, 2000, a separate abandoned 675 gallon UST containing unleaded gasoline was discovered on Tillamook Creamery property approximately 25 feet west of the recently discovered UST. The abandoned UST, identified as LUST site 29-00-0859, was eventually decommissioned in-place on November 1, 2000. The location of LUST site 29-00-0859 is illustrated on Figure 2.

On July 17, 2000, BB&A was retained by Tillamook to complete a preliminary assessment (PA) of the soil and groundwater conditions associated with the abandoned tank and to complete subsequent investigations<sup>1</sup>. During the PA, two (2) push probe borings were placed near the UST for the purpose of assessing soil and groundwater impacts. Soil and groundwater samples were collected and analyzed for the presence of gasoline by method TPH-Gx, benzene, toluene, ethylbenzene, xylenes (BTEX) and naphthalene. Laboratory results identified total petroleum hydrocarbons (TPH) in the gasoline range in soils adjacent to the tank at 720 milligrams per kilogram (mg/kg), in excess of the Level II Soil Matrix cleanup level of 80 mg/kg established for the site. Benzene was detected in groundwater at a concentration of 110 µg/L, in excess of DEQ's Risk-Based Concentration (RBC) for groundwater ingestion for the occupational receptor (established in DEQ's Risk-Based Decision Making, September 1999).

BB&A installed four (4) groundwater monitoring wells around the perimeter of the decommissioned UST to determine the full magnitude and extent of contamination. Soil samples were analyzed for TPH as gasoline using the NWTPH-Gx method, BTEX and gasoline-related volatile organic compounds (VOCs) using EPA Method 8260B, and total and leachable lead by EPA Method 7421/1311/7421. Neither TPH nor gasoline-related VOCs were detected in soil samples collected beyond the immediate location of the tank.

1

Investigation results are presented in the following reports: "Results of Subsurface Assessment of Abandoned Underground Storage Tank", dated August 17, 2000; "Investigation for Magnitude and Extent of Contamination and Low Impact Site Evaluation", dated December 8, 2000; "Update Report with Conceptual Site Model", dated September 12, 2001; and, Quarterly Update Reports dated November 21, 2001, February 21, 2001, and May 3, 2001, and March 6, 2002.



Between September 2000 and May 2001, BB&A conducted quarterly groundwater monitoring and sampling of the wells. Depth to groundwater was measured between approximately four (4) and seven (7) feet BLS. Groundwater samples collected from the wells were analyzed for BTEX compounds and gasoline-related VOCs using EPA Method 8260B and dissolved lead using EPA Method 7421. Groundwater samples collected from MW-4, located south-southeast of the tank site contained benzene at concentrations ranging from 5.7  $\mu$ g/L to 7.0  $\mu$ g/L. Dissolved lead was not detected in any of the wells. Based on groundwater monitoring results, impacts were limited to the immediate vicinity of the UST and are not migrating off-site.

BB&A developed a conceptual site model (CSM) for the site to identify routes of exposure. Based on the CSM, ingestion/inhalation of tap water was eliminated as a complete exposure pathway under future land use conditions and direct contact with groundwater by excavation workers was identified applicable to the site for contaminants of concern (benzene at 5.7 µg/L, and 1,2-dichloroethane at 2.0 ug/L). Later, a beneficial water use survey was completed and determined that ingestion by groundwater was incomplete. Trench worker exposure was eliminated because local utilities (power, telephone, and water) are located less than three (3) feet below land surface (BLS), preventing utility workers from encountering deeper contaminants of concern in the groundwater.

Based on the limited nature of residual soil contamination and low to non-detect groundwater concentrations from four (4) monitoring wells, the DEQ issued a "No Further Action" designation in a letter dated August 20, 2002. The location of former LUST 29-00-0859 and former monitoring wells MW-1 through MW-4 are illustrated on **Figure 2**.

# 2.0 SITE DESCRIPTION

#### 2.1 Site Location

The Tillamook Creamery facility is located in the southwest quarter of Section 18, Township 1 South, Range 9 West, as referenced to the Willamette Meridian. The subject property lies at an elevation of approximately 24 feet above mean sea level in a generally level area. Tillamook Bay lies 2.5 miles to the west of the site. The nearest surface water body to the site is the Wilson River which is located approximately 1500 feet south of the site.

The entire creamery occupies approximately 45 acres. The location of the abandoned UST is near the southeast entrance of the creamery facility off of Latimer Road. The abandoned UST lies approximately one-quarter (0.25) mile east of the intersection of Latimer Road and Highway 101 North and approximately 25 feet north of Latimer Road. The abandoned UST site is bordered by the gravel parking lot to the north and a drainage ditch, then Latimer Road to the south. The base of the ditch lies partially under public land and partially on Tillamook Creamery property.

#### 2.2 Current Use and Improvements

The subject site is zoned by the Tillamook County as *General Industrial* (M-1). Permitted uses within the M-1 zoning area include light and heavy industrial uses, warehousing, farming and other uses<sup>2</sup>. A small portion of the the site is zoned Rural Community (RC). Residential development is not permitted within the M-1 or RC zoning areas.

Site improvements include a large gravel parking area used for creamery delivery and tanker trucks and an entrance driveway to the west of the tank. Two (2) single-story warehouses are located over 200 feet east of the UST site and are occupied by Rod's Dairy Sales and J&K Distribution Company.

#### 2.3 Surrounding Land Use

Surrounding properties to the east are zoned *Forest Zone* (F) and properties to the south are zoned *Farming Zone* (F-1) (see **Appendix B** for a City of Tillamook Zoning Map and Zoning Information). Adjoining properties to the south include Latimer Road, then Bay Breeze Golf Course. The nearest off-site building is a storage building utilized by the golf course for irrigation and landscaping equipment located approximately 250 west-southwest of the abandoned UST.

Based on the designated zoning and current use, occupational and construction/excavation worker scenarios are deemed applicable for the subject property to the north and south and public right-of-ways adjacent to the site.

#### 2.4 Utility Information

A private power line and a telecommunication line are buried less than three (3) feet BLS and backfilled in native soil. Neither utility line is presumed to be conduits for contaminant migration. A private 2-inch diameter water line is located north of the abandoned UST and an eight (8) inch water main is located near the northern fog line for Latimer Road. The location of identified underground utilities in the area is illustrated on **Figure 2**. Information and contact persons for each of the utilities are listed below<sup>3</sup>:

1.) Utility: Power Line

Purpose: Electrical service line to Tillamook Creamery buildings located northeast of UST.

Depth: The approximate depth of the electrical service line is two (2) feet BLS.

Contact: Peoples Utility District (PUD)

1115 Pacific; Tillamook, OR 97141 Rick May - Operations Project Inspector

1-800-422-2535

Article 3.032 of Tillamook City Ordinance 979, amended December 3, 2003

Quarterly Update and Closure Report, LUST Facility 29-00-0859, Bergeson-Boese & Associates, Inc., March 2002

2.) Utility: Communication (i.e., telephone line)

Purpose: Telephone Service/Communication

Depth: The approximate depth of the communication service line is three (3) feet BLS.

Contact: Sprint

2714 6<sup>th</sup> Street; Tillamook, OR 97141

Jerry Luke - 1-541-966-6969

3.) Utility: Water Line (2-inch PVC)

Purpose: Potable Water

Depth: The approximate depth of the water line is two (2) to three (3) feet BLS.

Contact: Bay City Public Works Department

P.O. Box 3309; Bay City, OR 97107

John Law - 1-541-377-4121

3.) Utility: Water Line Purpose: Potable water

Depth: The approximate depth of the water line is two (2) to three (3) feet.

Contact: Bay City Public Works Department

P.O. Box 3309; Bay City, OR 97107

John Law - 1-541-377-4121

# 3.0 REGIONAL AND LOCAL GEOLOGY AND HYDROGEOLOGY

#### 3.1 Regional Hydrogeology

The regional geology of the Tillamook lowlands consists of shallow estuarine bay muds and sands, overlying lithified alluvial deposits. At depth, the alluvial deposits are considered to have high permeability. The primary aquifer in the area consists of permeable terrace gravels which occur at a depth of between 80 to 100 feet below land surface (BLS). The average annual rainfall for Tillamook is approximately 101.5 inches.

#### 3.2 Local Hydrogeology

Information on the local hydrogeology was gathered from previous reports prepared for former LUST 29-00-0859. Soils encountered during previous, and current investigations included gravel from the surface to approximately three (3) feet BLS, overlying silty clay and clayey silt from approximately three (3) feet BLS to approximately 13 feet BLS, and silt and silty gravels from 13 feet to 20 feet BLS. According to static water level measurements collected from monitoring wells MW-1 through MW-4 installed around the perimeter of former LUST site, the shallow groundwater table ranges from four (4) to seven (7) feet BLS. Groundwater table elevations were calculated using the measured depth to groundwater and surveyed reference points on the monitoring wells. The resulting calculated groundwater level elevations indicate that groundwater generally flows in southwest to south-southeast direction under a gradient from 0.013 to 0.030.

#### 3.3 Groundwater Occurrence - Water Well Query

The subject property is located in the Northwest Quarter of the Southwest Quarter of Section 18, Township 1 South, and Range 9 West. Using the Oregon Water Resources Department (OWRD) data base, a search for all well logs located within section 18 was queried. The results of this search and the corresponding well logs identified within the search area are listed below:

| Well Type                 | No. Of Wells |
|---------------------------|--------------|
| Monitoring Well Reports   | 9            |
| Geotechnical Hole Reports | 17           |
| Water Wells               | 11           |
| Abandoned Water Wells     | 1            |

Eleven (11) active water wells and one (1) abandoned water well were identified in the search area. Sufficient information was available to locate 10 of the water wells. Two (2) of the water wells are located within one-quarter (0.25) mile and two (2) water wells are located between one-quarter (0.25) and one-half (0.5) mile of the abandoned UST site. The locations of the mappable water wells are presented on **Figure 3**. Tabulated results of the water well query and copies of the OWRD wells logs are presented in **Appendix C**.

Three (3) of the closest wells to the UST site are described briefly below:

- Well Log TILL478, located on the Tillamook Creamery property, is listed for domestic use. The well, constructed in July 1974, is recorded with a total depth of 80 feet BLS with no perforations in its casing (i.e., the well draws water from 80 feet BLS). The well lies approximately 800 feet to the west-northwest of the abandoned UST site, although according to Tillamook Creamery personnel, the exact location of the well is unknown. The well is not currently being used. Potable water is supplied to the creamery by the city of Bay City and will continue to serve as the sole source of potable water in the future.
- Well Log TILL50600, is an irrigation well located at the Bay Breeze Golf Course approximately 550 west of the abandoned UST site. Well log information indicates the well was registered for repair or reconditioning to a depth of at least 90 feet BLS. Notes on the well log indicate the well was "unusable" following repair efforts. Casing is reportedly installed in the well from two (2) to 98 feet BLS with no reported perforations (i.e., the well draws water from a depth of 98 feet BLS). BB&A contacted Mr. Mike Lehman, owner of the Bay Breeze Golf Course and the well. According to Mr. Lehman, the well is currently not being used because of low yield and high suspended solids (mainly sand) in the water. Mr. Lehman stated a significant amount




FIGURE 3

# TILLAMOOK CREAMERY, 4185 HIGHWAY 101 N., Tillamook, OR

# OREGON WATER RESOURCES WATER WELL QUERY RESULTS



Bergeson-Boese & Associates, Inc.

32986 Roberts Court Coburg, Oregon 97408 (541) 484-9484

25195 SW Porkway Ave., Suite207 Wilsonville, Oregon 97070 (503) 570-9484

Job Code: TC02ISC.08UC CADD File: TC01ISC.08UC Scale: AS SHOWN

Drawn: KATHRYN DAVIS DESIGNS Checked: ERIK CHAPMAN Date: 07/17/08

of resources and expense would be required to repair the well to usable condition. Mr. Lehman did not indicate whether he had any plans for repairing the well in the future.

Well Log TILL477, is registered as a domestic well with a total depth of 100 feet BLS.
Construction details in the well log indicate the well is constructed with 6-inch diameter steel
casing installed from near surface to 98 feet BLS with no perforations (i.e., the well draws
water from a depth of 98 feet BLS). The well is located on the west side of Highway 101
North, just west of the intersection of Highway 101 North and Latimer Road, or approximately
one-quarter mile west of the abandoned UST.

Based on a description of lithology reported for the three (3) closest wells, subsurface lithology consists of "clay", "blue clay", and "clay and gravel" from approximately three (3) feet BLS to between 45 to 85 feet BLS. Water bearing zones were reported in TILL478 with in sandy beds encountered at depths of approximately 45 feet BLS and 70 feet BLS. The water bearing zone reported in well TILL477 was reported at approximately 85 feet BLS. No lithology was reported on well log TILL50600.

The average completion depth and the average depths of groundwater extraction for all wells within the search distance are greater than 100 feet. Based on lithology encountered during drilling, there appears to be a relatively consistent occurrence of a relatively low yield clay from near land surface to a minimum depth of 29 feet BLS. In wells closest to the abandoned UST, the impermeable clays extend to depths between 65 and 85 feet BLS. By comparison, groundwater impacts in the vicinity of the abandoned UST are limited to uppermost portion of the shallow groundwater aquifer and are laterally localized around the immediate area. Due to the depths of surrounding water wells, it is concluded that the release and shallow localized impact to groundwater does not threaten groundwater use in the area.

#### 3.4 Potential for Inter-Aquifer Connection

The potential for chemical transport between the upper and lower aquifers is dependent upon the hydrogeologic characteristics of the aquifers and the physical and chemical properties of the released contaminant. Impact to groundwater beneath the site appears to consist of gasoline-range petroleum hydrocarbon constituents (e.g., benzene, toluene, naphthalene, etc.). The specific gravity of these constituents are generally less than 1.0, and residual concentrations of gasoline-range petroleum hydrocarbons are expected to be confined to the upper portion of the saturated zone. Consequently lower aquifers should not be affected under static conditions. However, in situations were active groundwater withdrawal is occurring as a result of pumping, impacted groundwater could be drawn downward affecting lower portions of the shallow aquifer.

# 4.0 INITIAL SITE CHARACTERIZATION

#### 4.1 Soil and Water Sampling

On April 1, 2008, soil samples were collected from the sidewalls and floor of the excavation and from standing water in the excavation for the purpose of assessing soil and groundwater impacts. Based on the size of the tank (approximately 3.5 feet in diameter) and the depth of burial (approximately three [3] feet), the bottom of the tank was estimated to be approximately 6.5 feet BLS. Approximately 1.5 feet of standing water occupied the bottom of the pit measuring approximately six (6) feet by four (4) feet in area. The surface of the standing water was measured at approximately 4.5 feet BLS. At the time of the initial site characterization sampling, there was a slight hydrocarbon smell noted in the excavation, but no observable sheen on the water.

BB&A collected one (1) sample from the floor of the excavation (NFLOOR@7.5') from native soils at a depth of 7.5 feet BLS, or approximately one (1) foot below the bottom of the tank. The floor sample was collected from saturated soils underlying the standing water in the pit. Sidewall soil samples, EW@4.5' and WW@4.5', were collected from each end of the tank from native soils immediately above the standing water line. All soil samples were collected using a decontaminated stainless steel sampling trowel. Soil and groundwater samples were placed directly into laboratory-prepared containers with appropriate preservatives, uniquely labeled, and preserved on ice pending delivery to the laboratory. The soil and water samples were delivered to Test America in Beaverton, Oregon on April 1, 2008 under chain-of-custody.

Soil and groundwater samples were analyzed for the presence of total petroleum hydrocarbons by method NWTPH-HCID and benzene, toluene, ethylbenzene, xylenes (BTEX) by method EPA 8021B. The water sample was also analyzed for the presence of selected gasoline-related volatile organic compounds (VOCs) and fuel additives by method EPA 8260B and polynuclear aromatic compounds (PAHs) by method EPA 8270M-SIM. The Test America laboratory report and chain-of-custody documents are included in **Appendix D**.

#### 4.2 Results

Initial site characterization sample results are summarized on **Table 1** and illustrated on **Figure 4**. Laboratory results did not identify TPH in the gasoline, diesel or heavy oil range in any of the soil samples. BTEX analysis by EPA Method 8021B identified benzene at a concentration of 0.110 mg/kg in the floor sample along with low concentrations of toluene and xylene. BTEX was not detected in either sample WW@4.5' or EW@4.5'. Based on the absence of detectable TPH or BTEX constituents in sidewall samples WW@4.5' and EW@4.5', it appears that vadose zone soils were not impacted by the historical operation of the abandoned UST. The detected benzene concentration in floor sample NFLOOR@7.5' exceeds DEQ's most stringent Risk-Based Concentration (RBC), however this exposure pathway is later eliminated as a complete exposure pathway for the site.

# Table 1. Initial Site Characterization Measures Soil and Groundwater Sample Analytical Results

Soil concentrations in milligrams per kilogram (mg/Kg), or parts per million (ppm).

Groundwater concentrations in micrograms per liter (µg/L), or parts per billion (ppb)

ND: Indicates contaminant was not detected above method-reporting limit shown in parenthesis.

Shading indicates that analysis not performed.

\*: Indicates naphthalene detected by Method 8260B

| Contaminants-of-       |  | Water Sample Results (µg/L) |   |              |
|------------------------|--|-----------------------------|---|--------------|
| Potential-Concern      | EW@4.6'  | WW@4.6'                     | NFLOOR@7.5'                             | TC-WATER     |
| Gasoline-Range HCID    | ND (<30.4)   | ND (<31.1)                  | ND (<29.7)                              | DET          |
| Diesel-Range HCID      | ND (<75.9)   | ND (<77.8)                  | ND (<74.2)                              | ND (<600)    |
| Heavy Oil Range HCID   | ND (<152)  | ND (<156)                   | ND (<148)                               | ND (<600)    |
| Gasoline-Range TPH     |  |                             |   | 31,300       |
| Diesel-Range TPH       |  |                             |   |              |
| Heavy Oil Range TPH    |  |                             |   |              |
| Benzene                | ND (<0.0411)   | ND (<0.0395)                | 0.110                                   | 2,700        |
| Toluene                | ND (<0.0822)   | ND (<0.0790)                | 0.173                                   | 5,460        |
| Ethylbenzene           | ND (<0.0822)   | ND (<0.0790)                | ND (<0.0769)                            | 736          |
| Xylenes (Total)        | ND (<0.164)  | ND (<0.158)                 | 0.296                                   | 3,520        |
| MTBE                   |  |                             |   | ND (<200)    |
| 1,2-Dichloroethane     |  |                             |   | ND (<50.0)   |
| 1,2-Dibromoethane      | Texture Nove and   |                             |   | ND (<50.0)   |
| Isopropylbenzene       |  |                             |   | ND (<200)    |
| n-Propylbenzene        |  |                             |   | 98.0         |
| 1,3,5-Trimethylbenzene |  |                             |   | 135          |
| 1,2,4-Trimethylbenzene |  |                             |   | 538          |
| Naphthalene            |  |                             |   | ND*/249      |
| Acenaphthylene         |  |                             |   | ND (<0.571)  |
| Acenaphthene           | A STATE OF THE STA |                             | Transfer of the second                  | 0.505        |
| Fluorene               |  |                             | 10 - 10 - 10 - 10 - 10 - 10 - 10 - 10 - | ND (<0.886)  |
| Phenanthrene           |  |                             |   | 1.88         |
| Anthracene             |  |                             |   | 0.299        |
| Fluoranthene           |  |                             |   | ND (<0.503)  |
| Pyrene                 |  |                             |   | ND (<0.296)  |
| Benzo(a)anthracene     |  |                             |   | 0.249        |
| Chrysene               |  |                             |   | 0.187        |
| Benzo(b)fluoranthene   | 198  |                             |   | ND (<0.0952) |
| Benzo(k)fluoranthene   |  |                             |   | ND (<0.0952) |
| Benzo(a)pyrene         |  |                             | STREET, STREET                          | ND (<0.0952) |
| Indeno(1,2,3-cd)pyrene |  |                             |   | ND (<0.0952) |
| Dibenz(a,h)anthracene  |  |                             |   | ND (<0.190)  |
| Benzo(g,h,i)perylene   |  |                             |   | 0.101        |

Laboratory results of the water sample detected TPH in the gasoline range at 31,300 micrograms per liter ( $\mu$ g/L) along with several VOC's and PAH compounds. Among the VOCs detected, benzene was detected at a concentration of 2,700  $\mu$ g/L, and several PAH compounds were detected at low concentrations, including benzo(a)anthracene at 0.249  $\mu$ g/L and naphthalene at 249  $\mu$ g/L.

#### 4.3 Reporting


The results of the initial site characterization were presented in a Twenty-Day Report Form for UST Cleanup Project dated June 27, 2008 to fulfill initial reporting requirements associated with the discovery of a below ground release from the abandoned UST. The below ground release was reported to the DEQ by BB&A. Correspondingly, the DEQ issued UST Cleanup File Number LUST 29-08-0695.

# **5.0 SUBSURFACE INVESTIGATION**

#### 5.1 Push Probe Installations, Sampling, Analysis

On April 29, 2008, BB&A conducted a subsurface investigation around the perimeter of the abandoned UST to assess the magnitude and extent of contamination associated with the reported below ground release from the recently discovered abandoned UST. Specifically, the purpose of the subsurface investigation was to confirm the absence of soil impacts and to delineate the lateral extent of contaminated water found in the base of the investigation as identified during the April 1, 2008 initial site characterization sampling activities. Three push probes (P-1, P-2, and P-5) were installed northeast, west, and south-southeast (down gradient) of the abandoned UST. Push probe P-2 is located approximately six (6) feet east of former LUST site 29-00-0859 and approximately 14 feet west of the recently currently-investigated UST. Based on observed petroleum contamination in push probe P-2 near former LUST site 29-00-0859, two (2) additional push probes, P-3 and P-4, were installed in step-out locations further to the northwest and south-southwest of P-2 to delineate the lateral extent of historical residual soil contamination. Push probe locations are presented on **Figure 4**.

Soil samples were collected using GeoProbe stainless steel core barrels approximately 60 inches in length and 3.25 inches in diameter lined with polyethylene liners. Soils collected in the liners were characterized, as well as inspected for potential indications of soil contamination, such as visual or olfactory evidence (i.e., soil staining, or gasoline odors), and detectable volatile organic vapors using an Organic Vapor Meter with Photoionization detector (OVM-PID). Observations, measurements, and other field notes are recorded on the attached push probe logs, included in **Appendix E**.



Discrete soil samples were selected for analysis from soils containing the highest level of volatile organic vapors (using the OVM-PID), or other evidence of contamination. In the absence of observable soil impacts, soil samples were collected from immediately above the observed soil/water interface. Soil samples were collected using clean nitrile gloves, and placed in clean four (4) ounce glass jars, which were sealed with threaded, teflon-lined caps. The jars were filled such that remaining head space volume was minimized. The sample jars were uniquely labeled, logged on a chain-of-custody document, and placed in a refrigerated cooler. Soil samples were delivered to Test America Analytical Laboratories in Beaverton, Oregon for analysis.

Petroleum staining and measurable vapor readings were identified in push probe P-2 between approximately 4.5 feet BLS and 15 feet BLS. No observable evidence of petroleum contamination by field screening was found in the remaining borings. Based on field observations and the observed depth to water, three (3) soil samples were collected from push probe P-2 at depths between 4.5 feet and 15.5 feet BLS and one (1) sample each was collected from between 11 feet and 15.5 feet BLS in push probes P-3 through P-5. Soil samples were analyzed for the presence of TPH using method NWTPH-Gx, and BTEX constituents using EPA Method 8021B.

#### 5.2 Soil Sample Analytical Results

Analytical results of soil samples collected from the push probes are presented in **Table 2** and illustrated on **Figure 4**. The laboratory report and chain-of-custody record for the push probe soil samples are enclosed in **Appendix D**.

Laboratory results indicate the presence of TPH as gasoline in soil samples collected from push probe P-2 at depths of 4.5 feet, 9.5 feet, and 15.5 feet BLS in the vicinity of former LUST site 29-00-0859. TPH concentrations were detected at concentrations ranging from 53.6 mg/kg to a maximum of 590 milligrams per kilogram (mg/kg) with the highest concentrations in the samples collected from depths of 4.5 feet and 15.5 feet BLS. Analysis of BTEX constituents identified benzene in push probe P-2 at concentrations between 0.187 mg/kg to 2.35 mg/kg. Neither TPH nor BTEX constituents were detected above the MRL in samples collected from "step-out" push probe borings P-3, P-4, or P-5.

#### 5.3 Discussion of Analytical Results - Soil

Laboratory results indicate the presence of vadoze zone and saturated zone soil contamination in the vicinity of push probe P-2, located approximately six (6) feet east of former LUST site 29-00-0859. The soil impacts in this area appear to be limited in lateral extent, but extend vertically from approximately 4.5 feet to 15.5 feet BLS. The lateral extent of soil impacts are delineated to the northwest by push probe P-3, to the southwest by push probe P-4, and to the east by sidewall soil samples collected from the recent UST excavation.

Soil contamination in this area was previously identified during an August 2000 preliminary assessment (PA) conducted at the former LUST site 29-00-0859. During the PA, two (2) push

#### **Table 2. Soil Analytical Results**

Initial Site Characterization Soil Results - April 1, 2008 Subsurface Investigation - April 29, 2008

All analytical results in milligrams per kilogram (mg/kg).

Total Petroleum Hydrocarbons (TPH) as Gasoline analyzed according to Northwest Method NWTPH-Gx.

Volatile organic compounds analyzed according to EPA Method 8021B/8260B.

Toxicity Characteristic Leachate Procedure (TCLP) lead analyzed according to EPA 1311/6000/7000 Series Methods.

ND = not detected at or above method reporting limit (MRL). Where Shaded = Not Analyzed

The most stringent risk-based concentrations (RBCs) per Oregon Department of Environmental Quality's (DEQ's) Risk-Based Decision Making for the Remediation of Petroleum-Contaminated Sites, September 22, 2003. Screening levels were selected as the Vapor Intrusion into Buildings for the occupational receptor.

| Results         | Initial Site Characterization Results<br>April 1, 2008 |              |              | Subsurface Investigation Results April 29, 2008 |         |          |             |             |             |
|-----------------|--|--------------|--------------|---|---------|----------|-------------|-------------|-------------|
| (mg/kg)         | WW@4.5'  | EW@4.5'      | NFLOOR@7.5'  | P2@4.5'   | P2@9.5' | P2@15.5' | P3@11'      | P4@14.5'    | P5@15.5'    |
| TPH-HCID Gas    | ND   | ND           | ND           |   |         |          |             |             |             |
| TPH-HCID Diesel | ND   | ND           | ND           |   |         |          |             |             |             |
| TPH-HCID H. Oil | ND   | ND           | ND           |   |         |          |             |             |             |
| TPH-Gx          |  |              |              | 590   | 53.6    | 311      | ND (<59.0)  | ND (<64.2)  | ND (<66.2   |
| Benzene         | ND (<0.0395)   | ND (<0.0411) | 0.110        | 2.35  | 0.187   | 1.28     | ND (<0.369) | ND (<0.401) | ND (<0.414) |
| Toluene         | ND (<0.0790)   | ND (<0.0822) | 0.173        | 2.66  | 0.181   | 1.38     | ND (<0.737) | ND (<0.803) | ND (<0.827) |
| Ethylbenzene    | ND (<0.0790)   | ND (<0.0822) | ND (<0.0769) | 5.64  | 0.545   | 3.28     | ND (<0.737) | ND (<0.803) | ND (<0.827) |
| Xylenes (Total) | ND (<0.158)  | ND (<0.164)  | 0.296        | 12.4  | 1.08    | 7.78     | ND (<0.737) | ND (<0.803) | ND (<0.827) |

probes (P-1-00 and P-2-00, see **Figure 4**) were placed near the LUST for the purpose of assessing soil and groundwater conditions in support of the in-place decommissioning of the tank. Soil and groundwater samples were collected and analyzed for gasoline-range TPH, BTEX, naphthalene, and PAHs. Analytical results detected gasoline range TPH at a concentration of 720 mg/kg, in excess of Soil Matrix Level II cleanup level of 80 mg/kg. Based on the results of the PA and subsequent investigations, the lateral and vertical extent of soil contamination was determined to be limited to the immediate area surrounding the former LUST<sup>4</sup>. The estimated lateral extent of residual TPH in soil exceeding 100 mg/kg based on previous investigation results is shown on **Figure 4**.

Residual soil impacts associated with LUST site 29-00-0859 were eventually determined to be in compliance with DEQ cleanup requirements stipulated in OAR 340-122-205 through 340-122-360 for all applicable exposure pathways identified for the site<sup>5</sup>.

The only soil impacts attributed to the recent below ground release was found in soil sample NFLOOR@7.5' collected from saturated soils in the floor of the current UST excavation. Based on laboratory results, the detected benzene concentration in this sample (0.110 mg/kg) exceeds only the DEQ's occupational RBC for *Leaching to Groundwater*. None of the other detected BTEX constituents exceeded any of the generic occupational RBCs. Since the sample was collected below the water table, the *Leaching to Groundwater* exposure pathway is best evaluated by the direct sampling and analysis of groundwater. As described in the CSM later in this report, the *Leaching to Groundwater* is not considered to be a complete exposure pathway at the site since groundwater current and future use of groundwater is deemed unlikely.

#### 6.0 GROUNDWATER INVESTIGATION

#### 6.1 Temporary Well Installation and Groundwater Sampling

Upon completing each of the borings and collecting soil samples, temporary dedicated well casing comprised of 1-inch diameter polyvinyl chloride (PVC) was placed in each push probe boring to facilitate groundwater sampling. Each casing was fitted with a 10-foot long section of PVC with 0.010-inch slot size. Prior to sampling groundwater, approximately two (2) to three (3) gallons of groundwater was purged from each temporary well using a low-flow peristaltic pump. New polyethylene tubing was used at each sample location. None of the groundwater purged exhibited

The lateral and vertical extent of soil impactsat LUST site 29-00-0859 are described in BB&A's initial site characterization report entitled "Results of Subsurface Assessment of Abandoned Underground Storage Tank", dated August 1, 2000 and in a document entitled "Investigation For Magnitude and Extent of Contamination and Low Impact Site Evaluation", dated December 8, 2000. In these documents, maps and a cross-section illustrate the lateral and vertical extent of contamination in excess of 100 mg/kg as gasoline-range TPH.

BB&A developed a conceptual site model for the site and evaluated soil conditions utilizing DEQ's guidance document entitled Risk-Based Decision Making for Petroleum-Contaminated Sites, dated September 29, 1999, and specifically the section on Generic Remedy for Simple Risk-Based Cleanups. The evaluation was reported in BB&A's document titled Update Report and Conceptual Site Model, dated September 12, 2001.

any evidence of contamination (i.e., odor or sheen). Groundwater samples were collected from recharging formation water using the peristaltic pump at its lowest setting (0.3 to 0.5 liters per minute), and transferring groundwater directly into laboratory-supplied glassware with appropriate sample preservatives. Each sample container was labeled using a unique identification, logged onto a formal chain-of-custody record, placed on synthetic ice in a chilled cooler, and delivered to Test America Analytical Laboratory in Beaverton, Oregon for analysis.

After probing, temporary casings were removed and the push probe borings were abandoned by backfilling the borings with hydrated bentonite in accordance with OWRD rules.

Groundwater samples were submitted for analysis of petroleum identification using Method NWPTH-Gx, gasoline-range VOCs using EPA Method 8260B, and dissolved lead using EPA 6000/7000 Series Methods.

#### 6.2 Groundwater Analytical Results

Groundwater analytical results are summarized in **Table 3** and on **Figure 5**. Copies of the laboratory reports and chain-of-custody records for the groundwater samples are included in **Appendix D**.

TPH as gasoline was detected in groundwater samples collected from push probes P-2, P-4, and P-5. The highest concentration was detected in push probes P-2 followed by P-4 and P-5. The detected TPH concentrations ranged from  $562 \mu g/L$  to  $8,830 \mu c$  micrograms per liter ( $\mu g/L$ ).


Analytical results by EPA Method 8260B indicate the presence of gasoline-related VOCs in the same push probes (P-2, P-4, and P-5). The highest benzene concentration was detected at 50.1 µg/L. Other VOCs detected in soil samples from P-2, P-4, and P-5 included ethylbenzene xylenes, naphthalene, 1,2,4-trimethylbenzene, 1,3,5-trimethylbenzene, isopropylbenzene, and n-propylbenzene. No VOCs were detected above their respective MRLs in borings P-1, or P-3. Dissolved lead concentrations were detected in push probes P-2 and P-4 at concentrations of 0.00138 mg/L to 0.00293 mg/L, respectively. Lead was not detected above the MRL in borings P-1, P-3, or P-5.

# Table 3. Groundwater Analytical Results

All concentrations in micrograms per liter (µg/L), or parts per billion (ppb).

ND: Indicates contaminant was not detected above method-reporting limit shown in parenthesis.

| Analyte                | P-1           | P-2         | P-3           | P-4         | P-5           | RBC<br>Ingestion/Inhalation<br>Occup | GW in an<br>Excavation |
|------------------------|---------------|-------------|---------------|-------------|---------------|--------------------------------------|------------------------|
| Gasoline-Range TPH     | ND (<80.0)    | 8,830       | ND (<80.0)    | 588         | 562           | 400                                  | 12,000                 |
| 1,2-Dibromoethane      | ND <(0.500)   | ND <(0.500) | ND <(0.500)   | ND (<0.500) | ND (<0.500)   | 0.034                                | 28                     |
| 1,2-Dichloroethane     | ND <(0.500)   | ND <(0.500) | ND <(0.500)   | ND (<0.500) | ND (<0.500)   | 0.75                                 | 600                    |
| Benzene                | ND <(0.200)   | 5.25        | ND <(0.200)   | 4.99        | 50.1          | 2.2                                  | 1,700                  |
| Toluene                | ND <(0.500)   | ND <(0.500) | ND <(0.500)   | ND <(0.500) | 159           | 9,100                                | 200,000                |
| Ethylbenzene           | ND <(0.500)   | 290         | ND <(0.500)   | 14.7        | 24.3          | 5,400                                | 110,000                |
| Xylenes (Total)        | ND <(1.00)    | 385         | ND <(1.00)    | 14.0        | 146           | 820                                  | 22,000                 |
| MTBE                   | ND <(2.00)    | ND <(2.00)  | ND <(2.00)    | ND <(2.00)  | ND (<2.00)    | 64                                   | 59,000                 |
| Naphthalene            | ND <(2.00)    | 271         | ND <(2.00)    | 9.35        | ND (<2.00)    | 25                                   | 680                    |
| Isopropylbenzene       | ND <(2.00)    | 56.8        | ND <(2.00)    | 5.28        | ND (<0.500)   | 2,600                                | 51,000                 |
| n-Propylbenzene        | ND <(0.500)   | 198         | ND <(0.500)   | 9.90        | 1.11          | 240                                  | 4,500                  |
| 1,3,5-Trimethylbenzene | ND <(0.500)   | 248         | ND <(0.500)   | 3.80        | 4.39          | 49                                   | 1,400                  |
| 1,2,4-Trimethylbenzene | ND <(1.00)    | 748         | ND <(1.00)    | 26.5        | 10.7          | 49                                   | 1,300                  |
| Dissolved Lead         | ND (<0.00100) | 0.00293     | ND (<0.00100) | 0.00138     | ND (<0.00100) |                                      | _                      |



#### 6.3 Results Discussion - Groundwater

Dissolved TPH in the gasoline range and several gasoline-related VOCs are present in groundwater in an area of limited areal extent located between the former LUST 29-00-0859 and recently abandoned UST and Latimer Road. The highest groundwater impacts were identified at push probe P-2, located within a zone of residual soil contamination associated with the former LUST site. The lateral extent of groundwater impacts are delineated to the northwest by push probe P-3 and to the northeast by push probe P-1. The downgradient extent of groundwater impacts likely extends a short distance south-southeast of push probes P-4 and P-5 in the direction of the estimated groundwater flow direction<sup>6</sup>.

Based on a review of historical groundwater sample results from former LUST site 29-00-0859, benzene was initially detected in the immediate are of the former tank location at a concentration of 110  $\mu$ g/L (previous push probe P-2-00, August 2000 [**Figure 5**]). The detected benzene concentration in recent push probe P-2 was reported at 5.25  $\mu$ g/L. Historical benzene concentrations detected in former well MW-4 during sampling events conducted between September 2000 and December 2001 were reported at concentrations ranging from 5.7  $\mu$ g/L to 7.0  $\mu$ g/L<sup>7</sup>. The benzene concentration reported in push probe P-4 during this investigation was detected at 4.99  $\mu$ g/L. A comparison of historical and recent groundwater sample analytical data also indicates similar contaminants in groundwater during historic and recent investigations. Historical groundwater monitoring and sampling data from LUST site 29-00-0859 are presented in **Appendix F**.

A south-southeastern groundwater flow direction places push probe P-5 in a down gradient location and push probes P-2 and P-4 in a cross gradient location relative to the recently discovered UST excavation. The presence of groundwater impacts at P-2 and P-4 would indicate the former LUST site (LUST29-00-0859) as the source of groundwater impacts. Since the nature and magnitude of dissolved contaminants from the former tanks are similar, it is not possible to determine the source of dissolved contaminants at push probe P-5 with certainty. The presence of groundwater impacts at push probe P-5 indicates the down gradient extent of the groundwater impacts, regardless of source, is not delineated and likely extends beneath Latimer Road. The installation and sampling of one (1) additional push probe is recommended on the south side of Latimer Road to fully delineate the lateral extent of dissolved contaminants in accordance with OAR 340-122-0240.

Estimated groundwater flow direction is based upon historical groundwater level measurements from former monitoring wells MW-1 through MW-4 associated with former LUST site 29-00-0859. Groundwater flow directions have historically fluctuated from a southwest to a south-southeast direction. Cumulative results of historical groundwater monitoring results are presented in BB&A's document titled *Quarterly Update with Closure Report*, dated March 6, 2002.

Cumulative results of historical groundwater analytical results for the former LUST site (wells MW-1 through MW-4) are presented in Appendix B of BB&As report titled Quarterly Update and Closure Reportl, dated March 6, 2002.

# 7.0 CONCEPTUAL SITE MODEL

In this section, BB&A has developed an updated CSM for the recently discovered UST site for current and reasonably likely future land and water use conditions at the site. The following sections present a summary of the previous CSM and incorporates the findings into the current CSM where applicable. BB&A then compares recent constituent based soil and groundwater data to the current risk-based concentrations (RBCs) for all current exposure pathways deemed applicable for the site under current and reasonably likely future land and water use conditions. Evaluation results are then used to evaluate the site conditions for the purpose of obtaining regulatory site closure.

#### 7.1 Summary of Previous CSM (LUST 29-00-0859)

BB&A originally developed a Conceptual Site Model (CSM) for the previously reported release at LUST 29-00-0859 in September 2001. The original CSM was presented in a document entitled "Update Report With Conceptual Site Model, DEQ USTC No. 29-00-0859" dated September 12, 2001. Revisions to the CSM were completed in a document entitled "Quarterly Update and Closure Report", dated March 6, 2002.

BB&A compared constituent based soil and groundwater data to the RBCs for all complete exposure pathways identified in their CSM. The comparison used the RBCs in DEQ's original guidance document titled "Risk-Based Decision Making for the Remediation of Petroleum-Contaminated Sites", dated September 29, 1999. Site evaluation was completed under DEQ's guidance for Generic Remedy for Simple Risk-Based Cleanups. BB&A presented the evaluation of site conditions to the DEQ in their March 6, 2002 document titled "Update and Closure Report". Upon completing their review, the DEQ approved the CSM and CSM revision and determined that the site appeared to have met the requirements of OAR 340-122-205 through 340-122-360 and that no further action was required. The "no further action" determination was issued in a DEQ letter to Tillamook Creamery dated August 20, 2002.

#### 7.2 Risk-Based Concentrations

In September 2003, the DEQ issued the *revised* guidance document titled *Risk-Based Decision Making for the Remediation of Petroleum-Contaminated Sites*. Within that document, default risk-based cleanup levels were revised for one (1) or more of the 25 petroleum-related VOCs, PAHs, and fuel additives (including lead, MTBE, EDB, EDC, iso-propylbenzene, n-propylbenzene, 1,2,4-trimethylbenzene, and 1,3,5-trimethylbenzene) and expanded the list of RBCs to include generic gasoline-range, diesel-range, and heavy oil-range TPH. The default risk-based cleanup levels for these compounds are presented in the risk-based decision making (RBDM) guidance document as *Appendix A - Table of Risk-Based Concentrations* [RBCs].

#### 7.3 Evaluation of Applicable Exposure Pathways

A review of potential receptors that are appropriate for the site have not changed since 2001 based on current zoning and current and future likely use. As determined in BB&As 2001 CSM, the Occupational; Construction and Excavation Worker receptors scenarios are considered applicable for the site with respect to residual levels of gasoline and related compounds in soil and groundwater.

Routes of entry associated with chemical intake include inhalation of vapors, direct ingestion, and chemical absorption. The CSM evaluates site conditions to assess potential exposure to site contamination. The exposure potential for each pathway is evaluated in the following sections.

#### 7.4 Contaminants-of-Potential-Concern (CoPCs)

Based on historical information about the spill product and analysis of recent near surface soil and groundwater sampling data, the petroleum release at the site appears to be limited to gasoline in groundwater. Regulated contaminants-of-interest (COIs) related to gasoline generally include TPH as gasoline, gasoline-related VOCs (BTEX constituents, naphthalene, MTBE, iso-propylbenzene, n-propylbenzene, 1,2,4-trimethylbenzene, 1,3,5-trimethylbenzene, EDB/EDC), and lead. Those COIs detected by analysis in soil and/or groundwater samples collected from the site comprise the contaminants-of-potential-concern (CoCPs). For this site, the CoCPs include TPH as gasoline, BTEX compounds, naphthalene, n-propylbenzene, 1,2,4-trimethylbenzene, 1,3,5-trimethylbenzene and lead. During this investigation MTBE, iso-propylbenzene, EDB, or EDC were not detected in soil or groundwater, and are therefore not considered CoPCs. Each of the identified CoPCs are evaluated below in the Conceptual Site Model (CSM) for soil and groundwater exposure pathways.

#### 7.5 Extent of Soil and Groundwater Contamination

**Soil:** Laboratory analysis of soil samples collected from the vicinity of the recent below ground release has detected gasoline-range TPH and gasoline-related VOCs in site soils. Benzene, toluene and xylenes were detected in saturated soil below the water table in the floor of the current UST excavation. The detected concentrations were low and appeared to be limited in extent. No gasoline-range TPH or BTEX constituents were detected in the sidewalls of the excavation above the water table. A majority of the soil contamination appears to be related to a previous below ground release from former LUST 29-00-0859 and is limited in extent. Residual soil impacts from the previous below ground release at LUST 29-00-0859 has been evaluated and considered to meet the cleanup requirements of OAR 340-122-205 through 340-122-360 (DEQ correspondence dated August 20, 2002).

**Groundwater:** Dissolved TPH and VOCs are present in groundwater extending from the vicinity of the former LUST 29-00-0859 and the recently discovered UST and extends south-southeast of this area. Groundwater impacts are delineated upgradient of the former USTs in the northwest

and northeast directions, and groundwater impacts appear to extend to some unknown distance to the south-southeast of push probes P-4 and P-5. The installation of one (1) additional push probe boring is required to fully delineate the down gradient extent of dissolved contaminants.

#### 7.6 Evaluation of Applicable Exposure Pathways

Routes of entry associated with chemical intake include inhalation of vapors, direct ingestion, and chemical absorption. The CSM evaluates site conditions to assess potential exposure to

contaminated soil and groundwater. The exposure potential for each pathway is evaluated in the following sections.

#### 7.6.1 Vapor Intrusion of Soil Contaminants to Indoor Air

In this exposure scenario, inhalation of hazardous compounds may occur if residual soil contaminants volatilize and migrate as vapor-phase contaminants into the on-site structure through permeable portions of the foundation (e.g., cracks, expansion joints, utility hookups, etc.). In accordance with DEQ guidance<sup>8</sup>, this pathway should be considered whenever vadose zone soils contaminated with VOCs are located beneath or within 10 feet of a commercial building. Since the area of soil and groundwater contamination lies over 200 feet from the nearest building, the CSM considers this pathway **not viable** for the on-site occupational receptor.

#### 7.6.2 Volatilization of Soil Contaminants to Outdoor Air

Vapor-phase transport of volatile compounds within the vadose zone occurs primarily as a result of diffusion. Volatilized soil contaminants may migrate vertically through the pore spaces of unsaturated soils and escape to outdoor air. The *Volatilization to Outdoor Air* exposure scenario should be considered whenever vadose zone soils are contaminated with VOCs. Due to the presence of vadose zone soil impacts at push probe P-2, the CSM considers exposure associated with the volatilization of soil contaminants to outdoor air under the current land use scenario **viable** for the site.

#### 7.6.3 Incidental Ingestion, Inhalation, and Dermal Contact of Soil

Activities resulting from direct contact with residual PCS may result in chemical intake from a variety of incidental exposure pathways. The potential for incidental ingestion, inhalation, and dermal contact with contaminated soil is interpreted to be generally restricted to limited-duration construction projects and/or trench work. TPH and VOC-impacted soils are generally considered to be an exposure risk for the occupational receptors if contaminants are present in shallow soils less than three (3) feet BLS. Site contaminants were not detected in the upper three (3) feet of the soil column.

<sup>&</sup>quot;Risk-based Decision Making for the Remediation of Petroleum-Contaminated Sites", DEQ Land Quality Division, September, 2003; Table 2.4.

BB&A researched the type and depth of onsite utilities located within the zone of contamination and found that none of them were buried deeper than three (3) feet BLS. Based on current information, there have been no changes in the location or depth of utilities in the area. Based on BB&A's research, the excavation worker exposure pathway is incomplete for trench workers who are involved in maintaining existing lines because utilities (power, telephone, water) are located less than three (3) feet BLS, preventing trench utility workers from encountering the deeper contaminants of concern. Since future excavation work below three (3) feet is possible during future construction projects, the CSM considers exposure associated with incidental ingestion, inhalation, and dermal contact **complete** for future excavation and construction worker receptors but not complete for the current or future occupational worker.

#### 7.6.4 Leachate of Soil Contaminants to Groundwater

Impact to groundwater from UST releases generally occurs indirectly as a result of contaminants leaching from a primary contaminant source (i.e., impacted "source soils"). Dissolved groundwater contaminants may in turn be ingested directly or volatilized to indoor and/or outdoor air. Factors affecting the leaching potential of soil contaminants include annual precipitation rate, the fraction of organic carbon present in the soils, and the soil porosity. This pathway should be considered whenever vadose zone contamination is found overlying an aquifer that is currently used or is reasonably likely to be used for drinking water. The results of site investigation activities identified soil impacts beneath the water table (in the floor of the UST excavation) and as residual impacts near former LUST 29-00-0859. Residual soil contamination near former LUST 29-00-0859 has met the cleanup requirements of the DEQ and no further action is considered necessary. As a conservative measure, the CSM will evaluate the leaching to groundwater pathway, however, the potential for this pathway to be complete is actually very low since the shallow groundwater table is not likely to be used as a potable water source under current or future water use scenarios.

#### 7.6.5 Volatilization of Groundwater Contaminants to Indoor Air

Under certain conditions, dissolved-phase contaminants may volatilize at the water table surface and migrate as vapor within the unsaturated zone. Inhalation exposure may result if volatilized contaminants migrate vertically and enter indoor enclosed spaces. This pathway should be considered whenever vadose zone groundwater contaminated with VOCs are located beneath or within 10 feet of a commercial building or beneath or within 50 feet of a residential building. Since the nearest building lies over 200 feet to the east (cross gradient) of the zone of contamination, the CSM considers exposure via *Volatilization to Indoor Air* to be **not viable** for the on-site or off-site occupational receptors.

#### 7.6.6 Volatilization of Groundwater Contaminants to Outdoor Air

Dissolved petroleum hydrocarbons may volatilize at the water table surface and migrate as vapor

within the unsaturated zone. Inhalation exposure may occur if volatilized contaminants migrate vertically and escape to outside air. The CSM considers exposure associated with the volatilization of dissolved groundwater contaminants to outdoor air under the current and future land use scenario **viable**.

#### 7.6.7 Ingestion of and Inhalation from Tap Water

One (1) on-site and two (2) off-site water wells are located within one-quarter (0.25) mile from the site. The two (2) closest wells are currently not being used and are not considered likley to be used in the future since the site and surrounding properties to the south (golf course) derive their domestic water from the City of Bay City. In addition, all water wells in the area appear to draw water from a deeper aquifer (over 100 feet BLS). Based upon research performed and since the subject property and adjoining properties are supplied potable water by a municipal water system, the CSM considers this pathway **not viable** under the current and future land use scenario.

#### 7.6.8 Incidental Ingestion, Inhalation, and Dermal Contact of Excavation Groundwater

Activities resulting from direct contact with impacted groundwater may result in chemical intake from a variety of incidental exposure pathways. The potential for incidental ingestion, inhalation, and dermal contact with affected media is possible during construction projects performed in conjunction with site improvements and/or trench work. This pathway is considered complete where construction workers or excavation workers may come into contact with contaminated groundwater in a semi-enclosed space such as an excavation. Groundwater occurs beneath the site and general vicinity at depths greater than three (3) feet BLS. The depth of all utilities located within the impacted zone are buried less than three (3) feet BLS, preventing trench workers from encountering deeper soil and groundwater contamination. Nevertheless, construction work involving excavations for foundations or other structures is unlikely, but possible in the future. The CSM considers exposure to construction workers and trench workers working onsite and in adjoining rights-of-way as **viable**. A summary of exposure pathways is presented in **Table 4**.

Table 4. Summary of Conceptual Site Model Exposure Pathways

|   | Subject      | Property                     |  |  |  |
|---|--------------|------------------------------|--|--|--|
| Pathway   | Occupational | Excavation/<br>Const. Worker | Comments   |  |  |
| Vapor intrusion of soil contaminants into buildings                                 | No           | NIA                          | Excluded since nearby buildings are located over 50 feet fron soil impacts.  |  |  |
| Volatilization of soil contaminants to outdoor air                                  | Yes          | MIA                          | All soil impacts associated with the recent below ground release are below the water table and not present in vadose zone soils.   |  |  |
| Ingestion, inhalation, and dermal contact of soil contaminants                      | No           | Yes                          | Soil impacts are greater than three (3) feet BLS, preventing exposure to the occupational worker during maintenance work on existing utilities. Depth of utilities are less than three (3) feet BLS, preventing trench workers from exposure to deeper contaminants of concern. Future excavations may extend to deeper depths and result in contact with contaminated media.      |  |  |
| Leaching of soil contaminants to groundwater  | Yes          | Nug                          | Residual soil contaminants represent on-going source of groundwater impact. However, groundwater is not being consumed. All occupational receptors are excluded since nearby buildings are located over 50 feet from groundwater impacts.  |  |  |
| Volatilization of groundwater contaminants into buildings                           | No           | Nug                          | Not viable since the nearest building is over 200 feet from the zone of groundwater impacts.   |  |  |
| Volatilization of groundwater contaminants to outdoor air                           | Yes          | Nip                          | Due to the presence of groundwater contamination, this exposure pathway is viable, though very unlikely. The area is not occupied by occupational workers and there are not any nearby buildings. Future occupation and development is unlikely given the location (i.e., near the property line). Offsite, the area is a roadway. The use of the roadway is not likely to change. |  |  |
| Ingestion of groundwater,<br>volatilization from tap water                          | No           |                              | Not viable. The site and adjoining properties are supplied by municipal water system. Nearest private wells off-site are no located within one-quarter mile and draw water from a deeper aquifer. Future use of nearby wells is unlikely based on interviews with well owners.   |  |  |
| Ingestion, inhalation, and dermal contact of dissolved groundwater in an excavation |              | Yes                          | Contact with gasoline-impacted groundwater possible during future construction activities involving trenching and/or excavation greater than three (3) feet BLS.   |  |  |

#### 7.7 Risk-Based Concentrations for Applicable Exposure Pathways

#### 7.7.1 Soil RBC Comparisons

Current soil impacts associated with the recent below ground release appear to be limited to an area in the floor of the recent excavation and immediately surrounding former LUST 29-00-0859. Residual soil impacts from the previous below ground release at LUST 29-00-0859 has been evaluated and considered to meet the cleanup requirements of OAR 340-122-205 through 340-122-360 (DEQ correspondence dated August 20, 2002).

In **Table 5**, below, the analytical results of representative soil samples collected during the recent investigation (i.e., "worst case") are compared to the most stringent applicable RBCs. The leaching to groundwater RBCs are listed for comparison, however, the groundwater ingestion and inhalation from tap water pathway is deemed incomplete.

As presented in **Table 5**, none of the gasoline or gasoline constituent concentrations detected in the "worst case" soil samples collected on-site as represented by samples collected the floor of the recent UST excavation and push probe P-2, contained concentrations exceeding the RBCs for applicable exposure pathways (i.e, RBCs for leaching to groundwater excluded).

#### Table 5. Comparison of Contaminant Concentrations in Soil to Applicable Soil Exposure RBCs

All concentrations in parts per million (ppm).

Risk-Based Concentrations (RBCs) are for Occupational and Excavation receptor scenarios from Appendix A of DEQ's Risk-Based Decision Making for the Remediation of Petroleum-Contaminated Sites (9/2003)

>MAX: The constituent RBC for this pathway is greater than 100,000 mg/kg; an unlikely attainable concentration.

>Csat: RBC for direct contact at concentration above point of saturation.

NV: Not Volatile, therefore, this RBC is not applicable.

|                                       | NFLOOR@7.5'  | P-2@4.5'  | Leaching to<br>Groundwater | Volatilization to<br>Outdoor Air | Surface soil ingestion, dermal contact, & inhalation |                   |  |
|---------------------------------------|--------------|-----------|----------------------------|----------------------------------|--|-------------------|--|
| Contaminants-of-<br>Potential-Concern | (4/1/2008)   | (4/29/08) | Occupational               | Occupational                     | Construction Worker                                  | Excavation Worker |  |
| Gasoline-range<br>TPH-HCID            | ND (<29.7)   |           | 110                        | 80,000                           | 13,000   | >MAX              |  |
| Diesel-Range<br>TPH-HCID              | ND (<74.2)   |           | >MAX                       | >MAX                             | 23,000   | >MAX              |  |
| Heavy- Oil TPH-<br>HCID               | ND (<148)    |           | >MAX                       | >MAX                             | 40,000   | >MAX              |  |
| TPH Gasoline<br>NWTPH-Gx              |              | 590       | 110                        | 80,000                           | 13,000   | >MAX              |  |
| Benzene                               | ND (<0.0388) | 2.35      | 0.052                      | 48                               | 340  | 9,400             |  |
| Toluene                               | ND           | 2.66      | >Csat                      | >Csat                            | 24,000   | >MAX              |  |
| Ethylbenzene                          | 0.628        | 5.64      | >Csat                      | >Csat                            | 28,000   | >MAX              |  |
| Xylenes (Total)                       | 1.6          | 12.4      | 100                        | >Csat                            | 19,000   | >MAX              |  |

### 7.7.2 Groundwater RBC Comparisons

In **Table 6** below, the "worst case" groundwater sample collected during this site investigation ("TC-WATER" collected directly from standing water in the excavation) and one (1) sample collected from push probe P-2 are compared to applicable RBCs for on-site conditions. As presented in **Table 6**, petroleum constituents detected in the "worst case" groundwater samples representing conditions within the immediate area of the former UST pit (i.e., pit water in the excavation) exceed the RBCs for *Groundwater in an Excavation* for the Construction Worker and Excavation Worker. Based on groundwater data collected from push probe boring P-2, none of the detected constituents exceeded the applicable RBCs.

#### Table 6. Evaluation of RBCs for Applicable Groundwater Exposure Pathways

All concentrations in parts per billion (ppb), or micrograms per Liter (µg/L).

Risk-Based Concentrations (RBCs) are for Occupational and Excavation receptor scenarios from Appendix A of DEQ's Risk-Based Decision Making for the Remediation of Petroleum-Contaminated Sites (9/2006)

>S: The constituent RBC for this pathway is greater than the solubility limit of the constituent. Groundwater concentrations exceeding this value may Indicate free product. NV = Non Volatile. >Max = The constituent RBC for this pathway is greater than 100,000 mg/kg; an unlikely attainable concentration. NV = non-volatile. NE = Not Established

|                                       |                       |                        | Groundwater in an Excavation      | Volatilization to<br>Outdoor Air |  |
|---------------------------------------|-----------------------|------------------------|-----------------------------------|----------------------------------|--|
| Contaminants-of-<br>Potential-Concern | P-2-H20<br>(04/29/08) | TC-WATER<br>(04/01/08) | Construction & Excavation Workers | Occupational                     |  |
| Gasoline-Range TPH                    | 8,830                 | 31,300                 | 12,000                            | >S                               |  |
| Benzene                               | 5.25                  | 2,700                  | 1,700                             | 13,000                           |  |
| Toluene                               | ND <(2.50)            | 5,460                  | 200,000                           | >S                               |  |
| Ethylbenzene                          | 290                   | 736                    | 110,000                           | >S                               |  |
| Xylenes (Total)                       | 385                   | 3,520                  | 22,000                            | >S                               |  |
| MTBE                                  | ND <(10.0)            | ND <(200)              | 59,000                            | 1,100,000                        |  |
| Isopropylbenzene                      | 56.8                  | ND <(200)              | >S                                | >S                               |  |
| Naphthalene                           | 271                   | ND <(200)              | 680                               | >Max                             |  |
| n-Propylbenzene                       | 198                   | 98.0                   | >\$                               | >S                               |  |
| 1,2,4-Trimethylbenzene                | 748                   | 538                    | 51,000                            | >S                               |  |
| 1,3,5-Trimethylbenzene                | 248                   | 135                    | 38,000                            | >S                               |  |
| Naphthalene                           |                       | 249                    | 680                               | >Max                             |  |
| Acenaphthylene                        |                       | ND <(0.571)            | NE                                | NV                               |  |
| Acenaphthene                          |                       | 0.535                  | 25,000                            | NV                               |  |
| Fluorene                              |                       | 0.886                  | 14,000                            | NV                               |  |
| Phenanthrene                          |                       | 1.88                   | NE                                | NV                               |  |
| Anthracene                            |                       | 0.299                  | >Max                              | NV                               |  |
| Fluoranthene                          |                       | 0.503                  | NV                                | NV                               |  |
| Pyrene                                |                       | 0.296                  | NV                                | NV                               |  |
| Benzo(a)anthracene                    |                       | 0.249                  | NV                                | NV                               |  |
| Chrysene                              |                       | 0.187                  | NV                                | NV                               |  |
| Benzo(b)fluoranthene                  |                       | ND <(0.0952)           | NV                                | NV                               |  |
| Benzo(k)fluoranthene                  |                       | ND <(0.0952)           | NV                                | NV                               |  |
| Benzo(a)pyrene                        |                       | ND <(0.0952)           | NV                                | NV                               |  |
| Indeno(1,2,3-cd)pyrene                |                       | ND <(0.0952)           | NE .                              | NV                               |  |
| Dibenz (a,h)anthracene                |                       | ND <(0.190)            | 0.2                               | NV                               |  |
| Benzo(g,h,i)perylene                  |                       | 0.101                  | NE                                | NE                               |  |
| Dissolved Lead                        | 0.00293               | NA                     | NE                                | NV                               |  |

#### 7.8 Summary of Soil and Groundwater Evaluation

Based on analytical soil data collected to date, residual concentrations of TPH as gasoline and associated constituents are below all RBCs for all applicable exposure pathways (*Leaching to Groundwater* excluded). The *Leaching to Groundwater* pathway does not result in any unacceptable exposure risk since the groundwater ingestion and inhalation from tap water is deemed incomplete and current groundwater impacts are below *Volatilization to Outdoor Air* RBCs for the occupational receptor.

Exposure pathways considered complete for groundwater included *Groundwater in an Excavation* for the construction and excavation worker and *Volatilization to Outdoor Air* for the Occupational Worker. In the pit water sample, only TPH as gasoline and benzene exceed RBCs for *Groundwater in an Excavation*. Neither lead nor any of the detected PAH constituents exceeded applicable RBCs. Comparison of the pit water analytical results to applicable RBCs is an overly conservative estimate of risk since impacts in the pit water represent undiluted product from the tank and not actual groundwater concentrations. All detected contaminants of concern in groundwater from P-2 were below their respective generic RBCs for the site.

The lateral extent of groundwater impacts appears to be limited in extent, however, the down gradient extent was not determined in the south-southeast direction. Based on COC concentrations in down gradient push probe P-5, the down gradient edge of the plume is estimated to extend a short distance beneath Latimer Road. Occupational receptors to the south-southeast are not considered to be at risk in the future. This conclusion is supported by current soil and groundwater conditions that appear to be limited in extent and the use of the area immediately south of the site as a roadway. Future use of the roadway is not expected to change.

# 8.0 CONCLUSIONS AND RECOMMENDATIONS

#### 8.1 Conclusions

A summary of the findings of this investigation support the following conclusions:

- The site is currently an industrial property with DEQ Facility Identification Number of 4347. The recent below ground release has been assigned LUST Number 29-08-0695
- Surrounding land use is composed of industrial, farm, and rural community development. Based on the designated zoning for the subject property and its current use, and the zoning and current use of adjoining properties, occupational and construction/excavation worker scenarios are deemed applicable to the site.

- A below ground release of water and gasoline-range petroleum hydrocarbons occurred on March 31, 2008 when utility workers encountered an unregistered, abandoned 500-gallon UST within a utility trench. A release estimated at less than one (1) gallon occurred when the bucket of a backhoe punctured the top of the tank. Further releases were prevented by pumping out the contents of the tank and removing the tank from the excavation on the same day. Inspection of the tank revealed no evidence of heavy corrosion pits, holes, or cracked weld seams in the walls of the tank.
- Previous to this investigation, on July 27, 2000, one (1) abandoned 675-gallon UST containing unleaded gasoline was discovered and eventually decommissioned in-place on November 1, 2000. This separate cleanup site, identified as LUST site number 29-00-0859, is located approximately 25 feet east of the recently discovered UST. A preliminary assessment of the release identified soil and groundwater contamination by gasoline-range constituents. Four (4) monitoring wells were installed for the purpose of defining the full magnitude and extent of impacts. Based on the groundwater monitoring results, impacts were limited to within the vicinity of the UST and did not migrate off-site. Residual soil and groundwater impacts associated with LUST 29-00-0859 was considered to meet the cleanup requirements of OAR 340-122-205 through 340-122-360 and the LUST site was issued a "no further action" designation in a DEQ correspondence dated August 20, 2002.
- On April 1, 2008, BB&A completed an initial site characterization at the site to assess the presence of soil and groundwater impacts. Confirmation soil samples were collected from the sidewalls and floor of the excavation and screened for the presence of total petroleum hydrocarbons using NWTPH-HCID and BTEX using EPA Method 8021B. A water sample was collected from standing water in the excavation and analyzed by TPH-HCID, gasoline-range TPH by NWTPH-Gx method, gasoline-related VOCs by EPA Method 8260B, and PAHs by EPA Method 8270-SIM. Analytical results did not identify any detectable total petroleum hydrocarbons in the sidewall soil samples and low concentrations of BTEX in the floor of the excavation. Analytical results of the water sample indicated the presence of gasoline-range petroleum hydrocarbons, gasoline constituents, and low concentrations of PAHs. Gasoline-range TPH was detected at 31,300 μg/L and benzene was detected at 2,700 μg/L, although the water sample is not considered to represent groundwater conditions.
- On April 29, 2008, five (5) push probes, were advanced to a depth of 20 feet below land surface (BLS) to adequately sample soils and intercept the groundwater table. Soil and groundwater samples were collected from the push probes and monitoring wells for laboratory analyses. Soil samples were analyzed for gasoline-range TPH by NWTPH-Gx and BTEX constituents using EPA Method 8021B. Groundwater samples were analyzed by TPH-Gx, selected gasoline-range VOCs by EPA Method 8260B, and dissolved lead using EPA Method 6000/7000 Series Methods.
- TPH as gasoline and gasoline-related VOCs were detected in soils at push probe P-2, located near the former LUST site 29-00-0859. Soil samples collected from the remaining push probes did not contain TPH as gasoline or any BTEX constituents above their respective

MRLs. Soil impacts at push probe P-2 identified gasoline-range TPH and BTEX constituents in samples collected from 4.5 feet, 9.5 feet, and 15.5 feet BLS.

- TPH and gasoline-related VOCs were detected in groundwater samples collected from push probe P-2, P-4, and P-5. The highest concentrations were reported in push probe P-2 located six (6) feet east of the former LUST site 29-00-0859.
- As part of the investigation, BB&A developed an updated CSM for the site. Based on the current physical setting, the Occupational, Construction and Excavation Worker receptor scenarios are considered applicable for this release with respect to residual levels of gasoline related compounds in groundwater. The occupational *Leaching to Groundwater* and the *Volatilization to Outdoor Air* for the construction and excavation worker were identified in the CSM for soil.
- The CSM identified *Volatilization to Outdoor Air* for the Occupational Worker and *Groundwater in an Excavation* for the construction and excavation worker as complete pathways of exposure for site groundwater under current and future land and water use conditions.
- A water well query was completed for the site and surrounding properties within Section 18 of Township 2 South Range 9 West. Neither of two (2) active water wells located within one-quarter mile of the site are currently being used. Based on interviews with the well owners (Tillamook Creamery and Mr. Mike Lehman, owner of the Bay Breeze Golf Course), neither of the water wells are likely to be used in the future since the properties served by the wells are connected to municipal water supplies.
- As part of the CSM, BB&A compared the highest detected contaminants in soil and groundwater to risk-based concentrations (RBCs) developed by the DEQ for applicable exposure pathways and scenarios. Excluding the *Leaching to Groundwater* pathway, none of the detected BTEX consituents in the "worse-case" soil sample exceeded applicable RBCs. The occupational *Leaching to Groundwater* pathway is not likely to result in unacceptable risk since the occupational *Ingestion and Inhalation from Tapwater* pathway is deemed incomplete.
- Results of the evaluation indicates that TPH as gasoline and benzene exceeded the respective RBCs
  for the *Groundwater in an Excavation Pathway*, however this is considered to be an overlyconservative evaluation of risk. The detected COC concentrations in "worse-case" groundwater
  sample from push probe P-2 did not exceed any of the applicable RBCs.

### 8.2 Discussion/Recommendations

Based on the relatively small volume of fluids released during the recent release from LUST 29-08-0695, and results of soil and groundwater sampling completed during this investigation, the impacts to soil and groundwater appear to be limited to the immediate area around the abandoned tank. Some or all of the identified soil contamination appears to be associated with the historical below ground release from former

LUST 29-00-0859. Excluding contaminants found in standing water in the UST excavation, the levels of contaminants in groundwater appear to be protective of human health and the environment under current and future land and water use conditions.

According to historical monitoring data, the predominant groundwater flow direction is to the south-southeast. The down gradient extent of groundwater contamination was not delineated during this investigation as required under OAR 340-122-0240. As such, one (1) additional push probe located on the south side of Latimer Road is recommended. Groundwater samples collected from the new push probe should be analyzed for TPH in the gasoline range using NWTPH-Gx method and gasoline-related VOCs using EPA Method 8260B. Analytical results should then be documented in an addendum letter along with a request for the DEQ to issue a "no further action" determination for the site.

### 9.0 LIMITATIONS

Professional services provided by BB&A have been performed using the degree of care and skill ordinarily exercised, under similar circumstances, by reputable environmental research and consulting firms practicing in this or similar localities. No other warranty, expressed or implied, is made as to the professional advice included in this report.

No investigation is thorough enough to ensure that no contamination is present on a particular property or in a particular area. The analyses of the samples collected only indicates the presence and absence of contaminants in those discrete sample locations. Based on our experience with similar investigations, and within the limits of the scope of work and budget constraints of this project, the samples were collected from areas most likely to be impacted by potential contamination. However, the results from the collected samples should only be considered as an indicator of subsurface conditions and not as a guarantee of the absence of contaminants in areas not sampled.

Respectfully submitted,

Bergeson-Boese & Associates, Inc.

OREGON ERIK R. CHAPMAN

G2208

Erik R.D. Chapman, RG

Project Manager

Randall J. Boese, RG Senior Hydrogeologist RANDALL J. BOESE

G966

# APPENDIX A Zwald Industrial Services, Inc. Fluid Disposal Receipt and Don Averil Recycling Receipt



7540 Hurliman Hill Rd Tillamook, OR 97141 503-842-1005

## Inva

| Date     | Invoice # |  |
|----------|-----------|--|
| 4/4/2008 | 8106      |  |

B渊 To T.C.C.A Accounts Payable 4185 Hwy 101 N. Tillamook, OR 97141


Service Address T.C.C.A Accounts Payable 4185 HWY 101 N. Tillamook OR 97141


|                                |  | P.O. or Job No. | Opera  | tor  | Due Date                  |
|--------------------------------|--|-----------------|--|--|---------------------------|
|                                |  | 60229           | Nick/St  | eve  | 5/10/2008                 |
| Serviced                       | Description  | Loads           | Hours  | Rate   | Amount                    |
| /31/2008<br>/1/2008<br>/1/2008 | On site pumping out old underground tank Travel to and from Portland, OR to disposal site Disposal charges at Pacific Power Vac in Portland Oregon | 1               | 1.5<br>4.5<br>598  | 100.00<br>100.00<br>0.275  | 150.06<br>430.06<br>164.4 |
| ALK-                           | DATEMATERIAL GETTE<br>DATE MATERIAL GETTE<br>DATE PAIN<br>GLARY  | R 6 7 1908      |  |  |                           |
|                                | 6-34 Ce  | Thy .           |  |  |                           |
|                                |  |                 |  |  |                           |
| hank You! V                    | Ve appreciate your business.   | Total           | and the second s | A CONTRACTOR OF THE PROPERTY O | \$764.4                   |

### DOM AVERILL RECYCLING

1315 Eckloff RG TILLAMOOK, OR 9714 603-842-4588

| Customer's<br>Order No  | Date 3:2                      | \$ \( \frac{1}{20} \) |
|-------------------------|-------------------------------|-----------------------|
| lame 7 C                | 4                             |                       |
| Address                 |                               |                       |
| SCID ST CASH COLD       | OPARGE ON MUSE<br>ACCT ASTD I | TOO WAY               |
| QUAN. DESCR             | IPTION PRICE                  | TOUDINA               |
| affect t                | 4 19                          |                       |
| Anle soc                | SalTANK                       |                       |
|                         | /                             |                       |
| 188 1313                | Hosel or                      |                       |
| - 10                    | ocycle 17                     |                       |
| M R                     | 2 Grill                       |                       |
|                         |                               |                       |
|                         |                               |                       |
|                         | TAX                           |                       |
|                         | TOTAL                         |                       |
| 1001051                 | Rec'd by MIC                  |                       |
| All claims and returned | goods MUST be accompanie      | d by this bill.       |
|                         | Thank You                     | e sort                |







### SECTION 3.032: GENERAL INDUSTRIAL ZONE (M-1)


(1) PURPOSE: The purpose of the M-1 zone is to accommodate uses that cannot be accommodated in other zones due to off-site impacts that could, without sufficient buffers, interrupt the use or enjoyment of surrounding properties. Uses listed in Section 3.032 are permitted in the identified Port of Tillamook Bay Industrial Park "M-1 Zone" and the Tillamook Creamery "M-1 Zone" only.

Land is suitable for the M-1 zone if it:

- (a) Is needed;
- (b) Is physically capable of accommodating heavy industrial activities;
- (c) Has access to transportation routes capable of accommodating heavy traffic;
- (d) Is buffered from residential areas so as not to create conflicts; and
- (e) Is or can be adequately served by public utilities and services.
- (f) Land zoned for resource use cannot be zoned M-1 without an approved Exception to Goals 3, 4, and 14.
- (g) Land zoned for development cannot be zoned M-1 zone without an approved Exception to Goal 14.
- (2) USES PERMITTED OUTRIGHT: In the M-1 zone, the following uses and their accessory uses are permitted outright, subject to all applicable supplementary regulations contained in this Ordinance:
  - (a) Light industries.
  - (b) Heavy industries.
  - (c) Sales and service activities requiring large outdoor storage space, including the sale and repair of cars, trucks, farm equipment, heavy machinery, and marine craft; the storage of construction, plumbing, heating, paving, electrical, and painting materials; and parking for trucks as part of a construction or shipping operation.
  - (d) Warehousing, including mini-storage, wholesaling, truck dispatch, or storage facilities.
  - (e) Rock quarries, and the mining and processing of sand, gravel, peat and other earth products.

- (f) Farm uses, including aquaculture, and forest uses.
- (g) Energy resource exploration and extraction.
- (h) Public park and recreation uses.
- (i) Utility substations and power transmission lines.
- (j) Towers for communications, wind energy conversion systems, or structures having similar impacts.
- (k) Sanitary landfills, waste transfer stations or processing facilities, and recycling centers.
- (l) Water supply and treatment facilities and sewage treatment plants.
- (m) Airports.
- (n) Dwellings for caretakers or watchmen that are accessory to an established use, including mobile home or recreational vehicle.
- (o) Mobile homes or recreational vehicles used during the construction of a use for which a building permit has been issued.
- (p) Signs, subject to Section 4.020.
- (q) Uses listed in Subsections 3.032 (3) (c) through (f) are permitted outright in the Port of Tillamook Bay Industrial Park "M-1 Zone" only.
- (r) Off-Site Advertising Sign.
- (3) USES PERMITTED CONDITIONALLY: In the M-1 zone, except as provided in Subsection (2) (q) of this Section, the following uses and their accessory uses are permitted subject to the provisions of Article 6 and the requirements of all applicable supplementary regulations contained in this Ordinance:
  - (a) Industries with exceptionally heavy environmental impacts according to State Department of Environmental Quality standards.
  - (b) Mining and processing activities not specifically listed in Section 3.032 (2).
  - (c) Power generating facilities.
  - (d) Business, government, or professional offices.
  - (e) Convention facilities, including motels and restaurants.

- (f) Fire or ambulance stations.
- (g) Schools.
- (h) Community meeting buildings and associated facilities.
- (i) Temporary mobile kitchen units.
- (j) Auto wrecking yards.
- (k) Recreational campground, provided that in addition to the conditional use criteria contained in Section 6.040 the following criteria are met and/or applied as conditions if approval is granted.
  - 1. The proposed development will not conflict with any existing or emerging patterns of industrial development;
  - 2. Permanent facilities and structures are limited so that they can easily be removed to accommodate an industrial siting; and,
  - 3. Periodic review of the decision shall be conducted by the County Planning Staff to determine if a need is present for the subject parcel to be converted to industrial use.
- (1) Correctional facility.
- (m) Golf Course in Port of Tillamook Bay Industrial Park.
- (4) STANDARDS: Land development in the M-1 zone shall conform to the following standards, unless more restrictive supplemental regulations apply:
  - (a) The minimum yard adjacent to a residential use or zone shall be 20 feet.
  - (b) Building heights shall not exceed 75 feet.
  - (c) Outdoor storage abutting or facing a lot in a residential zone shall be screened with a sight-obscuring fence.
  - (f) Off-street parking and loading areas shall be provided as specified in Section 4.030.



### SECTION 3.020: RURAL COMMERCIAL ZONE (RC)

- (1) PURPOSE: The purpose of the RC zone is to permit a moderate level of commercial activities to serve the commercial needs of rural areas, and tourist areas. Commercial uses in the RC zone typically provide goods and services that would be required by most households in the area, and they have relatively few impacts on neighboring areas. Land is suitable for the RC zone because it:
  - (a) Is needed;
  - (b) Is physically capable of being developed;
  - (c) Can obtain access to a public road without causing traffic hazards or congestion;
  - (d) Will not cause significant conflicts with nearby residential uses; and
  - (e) Has sufficient land area to accommodate off-street parking.
- (2) USES PERMITTED OUTRIGHT: In the RC zone, the following uses and their accessory uses are permitted outright, subject to all applicable supplementary regulations contained in this ordinance.
  - (a) General retail trade establishments such as grocery stores, drug stores, or hardware stores, provided that such establishments do not require over 15 parking spaces.
  - (b) Business, government, professional, and medical offices, financial institutions, and libraries requiring less than 15 parking spaces.
  - (c) Eating and drinking establishments, excluding drive-in or fast food restaurants.
  - (d) A single-family dwelling, manufactured or mobile home for the owner of an active business located on the same lot or parcel.
  - (e) Mobile home or recreational vehicle used during the construction of a use for which a building or placement permit has been issued.
  - (f) Swimming, tennis, racquetball, or other similar facilities.
  - (g) Signs, subject to Section 4.020.
  - (h) Dwelling unit or units accessory to an active commercial use, located above the first story.
  - (i) Bed and breakfast enterprise.

- (j) Public park and recreation uses.
- (k) Miniature Golf Course.
- (1) Temporary produce stand- Not to exceed 45 days.
- (3) USES PERMITTED CONDITIONALLY: In the R C zone, the following uses and their accessory uses are permitted subject to the provisions of Article IV and the requirements of all applicable supplementary regulations contained in this ordinance:
  - (a) General retail trade establishments such as grocery stores, drug stores, and hardware stores, that require 25 parking spaces or fewer.
  - (b) Sales and service activities requiring a large outdoor storage space, including the sale and repair of cars, trucks, farm equipment, heavy machinery and marine craft; the storage of construction, plumbing, heating, paving, electrical and painting materials; and parking for trucks as part of a construction or shipping operation.
  - (c) Warehousing, including mini-storage.
  - (d) Animal hospitals, kennels or other animal boarding facilities.
  - (e) Lodges, clubs, or meeting facilities for private organizations.
  - (f) Temporary mobile kitchen units.
  - (g) Light industries.
  - (h) One-family dwelling,
  - (i) Mobile home or recreational vehicle.
  - (j) Churches and schools.
  - (k) Community meeting buildings and associated facilities.
  - (1) Hospitals, sanitariums, rest homes, and nursing homes.
  - (m) Fire and ambulance stations.
  - (n) Utility substations and power transmission lines.
  - (o) Towers for communications, wind energy conversion systems, or structures having similar impacts.

- (p) Water supply and treatment facilities, and sewage treatment plants.
- (q) Foster family home accommodating six or more children or adults.
- (r) Recreational campgrounds without full hook-up requiring community septic system.
- (s) Off-site advertising sign.
- (t) Residential care, training, or treatment facility as defined by ORS 443.400; any facility which provides care, training or treatment for six or more physically, mentally, emotionally, or behaviorally disabled individuals. Facilities that provide for five or less are addressed as ADULT FOSTER HOMES or FOSTER FAMILY HOMES.
- (4) STANDARDS: Land divisions and development in the RC zone shall conform to the following standards, unless more restrictive supplemental regulations apply:
  - (a) The minimum lot dimensions, yard setbacks, and building height restrictions for structures containing only residential use shall be the same as in the RR zone.
  - (b) Minimum yards for any structure on a lot or parcel adjacent to a residential zone shall be 5 feet on the side adjacent to the residential zone, and 10 feet in the front yard. No rear yard is required.
  - (c) For commercial or combined commercial-residential structures, structures shall be either constructed on the property line or setback at least 3 feet or as required in Section 3.020 (4) (b).
  - (d) All structures shall meet the requirements for clear-vision areas specified in Section 4.010.
  - (e) All uses shall meet off-street parking requirements as provided in Section 4.030.
  - (f) Outdoor storage abutting or facing a lot in a residential zone shall be screened with a sight-obscuring fence.
  - (g) The maximum building height for commercial structures shall be 35 feet except on ocean or bay frontage lots, where it shall be 24 feet, higher structures may be permitted as a conditional use in accordance with Article VI.
  - (h) Scale of Commercial uses:
    - a. Outside an unincorporated community, the use shall not exceed a total of 3,000 square feet of floor area per use within a building(s)

b. Outside an unincorporated community a lawfully established use that existed prior to the adoption of this Section (December 4. 2002) may be expanded to occupy a maximum of 3,000 square feet of floor area, or an additional 25% of the floor area currently occupied, whichever is greater.

# APPENDIX C Well Use Survey Data Base Results

# Well Log Query Results

Township: 1 S, Range: 9 W, Sections: 18, Type of Log: W

| Well<br>Log | T-R-S/<br>QQ-Q          | Taxlot | Street of Well             | Owner   |   | Special<br>Standards | Well Type | First Water | Completed | Static<br>Water Level | Yield | Completed<br>Date | Received<br>Date | Bonded<br>Constructor                               | Startcard | Well Id # | Nex  | Abandon<br>Deepen | Alteration | Conversion | Irrigation | Livestock | Industrial | Thermal | Dewatering<br>Piezometer |
|-------------|-------------------------|--------|----------------------------|---|---|----------------------|-----------|-------------|-----------|-----------------------|-------|-------------------|------------------|---|-----------|-----------|------|-------------------|------------|------------|------------|-----------|------------|---------|--------------------------|
| TILL 476    | 1.00S-9.00W-18          |        |                            | WILLIAMS, ELTON<br>PO BOX 56<br>BEAVER OR 97108               |   |                      | w         | 19.00       |           |                       | 3.0   | 07/24/1975        | 07/30/1975       | TURNER, RALPH<br>RALPH TURNER DRILLING CO.          |           |           | 1    |                   |            | 1          |            |           |            |         |                          |
| TILL 477    | 1.00S-9.00W-18<br>SW-SW |        |                            | GIENGER, LENHART A<br>4160 BOSQUIST RD<br>TILLAMOOK OR 97141  |   | 1                    | w         | 85.00       | 100.00    | 25.0                  | 30.0  | 08/31/1982        | 09/09/1982       | TRUSSELL, IRA                                       |           |           | 1    |                   |            | 1          |            |           |            |         |                          |
| TILL 478    | 1.00S-9.00W-18<br>NW-SW |        |                            |   | TILLAMOOK CHEESE FACTORY<br>BOX 313<br>TILLAMOOK OR 97141 |                      | w         | 45.00       | 85.00     | 10.0                  | 20.0  | 07/19/1974        | 07/22/1974       | TRUSSELL, IRA                                       |           |           | 1    |                   |            | 1          |            |           |            |         |                          |
| TILL 479    | 1.00S-9.00W-18<br>NW-SW |        |                            |   | GREEN ACRES MOTEL; FRED GITEN AUTO CAMP<br>OR 97141       |                      | w         |             | 187.00    | 10.0                  |       | 02/01/1962        | 02/01/1962       |   |           |           | 1    |                   |            |            |            |           |            |         |                          |
| TILL 1034   | 1.00S-9.00W-18<br>SE-SE | 400    |                            | TURNER, STAN<br>3680 LATIMER RD N<br>TILLAMOOK OR 97141       |   | 3                    | W         | 0.00        | 0.00      | 0.0                   |       |                   | 06/16/1992       | EVEY, LARRY C                                       |           |           |      | 1                 |            |            |            |           |            |         |                          |
| TILL_1220   | 1.00S-9.00W-18<br>NW-NW | 800    | JUNO HEIGHTS,<br>TILLAMOOK | HOFFMILLER, KAY<br>17166 SW BEEF BEND RD<br>SHERWOOD OR 97140 |   |                      | W         | 96.00       | 188.00    | 65.0                  | 10.0  | 04/30/1994        | 05/18/1994       | EVEY, LARRY C                                       | 60085     |           | 1    |                   |            | 1          |            |           |            |         |                          |
| TILL 1290   | 1.00S-9.00W-18<br>NW-NW | 1100   |                            | WEISSENFLUH, MICHAEL<br>4825 ELLEN AVE<br>TILLAMOOK OR 97141  |   | #<br>                | W         | 13.00       | 150.00    | 38.0                  | 15.0  | 02/07/1995        | 02/21/1995       | EVEY, LARRY C                                       | 64907     |           | 1    |                   |            | <b>—</b>   | 1          |           |            |         |                          |
| TILL 50600  | 1.00S-9.00W-18<br>NW-SW | 900    | 2325 LATIMER RD            | GIENGER, LENHARD<br>2325 LATIMER RD<br>TILLAMOOK OR 97141     |   | 1                    | W         |             |           | 12.0                  | 10.0  | 06/30/1999        | 07/13/1999       | EVEY, LARRY C<br>LARRY EVEY WELL DRILLING           | 118655    | 3029      | 9    |                   | <b>√</b>   |            |            |           |            |         |                          |
| TILL 50749  | 1.00S-9.00W-18<br>NW-NW | 900    | ELLEN AVE                  | MOON, KAREN<br>2509 7TH ST APT B<br>TILLAMOOK OR 97141        |   | =                    | w         | 115.00      | 145.00    | 35.0                  | 20.0  | 07/26/2000        | 07/28/2000       | EVEY, LARRY C<br>LARRY EVEY WELL DRILLING           | 126648    | 8 3635    | 10 4 |                   |            | 1          | /          |           |            |         |                          |
| TILL_51163  | 1.00S-9.00W-18<br>NW-NW | 200    | ELLEN AVE                  | RAWE, OGDER<br>PO BOX 1252<br>TILLAMOOK OR 97141              |   |                      | w         | 70.00       | 100.00    | 57.0                  | 24.0  | 06/24/2003        | 06/27/2003       | JANNSEN, ROY N<br>A M JANNSEN DRILLING              | 15621     | 5 6414    | .3 √ |                   |            |            | 1          |           |            |         |                          |
| TILL_51193  | 1.00S-9.00W-18<br>NW-NW | 1000   | 4805 ELLEN AVE             | STANFILL, RICHARD<br>4590 HWY 101 S<br>TILLAMOOK OR 97141     |   |                      | w         | 92.00       | 105.00    | 31.0                  | 30.0  | 08/22/2003        | 08/26/2003       | EVEY, LARRY C<br>LARRY EVEY WELL DRILLING           | 159796    | 6 6004    | 17 √ |                   |            |            | /          |           |            |         |                          |
| TILL 51329  | 1.00S-9.00W-18<br>SW-SW | 900    | 4000 BOQUIST RD            |   | GIENGER FARMS<br>4160 BOQUIST RD<br>TILLAMOOK OR 97141    |                      | w         | 87.00       | 100.00    | 19.0                  | 50.0  | 07/28/2004        | 08/02/2004       | BEIER, DALLAS L BEIER & WALDROOP WELL SERVICES INC. | 16303     | 4 7140    | )7   |                   | ~          |            | 1          |           |            |         |                          |

Download Data Return to Well Log Query The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON

JUL 3 0 1975
State Well No. 15/94-18

(Please type or pratater RESOURCES DEPT

|                     |                | WEGGGIGE. |              |    |
|---------------------|----------------|-----------|--------------|----|
| (Do not write above | e this line)SA | LEM, OREG | State Permit | No |

| (1) OWNER:  | (10) LOCATION OF WELL:   |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|
| Name Elton Williams   | County Tillamook Driller's well number   |  |  |  |  |  |  |
| Address P.O. Box 56 Beaver, Oregon 97108                    | 34 14 Section 18 T. 1-S R. 9-W W.M.  |  |  |  |  |  |  |
|   | Bearing and distance from section or subdivision corner  |  |  |  |  |  |  |
| (2) TYPE OF WORK (check):                                   | Bearing and abstance Bonn section of subdivision corner  |  |  |  |  |  |  |
| New Well    Deepening □ Reconditioning □ Abandon □          |  |  |  |  |  |  |  |
| If abandonment, describe material and procedure in Item 12. | (11) WAMED I DYDI . C  |  |  |  |  |  |  |
| (3) TYPE OF WELL: (4) PROPOSED USE (check):                 | (11) WATER LEVEL: Completed well.  |  |  |  |  |  |  |
|   | Depth at which water was first found 19 trace ft.  |  |  |  |  |  |  |
| Cable   | Static level 40 ft. below land surface. Date 7-24-75   |  |  |  |  |  |  |
| Dug   Bored   Irrigation   Test Well   Other                | Artesian pressure lbs. per square inch. Date   |  |  |  |  |  |  |
| CASING INSTALLED: Threaded D Welded N                       |  |  |  |  |  |  |  |
| CASING INSTALLED: Threaded Welded W                         | (12) WELL LOG: Diameter of well below casing 6   |  |  |  |  |  |  |
| "Diam from tt. to tt. Gage                                  | Depth drilled 110 ft. Depth of completed well 110 ft.  |  |  |  |  |  |  |
| "Diam from ft. to ft. Gage                                  | Formation: Describe color, texture, grain size and structure of materials;   |  |  |  |  |  |  |
| Diam, nom it. Gage  | and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in  |  |  |  |  |  |  |
| PERFORATIONS: Perforated?  Yes No.                          | position of Static Water Level and indicate principal water-bearing strata.  |  |  |  |  |  |  |
| Type of perforator used                                     | MATERIAL From To SWL   |  |  |  |  |  |  |
| Size of perforations in. by in.                             |  |  |  |  |  |  |  |
|   | Top soil 0 2   |  |  |  |  |  |  |
| perforations fromft. toft.                                  | Brown clay 2 14  |  |  |  |  |  |  |
| perforations from   | Boulders and sand 14 19  |  |  |  |  |  |  |
| periorations from   | Blue rock   19   75  |  |  |  |  |  |  |
| (7) SCREENS: Well screen installed?   Yes  No               |  |  |  |  |  |  |  |
| Manufacturer's Name   | Blue rock 85 110   |  |  |  |  |  |  |
| Type Model No.  | to the second se |  |  |  |  |  |  |
| Diam ft. to ft.   |  |  |  |  |  |  |  |
| Diam Slot size Set from ft. to ft.                          |  |  |  |  |  |  |  |
| (8) WELL TESTS: Drawdown is amount water level is           |  |  |  |  |  |  |  |
| lowered below static level                                  |  |  |  |  |  |  |  |
| Was a pump test made? ☐ Yes ☐ No If yes, by whom?           |  |  |  |  |  |  |  |
| Yield: gal./min. with ft. drawdown after hrs.               |  |  |  |  |  |  |  |
| " "   |  |  |  |  |  |  |  |
| 817 " " "   |  |  |  |  |  |  |  |
| Railer test 3 gal./min. with 50 ft. drawdown after 1 hrs.   |  |  |  |  |  |  |  |
| Artesian flow g.p.m.  |  |  |  |  |  |  |  |
|   | 7 21 75  |  |  |  |  |  |  |
| Tomperature of water Depth artesian flow encountered ft.    | Work started 7-24-75 19 Completed 7-24-75 19   |  |  |  |  |  |  |
| (9) CONSTRUCTION:   | Date well drilling machine moved off of well 7-24-75   |  |  |  |  |  |  |
| Well seal—Material usedCement                               | Drilling Machine Operator's Certification:   |  |  |  |  |  |  |
| Well sealed from land surface to 23 ft.                     | This well was constructed under my direct supervision.   |  |  |  |  |  |  |
| Diameter of well bore to bottom of seal 9 in.               | Materials used and information reported above are true to my best knowledge and belief.  |  |  |  |  |  |  |
| Diameter of well bore below seal6in.                        |  |  |  |  |  |  |  |
| Number of sacks of cement used in well sealsacks            | [Signed] Date 7-24-75 19   |  |  |  |  |  |  |
| Number of sacks of bentonite used in well sealsacks         | Drilling Machine Operator's License No254  |  |  |  |  |  |  |
| Brand name of bentonite                                     | 27 2   |  |  |  |  |  |  |
| Number of pounds of bentonite per 100 gallons               | Water Well Contractor's Certification:   |  |  |  |  |  |  |
| of waterlbs./100 gals.                                      | This well was drilled under my jurisdiction and this report is   |  |  |  |  |  |  |
| Was a drive shoe used? Yes No Plugs Size: location ft.      | true to the best of my knowledge and belief.  Name Ralph Turner Drilling Co.   |  |  |  |  |  |  |
| Old any strata contain unusable water? 🔲 Yes 🞽 No           | (Person, firm or corporation) (Type or print)  |  |  |  |  |  |  |
| Type of water? depth of strata                              | Address Rta 1 Box 141 Hillsboro, Oregon  |  |  |  |  |  |  |
| Method of sealing strata off                                |  |  |  |  |  |  |  |
|   | [Signed]   |  |  |  |  |  |  |
| Was well gravel packed? ☐ Yes ¥ No Size of gravel:          | (Water Well Contractor)  |  |  |  |  |  |  |
| ravel placed from ft. to ft.                                | Contractor's License No. 247 Date 7-24-75 , 19   |  |  |  |  |  |  |
| (USE ADDITIONAL SE  | IEETS IF NECESSARY) SDUARGE 110  |  |  |  |  |  |  |

# WATER WELL REPORT STATE OF OREGON

TILL 477

# RECEIVED

SEP 9 1982

State Well No. /5/9W-18CC

WATER RESOURCES DEPPjate Permit No. SALEM, OREGON

| (1) OWNER:   | (10) LOCATION OF WELL:  |
|--|---|
| Name Lendows H X) dendels  | A - ACCEPTANCE OF THE PARTY OF |
| Address HILO Brazilist 810   | Dimer's wen number  |
| City Villimack State Ozo   | 10 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1   |
| (2) TYPE OF WORK (check):  | Address at well location: While on He 101 af nations Rd   |
| New Well   |   |
| If abandonment, describe material and procedure in Item 12.  | (11) WATER LEVEL: Completed well.   |
| (3) TYPE OF WELL: (4) PROPOSED USE (check):  | Depth at which water was first found 85 ft.   |
| (0.000)  | Static level 25 ft. below land surface. Date 8-31   |
| Rotary Air Driven Domestic Industrial Municipal Domestic Irrigation Test Well Other Description Bored Driven Drive | Artesian pressure lbs. per square inch. Date  |
| A ABAIJECTOR B   | (12) WELL LOG: Diameter of well below casing  |
| (5) CASING INSTALLED: Steel Plastic  | Depth drilled ft. Depth of completed well 100 ft.   |
| Threaded Welded Welded Diam from + 2 ft to 98 ft Gauge 250   | Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry  |
| "7"  | for each change of formation. Report each change in position of Static Water Level  |
|  | and indicate principal water-bearing strata.  |
| LINER INSTALLED:   | MATERIAL From To SWL  |
|  | Soil 02   |
| (6) PERFORATIONS: Perforated? □ Yes No   | Brown Clay 2 15   |
| Type of perforator used  | Olive Clay 1 13 85  |
| Size of perforations in. by in.  | Blue Sand (Kinter) 85 100 20  |
| perforations from  |   |
| perforations fromft. toft  |   |
| perforations from  |   |
|  |   |
| (7) SCREENS: Well screen installed? Tes XNo Manufacturer's Name  |   |
| Type   |   |
| Diam. Slot Size Set from ft. to ft.  |   |
| Diam. Slot Size Set from ft. to ft.  |   |
| (8) WELL TESTS:  Drawdown is amount water level is lowered below static level  |   |
| as a pump test made?   Yes No If yes, by whom?   |   |
| old.   |   |
| gal/min. with ft. drawdown after hrs.  |   |
| Air test gal./min. with drill stem at ft. hrs.   |   |
| Pailantest 30 No. 11 No. 20  |   |
| paner test gal/min. with Cit. drawdown after hrs.  | 7"  |
| imperature of water 54 Depth artesian flow encountered ft.   | 6 70  |
|  | Work started 8-30 19 82 Completed 5'-3/ 19 82   |
| (9) CONSTRUCTION: Special standards: Yes No No Well seal—Material used   | Date well drilling machine moved off of well 8-31 1982  |
| Well sealed from land surface to   | Drilling Machine Operator's Certification:  |
| 7.   | This well was constructed under my direct supervision. Materials used   |
| Diameter of well bore to bottom of seal  | and information reported above are true to my best knowledge and belief.  [Signed]  |
| Number of solver for the first transfer of t | (Drilling Machine Operator)   |
| How was cement grout placed?   | Drilling Machine Operator's License No  |
|  | Water Well Contractor's Certification:  |
| The state of the s | This well was drilled under my jurisdiction and this report is true to  |
| Was pump installed? Type HP Depth ft.  | the best dry knowledge and belief.  |
| Was a drive shoe used? Yes No Plugs Size: location ft.   | Name Person, firm or corporation) (Type or mint)  |
| Did any strata contain unusable water?   Yes No  | Address Manning One (Type or print)   |
| Type of Water? depth of strata   |   |
| Method of sealing strata off   | [Signed] (Water Well Contractor)  |
| Was well gravel packed? Yes No Size of gravel:   | Contractor's License No. 4.7.2-Date. 8 - 3   19.82  |
| Gravel placed from   | 19.0.   |

| The original and first copy." of this report are to be  | LL REPORT  |                     |  |
|---|--|---------------------|--|
| filed with the  | OREGON STATE THOUSAND  | 15/9W-1             | 18cb                                   |
|   | e or print) STATE ENGINEED   | • f · . N           |  |
| within 30 days from the date of well completion.  | e or print) STATE ENGINEER Permit No bove this line SALEM. OREGON  | o                   |  |
|   | TONE GON   |                     | 141                                    |
| (1) OWNER:  | (10) LOCATION OF WELL:   |                     | _                                      |
| Name I Plansoff Cheese Vactory  | 1 1  | クス                  |  |
| Address Tallamooth Dre Box 3/3  | County Composition well nu   |                     | . v F-                                 |
| Address SARRAMOUTE VIL BOY 3/2  | NW 34 5W4 Section 18 T. 15   |                     | W.M.                                   |
| (2) TYPE OF WORK (check):   | Bearing and distance from section or subdivision   |                     |  |
|   | 300 6 4 300 S Q W/4C   | ones de             | 4/8                                    |
| New Well Deepening Reconditioning Abandon Li abandonment, describe material and procedure in Item 12.   | 135  |                     |  |
|   | (11) WATER LEVEL: Completed w  | ell.                |  |
| (3) TYPE OF WELL: (4) PROPOSED USE (check):   | Depth at which water was first found   | 1                   | 15 st.                                 |
| Rotary  | Static level / / ft. below land s  | urface. Date 7      | -19-74                                 |
| Dug ☐ Bored ☐ Irrigation ☐ Test Well ☐ Other ☐  | Artesian pressure Ibs. per square  |                     |  |
| CACING INGHAYAND  | ibs. per square  | e men. Date         |  |
| CASING INSTALLED: Threaded Welded   | (12) WELL LOG: Diameter of well, b   | elow opelne         | 6                                      |
| O" Diam. from   | Depth drilled & ft. Depth of comple  | . د سر              | ) ft.                                  |
| " Diam. fromft. toft. Gage  | Formation: Describe color, texture, grain size a   |                     |  |
| " Diam. fromft. toft. Gage  | and show thickness and nature of each stratum  | n and aquifer pen   | etrated.                               |
| PERFORATIONS: Perforated Ves II No.   | with at least one entry for each change of format<br>position of Static Water Level and indicate princ   | ion. Report each cl | hange in                               |
| Type of perforator used   |  |                     | strata.                                |
|   | MATERIAL   | From To             | 8WL                                    |
| Size of perforations 3 in. by 4 in.   | Soil   | 0 3                 |  |
| 72 perforations from 40 ft. to 80 ft.   | Brown Clay   | 3 45                | ————                                   |
| perforations fromft. toft.  | Water Reasing I are Stand  | 45 60               | 10                                     |
| perforations fromft. toft.  | Clay of Drawel   | 60 65               | 10                                     |
| (7) SCREENS: Well screen installed?   Yes   Yes   | Waldy hearing Jane   | 62 80               | 10                                     |
| Manufacturer's Name   | - Sayolone-  | 80 83               | 10                                     |
| Type Model No   |  |                     | -                                      |
| Diam Slot size ft. to ft.   |  |                     |  |
| Diam ft. to ft.   |  |                     |  |
| (8) WELL TESTS: Drawdown is amount water level is   |  |                     |  |
| lowered below static level  |  |                     |  |
| Was a pump test made? Tyes No It yes, by whom?  |  |                     |  |
| Yield: gal./min. with ft. drawdown after hrs.   |  |                     |  |
| , , , , , , , , , , , , , , , , , , ,   |  |                     |  |
| " " "   |  |                     |  |
| Baller test 20 gal./min. with 55t. drawdown after 2 hrs.  | New York Control of the Control of t |                     |  |
| Artesian flow g.p.m.  |  |                     |  |
| perature of water 5 4Depth artesian flow encounteredft.   | 7 10   |                     |  |
| the special design of the special design flow encountered   | Work started /- /8 1974 Complete   | a 7 - 19            | 19 74                                  |
| (9) CONSTRUCTION:   | Date well drilling machine moved off of well   | 7-19                | 1974                                   |
| Well seal-Material used Coment  | Drilling Machine Operator's Certification:   |                     | · (                                    |
| Well sealed from land surface to  | This well was constructed under my   | direct superv       | ision.                                 |
| Diameter of well bore to bottom of seal   | Materials used and information reported  | above are true      | to my                                  |
| Diameter of well bore below seal  | best knowledge and belief.   | 7 10                | <b>-</b>                               |
| Jumber of goals of compat and to any  | [Signed] (Drilling Machine Operator)   | Date 7-19,          | 19.1.4                                 |
|   | Drilling Machine Operator's License No.  | 533                 |  |
| Number of sacks of bentonite used in well sealsacks   |  |                     |  |
| Tumber of pounds of bentonite per 100 gallons   | Water Well Contractor's Certification:   |                     | <u> </u>                               |
|   | This wall was drilled under you include  | tion and this re    | nort le                                |
| f water   | This went was drifted under my jurishic  | of                  | port. In                               |
|   | This well was drilled under my jurisdic<br>true to the best of my knowledge and belie  | CA.                 |  |
| Vas a drive shoe used?   Yes   No Plugs Size location ft.   | true to the best of my knowledge and believe the |                     |  |
| Vas a drive shoe used?  Yes No Plugs Size location ft. Did any strata contain unusable water?  Yes No   | Name (Person, firm or corporation)   |                     | ········· ;                            |
| Was a drive shoe used?  Yes No Plugs Size location ft.  Did any strata contain unusable water?  Yes No  | true to the best of my knowledge and believe   | (Type on print      | ······································ |
| Was a drive shoe used?  Yes No Plugs Size location ft.  Did any strata contain unusable water? Yes No  Type of water? depth of strata  Method of sealing strata off | Name Of the best of my knowledge and believe to the best of the best o |                     | )<br>)<br>)                            |
| Was a drive shoe used?  Yes No Plugs Size location ft.  Did any strata contain unusable water? Yes No  Type of water? depth of strata  Method of sealing strata off | rue to the best of my knowledge and believe to | (Type on print      | ,                                      |
| Was a drive shoe used?  Yes No Plugs Size location ft.  Did any strata contain unusable water? Yes No  Type of water? depth of strata  Method of sealing strata off | Name Of A Name or corporation)  Address 130 Mannu  [Signed] A Na Omessel   | (Type on print      | 10 74                                  |

OBSERVATION WELL WELL SCHEDULE TILE

|         |             |   |           |                                       |                     |  |                 | -                         |  |
|---------|-------------|---|-----------|---------------------------------------|---------------------|--|-----------------|---------------------------|--|
| and Owr |             | ta Auto C                               | Address   | 2 miles                               | orth of             | Come ([E                               |                 |                           |  |
|         | n: State    |   | County_   | 7111                                  | ennole              |  | ******          | ± Sec                     | 3,   |
| ource_  |             | *************                           |           | dential                               |                     |  |                 | <del>1 1</del>            |  |
| _       | g Commenced | *************************************** |           | eted                                  |                     | ************************************** |                 | 1_1                       |  |
| -       | ,           |   | Addres    | 3.5                                   |                     |  | _               | 7 7                       | 1  |
|         | 7119        |   |           |                                       |                     | <del></del>                            |                 | 1                         | <del></del>  |
|         | onf         |   |           | Meas.                                 | -                   |  |                 | <del>-</del> <del>-</del> |  |
| ype of  |             | M                                       | lethod of | Drilling                              |                     | -                                      | _               | 1                         | 1  |
| epth    | Diam        | eter: top                               |           | _bottom_                              |                     |  | T               | N <sub>s</sub> ;          | R E  |
| hief Aq | quifer      |   | 'rom_     |                                       |                     | - :                                    |                 | 8                         | N  |
| Ot      | hers        |   |           |                                       |                     |  |                 |                           | •  |
| asing:  | Type        | Dept                                    | h         | Di a ma                               | ter                 | 0                                      | <br>creen       |                           |  |
| ater Le |             | above                                   |           |                                       | Market Wallet       |  | -               |                           |  |
|         | 10,         | below                                   |           | , , , , , , , , , , , , , , , , , , , |                     | ft.                                    | above<br>below- |                           |  |
| mp      |             |   |           | Power                                 |                     |  |                 |                           |  |
| ield    | Drawd       | own                                     | T4        | . pumping                             |                     | G.P.1                                  | M. Ti           | me                        |  |
| se      | Quali       | ty                                      |           |                                       |                     | Samples                                |                 |                           |  |
|         | From To     | Thick-                                  | Record    | Cor                                   | relation            | by:                                    |                 |                           |  |
| Log     | From To     |   |           |                                       | relation            | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation            | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation            | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation            | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation a          | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation            | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation a          | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation ermation   | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation ermation   | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation ermation   | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  | Charac    | Cor                                   | relation ermation   | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  |           | Cor                                   | relation armation a | by:                                    | rks             |                           |  |
|         | From To     | Thick-                                  | Charac    | Cor                                   | relation armation a | by:                                    | rks             |                           | Casing Ca |
|         | From To     | Thick-ness ft.                          | Charac    | ter of fo                             | relation ermation   | by:                                    | rks             |                           |  |
|         | From To     | Thick-ness ft.                          | Charac    | ter of fo                             | relation armation a | by:                                    | rks             |                           |  |
|         | From To     | Thick-ness ft.                          | Charac    | ter of fo                             | relation armation a | by:                                    | rks             |                           |  |
|         | From To     | Thick-ness ft.                          | Charac    | ter of fo                             | relation armation a | by:                                    | rks             |                           |  |
|         | From To     | Thick-ness ft.                          | Charac    | ter of fo                             | relation armation a | by:                                    | rks             |                           |  |

| STATE EN<br>Salem, ( |   |                      |          | State Well No  | 1/9W-18M(1)   |
|----------------------|---|----------------------|----------|--|---------------|
|                      |   |                      |          |  |               |
|                      |   | Water T              | evel Red |  | 0             |
|                      |   |                      |          |  |               |
|                      |   | PERES MOTEL          |          |  |               |
| escription           | of measuring                                | point: Ter of casing | AT 1.5.D |  |               |
|                      |   |                      |          |  |               |
|                      |   |                      |          |  |               |
| Date                 | Water Level<br>Feet (above)<br>Land Surface | Remarks              | Date     | Water Level<br>Feet (above)<br>(below)<br>Land Surface | Remarks       |
| -1-62                | 9.95  | RO                   |          |  |               |
|                      |   | _                    |          |  |               |
|                      | w .   |                      |          |  |               |
|                      |   |                      |          |  |               |
|                      |   |                      |          |  |               |
|                      |   |                      |          |  |               |
|                      |   |                      |          | 20%  |               |
|                      |   |                      |          |  |               |
|                      |   |                      |          |  |               |
|                      | 9   |                      |          |  |               |
|                      |   |                      |          | -  |               |
|                      |   |                      |          |  |               |
|                      | . 8   |                      |          |  |               |
|                      |   |                      |          |  | Company of 19 |
|                      |   |                      |          | fis .  |               |
|                      |   |                      |          | 42.  |               |
|                      |   |                      |          |  |               |
|                      |   |                      |          |  |               |
|                      |   | <u>.</u>             | 11 1     |  |               |

State Printing 89314

# STATE OF OREGON ATTER WELL REPORT (2.4) (11) (1.4) (1

| /5/ | 9w/  | 18d | d   |
|-----|------|-----|-----|
|     | 3450 |     | : • |

| WATER WELL REPORT 103 9   | ESOUPCES DEDT (START CARD) # 43450   |
|---|--|
| Name Stan Turner Well Number SAL  | EN (6) LOCATION OF WELL by legal description:  County I illa mook Latitude Longitude   |
| Address 3680 Latiner RA. N.   | Township / S N or S. Range 940 E or W. WM.   |
| City Tillamook State Oregon Zip 97/4/   | Section  |
| (2) TYPE OF WORK:   | Tax Lot 400 Lot Block Subdivision  |
| □ New Well □ Deepen □ Recondition ☒ Abandon   |  |
| (3) DRILL METHOD:   | Street Address of Well (or nearest address) SAME   |
| Rotary Air Rotary Mud Cable   | (10) STATIC WATER LEVEL:   |
| Other   | ft. below land_surface. Date   |
| (4) PROPOSED USE:   | Artesian pressure Ib. per square inch. Date  |
| Domestic Community Industrial Irrigation  | (11) WATER BEARING ZONES:  |
| ☐ Thermal ☐ Injection ☐ Other   |  |
| (5) BORE HOLE CONSTRUCTION:   | Depth at which water was first found   |
| Special Construction approval Yes No Depth of Completed Wellf   |  |
| Explosives used Yes No Type Amount  | From To Estimated Flow Rate SWL  |
|   |  |
| HOLE SEAL Amount Diameter From To   Material From To   sacks or pounds  |  |
| Julia 1 Julia |  |
|   |  |
|   | (3) YYDY Y Y O C   |
|   | (12) WELL LOG:   |
| How was seal placed: Method A B C D E   | Ground elevation   |
| Other   | Material From To SWL   |
| Backfill placed from ft. to ft. Material  | 100 100 100  |
| Gravel placed from ft. ft. Size of gravel   | Removed Casing from  |
| (6) CASING/LINER:   | he/x. 6" x 38' with 144  |
| Diameter From To Gauge Steel Plastic Welded Threaded  | The state of the s |
| Casing:   | Filled hale with 20  |
|   | bags of Concrete ussing  |
|   | grout pipe filling frum  |
|   |  |
| Liner:  | The Battom to the top  |
|   |  |
| Final location of shoe(s)   |  |
| (7) PERFORATIONS/SCREENS:   | =  |
| Perforations Method   |  |
| Screens Type Material   |  |
| _   |  |
| Slot Tele/pipe From To size Number Diameter size Casing Liner   |  |
|   |  |
|   |  |
|   |  |
|   |  |
|   |  |
|   |  |
| (8) WELL TESTS: Minimum testing time is 1 hour  |  |
| _ Flowing   | Date started 6-9-92 Completed 6-9-92   |
| Pump Bailer Air Artesian  | (unbonded) Water Well Constructor Certification:   |
| Yield gal/min Drawdown Drill stem at Time   | I certify that the work I performed on the construction, alteration, or abandon  |
| Dim stem at Thire   | ment of this well is in compliance with Oregon well construction standards. Material   |
| 1 hr.   | used and information reported above are true to my best knowledge and belief.  |
|   | - WWC Number   |
|   | Signed Date  |
|   |  |
| Temperature of Water Depth Artesian Flow Found  | (bonded) Water Well Constructor Certification:  I accept responsibility for the construction, alteration, or abandonment work per  |
| Was a water analysis done? Yes By whom  | formed on this well during the construction dates reported above. All work performed   |
| Did any strata contain water not suitable for intended use?   Too little  | during this time is in compliance with Oregon well construction standards. This report   |
| □ Salty □ Muddy □ Odor □ Colored □ Other  | is true to the best of my knowledge and belief.  |
| Depth of strata:  | Signed Frankli C Ercer Dete (29 93)  |

# STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

MAY 1 8 1994

RECEIVED

(START CARD) #\_

| Instructions for completing this report are on the last page of this form A  |  |                                  | . :            |             |              |             |
|--|--|----------------------------------|----------------|-------------|--------------|-------------|
| (1) OWNER: Well Number   | SALF MOCATEGORE  | WELL by legal                    | descriptio     | n:          |              |             |
| Name Kay Hoffmiller  | SALE MOREGO OF WELL by legal description:  County //// mook Latitude Longitude |                                  |                |             |              |             |
| Address /7/66 5.W. Beef Bend Rd.   | Township / 5   |                                  |                | Z Long      | E or W       | . 1171      |
|  |  |                                  | 1/4 <b>/</b>   | 13          | E or w       | . WM.       |
| City Sherwood State Oregon Zip 97140   | Section 18   | NW                               |                |             | 1/4          |             |
| 2) TYPE OF WORK  | Tax Lot 800  | ot Ble                           | ock            | Sub         | division     |             |
| New Well Deepening Alteration (repair/recondition) Abandonment   | Street Address of We   | ll (or nearest addre             | ess) <u>Ju</u> | no 6        | Leight       | 45,         |
| (3) DRILL METHOD:  | lillamook  | Oregan                           | 97             | 41          | <b>U</b>     | · ·         |
| Rotary Air Rotary Mud Cable Auger  | (10) STATIC WATE   |                                  |                |             | 2            |             |
| Other  | 65 ft. be  | low land surface.                |                | D           | ate 4/-3     | 20-94       |
| (4) PROPOSED USE:  | Artesian pressure  |                                  | r square incl  | a. D        | ate          | 1 1 22      |
| Domestic Community Industrial Irrigation   | (11) WATER BEAR  |                                  |                |             |              |             |
| Thermal Injection Livestock Other  | ` `  | -                                |                |             |              |             |
| (5) BORE HOLE CONSTRUCTION:  | Depth at which water wa  | s first found                    | 96             |             |              |             |
| Special Construction approval Yes No Depth of Completed Well /88 ft.   |  |                                  |                |             |              | <del></del> |
| Explosives used Yes No Type Amount   | From   | To                               |                |             | Flow Rate    | CHA         |
|  | From   | То                               |                | sumated     | riow Rate    | SWL         |
|  |  | -                                |                |             |              | <u> </u>    |
| Diameter From To Material From To Sacksor pounds   |  |                                  |                | <del></del> |              |             |
| 10 0 34 Bentonite 0 34 26  |  | 19.1                             |                |             |              |             |
| 6 34 188   |  | ļ                                |                |             |              | -           |
|  |  |                                  |                |             |              | Υ.          |
|  | (12) WELL LOG:   |                                  |                |             |              |             |
| How was seal placed: Method A B C D E  |  | d Elevation                      |                |             |              | •           |
| Other Placed in dry + prodded.   |  |                                  |                |             |              |             |
| Backfill placed from ft. to ft. Material   | Mater  | ial                              |                | From        | То           | SWL         |
| Gravel placed from ft. to ft. Size of gravel   | Top 3011   |                                  |                | 0           | /            |             |
| (6) CASING/LINER:  | Brown Cla  |                                  |                | 1           | 29           |             |
| Diameter From To Gauge Steel Plastic Welded Threaded   | Example Clause   | 5 - 0                            |                | 29          | 188          | 65          |
| 1 11/ 1704 200 100   | 13737  | •                                |                |             | (0)          | 0           |
| Casing: 6 7/3 /23 23 X   |  | •                                |                |             |              |             |
|  | I.   |                                  |                |             | -            |             |
|  |  |                                  |                |             |              |             |
| 1/ 12/100/100  |  |                                  |                |             |              |             |
| Liner: 10 188 160   X  | 1  |                                  |                |             |              |             |
|  | .  |                                  |                |             |              |             |
| Final location of shoe(s) 78/2   | ,  |                                  |                |             |              |             |
| 7) PERFORATIONS/SCREENS:   |  |                                  |                |             |              |             |
| Perforations Method Drilled  |  |                                  |                |             |              |             |
| Stot Telepipe  | -  |                                  |                |             |              |             |
| From To size Number Diameter size Casing Liner   |  |                                  |                |             |              |             |
| From To size Number Diameter size Casing Lines 128   185 - 240 9/16 4  |  |                                  |                |             | 18 °         |             |
|  |  | ÷ 77                             | :              |             |              | 1.0         |
|  |  |                                  | 17.            |             |              | •           |
|  |  |                                  |                |             |              |             |
|  |  | ". " <del>.</del> <del>.</del> . |                |             |              |             |
|  | •  |                                  | -              |             |              |             |
| 8) WELL TESTS: Minimum testing time is 1 hour  | Date started 4-24  | 7-94                             | Completed      | U.          | -30-         | 94          |
| -, · · · · · · · · · · · · · · · · · · ·   | (unbonded) Water Wel   |                                  |                |             | <i>a</i>     |             |
| Pump Bailer X Air Artesian   |  |                                  |                |             |              |             |
|  | I certify that the work of this well is in compliant.                          |                                  |                |             |              |             |
| Yield gal/min Drawdown Drill stem at Time  | Materials used and info  | mation reported a                | bove are true  | to the be   | est of my ki | owledge     |
| 10 10.5 170 1hr.   | and belief.  | -                                | W              |             |              |             |
|  |  |                                  | W              | WC Num      | -            |             |
|  | Signed   |                                  |                | I           | Date         |             |
| Temperature of water 54 Depth Artesian Flow Found  | (bonded) Water Well (  | Constructor Certi                | fication:      |             |              |             |
| Was a water analysis done? Yes By whom   | I accept responsibilit   |                                  |                |             |              |             |
| Did any strata contain water not suitable for intended use?   Too little   | performed on this well of<br>performed during this ti                          |                                  |                |             |              |             |
| Salty Muddy Odor Colored Other   | construction standards.  | This report is true              | to the best of | of my kno   | wledge and   | belief.     |
| Depth of strata:   |  | •                                |                | -           | nber /2      |             |
| The same of the sa | Signed La 1/1/   | 106                              | -1"            |             | Date 4       |             |
| DRIGINAL & EIRST CODY WATER RESOLIDATES DEBARTMENT S   | I siking Harris  |                                  | 4              |             | Date 7       | 20-17       |
| PRODUCT OF BIDSTIFFIDD WATED DECOMEDINED INDICATE OF   | COUNTY CONTROL   | THE COMPLETE                     | HIND CODY      | AT OF TOT   | CTA CO       |             |

# STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

TIU 50600

WELL I.D. # L. 30299
START CARD # //8655

| Instructions for completing this report are on the last page of this form.   | START CARD # 77 00 25   |  |
|--|---|--|
| (1) OWNER: Well Number /   | (9) LOCATION OF WELL by legal description:  |  |
| Name Lenhard Gienger   | County Tilamok Latitude Longitude   |  |
| Address 2325 Latimer Rd.   | Township / S N or S Range 9 W E or W. WM.   |  |
| City Tillamook State Oregon Zip 97/4   | Section /8 NW 1/4 5W 1/4  |  |
| (2) TYPE OF WORK   | Tax Lot 900 Lot Block Subdivision   |  |
| New Well Deepening Alteration (repair/recondition) Abandonment  (3) DRILL METHOD:  | Street Address of Well (or nearest address) SAME  |  |
| ☐ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger  | (10) STATIC WATTER LEVEL:   |  |
| Other  |   |  |
| (4) PROPOSED USE:  |   |  |
| Domestic Community Industrial Irrigation   | Artesian pressurelb. per square inchltlblblblblb  |  |
| Thermal Injection Livestock Other Golf Co.   | ,   |  |
| (5) BORE HOLE CONSTRUCTION:  | Depth at which water was first found  |  |
| Special Construction approval Yes No Depth of Completed Well ft.   |   |  |
| Explosives used Yes No Type Amount   | From To Estimated Flow Rate SWL   |  |
| HOLE SEAL  |   |  |
| Diameter From To Material From To Sacks or pounds  |   |  |
|  |   |  |
|  |   |  |
|  |   |  |
|  | (12) WELL LOG:  |  |
| How was seal placed: Method A B C D E  | Ground Elevation  |  |
| Other  |   |  |
| Backfill placed from ft. to ft.   Material   | Material From To SWL  |  |
| Gravel placed fromft. toft. Size of gravel  (6) CASING/LINER:  | Clean-out well only   |  |
| Diameter From To Gange Steel Plastic Welded Threaded   | Before pump installed   |  |
| 1 1 0 1001 - 1 -   | + Pilled  |  |
| Casing: 40 7-2 78 -250 X   | it filled in again  |  |
|  | Not Usable  |  |
|  | -V01  |  |
| Liner:   |   |  |
|  | RECEIVED  |  |
| Final location of shoe(s)  |   |  |
| (7) PERFORATIONS/SCREENS:  |   |  |
| Perforations Method  | JUL 1 3 1999  |  |
| Screens Type Material  |   |  |
| Slot Tele/pipe From To size Number Diameter size Casing Liner  | WATER RESOURCES DEP<br>SALEM, OREGON  |  |
|  | On-Lin, Onedon  |  |
|  |   |  |
|  |   |  |
|  |   |  |
|  |   |  |
| (8) WELL TESTS. Minimum testing the last   |   |  |
| (8) WELL TESTS: Minimum testing time is 1 hour   | Date started  |  |
| Flowing  | (unbonded) Water Well Constructor Certification:  |  |
| Pump Bailer XAir Artesian  | I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. |  |
| Yield gal/min Drawdown Drill stem at Thme  / O 78 90 1 hr.   | Materials used and information reported above are true to the best of my knowledge  |  |
| 70 78 90 1hr.  | and belief.   |  |
|  | WWC Number  |  |
| Temperature of water 55 Depth Artesian Flow Found  | Signed Date   |  |
| Temperature of water Depth Artesian Flow Found Was a water analysis done? Yes By whom  | (bonded) Water Well Constructor Certification:  |  |
| Did any strata contain water not suitable for intended use? Too little   | I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work             |  |
| Salty Muddy Odor Colored Other   | DETORMED during this time is in compliance with Oregon water supply wall  |  |
| Death of the state |   |  |
|  | Signed 1 211 C 9 WWC Number 1221  |  |
| ODICINAL & EIDET CODY WATER DESCRIPTION OF STREET  | Signed # Date 6-30-99   |  |
| ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SEC   | COND COPY-CONSTITUCTOR THIRD COPY-CUSTOMER  |  |

### STATE OF OREGON

# WATER SUPPLY WELL REPORT (as required by ORS 537.765)

WELL I.D. # L 36350 START CARD # 126648

| Instructions for completing this report are on the last page of this form             | 51/KI C/KD# 796675   |
|---|--|
| (1) LAND OWNER . Well Number  |  |
| Name Karen Moon   | County Tillemont Latitude Longitude  |
| Address 2509 71" St. Apt. B   | Township / S N or S Range 94 E or W. WM.   |
| City Tillamook State Oregon Zip 971   |  |
| (2) TYPE OF WORK  | Tax Lot 900 Lot Block Subdivision  |
| New Well Deepening Alteration (repair/recondition) Abandon                            | sment Street Address of Well (or nearest address) Filen Ave.   |
| (3) DRILL METHOD:   | Street Address of Well (of healest address)  |
| ☑ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger   | (10) STATIC WATER LEVEL:   |
| Other   | 35 ft. below land surface. Date 7-26-00  |
| (4) PROPOSED USE:   | Artesian pressurelb. per square inch Date  |
| ☑Domestic ☐ Community ☐ Industrial ☐ Irrigation                                       | (11) WATER BEARING ZONES:  |
| ☐ Thermal ☐ Injection ☐ Livestock ☐ Other   |  |
| (5) BORE HOLE CONSTRUCTION:   | Depth at which water was first found   |
| Special Construction approval Yes XNo Depth of Completed Well                         | From To Estimated Flow Rate SWL  |
| Explosives used  Yes No Type Amount Amount  | 115 145 20 35  |
| HOLE SEAL   |  |
| Diameter From To Material From To Sacksor pounds                                      |  |
| 6 31 145  |  |
|   |  |
|   | (12) WELL LOG:   |
| How was seal placed: Method $\square$ A $\square$ B $\square$ C $\square$ D $\square$ | E Ground Elevation   |
| Wother Placed in dry + prodded  | Material From To SWL   |
| Backfill placed fromft. toft. Material  | 100 to 36 (200 to 100 t |
| Gravel placed fromft. toft. Size of gravel  |  |
| (6) CASING/LINER: Diameter From To Gauge Steel Plastic Welded Three                   |  |
| Casing: 6 +12 984.250 X □ X   |  |
|   |  |
|   |  |
|   |  |
| Liner: 4/2 5 145 160 \( \)  | RECEIVED   |
|   | HEOEIVED   |
| Drive Shoe used ☐ Inside M Outside ☐ None Final location of shoe(s) 98 /2             |  |
| (7) PERFORATIONS/SCREENS:   | JUL 2. 8 2000  |
| Perforations Method Dv. 11ed  |  |
|   | WATER RESOURCES DEPT.  |
| Slot Tel pipc   | SALEM, UNEGON  |
| From To size Number Diameter size Casing 1  | Liner  |
| 85 145 - 240 /2 4/2 O   | ×  |
|   |  |
|   |  |
|   |  |
| (8) WELL TESTS: Minimum testing time is 1 hour  | Date started 7-25-00 Completed 7-26-00   |
| □ Pump □ Bailer ☑ Air □ Artesian  | (unbonded) Water Well Constructor Certification:   |
| Yield gal/min Drawdown Drill stem at Time   | I certify that the work I performed on the construction, alteration, or abandon-   |
| 20 65 100 lhr.  | ment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my  |
| 100   | knowledge and belief.  |
|   | WWC Number   |
| 55  | Signed Date  |
| Temperature of water <u>55</u> Depth Artesian Flow Found                              |  |
| Was a water analysis done? Yes By whom  | l accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work  |
| Did any strata contain water not suitable for intended use?                           | performed during this time is in compliance with Oregon water supply well  |
| ☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other  | construction standards. This report is true to the best of my knowledge and belief.  |
| Depth of strata:  | Signed Famy C Evry Date 7-26-00  |
|   |  |

### STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765) Instructions for completing this report are on the last page of this form. (1) LAND OWNER Well Number Name OGDER RAWE Address P.O. BOX 1252 City TILLAMOOK, OR 97141 State (2) TYPE OF WORK New Well Deepening Alteration (repair/recondition) Abandonment (3) DRILL METHOD: X Rotary Air Rotary Mud Cable Auger Other\_ (4) PROPOSED USE: ☐ Thermal ☐ Injection ☐ Livestock ☐ Other (5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well 100ft. Explosives used Yes XNo Type\_ Amount. HOLE SEAL Diameter From Material From To Sacks or pounds Bentonit 70 8 SKS Cement 10 SKS 6" 70 How was seal placed: Method $\Box$ A $\square$ B ₩ C $\Box$ E Other Poured slowly Backfill placed from \_ ft. to ft. Material Gravel placed from ft. to\_ \_\_ ft. Size of gravel\_ (6) CASING/LINER: Diameter From Gauge Steel To Plastic Welded Threaded Casing: 250 X X 100 160psi X X Drive Shoe used ☐ Inside ☐ Outside 🔀 None Final location of shoe(s). (7) PERFORATIONS/SCREENS: ☑ Perforations Mcthod Drilled ☐ Screens Type. Material PVC-160 Slot Tele/pipe From To Number Diameter size Casing 100 90

| (8) WELL TES      | TS: Minimum | testing time is 1 h              | our                |
|-------------------|-------------|----------------------------------|--------------------|
| ☐ Pump            | ☐ Bailer    | <b>⊠</b> Air                     | Flowing   Artesian |
| Yield gal/min     | Drawdown    | Drill stem at                    | Time               |
| 24                |             | 100                              | l hr.              |
| 18                |             | 89                               | 11                 |
| 12                |             | 70                               |                    |
| Temperature of wa |             | Depth Artesian Flow es By whom A |                    |

| WELL I.D. # L 64143 |  |
|---------------------|--|
| START CARD # 156215 |  |

| (9) LOCATION O   | F WELL by legal   | description:  |                        |             |  |
|--|---|---|------------------------|-------------|--|
| CountyTillam   | cok_Latitude  |   | Longitude              |             |  |
| Township 1S N or S Range 9W E or W. WM.  |   |   |                        |             |  |
| Section 18   | NW 1/4  | NW  | 1/4                    |             |  |
| Section         18         NW         1/4         NW         1/4           Tax Lot         200         Lot         Block         Subdivision |   |   |                        |             |  |
| Street Address of V  | Well (or nearest addres   | ···   | Subdivision _          |             |  |
|  | LEN AVE.  |   |                        |             |  |
| (10) STATIC WAT  | ER LEVEL:   |   |                        |             |  |
| fi. b  |   |   | Date _6-               | 24-03       |  |
| Artesian pressure _  | lb. per   | square inch   | Date                   |             |  |
| (11) WATER BEAD  | RING ZONES:   |   |                        |             |  |
| Depth at which water v   | was first found   | 70  |                        |             |  |
| From   | То  | Estimated   | Flow Rate              | SWL         |  |
| 70   | 100   | 24  |                        | 57          |  |
|  |   |   | P.                     |             |  |
|  |   |   |                        |             |  |
|  |   |   |                        |             |  |
|  |   |   |                        |             |  |
| (12) WELL LOG:   |   |   |                        |             |  |
| Grou   | and Elevation   |   |                        |             |  |
| Mate   | ria) lai  | From  | То                     | SWL         |  |
| Brn & gry br   |   |   |                        | SWL         |  |
| Soft brn cly   | u stiff cir   | <u>      0                              </u>              | 8                      | $\vdash$    |  |
| Gry brn silt   | scone .   | 10  | 10                     |             |  |
| Dark brn clay  | y Clay  | 29  | 31                     | <del></del> |  |
| Brn clay   | <del>-</del>  | 31  | 40                     |             |  |
| Soft red brn sandstone   |   | 40  | 49                     |             |  |
| Soft gry claystone   |   | 49  | 60                     |             |  |
| Gry sandstone  | e w/clav  |   | 1                      |             |  |
| stone.   |   | 60  | 100                    | 57'         |  |
|  |   |   |                        |             |  |
|  |   |   |                        |             |  |
|  |   |   |                        |             |  |
| DEC  | <del></del>   |   |                        |             |  |
| HEU  | EIVED   |   |                        |             |  |
| 16181  | 2 7 8882  |   |                        |             |  |
| אטג  | 2 7 2003  |   | +                      | 22          |  |
| WATER RES  | OURCES DEPT   |   | -                      |             |  |
| SALEN  | C, OREGON T   |   | <b> </b>               |             |  |
| Determined in the second   |   |   |                        | لـــــا     |  |
|  |   |   | 24-03                  |             |  |
| (unbonded) Water Well  |   |   | To the same            |             |  |
| I certify that the work<br>ment of this well is in cor<br>standards. Materials used<br>knowledge and belief.                                 | mpliance with Oregon  | n water supply w  | vell construction      | on          |  |
| Signed Mel   | Birch   | / WWC Nu  | mber 1492<br>Date 06/2 | 24/03       |  |
| (bonded) Water Well Constructor Certification:   |   |   |                        |             |  |
| l accept responsibility<br>performed on this well du<br>performed during this tim  | for the construction<br>ring the construction<br>e is in compliance w | a, alteration, or a<br>dates reported;<br>ith Oregon wate | above. All wor         | k           |  |
| construction standards. Th   | his report is true to th  |   | owledge and both       |             |  |

Did any strata contain water not suitable for intended use?

Depth of strata:\_

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other \_

Liner

X.

☐ Too little

STATE OF OREGON

### WELL I.D. # L 4 00 47 WATER SUPPLY WELL REPORT START CARD # 159796 (as required by ORS 537.765) Instructions for completing this report are on the last page of this form. (9) LOCATION OF WELL by legal description: (1) LAND OWNER Well Number \_ Stanfil Name Kichard County Tillamuk Latitude\_\_\_\_\_ \_Longitude \_ 9W Address 4590 Huyu, 101 Township 1 S \_\_\_\_N or S Range\_ \_E or W. WM. Section / NW 1/4 NW (2) TYPE OF WORK Tax Lot 1000 Lot \_\_\_\_\_ Block\_ New Well Deepening Alteration (repair/recondition) Abandonment Street Address of Well (or nearest address) 4805 Filen Ave (3) DRILL METHOD: Rotary Air Rotary Mud Cable Auger (10) STATIC WATER LEVEL: Other\_ \_ ft. below land surface. Artesian pressure \_ \_lb. per square inch (4) PROPOSED USE: Domestic Community Industrial Irrigation (11) WATER BEARING ZONES: ☐ Thermal ☐ Injection ☐ Livestock ☐ Other. Depth at which water was first found (5) BORE HOLE CONSTRUCTION: Special Construction approval Yes \No Depth of Completed Well 1951. Estimated Flow Rate SWL Explosives used Yes No Type\_ Amount \_ 105 30 31 SEAL. Material Diameter From From 0 50 105 (12) WELL LOG: How was seal placed: Method $\square$ B Ground Elevation \_ \* Other Placed in ary a prodded SWL From Backfill placed from\_ Material To Material Gravel placed from \_ Size of gravel Clar Brown 31 Solt Sandstohe 105 (6) CASING/LINER: Plastic Welded Diameter From Gauge Steel Threaded Liner: Drive Shoe used Inside Outside None Final location of shoc(s) (7) PERFORATIONS/SCREENS: ☐ Perforations Method ☐ Screens Material RECEIVED Slot Tele/pipe Casing To Number Diameter Liner From AUG 2 6 2005 WATER RESOURCES DE SALEM, OREGON Completed (8) WELL TESTS: Minimum testing time is 1 hour Flowing (unbonded) Water Well Constructor Certification: ☐ Pump ☐ Bailer X Air ☐ Artesian I certify that the work I performed on the construction, alteration, or abandon-Drill stem at Yield gal/min Drawdown Time ment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my 1 hr 30 80 knowledge and belief. WWC Number Signed \_ Temperature of water 5.5 (bonded) Water Well Constructor Certification: Depth Artesian Flow Found I accept responsibility for the construction, alteration, or abandonment work Was a water analysis done? Yes By whom. performed on this well during the construction dates reported above. All work Did any strata contain water not suitable for intended use? ☐ Too little performed during this time is in compliance with Oregon water supply well ☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other \_ construction standards. This report is true to the best of my knowledge and belief. WWC Number\_ Depth of strata: \_ Date 2

| STATE OF OREGON  |                    | (1   |  |                 |              |              |
|--|--------------------|--|--|-----------------|--------------|--------------|
| WATER SUPPLY WELL REPORT   |                    | Till   | WELL I.D. #                                  | 7140            | 7            |              |
| (as required by ORS 537.765)  Instructions for completing this report are on the last page of this form.   |                    | 51329  | START CARL                                   | # 163           | 074          |              |
|  |                    |  |  |                 | 3034         |              |
| (1) LAND OWNER Well Number   | 0016               | (9) LOCATION C                                     | F WELL by legal                              | description:    |              |              |
| Address 4160 Bognist Rd  |                    |  | Latitude                                     |                 |              |              |
| City Tillanok State OR   | Zip 9 7141         | 1  | N or S Rang                                  |                 |              | WM.          |
|  | 210 4 17-41        | Section  |  | SW              |              |              |
| (2) TYPE OF WORK   | 7.1                | Tax Lot <b>900</b>                                 | _LotBlo                                      | ckS             | ubdivision_  |              |
| □ New Well □ Deepening ★ Alteration (repair/recondition)   | Abandonment        | Street Address of                                  | Well (or nearest addres                      | s)              |              |              |
| (3) DRILL METHOD:  |                    | H_000_   | Doguesor                                     | Rel.            |              |              |
| Rotary Air Rotary Mud Cable Auger  |                    | (10) STATIC WAT                                    |  |                 |              | 11           |
| Other  |                    |  | below land surface.                          |                 | Date 97      | 28/04        |
| (4) PROPOSED USE:  |                    | Artesian pressure                                  | lb. per                                      | square inch     | Date         |              |
| ☐ Domestic ☐ Community ☐ Industrial   Irrigation   |                    | (11) WATER BEA                                     | RING ZONES:                                  |                 |              |              |
| ☐ Thermal ☐ Injection ☐ Livestock ☐ Other  |                    | 1  |  |                 |              |              |
| (5) BORE HOLE CONSTRUCTION:  |                    | Depth at which water                               | was first found                              |                 |              |              |
| Special Construction approval  Yes No Depth of Complete  |                    | From   | To   | Estimated F     | low Rate     | SWL          |
| Explosives used Yes No TypeAmount  |                    | Existian   |  |                 |              |              |
| HOLE SEAL  |                    | 27   | 100  | 50 +            | ) i          | 19           |
|  | s or pounds        | 01   |  | 223             |              | 18.3         |
| 12" 9 100 EXISTING   |                    |  | 1  |                 | -            |              |
|  |                    |  |  |                 |              | +            |
|  |                    | (10) 11/10/11 1 000                                |  |                 |              |              |
| How was seal placed: Method A B C  | D DE               | (12) WELL LOG:                                     | and Claustics                                |                 | 2            |              |
| Other Existing   |                    | Gre  | ound Elevation                               |                 |              |              |
| Backfill placed fromfl. toft. Material   |                    | Mate   | erial  | From            | То           | SWL          |
| Gravel placed fromft. toft. Size of grave  |                    |  |  |                 |              |              |
| (6) CASING/LINER:  |                    | Well WA  | GICADE                                       | dowt            | 000          |              |
| Diameter From To Gauge Steel Plastic Web   | led Threaded       | The same   | 3_0/6  | <i>U-U-1</i>    | LANTE        |              |
| Casing: 12"   #1   87   85   K   |                    | Dow Lo"  | 1.000  | vas ins         | +-11-        | 1            |
|  | -                  |  |  | A MALINA        | 1 4 1 6      | 4            |
|  |                    |  |  |                 |              |              |
|  |                    |  |  |                 |              |              |
| Liner: 10" 71 100 036 8 🗆 🖪  |                    |  |  |                 |              |              |
|  |                    |  | DEOEN  |                 |              |              |
| Drive Shoe used Inside Outside None  |                    |  | HEGEIA                                       |                 |              |              |
| Final location of shoe(s)  |                    |  |  |                 |              |              |
| (7) PERFORATIONS/SCREENS:  Perforations Method Torch   | Samuel Salar Salar | to reason at a                                     | AUG-0-2-20                                   | 04              |              |              |
|  |                    |  |  |                 |              |              |
| 100 May 100 Ma |                    | W  | ATER RESOURCE                                |                 | REI          | FIVE         |
|  | sing Liner         |  | SALEM, ORES                                  | BN.             | 1-1          |              |
| 92 100 4 78 32   | <b>S S</b>         |  | * ×  |                 | THEFT        | 0 3 2004     |
|  |                    |  |  |                 |              | 2004         |
|  |                    |  |  | W               | ATEILE.      | DURUS D      |
|  |                    |  |  |                 | SALER        | I, OREGON    |
|  |                    | Doto started 4.7 h.                                | 4 4 6  |                 | - 1-11       |              |
| 8) WELL TESTS: Minimum testing time is 1 hour  | Flowing            | Date started 7/28                                  |  | pleted 07/2     | 8/09         |              |
| □ Pump □ Bailer KAir □   | Artesian           | (unbonded) Water Wel                               |  |                 |              |              |
| Yield gal/min Drawdown Drill stem at   | Time               | ment of this well is in co                         | rk I performed on the compliance with Oregon |                 |              |              |
| 50+ 100  | l hr.              | standards. Materials use                           |  |                 |              |              |
|  |                    | knowledge and belief.                              |  |                 |              |              |
|  |                    | Cinned   |  |                 | ber          |              |
| 12   |                    | Signed   |  |                 | ate          |              |
| Temperature of water Depth Artesian Flow Found   |                    | (bonded) Water Well C                              |  |                 | ops 15       |              |
| Was a water analysis done? 1 Yes By whom   |                    | I accept responsibility performed on this well dis | ty for the construction                      |                 |              |              |
| oid any strata contain water not suitable for intended use?  | ☐ Too little       | performed during this tir                          |  |                 |              |              |
| Salty Muddy Odor Colored Other   |                    | construction standards.                            |  | best of my know | vledge and b | ejief.       |
| epth of strata:  |                    | مماليماك بسناء                                     | of states                                    | WWC Num         |              | -64          |
|  |                    | Signed   | _www.  | D:              | ate OLD      | <b>9/</b> 97 |

# APPENDIX D

Test America Laboratory Report and Chain-of-Custody

Documents



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

ORELAP#: OR100021

May 15, 2008

Erik Chapman Bergeson, Boese and Associates-Wilsonville 25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

RE: Tillamook Creamery

Enclosed are the results of analyses for samples received by the laboratory on 05/01/08 10:30. The following list is a summary of the Work Orders contained in this report, generated on 05/15/08 09:25.

If you have any questions concerning this report, please feel free to contact me.

Work Order PRE0022 Project

Tillamook Creamery

ProjectNumber TC021SC.080C

TestAmerica Portland

Damell Asseil Desired Messes

el W. Smil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.



THE LEADER IN ENVIRONMENTAL TESTING

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville Project Name: Tillamook Creamery

25195 SW Parkway Ave Suite 207 Project Number: TC021SC.080C Report Created: Wilsonville, OR 97070 Project Manager: Erik Chapman 05/15/08 09:25

### ANALYTICAL REPORT FOR SAMPLES

| Sample ID | Laboratory ID | Matrix | Date Sampled   | Date Received  |
|-----------|---------------|--------|----------------|----------------|
| P1-H2O    | PRE0022-01    | Water  | 04/29/08 14:00 | 05/01/08 10:30 |
| P2-H2O    | PRE0022-02    | Water  | 04/29/08 13:20 | 05/01/08 10:30 |
| P3-H2O    | PRE0022-03    | Water  | 04/29/08 12:30 | 05/01/08 10:30 |
| P4-H2O    | PRE0022-04    | Water  | 04/29/08 11:45 | 05/01/08 10:30 |
| P5-H2O    | PRE0022-05    | Water  | 04/29/08 15:00 | 05/01/08 10:30 |
| P2@4.5'   | PRE0022-12    | Soil   | 04/29/08 12:52 | 05/01/08 10:30 |
| P2@9.5'   | PRE0022-14    | Soil   | 04/29/08 13:05 | 05/01/08 10:30 |
| P2@15.5'  | PRE0022-16    | Soil   | 04/29/08 13:12 | 05/01/08 10:30 |
| P3@11'    | PRE0022-22    | Soil   | 04/29/08 12:20 | 05/01/08 10:30 |
| P4@14.5'  | PRE0022-27    | Soil   | 04/29/08 11:45 | 05/01/08 10:30 |
| P5@15.5'  | PRE0022-30    | Soil   | 04/29/08 14:45 | 05/01/08 10:30 |

TestAmerica Portland

Ornell W. Amil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manager



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created: 05/15/08 09:25

### Gasoline Hydrocarbons per NW TPH-Gx Method

TestAmerica Portland

| Analyte                     | Method    | Result | MDL* | MRL   | Units | Dil        | Batch       | Prepared       | Analyzed       | Notes |
|-----------------------------|-----------|--------|------|-------|-------|------------|-------------|----------------|----------------|-------|
| PRE0022-01 (P1-H2O)         | 2         |        | Wate | er    |       | Samp       | led: 04/29/ | 08 14:00       |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND     |      | 80.0  | ug/l  | lx         | 8050166     | 05/05/08 16:14 | 05/06/08 16:25 |       |
| Surrogate(s): 4-BFB         |           |        | 8    | 87.5% |       | 50 - 150 % | "           |                |                | u     |
| PRE0022-02 (P2-H2O)         |           |        | Wate | er    |       | Samp       | led: 04/29/ | 08 13:20       |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | 8830   |      | 400   | ug/l  | 5x         | 8050166     | 05/05/08 16:14 | 05/06/08 19:10 |       |
| Surrogate(s): 4-BFB         |           |        |      | 133%  |       | 50 - 150 % | lx          |                |                | u     |
| PRE0022-03 (P3-H2O)         |           |        | Wate | er    |       | Samp       | led: 04/29/ | 08 12:30       |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND     |      | 80.0  | ug/l  | lx         | 8050166     | 05/05/08 16:14 | 05/06/08 16:52 |       |
| Surrogate(s): 4-BFB         |           |        | 8    | 88.7% |       | 50 - 150 % | "           |                |                | n     |
| PRE0022-04 (P4-H2O)         |           |        | Wate | er    |       | Samp       | led: 04/29/ | 08 11:45       |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | 588    |      | 80.0  | ug/l  | lx         | 8050166     | 05/05/08 16:14 | 05/06/08 17:20 |       |
| Surrogate(s): 4-BFB         |           |        |      | 108%  |       | 50 - 150 % | "           |                |                | "     |
| PRE0022-05 (P5-H2O)         |           |        | Wate | er    |       | Samp       | led: 04/29/ | 08 15:00       |                | -     |
| Gasoline Range Hydrocarbons | NW TPH-Gx | 562    |      | 80.0  | ug/l  | lx .       | 8050166     | 05/05/08 16:14 | 05/06/08 17:47 |       |
| Surrogate(s): 4-BFB         | 7         |        | 9    | 01.3% |       | 50 - 150 % | n           |                |                | и .   |

TestAmerica Portland

hall W. Amil

Darrell Auvil, Project Manager

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory

www.testamericainc.com



Bergeson, Boese and Associates-Wilsonville

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Tillamook Creamery Project Name:

25195 SW Parkway Ave Suite 207 Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 05/15/08 09:25

## Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX per EPA Method 8021B

TestAmerica Portland

| Analyte            | ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | Method      | Result | MDL* | MRL    | Units     | Dil        | Batch       | Prepared       | Analyzed       |   | Notes |
|--------------------|--|-------------|--------|------|--------|-----------|------------|-------------|----------------|----------------|---|-------|
| PRE0022-12         | (P2@4.5')                              |             |        | Soil |        |           | Samp       | led: 04/29/ | 08 12:52       |                |   |       |
| Benzene            |  | NW-G, 8021B | 2.35   |      | 0.366  | mg/kg dry | 10x        | 8050092     | 05/02/08 15:00 | 05/03/08 05:10 |   |       |
| Toluene            |  | "           | 2.66   |      | 0.732  | "         | "          | "           |                | 310            |   |       |
| Ethylbenzene       |  | "           | 5.64   |      | 0.732  |           |            |             |                |                |   |       |
| Xylenes (total)    |  |             | 12.4   |      | 0.732  | н         |            | н           | *              | •              |   |       |
| Gasoline Range Hy  | drocarbons                             | "           | 590    |      | 58.6   |           |            |             |                | н              |   |       |
| Surrogate(s):      | a,a,a-TFT (FID)                        |             |        |      | 125%   |           | 50 - 150 % | n/          |                |                | " |       |
|                    | a,a,a-TFT (PID)                        |             |        |      | 134%   |           | 60 - 130 % | u           |                |                | n | ZX    |
| PRE0022-14         | (P2@9.5')                              |             |        | Soil |        |           | Samp       | led: 04/29/ | 08 13:05       |                |   |       |
| Benzene            |  | NW-G, 8021B | 0.187  |      | 0.0884 | mg/kg dry | 2x         | 8050092     | 05/02/08 15:00 | 05/03/08 06:33 |   |       |
| Toluene            |  | *           | 0.181  |      | 0.177  |           | н          |             | *              |                |   |       |
| Ethylbenzene       |  | ü           | 0.545  |      | 0.177  | н         |            |             | Ä.             |                |   |       |
| Xylenes (total)    |  |             | 1.08   |      | 0.177  |           |            | "           | *              |                |   |       |
| Gasoline Range Hy  | drocarbons                             |             | 53.6   |      | 14.1   | *         |            | "           |                | "              |   |       |
| Surrogate(s):      | a,a,a-TFT (FID)                        |             |        |      | 73.9%  |           | 50 - 150 % | "           |                |                | " |       |
|                    | a,a,a-TFT (PID)                        |             |        |      | 77.6%  |           | 60 - 130 % | "           |                |                | " |       |
| PRE0022-16         | (P2@15.5')                             |             |        | Soil |        |           | Samp       | led: 04/29/ | 08 13:12       |                |   |       |
| Benzene            |  | NW-G, 8021B | 1.28   |      | 0.373  | mg/kg dry | 10x        | 8050092     | 05/02/08 15:00 | 05/03/08 09:18 |   |       |
| Toluene            |  |             | 1.38   |      | 0.746  |           | * .        |             |                |                |   |       |
| Ethylbenzene       |  | н           | 3.28   |      | 0.746  |           | *          | w           |                |                |   |       |
| Xylenes (total)    |  |             | 7.78   |      | 0.746  | n         |            |             | *              | *              |   |       |
| Gasoline Range Hy  | drocarbons                             |             | 311    |      | 59.7   |           |            |             | *              |                |   |       |
| Surrogate(s):      | a,a,a-TFT (FID)                        |             |        |      | 110%   |           | 50 - 150 % | "           |                |                | " |       |
|                    | a,a,a-TFT (PID)                        |             |        |      | 110%   |           | 60 - 130 % | "           |                |                | " |       |
| PRE0022-22         | (P3@11')                               |             |        | Soil |        |           | Sampl      | led: 04/29/ | 08 12:20       |                |   |       |
| Benzene /          |  | NW-G, 8021B | ND     |      | 0.369  | mg/kg dry | 10x        | 8050092     | 05/02/08 15:00 | 05/03/08 10:41 |   | RL1   |
| Toluene            |  | "           | ND     |      | 0.737  |           | n          |             | н              |                |   | RL1   |
| Ethylbenzene       |  | **          | ND     |      | 0.737  | "         | и          |             | Ü              | н              |   | RL1   |
| Xylenes (total)    |  | н           | ND     |      | 0.737  |           |            | n.          | "              | н.             |   | RL1   |
| Gasoline Range Hyd | lrocarbons                             |             | ND     |      | 59.0   | "         |            | w           | ,              | *              |   | RL1   |
| Surrogate(s):      | a,a,a-TFT (FID)                        |             |        |      | 67.6%  |           | 50 - 150 % | ,,          |                |                | " |       |
|                    | a,a,a-TFT (PID)                        |             |        |      | 61.6%  |           | 60 - 130 % | "           |                |                | " |       |

TestAmerica Portland



9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070 Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 05/15/08 09:25

### Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX per EPA Method 8021B

TestAmerica Portland

| Analyte           |                                    | Method      | Result | MDL* | MRL            | Units     | Dil                      | Batch       | Prepared       | Analyzed       |   | Notes |
|-------------------|------------------------------------|-------------|--------|------|----------------|-----------|--------------------------|-------------|----------------|----------------|---|-------|
| PRE0022-27        | (P4@14.5')                         |             |        | So   | il             |           | Samp                     | led: 04/29/ | 08 11:45       |                |   |       |
| Benzene           |                                    | NW-G, 8021B | ND     |      | 0.401          | mg/kg dry | 10x                      | 8050092     | 05/02/08 15:00 | 05/03/08 09:45 |   | RL1   |
| Toluene           |                                    |             | ND     |      | 0.803          | "         |                          |             | 14             |                |   | RL1   |
| Ethylbenzene      |                                    |             | ND     |      | 0.803          |           |                          |             | n              |                |   | RLI   |
| Xylenes (total)   |                                    | "           | ND     |      | 0.803          | "         | н.                       |             |                |                |   | RL1   |
| Gasoline Range Hy | drocarbons                         |             | ND     |      | 64.2           |           |                          |             |                | н .            |   | RL1   |
| Surrogate(s):     | a,a,a-TFT (FID)<br>a,a,a-TFT (PID) |             |        |      | 72.2%<br>64.8% | 9         | 50 - 150 %<br>60 - 130 % | "           |                |                | " |       |
| PRE0022-30        | (P5@15.5')                         |             |        | So   | il             |           | Samp                     | led: 04/29/ | 08 14:45       |                |   |       |
| Benzene           |                                    | NW-G, 8021B | ND     |      | 0.414          | mg/kg dry | 10x                      | 8050092     | 05/02/08 15:00 | 05/03/08 06:05 |   | RL1   |
| Toluene           |                                    | ,,          | ND     |      | 0.827          |           | п                        |             | и.             |                |   | RL1   |
| Ethylbenzene      |                                    |             | ND     |      | 0.827          |           |                          |             | . "            |                |   | RL1   |
| Xylenes (total)   |                                    | ,           | ND     |      | 0.827          | *         | *                        | н           | : m            |                |   | RL1   |
| Gasoline Range Hy | drocarbons                         |             | ND     |      | 66.2           |           | ж .                      | н           | •              | *              |   | RL1   |
| Surrogate(s):     | a,a,a-TFT (FID)                    |             |        |      | 66.2%          |           | 50 - 150 %               | "           |                |                | " | RL1   |
|                   | a,a,a-TFT (PID)                    |             |        |      | 60.5%          |           | 60 - 130 %               | "           |                |                | " | RL1   |

TestAmerica Portland

bull W. Sail

Darrell Auvil, Project Manager



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 05/15/08 09:25

### Dissolved Metals per EPA 6000/7000 Series Methods

TestAmerica Portland

| Analyte    |          | Method   | Result  | MDL* | MRL     | Units | Dil  | Batch        | Prepared       | Analyzed       | Notes |
|------------|----------|----------|---------|------|---------|-------|------|--------------|----------------|----------------|-------|
| PRE0022-01 | (P1-H2O) |          |         | W    | ater    |       | Samp | oled: 04/29/ | 08 14:00       |                |       |
| Lead       |          | EPA 6020 | ND      |      | 0.00100 | mg/l  | 1x   | 8050245      | 05/07/08 08:30 | 05/08/08 02:19 |       |
| PRE0022-02 | (P2-H2O) |          |         | w    | ater    |       | Samp | oled: 04/29/ | 08 13:20       |                |       |
| Lead       |          | EPA 6020 | 0.00293 |      | 0.00100 | mg/l  | lx   | 8050245      | 05/07/08 08:30 | 05/08/08 02:28 |       |
|            |          |          |         |      |         |       |      |              |                |                |       |
| PRE0022-03 | (P3-H2O) |          |         | W    | ater    |       | Samp | oled: 04/29/ | 08 12:30       |                |       |
| Lead       |          | EPA 6020 | ND      |      | 0.00100 | mg/l  | 1x   | 8050245      | 05/07/08 08:30 | 05/08/08 02:36 | X     |
| PRE0022-04 | (P4-H2O) |          |         | w    | ater    |       | Samp | oled: 04/29/ | 08 11:45       |                |       |
| Lead       |          | EPA 6020 | 0.00138 |      | 0.00100 | mg/l  | lx   | 8050245      | 05/07/08 08:30 | 05/08/08 02:44 |       |
| PRE0022-05 | (P5-H2O) |          |         | W    | ater    |       | Samp | oled: 04/29/ | 08 15:00       |                |       |
| Lead       |          | EPA 6020 | ND      |      | 0.00100 | mg/l  | 1x   | 8050245      | 05/07/08 08:30 | 05/08/08 02:52 |       |

TestAmerica Portland

Und W. Amil

Darrell Auvil, Project Manager

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

www.testamericainc.com



PORTLAND, OR

9405 S.W. NIMBUS AVENUE

BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Report Created:

Erik Chapman 05/15/08 09:25

### Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B

TestAmerica Portland

| Analyte  | Method    | Result  | MDL* | MRL  | Units | Dil                      | Batch             | Prepared                   | Analyzed       | Notes |
|--|-----------|---|------|--|-------|--------------------------|-------------------|----------------------------|----------------|-------|
| PRE0022-01 (P1-H2O)  |           |   | W    | ater   |       | Samp                     | led: 04/29/       | 08 14:00                   |                |       |
| 1,2-Dibromoethane  | EPA 8260B | ND  |      | 0.500  | ug/l  | lx                       | 8050251           | 05/08/08 07:00             | 05/08/08 13:34 |       |
| 1,2-Dichloroethane   | "         | ND  | ,    | 0.500  |       |                          |                   |                            | ж              |       |
| Benzene  | •         | ND  |      | 0.200  | *     |                          | •                 | W.                         | Ti .           |       |
| Toluene  |           | ND  |      | 0.500  | н     | 111                      | w                 | "                          |                |       |
| Ethylbenzene   |           | ND  |      | 0.500  |       |                          |                   |                            |                |       |
| Xylenes (total)  |           | ND  |      | 1.00   | "     |                          | n                 | *                          |                |       |
| Methyl tert-butyl ether  |           | ND  |      | 2.00   | "     |                          | н                 |                            |                |       |
| Naphthalene  |           | ND  |      | 2.00   |       |                          | н                 |                            |                |       |
| 1,2,4-Trimethylbenzene   | Ü         | ND  |      | 1.00   |       |                          |                   |                            |                |       |
| 1,3,5-Trimethylbenzene   |           | ND  |      | 0.500  |       | · ·                      |                   |                            |                |       |
| Isopropylbenzene   | "         | ND  |      | 2.00   | *     |                          | "                 |                            | *              |       |
| n-Propylbenzene  | ,         | ND  |      | 0.500  |       | ,                        |                   | "                          | *              |       |
| Surrogate(s): 4-BFB  |           |   |      | 101%   |       | 80 - 120 %               | "                 |                            |                | u .   |
| 1,2-DCA-d4   |           |   |      | 103%   |       | 80 - 120 %               | "                 |                            |                | n     |
| 1,2-DCA-44   |           |   |      |  |       |                          | "                 |                            |                | "     |
| Dibromofluore  | omethane  |   |      | 103%   |       | 80 - 120 %               |                   |                            |                |       |
|  | omethane  |   |      | 103%<br>102%   |       | 80 - 120 %<br>80 - 120 % | "                 |                            |                | "     |
| Dibromofluore  | omethane  |   | w    |  |       | 80 - 120 %               |                   | 08 13:20                   |                | " RL  |
| Dibromofluore<br>Toluene-d8  | EPA 8260B | . ND  | W    | 102%   | ug/l  | 80 - 120 %               | "                 | 08 13:20<br>05/08/08 07:00 | 05/08/08 14:01 | " RL  |
| Dibromofluoro Toluene-d8  PRE0022-02 (P2-H2O)  |           | ND<br>ND  |      | 102%<br>ater   | ug/l  | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            | 05/08/08 14:01 | " RL  |
| Dibromofluore Toluene-d8  PRE0022-02 (P2-H2O)  1,2-Dibromoethane   |           |   |      | 102%<br>ater   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dichloroethane  |           | ND  |      | 2.50<br>2.50   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | "     |
| PRE0022-02 (P2-H2O)  1,2-Dichloroethane 1,2-Dichloroethane Benzene   |           | ND<br>5.25  |      | 2.50<br>2.50<br>1.00   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene  |           | ND<br>5.25<br>ND  |      | 2.50<br>2.50<br>1.00<br>2.50   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene   |           | ND<br>5.25<br>ND<br>290                                   |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total)   |           | ND<br>5.25<br>ND<br>290<br>385                            |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene   |           | ND<br>5.25<br>ND<br>290<br>385<br>ND                      |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene 1,2,4-Trimethylbenzene  |           | ND<br>5.25<br>ND<br>290<br>385<br>ND<br>271               |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00<br>10.0   |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | , RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene   |           | ND<br>5.25<br>ND<br>290<br>385<br>ND<br>271<br>748<br>248 |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00<br>10.0<br>5.00                                 |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene 1,2,4-Trimethylbenzene  |           | ND<br>5.25<br>ND<br>290<br>385<br>ND<br>271<br>748        |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00<br>10.0<br>5.00<br>2.50                         |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| Dibromofluore Toluene-d8  PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene Isopropylbenzene n-Propylbenzene                      |           | ND 5.25<br>ND 290 385<br>ND 271 748 248                   |      | 2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00<br>10.0<br>5.00<br>2.50                         |       | 80 - 120 %<br>Samp       | "<br>oled: 04/29/ |                            |                | " RL  |
| PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene Isopropylbenzene  |           | ND 5.25<br>ND 290 385<br>ND 271 748 248                   |      | 2.50<br>2.50<br>2.50<br>1.00<br>2.50<br>2.50<br>5.00<br>10.0<br>5.00<br>2.50<br>10.0<br>2.50 |       | 80 - 120 %  Samp  5x     | 8050251           |                            |                |       |
| Dibromofluore Toluene-d8  PRE0022-02 (P2-H2O)  1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl ether Naphthalene 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene Isopropylbenzene n-Propylbenzene  Surrogate(s): 4-BFB | EPA 8260B | ND 5.25<br>ND 290 385<br>ND 271 748 248                   |      | 2.50<br>2.50<br>2.50<br>1.00<br>2.50<br>5.00<br>10.0<br>5.00<br>2.50<br>10.0<br>2.50         |       | 80 - 120 %  Samp  5x     | 8050251           |                            |                |       |

TestAmerica Portland

Darrell Auvil, Project Manager



Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

Project Number: TC02
Project Manager: Erik

TC021SC.080C Erik Chapman Report Created: 05/15/08 09:25

### Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B

TestAmerica Portland

| Analyte  |  | Method               | Result   | MDL* | MRL   | Units      | Dil   | Batch                       | Prepared       | Analyzed       | Notes                                    |     |
|--|--|----------------------|--|------|---|------------|---|-----------------------------|----------------|----------------|--|-----|
| PRE0022-03   | (P3-H2O)   |                      | 5  | Wa   | ater  |            | Sampl   | led: 04/29/                 | 08 12:30       |                |  |     |
| 1,2-Dibromoethane  |  | EPA 8260B            | ND   |      | 0.500   | ug/l       | lx  | 8050251                     | 05/08/08 07:00 | 05/08/08 14:28 |  |     |
| 1,2-Dichloroethane   |  |                      | ND   |      | 0.500   |            |   | "                           | н              |                |  |     |
| Benzene  |  |                      | ND   | ,    | 0.200   | **         |   | · ·                         | н.             | u              |  |     |
| Toluene  |  |                      | ND   |      | 0.500   | H          |   | u                           | и.             | и              |  |     |
| Ethylbenzene   |  |                      | ND   |      | 0.500   | н          | ü   | ·                           | .110           |                |  |     |
| Xylenes (total)  |  | •                    | ND   |      | 1.00  | *          |   | "                           | н              | n.             |  |     |
| Methyl tert-butyl eth  | her  |                      | ND   |      | 2.00  | н          | ï.  | H.                          | и              | н              |  |     |
| Naphthalene  |  |                      | ND   |      | 2.00  |            | *   | "                           | и.             | э.             |  |     |
| 1,2,4-Trimethylbenz  | zene   |                      | ND   |      | 1.00  | - <u>u</u> |   |                             | н              | и              |  |     |
| 1,3,5-Trimethylbenz  | zene   | н.                   | ND   |      | 0.500   |            |   |                             | **             | *              |  |     |
| Isopropylbenzene   |  |                      | ND   |      | 2.00  |            |   | "                           | **             |                |  |     |
| n-Propylbenzene  |  |                      | ND   |      | 0.500   |            |   | "                           |                | *              |  |     |
| Surrogate(s):  | 4-BFB  |                      |  |      | 101%  | Ä          | 80 - 120 %  | "                           |                |                | "  |     |
|  | 1,2-DCA-d4   |                      |  |      | 103%  |            | 80 - 120 %  | n                           |                |                | "  |     |
|  |  |                      |  |      |   |            | 00 120 04   | "                           |                |                | "  |     |
|  | Dibromofluoro  | methane              |  |      | 100%<br>101%  |            | 80 - 120 %<br>80 - 120 %                                | "                           |                |                | n E                                      |     |
|  |  | methane              |  |      |   |            |   | ,,                          |                |                | и В                                      |     |
| PRE0022-04 (   | Dibromofluoro  | methane              | 75   | W    |   |            | 80 - 120 %  | "<br>led: 04/29/            | 08 11:45       |                | # 8                                      |     |
| PRE0022-04 (   | Dibromofluoron Toluene-d8 (P4-H2O)                   | methane<br>EPA 8260B | ND   | W:   | 101%  | ug/l       | 80 - 120 %  |                             | 08 11:45       | 05/08/08 14:54 | н  |     |
| 1,2-Dibromoethane  | Dibromofluoroi Toluene-d8 (P4-H2O)                   |                      | ND<br>ND   |      | 101%<br>ater  | ug/l       | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и Е                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane   | Dibromofluoroi Toluene-d8 (P4-H2O)                   | EPA 8260B            |  |      | 101%<br>nter<br>0.500   |            | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      |     |
| 1,2-Dibromoethane<br>1,2-Dichloroethane<br>Benzene   | Dibromofluoroi Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND   |      | 0.500<br>0.500  | и          | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene   | Dibromofluoroi Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br><b>4.9</b> 9   |      | 0.500<br>0.500<br>0.200   | и          | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene  | Dibromofluoroi Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br><b>4.99</b><br>ND  |      | 0.500<br>0.500<br>0.200<br>0.500  | и          | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | # ÷                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total)  | Dibromofluoron<br>Toluene-d8<br>(P4-H2O)             | EPA 8260B            | ND<br>4.99<br>ND<br>14.7   |      | 0.500<br>0.500<br>0.200<br>0.500  | n<br>n     | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth  | Dibromofluoron<br>Toluene-d8<br>(P4-H2O)             | EPA 8260B            | ND<br>4.99<br>ND<br>14.7   |      | 0.500<br>0.500<br>0.200<br>0.500<br>0.500<br>1.00   | n<br>n     | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth  | Dibromofluoron Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0                                       |      | 0.500<br>0.500<br>0.200<br>0.500<br>0.500<br>1.00<br>2.00   | n<br>n     | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      | -   |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth Naphthalene 1,2,4-Trimethylben   | Dibromofluoror Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0<br>ND<br>9.35                         |      | 0,500<br>0,500<br>0,500<br>0,200<br>0,500<br>0,500<br>1,00<br>2,00                                  |            | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | "  |     |
|  | Dibromofluoror Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0<br>ND<br>9.35<br>26.5                 |      | 0.500<br>0.500<br>0.500<br>0.500<br>0.500<br>0.500<br>1.00<br>2.00<br>2.00                          |            | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | # ·                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth Naphthalene 1,2,4-Trimethylben 1,3,5-Trimethylben                                  | Dibromofluoror Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0<br>ND<br>9.35<br>26.5<br>3.80         |      | 0.500<br>0.500<br>0.500<br>0.500<br>0.500<br>0.500<br>1.00<br>2.00<br>2.00<br>1.00<br>0.500         |            | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                | 05/08/08 14:54 | и :                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth Naphthalene 1,2,4-Trimethylben 1,3,5-Trimethylben Isopropylbenzene                 | Dibromofluoror Toluene-d8 (P4-H2O)                   | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0<br>ND<br>9.35<br>26.5<br>3.80<br>5.28 |      | 0.500<br>0.500<br>0.500<br>0.500<br>0.500<br>0.500<br>1.00<br>2.00<br>2.00<br>1.00<br>0.500<br>2.00 | **         | 80 - 120 %<br>Samp                                      | led: 04/29/                 |                |                | и .                                      |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth Naphthalene 1,2,4-Trimethylben 1,3,5-Trimethylben Isopropylbenzene n-Propylbenzene | Dibromofluoror Toluene-d8 (P4-H2O)  her              | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0<br>ND<br>9.35<br>26.5<br>3.80<br>5.28 |      | 0.500 0.500 0.500 0.500 0.500 0.500 1.00 2.00 1.00 0.500 2.00 1.00 0.500 2.00 0.500                 | **         | 80 - 120 %  Samp  | 8050251 " " " " " " " " "   |                |                |  |     |
| 1,2-Dibromoethane 1,2-Dichloroethane Benzene Toluene Ethylbenzene Xylenes (total) Methyl tert-butyl eth Naphthalene 1,2,4-Trimethylben 1,3,5-Trimethylben Isopropylbenzene n-Propylbenzene | Dibromofluoror Toluene-d8  (P4-H2O)  her nzene 4-BFB | EPA 8260B            | ND<br>4.99<br>ND<br>14.7<br>14.0<br>ND<br>9.35<br>26.5<br>3.80<br>5.28 |      | 0.500 0.500 0.500 0.500 0.500 1.00 2.00 1.00 0.500 2.00 1.00 0.500 2.00 1.00                        | **         | 80 - 120 %  Samp  1x  " " " " " " " " " " " " " " " " " | 8050251 " " " " " " " " " " |                |                | TI T | · · |

TestAmerica Portland

and W. Smil

Darrell Auvil, Project Manager



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070 Project Manager:

Project Name: Tillamook Creamery

Project Number: TC021SC.080C

: Erik Chapman

Report Created: 05/15/08 09:25

### Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B

TestAmerica Portland

| Analyte                 | Method    | Result | MDL* | MRL   | Units | Dil        | Batch       | Prepared       | Analyzed       | Notes |
|-------------------------|-----------|--------|------|-------|-------|------------|-------------|----------------|----------------|-------|
| PRE0022-05 (P5-H2O)     |           |        | W    | ater  |       | Samp       | led: 04/29/ | 08 15:00       |                |       |
| 1,2-Dibromoethane       | EPA 8260B | ND     |      | 0.500 | ug/l  | lx         | 8050251     | 05/08/08 07:00 | 05/08/08 15:21 |       |
| 1,2-Dichloroethane      | ,         | ND     |      | 0.500 |       |            |             | n              |                |       |
| Benzene                 | н         | 50.1   |      | 0.200 | "     |            |             |                |                |       |
| Toluene                 |           | 159    |      | 0.500 |       | *          | "           |                |                |       |
| Ethylbenzene            |           | 24.3   |      | 0.500 |       |            | "           |                |                |       |
| Xylenes (total)         |           | 146    |      | 1.00  |       |            | "           |                |                |       |
| Methyl tert-butyl ether | ě         | ND     |      | 2.00  | in.   |            | "           |                |                |       |
| Naphthalene             |           | ND     |      | 2.00  |       |            | "           | "              |                |       |
| 1,2,4-Trimethylbenzene  | <b>#</b>  | 10.7   |      | 1.00  | 74    |            | "           | *              |                |       |
| 1,3,5-Trimethylbenzene  | **        | 4.39   |      | 0.500 |       |            |             |                |                |       |
| Isopropylbenzene        |           | ND     |      | 2.00  |       | u          | "           |                |                |       |
| n-Propylbenzene         | "         | 1.11   |      | 0.500 | "     |            | "           | *              |                |       |
| Surrogate(s): 4-BFB     |           |        |      | 102%  |       | 80 - 120 % | "           |                |                | :#    |
| 1,2-DCA-d4              |           |        |      | 101%  |       | 80 - 120 % | n           |                |                | "     |
| Dibromofluore           | methane   |        |      | 100%  |       | 80 - 120 % | "           |                |                | "     |
| Toluene-d8              |           |        |      | 99.8% |       | 80 - 120 % | "           |                |                | "     |

TestAmerica Portland

Charle W. Amil

Darrell Auvil, Project Manager

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

www.testamericainc.com



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created: 05/15/08 09:25

### Percent Dry Weight (Solids) per Standard Methods

TestAmerica Portland

| Analyte    |            | Method  | Result | MDL* | MRL        | Units          | Dil | Batch        | Prepared       | Analyzed       | Notes |
|------------|------------|---------|--------|------|------------|----------------|-----|--------------|----------------|----------------|-------|
| PRE0022-12 | (P2@4.5')  |         |        | Soil | l          |                | Sam | pled: 04/29/ | 08 12:52       |                |       |
| % Solids   |            | NCA SOP | 68.3   |      | 0.0100     | % by<br>Weight | lx  | 8050210      | 05/06/08 14:25 | 05/06/08 14:25 |       |
| PRE0022-14 | (P2@9.5')  |         |        | Soil |            |                | Sam | pled: 04/29/ | 08 13:05       |                |       |
| % Solids   | e          | NCA SOP | 54.1   |      | 0.0100     | % by<br>Weight | 1x  | 8050210      | 05/06/08 14:25 | 05/06/08 14:25 |       |
| PRE0022-16 | (P2@15.5') |         |        | Soi  | 1          |                | Sam | pled: 04/29/ | 08 13:12       |                |       |
| % Solids   |            | NCA SOP | 65.1   |      | 0.0100     | % by<br>Weight | lx  | 8050210      | 05/06/08 14:25 | 05/06/08 14:25 | Ţ.    |
| PRE0022-22 | (P3@11')   |         |        | Soi  | l          |                | Sam | pled: 04/29/ | 08 12:20       |                |       |
| % Solids   |            | NCA SOP | 67.0   |      | 0.0100     | % by<br>Weight | lx  | 8050210      | 05/06/08 14:25 | 05/06/08 14:25 |       |
| PRE0022-27 | (P4@14.5') |         |        | Soil | <b>l</b> . |                | Sam | pled: 04/29/ | 08 11:45       |                |       |
| % Solids   |            | NCA SOP | 62.3   |      | 0.0100     | % by<br>Weight | lx  | 8050210      | 05/06/08 14:25 | 05/06/08 14:25 |       |
| PRE0022-30 | (P5@15.5') |         |        | Soi  | l          |                | Sam | pled: 04/29/ | 08 14:45       |                | 2 "   |
| % Solids   |            | NCA SOP | 59.2   |      | 0.0100     | % by<br>Weight | lx  | 8050210      | 05/06/08 14:25 | 05/06/08 14:25 |       |

TestAmerica Portland

Darrell Auvil, Project Manager



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created: 05/15/08 09:25

### Gasoline Hydrocarbons per NW TPH-Gx Method - Laboratory Quality Control Results

TestAmerica Portland

| The park and the Monthly and | y — Websteld to | and the Francisco |           | TestAmerica For | tialiu    |                  |        | a 1945, I |             |          | 810   | I American Print | 582   |
|------------------------------|-----------------|-------------------|-----------|-----------------|-----------|------------------|--------|-----------|-------------|----------|-------|------------------|-------|
| QC Batch: 8050166            | Water I         | Preparation       | n Method: | EPA 5030B       |           |                  |        |           |             |          |       |                  |       |
| Analyte                      | Method          | Result            | MDL*      | MRL Un          | nits Dil  | Source<br>Result |        | %<br>REC  | (Limits)    | %<br>RPD | (Limi | ts) Analyzed     | Notes |
| Blank (8050166-BLK1)         |                 |                   |           |                 |           | (*)              | Extrac | ted: (    | 05/05/08 16 | :14      |       |                  |       |
| Gasoline Range Hydrocarbons  | NW TPH-Gx       | ND                |           | 80.0 ug/        | /I lx     |                  | -      |           |             |          |       | 05/06/08 05:08   |       |
| Surrogate(s): 4-BFB          |                 | Recovery:         | 85.3%     | Limits: 5       | 10-150% " |                  |        |           |             |          |       | 05/06/08 05:08   |       |
| LCS (8050166-BS1)            |                 |                   |           |                 |           |                  | Extrac | ted: (    | 05/05/08 16 | :14      |       |                  |       |
| Gasoline Range Hydrocarbons  | NW TPH-Gx       | 453               |           | 80.0 ug/        | /l 1x     |                  | 500 9  | 0.7%      | (70-130)    |          |       | 05/06/08 04:14   |       |
| Surrogate(s): 4-BFB          |                 | Recovery:         | 93.4%     | Limits: 5       | 0-150% "  |                  |        |           |             |          |       | 05/06/08 04:14   |       |
| LCS Dup (8050166-BSD1)       |                 |                   |           |                 |           |                  | Extrac | ted:      | 05/05/08 16 | :14      |       |                  |       |
| Gasoline Range Hydrocarbons  | NW TPH-Gx       | 491               |           | 80.0 ug/        | /l lx     |                  | 500 9  | 8.2%      | (70-130)    | 8.01%    | (35)  | 05/06/08 04:41   |       |
| Surrogate(s): 4-BFB          |                 | Recovery:         | 93.0%     | Limits: 5       | 0-150% "  |                  |        |           |             |          |       | 05/06/08 04:41   |       |
| Duplicate (8050166-DUP1)     |                 |                   |           | QC Source: PRE  | 00022-01  |                  | Extrac | ted: (    | 05/05/08 16 | :14      |       |                  |       |
| Gasoline Range Hydrocarbons  | NW TPH-Gx       | ND                |           | 80.0 ug/        | /l 1x     | ND               |        |           |             | NR       | (35)  | 05/06/08 20:32   |       |
| Surrogate(s): 4-BFB          |                 | Recovery:         | 88.0%     | Limits: 50      | 0-150% "  |                  |        |           |             |          |       | 05/06/08 20:32   |       |
| Duplicate (8050166-DUP2)     |                 |                   |           | QC Source: PRE  | 00022-02  |                  | Extrac | ted: (    | 05/05/08 16 | :14      |       |                  |       |
| Gasoline Range Hydrocarbons  | NW TPH-Gx       | 1540              |           | 80.0 ug/        | 1 lx      | 8830             |        |           |             | 141%     | (35)  | 05/06/08 21:00   | R     |
| Surrogate(s): 4-BFB          |                 | Recovery:         | 133%      | Limits: 50      | 0-150% "  |                  |        |           |             |          |       | 05/06/08 21:00   |       |

TestAmerica Portland

hall W. Amil



Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 05/15/08 09:25

# Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX per EPA Method 8021B - Laboratory Quality Control Results

TestAmerica Portland

| QC Batch: 8050092             | Soil Pr        | eparation M | 1ethod: EP. | A 5035 M  | odified        |     |                  |              |          |             |          |         |                |       |
|-------------------------------|----------------|-------------|-------------|-----------|----------------|-----|------------------|--------------|----------|-------------|----------|---------|----------------|-------|
| Analyte                       | Method         | Result      | MDL*        | MRL       | Units          | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits | ) Analyzed     | Notes |
| Blank (8050092-BLK1)          |                |             |             |           |                |     |                  | Exti         | racted:  | 05/02/08 15 | 5:00     |         |                |       |
| Benzene                       | NW-G,<br>8021B | ND          |             | 0.0249    | mg/kg wet      | lx  |                  |              |          |             |          |         | 05/03/08 04:43 |       |
| Toluene                       | "              | ND          |             | 0.0497    | "              |     |                  |              |          |             |          |         |                |       |
| Ethylbenzene                  | ж              | ND          |             | 0.0497    | **             | •   |                  |              |          |             |          |         |                |       |
| Xylenes (total)               |                | ND          |             | 0.0497    | 1.00           | "   |                  |              |          |             |          |         |                |       |
| Gasoline Range Hydrocarbons   | w              | ND          |             | 3.98      |                |     |                  |              |          |             |          |         | m t            |       |
| Surrogate(s): a,a,a-TFT (FID) |                | Recovery:   | 102%        | L         | imits: 50-150% | 6 " |                  |              |          |             |          | -       | 05/03/08 04:43 |       |
| a,a,a-TFT (PID)               |                |             | 102%        |           | 60-130         | % " |                  |              |          |             |          |         | "              |       |
| LCS (8050092-BS1)             |                |             |             |           |                |     |                  | Exti         | racted:  | 05/02/08 15 | :00      |         |                |       |
| Benzene                       | NW-G,<br>8021B | 0.466       |             | 0.0244    | mg/kg wet      | lx  |                  | 0.488        | 95.5%    | (65-130)    |          |         | 05/03/08 03:48 |       |
| Toluene                       | "              | 0.479       |             | 0.0488    |                |     |                  |              | 98.3%    | : 11        |          |         |                |       |
| Ethylbenzene                  |                | 0.493       |             | 0.0488    |                |     |                  |              | 101%     | н           |          |         | w              |       |
| Xylenes (total)               | и              | 1.47        |             | 0.0488    |                |     |                  | 1.46         | 101%     |             |          |         |                |       |
| Surrogate(s): a,a,a-TFT (PID) |                | Recovery:   | 105%        | L         | imits: 60-130% | 6 " |                  |              |          |             |          |         | 05/03/08 03:48 |       |
| LCS (8050092-BS2)             |                |             |             |           |                |     |                  | Exti         | racted:  | 05/02/08 15 | :00      |         |                |       |
| Gasoline Range Hydrocarbons   | NW-G,<br>8021B | 19.9        |             | 7.53      | mg/kg wet      | lx  | -                | 23.5         | 84.4%    | (70-130)    |          | -       | 05/03/08 04:15 |       |
| Surrogate(s): a,a,a-TFT (FID) |                | Recovery:   | 105%        | L         | imits: 50-150% | 6 " |                  |              |          |             |          |         | 05/03/08 04:15 |       |
| Duplicate (8050092-DUP1)      |                |             |             | QC Sourc  | e: PRE0022-3   | 0   |                  | Exti         | racted:  | 05/02/08 15 | :00      |         |                |       |
| Gasoline Range Hydrocarbons   | NW-G,<br>8021B | ND          |             | 66.2      | mg/kg dry      | 10x | ND               |              | ,        |             | NR       | (40)    | 05/03/08 05:38 | RL    |
| Surrogate(s): a,a,a-TFT (FID) |                | Recovery:   | 65.8%       | L         | imits: 50-150% | 6 " |                  |              |          |             |          |         | 05/03/08 05:38 |       |
| Matrix Spike (8050092-MS1)    |                |             |             | QC Sourc  | e: PRE0022-1   | 4   |                  | Ext          | acted:   | 05/02/08 15 | :00      |         |                |       |
| Benzene                       | NW-G,<br>8021B | 1.83        |             | 0.0884    | mg/kg dry      | 2x  | 0.187            | 1.77         | 93.1%    | (65-130)    |          |         | 05/03/08 07:00 |       |
| Toluene                       | "              | 1.88        |             | 0.177     |                |     | 0.181            |              | 95.9%    | *           |          |         | <b>"</b>       |       |
| Ethylbenzene                  | 2.5            | 2.27        |             | 0.177     |                |     | 0.545            |              | 97.6%    | н           |          |         |                |       |
| Xylenes (total)               |                | 6.22        |             | 0.177     |                |     | 1.08             | 5.30         | 97.0%    | н           |          | 144     | "              |       |
| Surrogate(s): a,a,a-TFT (PID) | 2              | Recovery:   | 76.3%       | L         | imits: 60-130% | 6 " |                  |              |          |             | 7        |         | 05/03/08 07:00 |       |
| Matrix Spike (8050092-MS2)    |                |             |             | QC Source | e: PRE0022-2   | 7   |                  | Exti         | acted:   | 05/02/08 15 | :00      |         |                |       |
| Gasoline Range Hydrocarbons   | NW-G,<br>8021B | 169         |             | 64.2      | mg/kg dry      | 10x | ND               | 201          | 84.1%    | (65-130)    |          |         | 05/03/08 10:13 |       |
| Surrogate(s): a,a,a-TFT (FID) |                | Recovery:   | 117%        | L         | imits: 50-150% | 5 " |                  |              |          | -           | 4        |         | 05/03/08 10:13 |       |

TestAmerica Portland

Und W. Smil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil. Project Manager



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070 Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 05/15/08 09:25

Gasoline Hydrocarbons per NW TPH-Gx Method and BTEX per EPA Method 8021B - Laboratory Quality Control Results

TestAmerica Portland

| QC Batch: 8050092             | Soil Pr        | eparation M | ethod: EPA | 5035 M    | odified        |     | ×                |              |          |             |          |          |                |       |
|-------------------------------|----------------|-------------|------------|-----------|----------------|-----|------------------|--------------|----------|-------------|----------|----------|----------------|-------|
| Analyte                       | Method         | Result      | MDL*       | MRL       | Units          | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits) | Analyzed       | Notes |
| Matrix Spike Dup (8050092-M   | (ISD1)         |             |            | QC Source | e: PRE0022-1   | 4   |                  | Extr         | acted:   | 05/02/08 15 | :00      |          |                |       |
| Benzene                       | NW-G,<br>8021B | 1.81        |            | 0.0884    | mg/kg dry      | 2x  | 0.187            | 1.77         | 91.5%    | (65-130)    | 1.52%    | (20)     | 05/03/08 07:28 |       |
| Toluene                       | и              | 1.87        |            | 0.177     |                |     | 0.181            | "            | 95.4%    |             | 0.425%   | , "      |                |       |
| Ethylbenzene                  |                | 2.27        |            | 0.177     | m .            |     | 0.545            | "            | 97.5%    | н           | 0.08179  | 6 "      |                |       |
| Xylenes (total)               |                | 6.20        |            | 0.177     |                |     | 1.08             | 5.30         | 96.6%    |             | 0.299%   | , "      | "              |       |
| Surrogate(s): a,a,a-TFT (PID) |                | Recovery:   | 76.7%      | L         | imits: 60-130% | 6 " |                  |              |          |             |          |          | 05/03/08 07:28 |       |

TestAmerica Portland

Darrell Auvil, Project Manager



Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Tillamook Creamery Project Name:

Project Number: TC021SC.080C Report Created: Project Manager: Erik Chapman 05/15/08 09:25

Dissolved Metals per EPA 6000/7000 Series Methods - Laboratory Quality Control Results

|                              |          |              |           | ΓestAmeric | a Portlan | d   |                  |                    |             |          |          |                |       |
|------------------------------|----------|--------------|-----------|------------|-----------|-----|------------------|--------------------|-------------|----------|----------|----------------|-------|
| QC Batch: 8050245            | Water P  | reparation M | lethod: E | PA 200/30  | 05 Diss   |     |                  |                    |             |          |          |                |       |
| Analyte                      | Method   | Result       | MDL*      | MRL        | Units     | Dil | Source<br>Result | Spike %<br>Amt REC | (Limits)    | %<br>RPD | (Limits) | Analyzed       | Notes |
| Blank (8050245-BLK1)         |          |              |           |            |           |     |                  | Extracted:         | 05/07/08 08 | 8:30     |          |                |       |
| Lead                         | EPA 6020 | ND           |           | 0.00100    | mg/l      | lx  | ==               |                    |             |          |          | 05/08/08 02:03 |       |
| LCS (8050245-BS1)            |          |              |           |            |           |     |                  | Extracted:         | 05/07/08 08 | 8:30     | 5.1      |                |       |
| Lead                         | EPA 6020 | 0.105        |           | 0.00111    | mg/l      | lx  |                  | 0.111 94.3%        | (80-120)    |          | -        | 05/08/08 02:11 |       |
| Duplicate (8050245-DUP1)     |          |              |           | QC Source: | PRE0174   | -07 |                  | Extracted:         | 05/07/08 08 | 8:30     |          |                |       |
| Lead                         | EPA 6020 | ND           |           | 0.00100    | mg/l      | lx  | ND               |                    |             | 4.29%    | (20)     | 05/08/08 04:14 |       |
| Matrix Spike (8050245-MS1)   |          |              |           | QC Source: | PRE0174   | -07 |                  | Extracted:         | 05/07/08 08 | 8:30     |          |                | 5     |
| Lead                         | EPA 6020 | 0.102        |           | 0.00111    | mg/l      | lx  | 0.000137         | 0.111 91.7%        | (75-125)    |          | -        | 05/08/08 04:31 |       |
| Matrix Spike Dup (8050245-MS | SD1)     |              |           | QC Source: | PRE0174   | -07 |                  | Extracted:         | 05/07/08 08 | 8:30     |          |                |       |
| Lead                         | EPA 6020 | 0.102        |           | 0.00111    | mg/l      | lx  | 0.000137         | 0.111 91.5%        | (75-125)    | 0.251%   | (20)     | 05/08/08 04:39 |       |
| Post Spike (8050245-PS1)     |          |              |           | QC Source: | PRE0174   | -07 |                  | Extracted:         | 05/07/08 08 | 8:30     |          |                |       |
| Lead                         | EPA 6020 | 0.0924       |           |            | ug/ml     | lx  | 0.000137         | 0.100 92.3%        | (75-125)    |          |          | 05/08/08 04:47 |       |

TestAmerica Portland

Il W. Amil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manager



PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132

ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

Project Number:

TC021SC.080C

Report Created:

Project Manager: Erik Chapman

05/15/08 09:25

# Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B - Laboratory Quality Control Results TestAmerica Portland

| QC Batch: 8050251 | Water F | reparation M | ethod: EP | A 5030B |       |     |                  |              |          |          |          |          |          |       |
|-------------------|---------|--------------|-----------|---------|-------|-----|------------------|--------------|----------|----------|----------|----------|----------|-------|
| analyte           | Method  | Result       | MDL*      | MRL     | Units | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits) | %<br>RPD | (Limits) | Analyzed | Notes |

| Analyte               |                      | Method     | Result    | MDL*  | MRL   | Units        | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limit | s) Analyzed    | Notes |
|-----------------------|----------------------|------------|-----------|-------|-------|--------------|-----|------------------|--------------|----------|-------------|----------|--------|----------------|-------|
| Blank (80502          | 51-BLK1)             |            |           |       |       |              |     |                  | Exti         | acted:   | 05/08/08 07 | 7:00     |        |                |       |
| 1,2-Dibromoethane     |                      | EPA 8260B  | ND        |       | 0.500 | ug/l         | lx  |                  |              |          | -           |          |        | 05/08/08 10:27 |       |
| 1,2-Dichloroethane    |                      | "          | ND        | ***   | 0.500 |              | н   | -                |              |          |             |          | **     |                |       |
| Benzene               |                      |            | ND        |       | 0.200 | 101          | 199 |                  |              |          |             |          |        |                |       |
| Toluene               | 101                  |            | ND        |       | 0.500 |              | *   |                  |              |          |             |          |        |                |       |
| Ethylbenzene          |                      |            | ND        |       | 0.500 |              | **  |                  |              |          |             |          |        |                |       |
| Xylenes (total)       |                      | *          | ND        |       | 1.00  |              |     |                  |              |          |             |          |        |                |       |
| Methyl tert-butyl eth | ner                  | "          | ND        |       | 2.00  |              |     |                  |              |          |             |          |        |                |       |
| Naphthalene           |                      |            | ND        |       | 2.00  |              |     |                  |              |          |             |          |        | •              |       |
| 1,2,4-Trimethylbenz   | ene                  |            | ND        |       | 1.00  |              | **  |                  |              |          |             |          |        |                |       |
| 1,3,5-Trimethylbenz   | ene                  | *          | ND        |       | 0.500 | "            | *   |                  |              |          |             |          |        | •              |       |
| Isopropylbenzene      |                      | *          | ND        |       | 2.00  |              | "   |                  |              |          |             |          |        |                |       |
| n-Propylbenzene       |                      |            | ND        |       | 0.500 | "            | •   |                  |              |          |             |          |        | •              |       |
| Surrogate(s):         | 4-BFB                |            | Recovery: | 105%  | Lim   | its: 80-120% | "   |                  |              |          |             |          |        | 05/08/08 10:27 |       |
|                       | 1,2-DCA-d4           |            |           | 104%  |       | 80-120%      | "   |                  |              |          |             |          |        | "              |       |
|                       | Dibromofluoromethane |            |           | 105%  |       | 80-120%      | "   |                  |              |          |             |          |        | "              |       |
|                       | Toluene-d8           |            |           | 105%  |       | 80-120%      | "   |                  |              |          |             |          |        | "              |       |
| LCS (8050251          | -BS1)                |            |           |       |       |              |     |                  | Extr         | acted:   | 05/08/08 07 | :00      |        |                |       |
| 1,2-Dibromoethane     |                      | EPA 8260B  | 21.7      |       | 0.500 | ug/l         | lx  |                  | 20.0         | 109%     | (80-140)    |          |        | 05/08/08 08:29 |       |
| 1,2-Dichloroethane    |                      |            | 20.5      |       | 0.500 |              |     |                  |              | 103%     | (75-135)    |          |        |                |       |
| Benzene               |                      |            | 21.4      | lere. | 0.200 |              |     |                  |              | 107%     | (80-120)    |          |        |                |       |
| Toluene               |                      |            | 21.9      |       | 0.500 |              | "   |                  |              | 109%     | (80-125)    |          |        |                |       |
| Ethylbenzene          |                      |            | 22.0      |       | 0.500 |              |     |                  | ñ            | 110%     | (80-130)    |          |        |                |       |
| Xylenes (total)       |                      | н          | 63.1      |       | 1.00  |              |     |                  | 60.0         | 105%     | "           |          |        |                |       |
| Methyl tert-butyl eth | er                   | 100        | 20.4      |       | 2.00  |              |     |                  | 20.0         | 102%     | (80-135)    |          |        |                |       |
| Naphthalene           |                      | н          | 20.2      |       | 2.00  |              |     |                  |              | 101%     | (60-150)    |          |        |                |       |
| 1,2,4-Trimethylbenz   | ene                  | 3 <b>H</b> | 21.1      |       | 1.00  |              |     |                  |              | 106%     | (75-125)    |          |        |                |       |
| 1,3,5-Trimethylbenz   | ene                  | и          | 20.9      |       | 0.500 | ñ            |     |                  |              | 105%     | (75-135)    |          |        |                |       |
| Isopropylbenzene      |                      | н          | 21.6      |       | 2.00  | H.           |     |                  |              | 108%     | (80-140)    |          |        | w .            |       |
| n-Propylbenzene       |                      |            | 21.4      |       | 0.500 |              |     |                  |              | 107%     | (80-130)    |          |        |                |       |
| Surrogate(s):         | 4-BFB                |            | Recovery: | 98.4% | Lim   | its: 80-120% | "   |                  |              |          |             |          |        | 05/08/08 08:29 |       |
|                       | 1,2-DCA-d4           |            |           | 98.2% |       | 80-120%      | "   |                  |              |          |             |          |        | "              |       |
|                       | Dibromofluoromethane |            |           | 100%  |       | 80-120%      | n   |                  |              |          |             |          |        | "              |       |
|                       | Toluene-d8           |            |           | 101%  |       | 80-120%      | n   |                  |              |          |             |          |        | "              |       |

TestAmerica Portland

and W. Smil

Darrell Auvil, Project Manager

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

www.testamericainc.com



Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created: 05/15/08 09:25

# Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B - Laboratory Quality Control Results

TestAmerica Portland

| QC Batch: 8050251       | Water P   | reparation | Method: El | PA 5030B |              |     |                  |              |          |             |          |         |                |      |
|-------------------------|-----------|------------|------------|----------|--------------|-----|------------------|--------------|----------|-------------|----------|---------|----------------|------|
| Analyte                 | Method    | Result     | MDL*       | MRL      | Units        | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits | ) Analyzed     | Note |
| LCS Dup (8050251-BSD1)  |           |            |            |          |              |     |                  | Ext          | racted:  | 05/08/08 07 | 7:00     |         |                |      |
| 1,2-Dibromoethane       | EPA 8260B | 23.1       |            | 0.500    | ug/l         | lx  |                  | 20.0         | 115%     | (80-140)    | 6.16%    | (25)    | 05/08/08 08:57 |      |
| 1,2-Dichloroethane      |           | 21.6       |            | 0.500    |              | *   |                  |              | 108%     | (75-135)    | 4.89%    | . "     |                |      |
| Benzene                 | H         | 22.4       |            | 0.200    | эн           |     |                  | 310          | 112%     | (80-120)    | 4.66%    | . "     |                |      |
| Toluene                 | н         | 22.9       |            | 0.500    |              |     |                  |              | 114%     | (80-125)    | 4.56%    | · "     |                |      |
| Ethylbenzene            | **        | 23.7       |            | 0.500    | m.           | H   |                  |              | 118%     | (80-130)    | 7.53%    | 5 "     |                |      |
| Xylenes (total)         | **        | 70.5       |            | 1.00     |              |     |                  | 60.0         | 118%     |             | 11.1%    | . "     |                |      |
| Methyl tert-butyl ether |           | 22.0       |            | 2.00     | "            |     |                  | 20.0         | 110%     | (80-135)    | 7.74%    | . "     |                |      |
| Naphthalene             | н         | 23.0       |            | 2.00     | п            | "   |                  |              | 115%     | (60-150)    | 12.7%    | . "     |                |      |
| ,2,4-Trimethylbenzene   | н         | 24.0       |            | 1.00     |              | "   |                  |              | 120%     | (75-125)    | 12.6%    | . "     | 180            |      |
| ,3,5-Trimethylbenzene   | *         | 24.1       |            | 0.500    | "            | н   |                  | н            | 120%     | (75-135)    | 14.1%    | . "     |                |      |
| sopropylbenzene         | н         | 23.7       |            | 2.00     |              | *   |                  |              | 119%     | (80-140)    | 9.53%    | . "     |                |      |
| n-Propylbenzene         | *         | 24.3       |            | 0.500    |              |     |                  |              | 121%     | (80-130)    | 12.5%    | . "     | . "            |      |
| Surrogate(s): 4-BFB     |           | Recovery:  | 99.2%      | Lim      | its: 80-120% | "   |                  |              |          |             |          |         | 05/08/08 08:57 |      |
| 1,2-DCA-d4              |           |            | 96.7%      |          | 80-120%      | n   |                  |              |          |             |          |         | "              |      |
| Dibromofluoromethane    |           |            | 97.2%      |          | 80-120%      | "   |                  |              |          |             |          |         | "              |      |
| Toluene-d8              |           |            | 98.6%      |          | 80-120%      | n   |                  |              |          |             |          |         | "              |      |

TestAmerica Portland

and W. Smil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manager



9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

0.893% (20)

Bergeson, Boese and Associates-Wilsonville

NCA SOP

78.7

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

% Solids

Project Name:

Tillamook Creamery

78.0

Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 05/15/08 09:25

05/06/08 14:25

Percent Dry Weight (Solids) per Standard Methods - Laboratory Quality Control Results

TestAmerica Portland

QC Batch: 8050210 Other dry Preparation Method: Dry Weight

Analyte Method Result MDL\* MRL Units Dil Source Result Amt REC (Limits) 6% (Limits) Analyzed Notes

Duplicate (8050210-DUP1)

QC Source: PRE0019-02 Extracted: 05/06/08/14:25

0.0100 % by Weight

TestAmerica Portland

Und W. Amil

Darrell Auvil, Project Manager



9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 05/15/08 09:25

#### **Notes and Definitions**

#### Report Specific Notes:

R2 The RPD exceeded the acceptance limit.

RL1 Reporting limit raised due to sample matrix effects.

RL7 Sample required dilution due to high concentrations of target analyte.

ZX Due to sample matrix effects, the surrogate recovery was outside the acceptance limits.

#### **Laboratory Reporting Conventions:**

DET Analyte DETECTED at or above the Reporting Limit. Qualitative Analyses only.

ND Analyte NOT DETECTED at or above the reporting limit (MDL or MRL, as appropriate).

NR/NA Not Reported / Not Available

dry Sample results reported on a Dry Weight Basis. Results and Reporting Limits have been corrected for Percent Dry Weight.

Sample results and reporting limits reported on a Wet Weight Basis (as received). Results with neither 'wet' nor 'dry' are reported wet on a Wet Weight Basis.

RPD RELATIVE PERCENT DIFFERENCE (RPDs calculated using Results, not Percent Recoveries).

MRL METHOD REPORTING LIMIT. Reporting Level at, or above, the lowest level standard of the Calibration Table.

METHOD DETECTION LIMIT. Reporting Level at, or above, the statistically derived limit based on 40CFR, Part 136, Appendix B. MDL\* \*MDLs are listed on the report only if the data has been evaluated below the MRL. Results between the MDL and MRL are reported as Estimated Results

Dil Dilutions are calculated based on deviations from the standard dilution performed for an analysis, and may not represent the dilution found on the analytical raw data.

Reporting -Reporting limits (MDLs and MRLs) are adjusted based on variations in sample preparation amounts, analytical dilutions and Limits percent solids, where applicable.

Electronic - Electronic Signature added in accordance with TestAmerica's Electronic Reporting and Electronic Signatures Policy. Signature Application of electronic signature indicates that the report has been reviewed and approved for release by the laboratory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Test America Portland

and W. Sail

# Test/America

11720 North Creek Pkwy N Suite 400, Bothell, WA 98011-8244

11922 E. First Ave. Spokane, WA 99206-5302

509-924-9200 FAX 924-9290 FAX 906-9210

9405 SW Nimbus Ave, Beaverton, OR 97008-7145 2000 W International Airport Rd Sic A10. Anchorage, AK 99502-4119

907-563-9200 FAX 563-9210

425-420-9200 FAX 420-9210

| CH   | IAIN (      | OF CU  |       | DDY REPO      |                |             |         |       |       | Work O              | rder #:         | PRECO2   | 2            |
|--|-------------|--------|-------|---------------|----------------|-------------|---------|-------|-------|---------------------|-----------------|--|--------------|
| REPORT TO: Bergeson - Boese; Associa   | tes.        | The    | 1411  | INVOICE TO:   | COBURG<br>ATTN | PEN BER     | () E30× |       |       |                     | TURNARO         | OUND REQUEST                                   |              |
| REPORT TO: Bergeson-Base ? Assuc<br>ADDRESS: 25195 SW Parking Ave<br>Wilbury Lie OR 97010<br>PHONE: 573 570-9484 FAX: 503 570-03 | # 20        | 7      |       | P.O. NUMBER:  | /242           | -08-n       | ,       |       |       | STD 7               | Batrolaum H     | organic Analyses  4 3 2 1  ydrocarbon Analyses | < 1          |
| PROJECTNAME: Tillamode Creemen   | 37          |        |       | 1.0.1.0110010 | PRESERV        |             |         |       |       | V                   | 14              | 3 2 1 < 1                                      | 1            |
| PROJECT NUMBER: TOOZ 15C . OBUC  |             |        |       |               |                |             |         |       |       | STO                 | ,               |  | _            |
| 1  |             | 3      | 0 0   |               | REQUESTED      | ANALYSES    |         | Ţ     |       | 0                   | THER Sp         | secify:  |              |
| SAMPLED BY: Et Chapman Rb.   | AA          | 240    | 2 3 3 |               |                |             |         |       |       | * Turnaround        | Requests less t | han standard may incur R                       | ush Charges. |
| CLIENT SAMPLE SAMPLING IDENTIFICATION DATE/TIME  | WWTAA<br>GX | \$ 20% | 203   |               |                |             |         |       |       | MATRIX<br>(W. S. O) | # OF<br>CONT.   | LOCATION /<br>COMMENTS                         | TA<br>WO ID  |
| PI-420 4/29/08 1400  | 4           | *      | X     |               |                |             |         |       |       | W                   | HEA             | 2  |              |
| : P2-H20 1320  | ×           | X      | X     |               |                |             |         |       |       |                     | linun           | -  |              |
| , P3-Hzo /230  | X           | X      | K     |               |                |             |         |       |       |                     | Man             |  |              |
| , P4-H20 1145  | X           | X      | X     |               |                |             |         |       |       |                     | IK for          |  |              |
| 8P5-HZO V 1500   | X           | ×      | X     |               |                |             |         |       |       |                     | MA              |  |              |
| 6  |             |        |       |               |                |             |         |       |       | Ψ                   |                 |  |              |
| 7  |             |        |       |               |                |             |         |       |       |                     |                 |  |              |
| 8  |             |        |       |               |                |             |         |       |       |                     |                 |  |              |
| ,  |             |        |       |               |                |             |         |       |       |                     |                 |  |              |
| 10   |             |        |       |               |                |             |         |       | _     |                     |                 |  | . /          |
| RELEASED BY  |             | -      |       | DATE: 4       | 30/08          | RECEIVED BY | 1       | 90    |       | )                   |                 | DATE: .5                                       |              |
| PRINT NAME: EXIL Chaption FIRM: G  | 3B4         |        |       | DATE: 5       | 200            | PRINT NAME: |         | 5     |       | FIRM:               | TA              |  |              |
| PRINT NAME: ENC CHAPMAN FIRM: 6 RELEASED BY: PRINT NAME: BUT FIRM: TO  | 10          |        |       | TIME: 10      | 108            | PRINT NAME: | 7-      | 'J    | thel- | FIRM                | 7918            | DATE:  | 10:30        |
| ADDITIONAL REMARKS: TAL-1000 0907  |             |        |       | 16.           | 70             |             |         | , , , |       |                     |                 | TEMP:  | . 16         |

# Test/merica

11720 North Creek Pkwy N Suite 400, Bothell, WA 98011-8244 11922 E. First Ave, Spokane, WA 99206-5302

9405 SW Nimbus Ave. Beaverton, OR 97008-7145

503-906-9200 FAX 906-9210 907-563-9200 FAX 563-9210

425-420-9200 FAX 420-9210

509-924-9200 FAX 924-9290

2000 W International Airport Rd Ste A10, Anchorage, AK 99502-1119 907-563-9200

**CHAIN OF CUSTODY REPORT** Work Order #: 1250022 REPORT TO: Bergesn-Bosse; Assertifes, FAL

REPORT TO: Bergesn-Bosse; Asser Echennyan

ADDRESS:

25,95 Ser Parkway Arx # 201

W. LSONDOLLY OR 97070

PHONE (50) 570-9484 FAX: (503) 570-0384

PROJECT NAME: Teligrapore Creaming INVOICE TO: COSURI, OFFEE TURNAROUND REQUEST ATTN Con Buggson in Business Days \* Organic & Inorganic Analyses 5 4 3 2 1 <1
Petroleum Hydrocarbon Analyses P.O. NUMBER: 1242-08-W 3 2 1 < 1 PRESERVATIVE PROJECT NUMBER: TOO'Z ISC. EBUC OTHER REQUESTED ANALYSES Turnaround Requests less than standard may incur Rush Charge SAMPLED BY: E diapuan MATRIX # OF LOCATION TA SAMPLING CLIENT SAMPLE COMMENTS WO ID (W. S. O) CONT DATE/TIME IDENTIFICATION P1 @ 3.5" 1338 1342 , Ple 8,5' 1344 Plen 1348 1350 Ple15.5' 1352 , PZ@4.5' 1252 12.55 1305 1310 DATE: 4/30/08 RECEIVED BY: PRINT NAME: PRINT NAME: RELEASED BY PRINT NAME: ADDITIONAL REMARKS: TAL-1000 0907

# Test/America

11720 North Creek Pkwy N Suite 400, Bothell, WA 98011-8244

425-420-9200 FAX 420-9210 509-924-9200 FAX 924-9290 11922 E. First Ave. Spokane. WA 99206-5302 503-906-9200 FAX 906-9210 9405 SW Nimbus Ave, Beaverton, OR 97008-7145 2000 W. International Airport Rd Ste A10, Anchorage, AK 99502-1119 907-563-9200 FAX 563-9210

|                                    |                     | CHA       | AIN OF CUS  | TODY RE   | PORT .   |             |      |       | Work O       | rder #: | PREDOZ                          | 2            |
|------------------------------------|---------------------|-----------|---|-----------|----------|-------------|------|-------|--------------|---------|---------------------------------|--------------|
| REPORT TO: Berger ADDRESS: 25,95 S | n - Boise ;         | ASSEX 100 | fee, Fre  | INVOICE T | O: COSUR | i, offee    |      |       |              |         | OUND REQUEST                    |              |
| PERCETTO: BALLER                   | -Boese 5            | of rice   | E chizana   | res .     | ATEN .   | Cor Buzz    | sn   |       |              | in F    | Business Days *                 |              |
| ADDRESS:                           | in Parkewy          | By ±      | 2007  | '         |          |             |      |       |              |         | norganic Analyses               | -1: -1       |
| (50 mill                           | 1 UR 970.           | 10        |   |           |          |             |      |       | 7            | 5       | 4 3 2 1<br>Hydrocarbon Analyses | < 1          |
| PHONE (503) 570 - 9487             | FAX: GD37 S         | 120-038   | 7   | P.O. NUMB | ER: 1242 | -08-W       |      |       | - " K        |         | 3 2 1 <                         | ิ อ          |
| PROJECT NAME: Telien               | rock treame         | ng        |   |           | PRESE    | RVATIVE     |      | T     | STL          |         |                                 | ت            |
| PROJECT NUMBER: TCO'2              | ISC DBUC            | 0         |   |           |          | ED ANALYSES |      |       |              | THER    | Specify:                        |              |
|                                    |                     | 1         | - 21  |           | KEQUESTE | D ANACISCS  | T    |       | • Turnaround |         | than standard may incur         | Rush Charges |
| SAMPLED BY: E Change               |                     |           | 353   |           |          |             |      |       | MATRIX       | # OF    | LOCATION                        | TA           |
| CLIENT SAMPLE IDENTIFICATION       | SAMPLII<br>DATE/TII | ME ,      | 200 X |           |          |             |      |       | (W, S. O)    | CONT.   | COMMENTS                        | WO ID        |
| P2@15.5°                           | 4/29/08             | 1312      | X   |           |          |             |      |       | 5            | 1       |                                 |              |
| , PZ@ 18'                          | i                   | 1315      |   |           |          |             |      |       | 1            | -       |                                 |              |
| 1930 3'                            |                     | 1205      |   |           |          |             |      |       |              |         |                                 |              |
| P3Q 4.5°                           |                     | 1210      |   |           |          |             |      |       |              |         |                                 |              |
| , P3e6'                            |                     | 1214      |   |           |          |             |      |       |              |         |                                 |              |
| , P308'                            |                     | 1216      |   |           |          |             |      |       |              |         |                                 | _            |
| 1 P3011.8'                         |                     | 1220      | X   |           |          |             |      |       |              |         |                                 |              |
| 8 P4 @ 3'                          |                     | 1120      |   |           |          |             |      |       |              | 111     |                                 | _            |
| , P4065'                           |                     | 1124      |   |           |          |             |      |       | 1            |         |                                 | _            |
| 10 PU Q \$51                       | V                   | 1130      |   |           | W2-100   |             |      |       | 40           | W       | DATES                           | 11/08        |
| RELEASED BY.                       |                     | D         | Ca.   |           | 13008    | RECEIVED B  | -0.1 | F     | FIRM         | 7,91    | O TIME:9                        | 1-50         |
| PRINT NAME: ENC Cha                | pman                | FIRM: 5   | BA  | DATE: =   | 11/08    | RECEIVED B  | 1    | 1.00- | _            | 10/     | DATE: S                         | 1.55         |
| PRINT NAME:                        |                     | FIRM: T   | 40  | TIME: 1   |          | PRINT NAME  | /    | eland | FIRM         | ST      | TIME:                           | 0:30         |
| ADDITIONAL REMARKS                 |                     |           | 11  | :         |          |             |      | ,     |              | ي ع     | TEMP:                           | 30F/         |
| [IAL-TOWN (PA)]                    |                     |           |   | 10        |          |             |      |       |              |         | 5.9                             |              |

# Test/America

11720 North Creek Pkwy N Suite 400, Bothell, WA 98011-8244 11922 E. First Ave, Spokane, WA 99206-5302

9405 SW Nimbus Ave, Beaverton, OR 97008-7145 2000 W. International Airport Rd Ste A10, Anchorage, AK 99502-1119 425-420-9200 FAX 420-9210 509-924-9200 FAX 924-9290 FAX 906-9210

907-563-9200 FAX 563-9210


J 5.9

|                                     |                       | HAIN OF CUSTO                            |             |           |           |         |         |     | Work O              | rder #:       | TREODE   | 22                       |
|-------------------------------------|-----------------------|--|-------------|-----------|-----------|---------|---------|-----|---------------------|---------------|--|--------------------------|
| REPORT TO: Bergern ADDRESS: 25,45 5 | - Bouse & ASSEXI      | infex, FAC                               | INVOICE TO  | ATTA L    | OFFEE     | 1       |         |     |                     |               | OUND REQUES  |                          |
| REPORT TO: Bergeson                 | -Bouse & Assec.       | Echizonay                                |             | ATTA L    | or Sug    | -sn     |         | 1   |                     | in B          | Business Days *  |                          |
| ADDRESS: 25 5                       | in Parkeway our       | # 7007                                   |             |           |           |         |         | 1   |                     |               | norganic Analyses  |                          |
| w. Usomuille                        | OR 97070              |  |             |           |           |         |         |     | 7                   |               | 4 3 2  | 1 <1                     |
| PHONE (503) 570 -9481               | FAX. (503) 570-03     | 87                                       | P.O. NUMBER | 1242-     |           |         |         |     | N.                  |               | lydrocarbon Analyses   |                          |
| PROJECT NAME: Telian                | al Creamens           | <u> </u>                                 | 1           | PRESERV   | ATIVE     |         | T       |     | STD                 | المناط        | 3 2 1  | <1                       |
| PROJECT NUMBER: TCO2 1              | SC. DEUC              |  |             | REQUESTED | ANALVSES  |         |         | 1   | O                   | THER S        | specify:   |                          |
| SAMPLED BY: E CARP                  |                       | * #                                      |             | REQUESTED | AIVALTSES |         | T       | T . |                     |               | than standard may incu   | er Rush Charge           |
| CLIENT SAMPLE IDENTIFICATION        | SAMPLING<br>DATE/TIME | 100 A 65 A |             |           |           |         |         |     | MATRIX<br>(W, S, O) | # OF<br>CONT. | LOCATION (   | TA<br>WO ID              |
| PYEILS!                             | 4/29/08 1140          |  |             |           |           |         |         |     | 5                   | 1             |  |                          |
| 2 PY 0 14.5'                        | 1/45                  | - X                                      |             |           |           |         |         |     |                     |               |  |                          |
| PSG B.S'                            | 1437                  |  |             |           |           |         |         |     |                     |               |  |                          |
| 1 P50 10.5"                         | 1440                  |  |             |           |           |         |         |     |                     | W             |  |                          |
| P5@ 15.5'                           | 1445                  | X  |             |           |           |         |         |     |                     | 2             |  | _                        |
| 6                                   |                       |  |             |           |           |         |         |     |                     | 1             |  |                          |
| 7                                   |                       |  |             |           |           |         |         |     | _                   |               |  | And a place of the place |
| 8                                   |                       |  |             |           |           |         |         |     | -                   |               | April 1990 Marie Control of the Cont |                          |
| 9                                   |                       |  |             |           |           |         |         |     | V                   | 4             |  |                          |
| RELEASED BY:                        | 2                     |  | DATE: 4     | 2/08      | RECEIVED  | BY 1360 | 19      |     |                     |               | DATE:  | 5/1/0                    |
| PRINT NAME: EN Chan                 | PARKIN FIRM:          | BGA                                      |             |           | PRINT NAM |         | F       |     | FIRM:               | TAF           | 2 TIME:  | 7.5                      |
| RELEASED BY: But                    |                       | _1 0                                     | DATE: 5     | 11/08     | RECEIVED  | BY Jam  | rejains | el  |                     | TAR           | DATE:  | 3/1/08                   |
| PRINT NAME: Boh                     | FIRM: /               | 41                                       | TIME:       |           | PRINT NAM | T. J.   | reland  |     | FIRM:               | 11/1          | TIME: TEMP:  | 10:30                    |
| ADDITIONAL REMARKS:                 |                       | 2  |             |           |           |         |         |     |                     |               | 3. O PAG   | GE 40F 4                 |

TestAmerica Sample Receipt Checklist Received by: Unpacked by: Work Order No. TRE0022 Logged-in by: "(section A) '(section B) Client: BBA Date: 5/1 Project: Tillamook Creamery Initials BLE Temperature out of range: Not enough Ice \*\*\*ESI Clients (see Section C) No Ice Ice Melled Cooler Temperature (IR): 5 9 C plastic glass NA (oil/air samples, ESI client) W/in 4 Hours Temperature Blank: \_\_\_\_\_ C Custody Seals: (# ) B Sample Status: Signature: Y N Dated (If N circled, see NOD) Received from: ✓ None XTA Courier General: Container Type: Intact? Senvoy N 2 #Cooler(s) UPS # Containers Match COC? N, none given #Box(s) Fed Ex None ( #Other: IDs Match COC? Client For Analyses Requested: TDP Coolant Type: Correct Type & Preservation? N DHL Gelice Adequate Volume? SDS N Loose Ice Mid-Valley None Within Hold Time? N GS/TA Volatiles/ Oil Quality: Packing Material: GS/Senvoy VOAs/ Syringes free of Headspace? NA \_Bubble Bags Other: TB on COC? not provided Ν Styrofoam Cubbies NA Metals: None ( Other: HNO3 Preserved? NA Dissolved Metals Filtered? NA \*ESI Clients Only: FED EX/ UPS: Was the tracking paper keepable? NO Temperature Blank: C not provided If circled NO, what is the Tracking number? All preserved bottles checked NA (voas/soils/all unp.) FED EX Goldstreak **UPS** Other: All preserved accordingly? DHL Y N (see NOD) NA (voas/soils/all unp.) Project Managers: Comments:

(Initial/Date)

PM Reviewed:





PORTLAND, OR 9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132

ph: (503) 906.9200 fax: (503) 906.9210

April 17, 2008

Erik Chapman Bergeson, Boese and Associates-Wilsonville 25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

RE: Tillamook Creamery

Enclosed are the results of analyses for samples received by the laboratory on 04/01/08 15:02. The following list is a summary of the Work Orders contained in this report, generated on 04/17/08 13:02.

If you have any questions concerning this report, please feel free to contact me.

Work OrderProjectProjectNumberPRD0028Tillamook CreameryTC021SC.080C

TestAmerica Portland

hall W. Amil

Darrell Auvil, Project Manager





9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132

ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070 Project Number:

TC021SC.080C

Report Created:

Project Manager:

Erik Chapman

04/17/08 13:02

### ANALYTICAL REPORT FOR SAMPLES

| Sample ID   | Laboratory ID | Matrix | Date Sampled   | Date Received  |
|-------------|---------------|--------|----------------|----------------|
| EW@4.6'     | PRD0028-04    | Soil   | 04/01/08 10:15 | 04/01/08 15:02 |
| WW@4.6'     | PRD0028-06    | Soil   | 04/01/08 10:17 | 04/01/08 15:02 |
| NFLOOR@7.5' | PRD0028-09    | Soil   | 04/01/08 12:10 | 04/01/08 15:02 |
| TC-WATER    | PRD0028-10    | Water  | 04/01/08 12:00 | 04/01/08 15:02 |

TestAmerica Portland

and W. Smil

Darrell Auvil, Project Manager





9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

THE LEADER IN ENVIRONMENTAL TESTING

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 04/17/08 13:02

### Hydrocarbon Identification per NW-TPH Methodology

TestAmerica Portland

| Analyte                          | Method     | Result | MDL*  | MRL   | Units      | Dil      | Batch       | Prepared       | Analyzed       | Notes |
|----------------------------------|------------|--------|-------|-------|------------|----------|-------------|----------------|----------------|-------|
| PRD0028-04 (EW@4.6')             |            | Soi    | 1     |       | Sampl      | ed: 04/0 | 01/08 10:15 |                |                |       |
| Gasoline Range Hydrocarbons      | NWTPH HCID | ND     |       | 30.4  | mg/kg dry  | lx       | 8040083     | 04/02/08 16:25 | 04/02/08 21:32 |       |
| Diesel Range Hydrocarbons        | и.         | ND     |       | 75.9  |            | 100      | 111         | 111            |                |       |
| Heavy Oil Range Hydrocarbons     | W I        | ND     |       | 152   | "          | **       | "           | н              | n              |       |
| Surrogate(s): 1-Chlorooctadecane |            | _      | 91.2% |       | 50 - 150 % | "        |             |                | "              |       |
| PRD0028-06 (WW@4.6')             | и          | Soi    | l     |       | Sampl      | ed: 04/0 | 01/08 10:17 |                |                |       |
| Gasoline Range Hydrocarbons      | NWTPH HCID | ND     |       | 31.1  | mg/kg dry  | 1x       | 8040083     | 04/02/08 16:25 | 04/02/08 22:01 |       |
| Diesel Range Hydrocarbons        |            | ND     |       | 77.8  |            |          | н           |                |                |       |
| Heavy Oil Range Hydrocarbons     |            | ND     |       | 156   | *          | n        | н           | *              | "              |       |
| Surrogate(s): 1-Chlorooctadecane |            |        | 91.2% |       | 50 - 150 % | "        |             |                | "              |       |
| PRD0028-09 (NFLOOR@7.5')         |            | Soi    | l     |       | Sampl      | ed: 04/0 | 01/08 12:10 |                |                |       |
| Gasoline Range Hydrocarbons      | NWTPH HCID | ND     |       | 29.7  | mg/kg dry  | lx       | 8040083     | 04/02/08 16:25 | 04/02/08 22:30 |       |
| Diesel Range Hydrocarbons        | и.         | ND     |       | 74.2  |            |          |             |                |                |       |
| Heavy Oil Range Hydrocarbons     | *          | ND     |       | 148   |            | н        |             |                | н              |       |
| Surrogate(s): 1-Chlorooctadecane |            |        | 94.9% |       | 50 - 150 % | "        |             |                | "              |       |
| PRD0028-10 (TC-WATER)            |            | Wa     | iter  |       | Sampl      | ed: 04/0 | 01/08 12:00 |                | 8              |       |
| Gasoline Range Hydrocarbons      | NWTPH HCID | DET    |       | 0.238 | mg/l       | lx       | 8040170     | 04/04/08 13:50 | 04/06/08 11:29 |       |
| Diesel Range Hydrocarbons        | *          | ND     |       | 0.600 | "          |          |             | 200            | w e            |       |
| Heavy Oil Range Hydrocarbons     | *          | ND     |       | 0.600 |            |          |             |                | и.             |       |
| Surrogate(s): 1-Chlorooctadecane |            |        | 105%  |       | 50 - 150 % | "        |             |                | n              |       |

TestAmerica Portland

hall W. Sail





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created:

04/17/08 13:02

### Gasoline Hydrocarbons per NW TPH-Gx Method

TestAmerica Portland

| Analyte                     | Method    | Result                       | MDL*  | MRL  | Units      | Dil      | Batch      | Prepared       | Analyzed       | Notes |
|-----------------------------|-----------|------------------------------|-------|------|------------|----------|------------|----------------|----------------|-------|
| PRD0028-04 (EW@4.6')        |           | Soil                         |       |      | Sampl      | ed: 04/0 | 1/08 10:15 |                |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND                           |       | 3.29 | mg/kg dry  | lx       | 8040217    | 04/07/08 14:30 | 04/08/08 11:03 |       |
| Surrogate(s): a,a,a-TFT     |           |                              | 73.1% |      | 50 - 150 % | "        |            |                | "              |       |
| PRD0028-06 (WW@4.6')        |           | Soil                         |       |      | Sampl      | ed: 04/0 | 1/08 10:17 |                |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND                           |       | 3.16 | mg/kg dry  | lx       | 8040217    | 04/07/08 14:30 | 04/08/08 11:31 |       |
| Surrogate(s): a,a,a-TFT     |           |                              | 78.1% |      | 50 - 150 % | "        |            |                | "              |       |
| PRD0028-09 (NFLOOR@7.5')    |           | Soil Sampled: 04/01/08 12:10 |       |      |            |          |            |                |                |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | 5.03                         |       | 3.08 | mg/kg dry  | lx       | 8040217    | 04/07/08 14:30 | 04/08/08 11:58 |       |
| Surrogate(s): a,a,a-TFT     |           |                              | 76.6% |      | 50 - 150 % | "        |            |                | "              |       |

TestAmerica Portland

el W. Amil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manager





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070 Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 04/17/08 13:02

### BTEX per EPA Method 8021B

TestAmerica Portland

|                 |                 |           |        | 7 000 11110 | 1100 1 01 |            |          |             |                |                |       |
|-----------------|-----------------|-----------|--------|-------------|-----------|------------|----------|-------------|----------------|----------------|-------|
| Analyte         |                 | Method    | Result | MDL*        | MRL       | Units      | Dil      | Batch       | Prepared       | Analyzed       | Notes |
| PRD0028-04      | (EW@4.6')       |           | Soi    | l           |           | Sampl      | ed: 04/0 | 01/08 10:15 |                |                |       |
| Benzene         |                 | EPA 8021B | ND     |             | 0.0411    | mg/kg dry  | lx       | 8040217     | 04/07/08 14:30 | 04/08/08 11:03 |       |
| Toluene         |                 | <u>n</u>  | ND     |             | 0.0822    | "          |          | ·           |                |                |       |
| Ethylbenzene    |                 | *         | ND     |             | 0.0822    |            |          |             |                | "              |       |
| Xylenes (total) |                 | H         | ND     |             | 0.164     | ii.        |          |             | н              | "              |       |
| m,p-Xylene      |                 | *         | 0.118  |             | 0.0822    | : 11       | **       | ï           | "              | "              |       |
| o-Xylene        |                 | W1        | ND     |             | 0.0822    | <u>n</u>   |          | "           | *              |                |       |
| Surrogate(s):   | 4-BFB (PID)     |           | _      |             |           | 70 - 130 % | "        |             |                | "              |       |
|                 | a,a,a-TFT (PID) |           |        | 77.0%       |           | 60 - 130 % | "        |             |                | "              |       |
| PRD0028-06      | (WW@4.6')       |           | Soi    | l           |           | Sampl      | ed: 04/0 | 01/08 10:17 |                |                |       |
| Benzene         |                 | EPA 8021B | ND     |             | 0.0395    | mg/kg dry  | lx       | 8040217     | 04/07/08 14:30 | 04/08/08 11:31 | λ.    |
| Toluene         |                 |           | ND     |             | 0.0790    |            |          |             |                | **             |       |
| Ethylbenzene    |                 | "         | ND     |             | 0.0790    |            |          | N.          | н              |                |       |
| Xylenes (total) |                 | •         | ND     |             | 0.158     | "          |          | 2           |                | <b>y</b> -     |       |
| m,p-Xylene      |                 |           | ND     |             | 0.0790    | "          |          |             | *              | *              |       |
| o-Xylene        |                 |           | , ND   |             | 0.0790    | ű.         |          | *           | **             | "              |       |
| Surrogate(s):   | 4-BFB (PID)     |           |        |             |           | 70 - 130 % | "        |             |                | n              |       |
|                 | a,a,a-TFT (PID) |           |        | 81.2%       |           | 60 - 130 % | n        |             |                | "              |       |
| PRD0028-09      | (NFLOOR@7.5')   | ž.        | Soi    | l           |           | Sampl      | ed: 04/0 | 01/08 12:10 |                |                |       |
| Benzene         | 2               | EPA 8021B | 0.110  |             | 0.0385    | mg/kg dry  | lx       | 8040217     | 04/07/08 14:30 | 04/08/08 11:58 |       |
| Гoluene         |                 |           | 0.173  |             | 0.0769    |            |          |             | 10             |                |       |
| Ethylbenzene    |                 | •         | ND     |             | 0.0769    |            |          | н           |                |                |       |
| Kylenes (total) |                 |           | 0.296  |             | 0.154     | ,,         |          | "           |                | v              |       |
| n,p-Xylene      |                 | и         | 0.205  |             | 0.0769    |            |          | н           | n              | *              |       |
| o-Xylene        |                 |           | 0.0912 |             | 0.0769    |            |          | "           | , 11           |                |       |
| 0 (1            | 4-BFB (PID)     |           |        |             |           | 70 - 130 % | ,,       |             |                | "              |       |
| Surrogate(s):   | 7-DID (11D)     |           |        |             |           | ,0 100 /0  |          |             |                |                |       |

TestAmerica Portland

and W. Amil

Darrell Auvil, Project Manager





Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR 9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Tillamook Creamery Project Name:

Project Number: TC021SC.080C

Erik Chapman Project Manager:

Report Created: 04/17/08 13:02

### Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B

TestAmerica Portland

| Analyte                 | Method    | Result | MDL*  | MRL  | Units      | Dil        | Batch      | Prepared       | Analyzed       | Notes |
|-------------------------|-----------|--------|-------|------|------------|------------|------------|----------------|----------------|-------|
| PRD0028-10 (TC-WATER)   |           | Wa     | iter  |      | Samp       | oled: 04/0 | 1/08 12:00 |                |                | RL7   |
| 1,2-Dibromoethane       | EPA 8260B | ND     |       | 50.0 | ug/l       | 100x       | 8040320    | 04/09/08 08:00 | 04/09/08 16:07 |       |
| 1,2-Dichloroethane      |           | ND     |       | 50.0 | ü          | н          |            |                | ,              |       |
| Benzene                 |           | 2700   |       | 20.0 | ,          | н          | "          | "              | n              |       |
| Toluene                 |           | 5460   |       | 50.0 | "          | H          |            | "              |                |       |
| Ethylbenzene            | W         | 736    |       | 50.0 |            |            |            | и              |                |       |
| Xylenes (total)         |           | 3520   |       | 100  |            | н          |            | н              |                |       |
| Methyl tert-butyl ether |           | ND     |       | 200  |            | n          | "          |                |                |       |
| Naphthalene             | н         | ND     |       | 200  |            | "          |            |                |                |       |
| 1,2,4-Trimethylbenzene  | "         | 538    |       | 100  | ,,         | **         | "          | **             | и.             |       |
| 1,3,5-Trimethylbenzene  |           | 135    |       | 50.0 | "          |            |            | w              | w."            |       |
| Isopropylbenzene        | н:        | ND     |       | 200  |            |            | "          |                | ,,             |       |
| n-Propylbenzene         | "         | 98.0   |       | 50.0 | "          |            |            | •              | ,,             |       |
| Surrogate(s): 4-BFB     |           |        | 92.8% |      | 80 - 120 % | 1x         |            |                | "              |       |
| 1,2-DCA-d4              |           |        | 101%  |      | 80 - 120 % | "          |            |                | n              |       |
| Dibromofluoromen        | hane      |        | 95.8% |      | 80 - 120 % | "          |            |                | "              |       |
| Toluene-d8              |           |        | 97.6% |      | 80 - 120 % | "          |            |                | "              |       |

TestAmerica Portland

had W. Amil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manager





Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 04/17/08 13:02

Polynuclear Aromatic Compounds per EPA 8270M-SIM

TestAmerica Portland

| Analyte              |                      | Method    | Result | MDL*  | MRL    | Units      | Dil      | Batch      | Prepared       | Analyzed       | Notes       |
|----------------------|----------------------|-----------|--------|-------|--------|------------|----------|------------|----------------|----------------|-------------|
| PRD0028-10           | (TC-WATER)           |           | Wa     | ter   |        | Sampl      | ed: 04/0 | 1/08 12:00 |                |                | at a second |
| Acenaphthene         |                      | EPA 8270m | 0.535  |       | 0.0952 | ug/l       | lx       | 8040088    | 04/02/08 17:50 | 04/03/08 23:34 |             |
| Acenaphthylene       | *                    |           | ND     |       | 0.571  | "          |          | ne         |                |                | RL1         |
| Anthracene           |                      | н         | 0.299  |       | 0.0952 |            |          | и.         |                | "              |             |
| Benzo (a) anthrace   | ne                   |           | 0.249  |       | 0.0952 | "          | "        | п          |                | "              |             |
| Benzo (a) pyrene     |                      | "         | ND     |       | 0.0952 |            | **       |            | n              | "              |             |
| Benzo (b) fluoranth  | ene                  |           | ND     |       | 0.0952 |            |          | "          | н              | H              |             |
| Benzo (ghi) peryler  | ne                   |           | 0.101  |       | 0.0952 | "          | 11       |            | "              | n              |             |
| Benzo (k) fluoranth  | ene                  |           | ND     |       | 0.0952 |            | n        | "          | н              |                |             |
| Chrysene             |                      |           | 0.187  |       | 0.0952 | н          |          | "          |                | *              |             |
| Dibenzo (a,h) anthra | acene                | n .       | ND     |       | 0.190  | 11         |          |            | н              |                |             |
| Fluoranthene         |                      |           | 0.503  |       | 0.0952 | "          | н        |            | н              |                |             |
| Fluorene             |                      |           | 0.886  |       | 0.0952 | н          | "        |            |                | "              |             |
| Indeno (1,2,3-cd) py | yrene                |           | ND     |       | 0.0952 | "          |          |            |                |                |             |
| Naphthalene          |                      |           | 249    |       | 4.76   |            | 50x      |            | , m            | 04/05/08 22:55 |             |
| Phenanthrene         |                      |           | 1.88   |       | 0.0952 |            | 1x       | "          | 18             | 04/03/08 23:34 |             |
| Pyrene               |                      | н         | 0.296  |       | 0.0952 |            |          | "          | н              | н              |             |
| Surrogate(s):        | Fluorene-d10         |           |        | 73.5% |        | 25 - 125 % | "        |            |                | n .            |             |
|                      | Pyrene-d10           |           |        | 55.4% |        | 23 - 150 % | "        |            |                | "              |             |
|                      | Benzo (a) pyrene-d12 |           |        | 34.8% |        | 10 - 125 % | "        |            |                | "              |             |

TestAmerica Portland

hall W. Amil

Darrell Auvil, Project Manager





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created:

04/17/08 13:02

### Percent Dry Weight (Solids) per Standard Methods

TestAmerica Portland

| Analyte    |               | Method  | Result | MDL* | MRL    | Units          | Dil       | Batch      | Prepared       | Analyzed       | Notes |
|------------|---------------|---------|--------|------|--------|----------------|-----------|------------|----------------|----------------|-------|
| PRD0028-04 | (EW@4.6')     |         | Soil   |      |        | Samp           | led: 04/0 | 1/08 10:15 |                |                |       |
| % Solids   |               | NCA SOP | 59.9   |      | 0.0100 | % by<br>Weight | 1x        | 8040263    | 04/07/08 16:07 | 04/07/08 16:07 |       |
| PRD0028-06 | (WW@4.6')     |         | Soil   | *    |        | Samp           | led: 04/0 | 1/08 10:17 |                |                |       |
| % Solids   |               | NCA SOP | 61.4   |      | 0.0100 | % by<br>Weight | lx        | 8040263    | 04/07/08 16:07 | 04/07/08 16:07 |       |
| PRD0028-09 | (NFLOOR@7.5') |         | Soil   |      |        | Samp           | led: 04/0 | 1/08 12:10 |                |                |       |
| % Solids   |               | NCA SOP | 64.9   |      | 0.0100 | % by<br>Weight | lx        | 8040263    | 04/07/08 16:07 | 04/07/08 16:07 |       |

TestAmerica Portland

and W. Sail





9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070 Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 04/17/08 13:02

Gasoline Hydrocarbons by NWTPH-Gx and BTEX by EPA Method 8021B

TestAmerica Spokane

| Analyte                     | Method            | Result | MDL* | MRL  | Units      | Dil       | Batch      | Prepared       | Analyzed       | Notes |
|-----------------------------|-------------------|--------|------|------|------------|-----------|------------|----------------|----------------|-------|
| PRD0028-10 (TC-WATER)       |                   | Wa     | ter  |      | Sampl      | led: 04/0 | 1/08 12:00 |                |                |       |
| Gasoline Range Hydrocarbons | NWTPH-G/8021<br>B | 31300  | 1    | 1000 | ug/l       | 10x       | 8040081    | 04/11/08 12:00 | 04/14/08 14:54 |       |
| Surrogate(s): 4-BFB (FID)   |                   |        | 138% |      | 36 - 150 % | lx        |            |                | "              |       |

TestAmerica Portland

and W. Sail

Darrell Auvil, Project Manager





Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 04/17/08 13:02

### Hydrocarbon Identification per NW-TPH Methodology - Laboratory Quality Control Results

TestAmerica Portland

| QC Batch: 8040083                | Soil Pre      | eparation M | ethod: EP. | A 3550 Fu | els           |     |                  |              |          |             |          |         |                |       |
|----------------------------------|---------------|-------------|------------|-----------|---------------|-----|------------------|--------------|----------|-------------|----------|---------|----------------|-------|
| Analyte                          | Method        | Result      | MDL*       | MRL       | Units         | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits | ) Analyzed     | Notes |
| Blank (8040083-BLK1)             |               |             |            |           |               |     |                  | Extr         | acted:   | 04/02/08 16 | :25      |         |                |       |
| Gasoline Range Hydrocarbons      | NWTPH<br>HCID | ND          |            | 20.0      | mg/kg wet     | lx  |                  |              |          |             |          |         | 04/02/08 18:39 |       |
| Diesel Range Hydrocarbons        | "             | ND          | ()         | 50.0      | н             | "   |                  |              |          |             |          |         |                |       |
| Heavy Oil Range Hydrocarbons     | н             | ND          |            | 100       |               |     |                  |              |          |             |          | -       | н              |       |
| Surrogate(s): 1-Chlorooctadecane |               | Recovery:   | 104%       | L         | mits: 50-150% | "   |                  |              |          |             |          |         | 04/02/08 18:39 | -     |
| Duplicate (8040083-DUP1)         |               |             |            | QC Source | e: PRC0900-0  | 1   | ,                | Extr         | acted:   | 04/02/08 16 | 5:25     |         |                |       |
| Gasoline Range Hydrocarbons      | NWTPH<br>HCID | ND          |            | 23.7      | mg/kg dry     | lx  | ND               | =            |          |             | NR       | (50)    | 04/02/08 19:08 |       |
| Diesel Range Hydrocarbons        | н             | ND          |            | 59.2      |               |     | ND               |              |          |             | NR       |         | •              |       |
| Heavy Oil Range Hydrocarbons     |               | ND          |            | 118       |               |     | ND               |              |          |             | NR       | "       | "              |       |
| Surrogate(s): 1-Chlorooctadecane |               | Recovery:   | 96.3%      | L         | mits: 50-150% | "   |                  |              |          |             |          |         | 04/02/08 19:08 |       |

| QC Batch: 8040170                | Water 1       | Preparation M | ethod: EP | A 3510 F | uels          |     |                  |              |          |             |          |          |                |       |
|----------------------------------|---------------|---------------|-----------|----------|---------------|-----|------------------|--------------|----------|-------------|----------|----------|----------------|-------|
| Analyte                          | Method        | Result        | MDL*      | MRL      | Units         | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits) | Analyzed       | Notes |
| Blank (8040170-BLK1)             |               |               |           |          |               |     |                  | Extr         | acted:   | 04/04/08 13 | 3:50     |          |                |       |
| Gasoline Range Hydrocarbons      | NWTPH<br>HCID | ND            |           | 0.125    | mg/l          | lx  |                  |              |          |             |          | -        | 04/06/08 11:01 |       |
| Diesel Range Hydrocarbons        |               | ND            |           | 0.315    | 3 M           | н   |                  |              |          |             |          |          | н              |       |
| Heavy Oil Range Hydrocarbons     |               | ND            |           | 0.315    |               |     |                  |              | -        |             |          |          |                |       |
| Surrogate(s): 1-Chlorooctadecane |               | Recovery: 82  | .5%       | Lin      | nits: 50-150% | 6 " |                  |              |          |             |          |          | 04/06/08 11:01 |       |

TestAmerica Portland

and W. Smil





9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

QC Batch: 8040217

Project Name:

Tillamook Creamery

Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 04/17/08 13:02

Gasoline Hydrocarbons per NW TPH-Gx Method - Laboratory Quality Control Results

TestAmerica Portland

AK101 Prep

Soil Preparation Method:

| Analyte                     | Method    | Result    | MDL*   | MRL  | Units         | Dil | Source<br>Result | Spike<br>Amt | %<br>REC |             | %<br>RPD | (Limit | s) Analyzed    | Notes |
|-----------------------------|-----------|-----------|--|------|---------------|-----|------------------|--------------|----------|-------------|----------|--------|----------------|-------|
| Blank (8040217-BLK1)        |           |           |  |      |               |     |                  | Extr         | acted:   | 04/07/08 14 | 4:30     |        | 9              |       |
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND        |  | 1.94 | mg/kg wet     | lx  |                  |              |          |             |          |        | 04/07/08 22:57 |       |
| Surrogate(s): a,a,a-TFT     | 2         | Recovery: | 103%   | Li   | mits: 50-150% | "   |                  |              |          |             |          |        | 04/07/08 22:57 |       |
| LCS (8040217-BS1)           |           |           | To the state of th |      |               |     |                  | Extr         | acted:   | 04/07/08 14 | 4:30     |        |                |       |
| a,a,a-TFT                   |           |           | 103%   |      | 50-150%       | lx  |                  |              |          |             |          |        | 04/07/08 22:02 |       |

| LCS (8040217-BS2)           |           |              |     |                |       | Ext      | racted: | 04/07/08 14: | 30 |                    |  |
|-----------------------------|-----------|--------------|-----|----------------|-------|----------|---------|--------------|----|--------------------|--|
| Gasoline Range Hydrocarbons | NW TPH-Gx | 22.6         |     | 3.78 mg/kg wet | lx    | <br>23.6 | 95.5%   | (70-130)     |    | <br>04/07/08 22:30 |  |
| Surrogate(s): a a a-TFT     |           | Recovery: 10 | 14% | Limits: 50-15  | 00/ " |          |         |              |    | 04/07/08 22:30     |  |

| Duplicate (8040217-DUP1)    |           |           |       | QC Source: PRC0833-0 | 2   |    | Exti | racted: 0 | 4/07/08 1 | 4:30       |                |
|-----------------------------|-----------|-----------|-------|----------------------|-----|----|------|-----------|-----------|------------|----------------|
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND        |       | 2.61 mg/kg dry       | lx  | ND | 1000 |           |           | 4.30% (40) | 04/07/08 23:24 |
| Surrogate(s): a,a,a-TFT     |           | Recovery: | 76.7% | Limits: 50-150%      | 5 " |    |      |           |           |            | 04/07/08 23:24 |
| D 1' (00.40217 DUD2)        |           |           |       | OGG PROMOS           |     |    |      |           |           |            |                |

| Duplicate (8040217-DUP2)    |           |           |       | QC Source: PRC0900-0 | 1   |    | Extr        | acted: | 04/07/08 1 | 4:30 |      | 4 4            |  |
|-----------------------------|-----------|-----------|-------|----------------------|-----|----|-------------|--------|------------|------|------|----------------|--|
| Gasoline Range Hydrocarbons | NW TPH-Gx | ND        |       | 2.50 mg/kg dry       | lx  | ND | , I <b></b> |        |            | NR   | (40) | 04/08/08 00:18 |  |
| Surrogate(s): a,a,a-TFT     |           | Recovery: | 82.7% | Limits: 50-150%      | 6 " |    |             |        |            |      |      | 04/08/08 00:18 |  |

| Matrix Spike (8040217-MS2)  |           |           |       | QC Source: PRC0900-03 | 3  |       | Ext  | racted: | 04/07/08 14: | 30 |                    |
|-----------------------------|-----------|-----------|-------|-----------------------|----|-------|------|---------|--------------|----|--------------------|
| Gasoline Range Hydrocarbons | NW TPH-Gx | 14.3      |       | 2.40 mg/kg dry        | lx | 0.348 | 15.0 | 93.2%   | (65-130)     |    | <br>04/08/08 07:30 |
| Surrogate(s): a,a,a-TFT     |           | Recovery: | 87.9% | Limits: 50-150%       | "  |       |      |         |              |    | 04/08/08 07:30     |

TestAmerica Portland

and w. Amil





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070 Project Number: Project Manager: TC021SC.080C Erik Chapman Report Created: 04/17/08 13:02

### BTEX per EPA Method 8021B - Laboratory Quality Control Results

TestAmerica Portland


| QC Batch: 8040217             | Soil Pre  | paration M | lethod: AK | 01 Prep   | 2              |     |                  |              |          |             |          |          |  |       |
|-------------------------------|-----------|------------|------------|-----------|----------------|-----|------------------|--------------|----------|-------------|----------|----------|--|-------|
| Analyte                       | Method    | Result     | MDL*       | MRL       | Units          | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits) | Analyzed   | Notes |
| Blank (8040217-BLK1)          |           |            |            |           |                |     |                  | Extr         | acted:   | 04/07/08 14 | :30      |          |  |       |
| Benzene                       | EPA 8021B | ND         | 1          | 0.0243    | mg/kg wet      | 1x  |                  |              |          |             |          |          | 04/07/08 22:57   |       |
| Toluene                       | н         | ND         |            | 0.0485    |                | *   |                  |              |          |             |          |          | *  |       |
| Ethylbenzene                  | W         | ND         |            | 0.0485    | *              |     |                  |              |          |             | -        |          |  |       |
| Xylenes (total)               |           | ND         |            | 0.0971    |                |     | ••               |              |          | 122         |          |          | н  |       |
| m,p-Xylene                    | *         | ND         |            | 0.0485    |                |     |                  |              |          |             |          |          | н  |       |
| o-Xylene                      | и         | ND         |            | 0.0485    |                |     |                  |              |          |             |          |          | н  |       |
| Surrogate(s): a,a,a-TFT (PID) |           | Recovery:  | 107%       | L         | imits: 60-130% | "   |                  |              |          |             |          |          | 04/07/08 22:57   |       |
| LCS (8040217-BS1)             |           |            |            |           |                |     |                  | Extr         | acted:   | 04/07/08 14 | :30      |          |  |       |
| Benzene                       | EPA 8021B | 0.502      |            | 0.0250    | mg/kg wet      | lx  |                  | 0.500        | 100%     | (75-135)    |          |          | 04/07/08 22:02   |       |
| Toluene                       |           | 0.502      |            | 0.0500    |                | •   |                  |              | 100%     | (80-130)    |          |          | w  |       |
| Ethylbenzene                  |           | 0.512      |            | 0.0500    |                | *   |                  |              | 103%     |             |          |          |  |       |
| Xylenes (total)               | *         | 1.56       |            | 0.100     | ,              |     |                  | 1.50         | 104%     | n.          |          |          | and the same of th |       |
| Surrogate(s): a,a,a-TFT (PID) |           | Recovery:  | 107%       | L         | imits: 60-130% | "   |                  |              |          |             |          |          | 04/07/08 22:02   |       |
| Matrix Spike (8040217-MS1)    |           |            |            | QC Source | e: PRC0900-0   | 2   |                  | Extr         | acted:   | 04/07/08 14 | :30      |          |  |       |
| Benzene                       | EPA 8021B | 0.584      |            | 0.0297    | mg/kg dry      | lx  | ND               | 0.593        | 98.4%    | (65-135)    |          |          | 04/08/08 01:40   |       |
| Toluene                       |           | 0.582      |            | 0.0593    | m .            | н   | ND               | "            | 98.2%    | (70-130)    |          |          | ,,   |       |
| Ethylbenzene                  |           | 0.592      |            | 0.0593    |                |     | ND               |              | 99.9%    | (70-140)    |          |          | n  |       |
| Xylenes (total)               | "         | 1.79       |            | 0.119     |                |     | ND               | 1.78         | 101%     | (65-140)    |          |          |  |       |
| Surrogate(s): a,a,a-TFT (PID) |           | Recovery:  | 86.2%      | L         | imits: 60-130% | "   |                  |              | ·        |             |          |          | 04/08/08 01:40   |       |
| Matrix Spike Dup (8040217-MS  | D1)       |            |            | QC Source | e: PRC0900-0   | 2   |                  | Extr         | acted:   | 04/07/08 14 | :30      |          |  |       |
| Benzene                       | EPA 8021B | 0.649      |            | 0.0297    | mg/kg dry      | 1x  | ND               | 0.593        | 109%     | (65-135)    | 10.6%    | (20)     | 04/08/08 02:07   |       |
| Toluene                       |           | 0.645      |            | 0.0593    |                |     | ND               | ü            | 109%     | (70-130)    | 10.2%    |          |  |       |
| Ethylbenzene                  |           | 0.657      |            | 0.0593    | "              |     | ND               |              | 111%     | (70-140)    | 10.4%    |          |  |       |
| Xylenes (total)               | W         | 2.00       |            | 0.119     |                |     | ND               | 1.78         | 112%     | (65-140)    | 10.7%    |          |  |       |
| Surrogate(s): a,a,a-TFT (P1D) |           | Recovery:  | 90.4%      | L         | imits: 60-130% | "   |                  |              |          |             |          |          | 04/08/08 02:07   |       |

TestAmerica Portland

hall W. Sail

Darrell Auvil, Project Manager





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132

ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

Project Number: Project Manager: TC021SC.080C Erik Chapman

Report Created: 04/17/08 13:02

#### Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B - Laboratory Quality Control Results TestAmerica Portland

| QC Batch:               | 8040320              | Water P   | reparation | Method: EI | PA 5030B |               |     |                  |              |          |             |          |          |                |       |
|-------------------------|----------------------|-----------|------------|------------|----------|---------------|-----|------------------|--------------|----------|-------------|----------|----------|----------------|-------|
| Analyte                 |                      | Method    | Result     | MDL*       | MRL      | Units         | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits) | Analyzed       | Notes |
| Blank (8040320-         | ·BLK1)               |           |            |            |          |               |     |                  | Extr         | acted:   | 04/09/08 08 | 3:00     |          |                |       |
| 1,2-Dibromoethane       |                      | EPA 8260B | ND         |            | 0.500    | ug/l          | lx  |                  |              |          |             |          | (        | 04/09/08 10:20 |       |
| 1,2-Dichloroethane      |                      |           | ND         |            | 0.500    | n             | "   |                  |              |          |             |          |          | *              |       |
| Benzene                 |                      | *         | ND         |            | 0.200    | т.            | "   |                  |              |          |             |          |          |                | A-0   |
| Toluene                 |                      | "         | ND         |            | 0.500    | н             |     |                  |              |          |             |          |          |                |       |
| Ethylbenzene            |                      | <u></u>   | ND         |            | 0.500    |               |     |                  |              |          |             |          |          | *              |       |
| Xylenes (total)         |                      | <u>"</u>  | ND         |            | 1.00     | **            |     |                  |              |          |             |          |          |                |       |
| Methyl tert-butyl ether |                      |           | ND         |            | 2.00     |               |     |                  |              |          |             |          |          |                |       |
| Naphthalene             |                      |           | ND         |            | 2.00     |               | ,,  |                  |              | -        |             |          | 122      |                |       |
| 1,2,4-Trimethylbenzene  | ε -                  |           | ND         |            | 1.00     |               |     |                  |              |          |             |          | (==)     | m:             |       |
| 1,3,5-Trimethylbenzene  |                      |           | ND         |            | 0.500    |               |     |                  |              |          |             |          |          | w.             |       |
| Isopropylbenzene        |                      |           | ND         |            | 2.00     |               |     | ,                |              |          |             |          |          |                |       |
| n-Propylbenzene         |                      | "         | ND         |            | 0.500    |               |     | -                |              |          |             |          |          |                |       |
| Surrogate(s): 4         | -BFB                 |           | Recovery:  | 92.4%      | Lin      | nits: 80-120% | 6 " |                  |              |          |             |          |          | 04/09/08 10:20 |       |
| 1                       | ,2-DCA-d4            |           |            | 102%       |          | 80-120        | % " |                  |              |          |             |          |          | "              |       |
|                         | Dibromofluoromethane |           |            | 96.0%      |          | 80-120        |     |                  |              |          |             |          |          | <i>n</i> .     |       |
| T                       | oluene-d8            |           |            | 98.4%      |          | 80-120        | % " |                  |              |          |             |          |          | "              |       |
| LCS (8040320-B          | <b>3S1</b> )         |           |            |            |          |               |     |                  | Exti         | racted:  | 04/09/08 08 | 8:00     |          |                |       |
| 1,2-Dibromoethane       |                      | EPA 8260B | 20.5       |            | 0.500    | ug/l          | lx  |                  | 20.0         | 103%     | (80-140)    |          | (        | 04/09/08 08:53 |       |
| 1,2-Dichloroethane      |                      |           | 19.7       |            | 0.500    |               |     |                  | **           | 98.4%    | (75-135)    |          |          |                |       |
| Benzene                 |                      |           | 19.1       |            | 0.200    |               |     |                  |              | 95.4%    | (80-120)    |          |          |                |       |
| Toluene                 |                      |           | 19.6       |            | 0.500    | н             |     |                  |              | 97.8%    | (80-125)    |          | -        |                |       |
| Ethylbenzene            |                      |           | 20.2       |            | 0.500    |               | ,,  |                  |              | 101%     | (80-130)    |          | -        |                |       |
| Xylenes (total)         |                      |           | 60.2       |            | 1.00     | "             |     |                  | 60.0         | 100%     |             |          | -        |                |       |
| Methyl tert-butyl ether |                      | *         | 18.6       |            | 2.00     | "             | , m |                  | 20.0         | 93.1%    | (80-135)    |          |          | HE             |       |
| Naphthalene             |                      |           | 21.7       |            | 2.00     |               |     |                  |              | 108%     | (60-150)    |          |          | и.             |       |
| 1,2,4-Trimethylbenzene  |                      |           | 21.4       |            | 1.00     |               |     |                  |              | 107%     | (75-125)    |          |          | и.             |       |
| 1,3,5-Trimethylbenzene  |                      |           | 20.4       |            | 0.500    | au .          |     |                  |              | 102%     | (75-135)    |          |          | и.             |       |
| Isopropylbenzene        |                      |           | 20.4       |            | 2.00     | 10            |     |                  |              | 102%     | (80-140)    |          |          |                |       |
| n-Propylbenzene         |                      | "         | 21.0       |            | 0.500    | *             |     |                  | **           | 105%     | (80-130)    |          |          |                |       |
| Surrogate(s): 4         | -BFB                 |           | Recovery:  | 97.5%      | I in     | iits: 80-1209 | 6 " |                  |              |          |             |          |          | 04/09/08 08:53 |       |
|                         | .2-DCA-d4            |           | necorety.  | 101%       | LIII     | 80-120        |     |                  |              |          |             |          |          | "              |       |

80-120%

80-120%

TestAmerica Portland

and W. Smil

Dibromofluoromethane

Toluene-d8

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manager



100%

99.6%



Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

Wilsonville, OR 97070

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

Project Number: Project Manager: TC021SC.080C

Erik Chapman

Report Created: 04/17/08 13:02

Selected Volatile Organic Compounds (Including BTEX) per EPA Method 8260B - Laboratory Quality Control Results

TestAmerica Portland

| QC Batch: 8040320       | Water I   | Preparation | Method: EF | PA 5030B |              |     |                  |              |          | 25          |          |         |                |       |
|-------------------------|-----------|-------------|------------|----------|--------------|-----|------------------|--------------|----------|-------------|----------|---------|----------------|-------|
| Analyte                 | Method    | Result      | MDL*       | MRL      | Units        | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits | ) Analyzed     | Notes |
| LCS Dup (8040320-BSD1)  |           |             |            |          |              |     |                  | Ext          | racted:  | 04/09/08 08 | 3:00     |         |                |       |
| 1,2-Dibromoethane       | EPA 8260B | 19.9        |            | 0.500    | ug/l         | lx  |                  | 20.0         | 99.6%    | (80-140)    | 2.87%    | (25)    | 04/09/08 09:22 |       |
| 1,2-Dichloroethane      | *         | 18.6        |            | 0.500    |              | *   |                  | "            | 93.1%    | (75-135)    | 5.48%    |         |                |       |
| Benzene                 | н.        | 18.0        |            | 0.200    | "            |     |                  | н            | 90.2%    | (80-120)    | 5.66%    | *       |                |       |
| Toluene                 | *         | 18.5        |            | 0.500    | ii .         |     |                  |              | 92.4%    | (80-125)    | 5.73%    | "       |                |       |
| Ethylbenzene            |           | 19.1        |            | 0.500    |              |     |                  |              | 95.6%    | (80-130)    | 5.40%    | w       | **             |       |
| Xylenes (total)         | *         | 56.9        |            | 1.00     |              |     |                  | 60.0         | 94.9%    |             | 5.65%    | и       | "              |       |
| Methyl tert-butyl ether | н         | 18.0        |            | 2.00     |              |     |                  | 20.0         | 90.0%    | (80-135)    | 3.39%    | н       | •              |       |
| Naphthalene             |           | 21.9        |            | 2.00     |              |     |                  |              | 110%     | (60-150)    | 1.15%    | "       | •              |       |
| 1,2,4-Trimethylbenzene  | н         | 20.4        |            | 1.00     | ï            |     |                  | *            | 102%     | (75-125)    | 4.54%    |         | •              |       |
| 1,3,5-Trimethylbenzene  | н         | 19.4        |            | 0.500    |              | **  |                  |              | 97.0%    | (75-135)    | 4.98%    |         | *              |       |
| Isopropylbenzene        | *         | 19.4        |            | 2.00     | "            |     |                  |              | 96.8%    | (80-140)    | 5.43%    | н       |                |       |
| n-Propylbenzene         | . н       | 19.8        |            | 0.500    | "            |     |                  |              | 98.9%    | (80-130)    | 5.94%    | *       | н              |       |
| Surrogate(s): 4-BFB     |           | Recovery:   | 97.2%      | Lim      | its: 80-120% | "   |                  |              |          |             |          |         | 04/09/08 09:22 | -     |
| 1,2-DCA-d4              |           |             | 102%       |          | 80-120%      | "   |                  |              |          |             |          |         | "              |       |
| Dibromofluorometha      | ne        |             | 99.6%      |          | 80-120%      | "   |                  |              |          |             |          |         | "              |       |
| Toluene-d8              |           |             | 100%       |          | 80-120%      | "   |                  |              |          |             |          |         | "              |       |

TestAmerica Portland

hall W. Sail





Bergeson, Boese and Associates-Wilsonville

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Project Name: Tillamook Creamery

25195 SW Parkway Ave Suite 207Project Number:TC021SC.080CReport Created:Wilsonville, OR 97070Project Manager:Erik Chapman04/17/08 13:02

### Polynuclear Aromatic Compounds per EPA 8270M-SIM - Laboratory Quality Control Results

TestAmerica Portland

| Part   Part | Manual   | analyte               |                      | Method    | Result    | MDL*    | MRL   | Units  | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits) | Analyzed       | Notes |
|---|--|-----------------------|----------------------|-----------|-----------|---------|-------|--|-----|------------------|--------------|----------|-------------|----------|----------|----------------|-------|
| Acemaphthylene  | Acentaphthylene  | Blank (804008         | 88-BLK1)             |           |           |         |       |  |     |                  |              |          | 04/02/08 17 |          |          |                |       |
| Anthracere  | Anthracene   | Acenaphthene          |                      | EPA 8270m | ND        |         | 0.100 | ug/l   | lx  |                  |              |          |             |          |          | 04/03/08 21:23 |       |
| Benzo (a) anthracene  | Benzo (a) anthracene   | Acenaphthylene        |                      | ,,        | ND        |         | 0.100 | н  |     |                  |              |          |             |          |          |                |       |
| Benzo (a) pyrene  | Benzo (a) pyrene Benzo (b) fluoranthene  | Anthracene            |                      | ,         | ND        |         | 0.100 | и.   | "   |                  |              |          |             |          |          |                |       |
| Benzo (s) fluoranthene  | Benzo (b) fluoranthene   | Benzo (a) anthracene  | e                    |           | ND        |         | 0.100 | "  | H   |                  |              |          |             |          |          |                |       |
| Benzo (ghi) perylene  | Benzo (ghi) perylene   | Benzo (a) pyrene      |                      |           | ND        |         | 0.100 |  |     |                  | -            |          |             |          | -        |                |       |
| Benzo (k) fluoranthene  | Benzo (k) fluoranthene   | Benzo (b) fluoranthe  | ene                  |           | ND        |         | 0.100 |  | ä   |                  |              |          |             |          |          | ,              |       |
| ND  | Chrysene   | Benzo (ghi) perylene  | e                    | "         | ND        |         | 0.100 |  |     |                  |              |          |             |          |          |                |       |
| ND  | Chrysene   | Benzo (k) fluoranthe  | ene                  |           | ND        |         | 0.100 |  |     |                  |              |          |             |          |          |                |       |
| Ditenzo (a,h) anthrace  | Dibenzo (a,h) anthracee  |                       |                      |           |           |         |       |  |     |                  |              |          |             |          | -        |                |       |
| Fluoranthene  | Fluoranthene   |                       | icene                |           |           |         |       |  |     | -                |              |          |             | -        | 100      |                |       |
| Fluorene  | Fluorene "ND " 0.100 """ " 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.   |                       |                      |           |           |         |       |  |     |                  |              |          |             |          |          |                |       |
| Naphthalene (1,2,3-cd) pyrere   | Indeno (1,2,3-cd) pyrere   |                       |                      |           |           |         |       | "  |     |                  |              | -        |             |          |          |                |       |
| Naphthalene   | Naphthalene " ND " 0.100 " " " " " " " " " " " " " " " " " "   |                       | rene                 | ii .      |           |         |       |  | ,,  |                  |              |          |             | -        |          |                |       |
| Phenanthrene "ND "1010 """ "1 "1 "1 "1 "1 "1 "1 "1 "1 "1 "1 "1  | Phenanthrene "ND "0.100 """ " " " " " " " " " " " " " " " "  | 1 1 1 1 1 1 1 1 1 1 1 |                      | ,,        |           |         |       | "  |     |                  |              |          |             |          |          |                |       |
| Surrogate(s):   Fluorene-d10  | Surrogate(s):   Fluorene-d10   |                       |                      |           |           |         |       |  |     |                  |              |          |             |          |          |                |       |
| Surrogate(s):   Fluorene-d10  | Surrogate(s): Fluorene-d10   |                       |                      |           |           |         |       |  |     |                  |              | -        |             |          |          |                |       |
| Pyrene-d10   63.3%   23-150%   "  | Pyrene-d10   |                       | Electric             |           |           |         |       | TOTAL MATTER VALUE OF THE PARTY |     |                  |              |          |             |          |          |                |       |
| LCS (8040088-BS1)   | LCS (8040088-BS1)  | Surrogate(s):         |                      |           | Recovery: |         | Lir   |  | o . |                  |              |          |             |          |          |                |       |
| LCS (8040088-BS1)   EPA 8270m   2.15     0.100   ug/l   lx     2.50   85.9%   (26-135)     0.4/03/08 21:51  | LCS (8040088-BS1)   EPA 8270m   2.15     0.100   ug/l   1x     2.50   85.9%   (26-135)       04/03/08 21:51  |                       |                      |           |           |         |       |  |     |                  |              |          |             |          |          |                |       |
| Acenaphthene  | Acenaphthene   |                       | (17) // (11)         |           |           | 7 1.070 |       | 10-125   | , , |                  |              |          |             |          |          |                |       |
| Benzo (a) pyrene " 2.25 0.100 " " " 89.9% (38-137) " " " Pyrene " 1.82 0.100 " " " 72.7% (33-133) "   | Benzo (a) pyrene " 2.25 0.100 " " " 89.9% (38-137) "  Pyrene " 1.82 0.100 " " " 72.7% (33-133) "  Surrogate(s): Fluorene-d10   | LCS (8040088          | 3-BS1)               |           |           |         |       | ,  |     |                  | Ext          | racted:  | 04/02/08 17 | 7:50     |          |                |       |
| Pyrene " 1.82 0.100 " " " " 72.7% (33-133) " " 04/03/08 21:51  Surrogate(s): Fluorene-d10   | Pyrene " 1.82 0.100 " " " 72.7% (33-133) "  Surrogate(s): Fluorene-d10   | Acenaphthene          |                      | EPA 8270m | 2.15      |         | 0.100 | ug/l   | lx  |                  | 2.50         | 85.9%    | (26-135)    |          |          | 04/03/08 21:51 |       |
| Surrogate(s): Fluorene-d10 Recovery: 88.5% Limits: 25-125% "  | Surrogate(s): Fluorene-d10 Recovery: 88.5% Limits: 25-125% " 04/03/08 21:5. " 04/03/08 21:5. " 04/03/08 21:5. " 04/03/08 21:5. " 04/03/08 21:5. " 04/03/08 21:5. " 04/03/08 21:5. " 04/03/08 22:38 Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " " Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " " Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38  | Benzo (a) pyrene      |                      | 200       | 2.25      |         | 0.100 |  |     |                  |              | 89.9%    | (38-137)    |          |          |                |       |
| Pyrene-d10  | Pyrene-d10 Benzo (a) pyrene-d12 80.3% 10-125% "  Extracted: 04/02/08 17:50  LCS Dup (8040088-BSD1)  Acenaphthene EPA 8270m 2.07 0.100 ug/l 1x 2.50 82.9% (26-135) 3.60% (60) 04/03/08 22:38 Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " " Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  64/03/08 22:38   | yrene                 |                      |           | 1.82      |         | 0.100 |  |     |                  |              | 72.7%    | (33-133)    |          |          |                |       |
| Pyrene-d10  | Pyrene-d10   | Surrogate(s):         | Fluorene-d10         |           | Recovery: | 88.5%   | Lin   | nits: 25-1259  | 6 " |                  |              |          |             |          | -        | 04/03/08 21:51 |       |
| LCS Dup (8040088-BSD1)   Extracted: 04/02/08 17:50     Extracted: 04/02/08 17:50     Extracted: 04/02/08 17:50     EPA 8270m   2.07     0.100   ug/l   1x     2.50   82.9%   (26-135)   3.60%   (60)   04/03/08 22:38     EBDIZO (a) pyrene   "   2.26     0.100   "   "     "   90.4%   (38-137)   0.560%   "   "  | Extracted: 04/02/08 17:50     CCS Dup (8040088-BSD1)     CCS Dup (8040088-BSD1)     Extracted: 04/02/08 17:50     CCS Dup (8040088-BSD1)     CCS Dup (8040088-BSD1)     CCS Dup (8040088-BSD1)     Extracted: 04/02/08 17:50     CCS Dup (8040088-BSD1)     CCS Dup (8040088-BSD1)   CCS Dup (8040088-BSD1)     CCS |                       | Pyrene-d10           |           |           | 70.8%   |       | 23-150   | % " |                  |              |          |             |          |          |                |       |
| Acenaphthene EPA 8270m 2.07 0.100 ug/l 1x 2.50 82.9% (26-135) 3.60% (60) 04/03/08 22:38  Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " "  Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 104/03/08 22:38  | Acenaphthene EPA 8270m 2.07 0.100 ug/l lx 2.50 82.9% (26-135) 3.60% (60) 04/03/08 22:38 Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " "  Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 9.40% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40% (38-137) 0.560% " 9.40%                    |                       | Benzo (a) pyrene-d12 |           |           | 80.3%   |       | 10-125   | % " |                  |              |          |             |          |          | "              |       |
| Acenaphthene EPA 8270m 2.07 0.100 ug/l 1x 2.50 82.9% (26-135) 3.60% (60) 04/03/08 22:38  Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " "  Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 104/03/08 22:38  | Acenaphthene EPA 8270m 2.07 0.100 ug/l lx 2.50 82.9% (26-135) 3.60% (60) 04/03/08 22:38 Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " "  Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38   |                       |                      |           |           |         |       |  |     |                  |              |          |             |          |          |                |       |
| Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " "  Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38  | Benzo (a) pyrene " 2.26 0.100 " " " 90.4% (38-137) 0.560% " "  Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38   |                       | 10088-BSD1)          |           |           |         |       |  |     |                  | Ext          | racted:  | 04/02/08 17 | 7:50     |          |                |       |
| Pyrene " 1.85 0.100 " " "74.2% (33-133) 1.94% " "  Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38  | Pyrene " 1.85 0.100 " " " 74.2% (33-133) 1.94% " "  **Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38  | -                     |                      | EPA 8270m | 2.07      |         | 0.100 | ug/l   | lx  | 100              | 2.50         | 82.9%    | (26-135)    | 3.60%    | 60)      | 04/03/08 22:38 |       |
| Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38   | Surrogate(s): Fluorene-d10 Recovery: 84.6% Limits: 25-125% " 04/03/08 22:38  | 2.5 500               |                      | •         | 2.26      |         | 0.100 |  |     |                  | HC.          | 90.4%    | (38-137)    | 0.560%   | 6 "      | "              |       |
|   |  | yrene                 |                      |           | 1.85      |         | 0.100 | н  | **  |                  | **           | 74.2%    | (33-133)    | 1.94%    | . "      | "              |       |
| Pyrene-d10 71.8% 23-150% " "  | Pyrene-d10 71.8% 23-J50% " "   | Surrogate(s):         | Fluorene-d10         |           | Recovery: | 84.6%   | Lin   | nits: 25-1259  | 6 " | 1100000          |              |          |             |          |          | 04/03/08 22:38 |       |
|   |  |                       | Pyrene-d10           |           |           | 71.8%   |       | 23-150   | % " |                  |              |          |             |          |          | "              |       |

TestAmerica Portland

and W. Sail

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Darrell Auvil, Project Manage





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132

ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207

Project Number:

TC021SC.080C

Report Created:

Wilsonville, OR 97070

Project Manager:

Erik Chapman

04/17/08 13:02

Percent Dry Weight (Solids) per Standard Methods - Laboratory Quality Control Results

TestAmerica Portland

QC Batch: 8040263

Other dry Preparation Method: Dry Weight

Result

Analyte Method MDL\*

MRL Units QC Source: PRD0028-04

Source Result Dil

 $\begin{array}{cccc} \text{Spike} & \text{\%} & \text{(Limits)} & \text{\%} & \text{(Limits)} & \text{Analyzed} \\ \text{Amt} & \text{REC} & & & & \\ \end{array}$ 

Notes

Duplicate (8040263-DUP1) % Solids

NCA SOP

59.9

0.0100 % by Weight

59.9

Extracted: 04/07/08 16:07

0.00% (20)

04/07/08 16:07

TestAmerica Portland

all W. Amil

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.

Page 16 of 18



Bergeson, Boese and Associates-Wilsonville

25195 SW Parkway Ave Suite 207

PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Tillamook Creamery

Project Name: Project Number:

TC021SC.080C

Report Created: 04/17/08 13:02

Wilsonville, OR 97070

Project Manager:

Erik Chapman

Gasoline Hydrocarbons by NWTPH-Gx and BTEX by EPA Method 8021B - Laboratory Quality Control Results TestAmerica Spokane

| QC Batch: 8040081           | Water P           | reparation | Method: GO | Volatile | es            |     |                  |              |          |             |          |         |                |       |
|-----------------------------|-------------------|------------|------------|----------|---------------|-----|------------------|--------------|----------|-------------|----------|---------|----------------|-------|
| Analyte                     | Method            | Result     | MDL*       | MRL      | Units         | Dil | Source<br>Result | Spike<br>Amt | %<br>REC | (Limits)    | %<br>RPD | (Limits | ) Analyzed     | Notes |
| Blank (8040081-BLK1)        |                   |            |            |          |               |     |                  | Exti         | acted:   | 04/11/08 12 | :00      |         |                |       |
| Gasoline Range Hydrocarbons | NWTPH-G/8<br>021B | ND         |            | 100      | ug/l          | lx  |                  |              |          |             |          |         | 04/11/08 14:01 |       |
| Surrogate(s): 4-BFB (FID)   |                   | Recovery:  | 105%       | Lin      | nits: 36-150% | "   |                  |              |          |             |          |         | 04/11/08 14:01 |       |
| LCS (8040081-BS1)           |                   |            |            |          |               |     |                  | Exti         | racted:  | 04/11/08 12 | :00      |         |                |       |
| Gasoline Range Hydrocarbons | NWTPH-G/8<br>021B | 868        |            | 100      | ug/l          | lx  |                  | 1000         | 86.8%    | (80-120)    |          | -       | 04/11/08 17:31 |       |
| Surrogate(s): 4-BFB (FID)   |                   | Recovery:  | 125%       | Lin      | nits: 36-150% | "   |                  |              |          |             |          | la la   | 04/11/08 17:31 |       |

| Duplicate (8040081-DUP1)    |                   |             |     | QC Source: | SRD0066-    | 04  |    | Exti | acted: ( | 04/11/08 1: | 2:00       |                |
|-----------------------------|-------------------|-------------|-----|------------|-------------|-----|----|------|----------|-------------|------------|----------------|
| Gasoline Range Hydrocarbons | NWTPH-G/8<br>021B | ND          |     | 100        | ug/l        | lx  | ND |      |          |             | 10.9% (35) | 04/11/08 16:37 |
| Surrogate(s): 4-BFB (F1D)   |                   | Recovery: 1 | 01% | Lim        | its: 36-150 | % " |    |      |          |             |            | 04/11/08 16:37 |
| Matrix Spike (8040081-MS1)  |                   |             |     | QC Source: | SRD0066-    | 04  |    | Exti | acted: ( | 04/11/08 1  | 2:00       |                |

| Gasoline Range Hydrocarbons | NWTPH-G/8<br>021B | 906       |      | 100 ug/l        | lx | 32.1 | 1000 | 87.4% (55.6-126) | - | - | 04/11/08 17:04 |  |
|-----------------------------|-------------------|-----------|------|-----------------|----|------|------|------------------|---|---|----------------|--|
| Surrogate(s): 4-BFB (FID)   |                   | Recovery: | 123% | Limits: 36-150% | "  |      |      |                  |   |   | 04/11/08 17:04 |  |

TestAmerica Portland

hall W. Amil Darrell Auvil, Project Manager

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.





PORTLAND, OR

9405 S.W. NIMBUS AVENUE BEAVERTON, OR 97008-7132 ph: (503) 906.9200 fax: (503) 906.9210

Bergeson, Boese and Associates-Wilsonville

Project Name:

Tillamook Creamery

25195 SW Parkway Ave Suite 207 Wilsonville, OR 97070

Project Number: Project Manager: TC021SC.080C

Report Created: 04/17/08 13:02

Erik Chapman

**Notes and Definitions** 

### Report Specific Notes:

A-01 system contamination

RL1 Reporting limit raised due to sample matrix effects.

RL7 Sample required dilution due to high concentrations of target analyte.

### Laboratory Reporting Conventions:

DET Analyte DETECTED at or above the Reporting Limit. Qualitative Analyses only.

ND Analyte NOT DETECTED at or above the reporting limit (MDL or MRL, as appropriate).

NR/NA Not Reported / Not Available

Sample results reported on a Dry Weight Basis. Results and Reporting Limits have been corrected for Percent Dry Weight. dry

Sample results and reporting limits reported on a Wet Weight Basis (as received). Results with neither 'wet' nor 'dry' are reported wet

on a Wet Weight Basis.

RELATIVE PERCENT DIFFERENCE (RPDs calculated using Results, not Percent Recoveries). RPD

MRL METHOD REPORTING LIMIT. Reporting Level at, or above, the lowest level standard of the Calibration Table.

MDL\* METHOD DETECTION LIMIT. Reporting Level at, or above, the statistically derived limit based on 40CFR, Part 136, Appendix B. \*MDLs are listed on the report only if the data has been evaluated below the MRL. Results between the MDL and MRL are reported

as Estimated Results.

Dil Dilutions are calculated based on deviations from the standard dilution performed for an analysis, and may not represent the dilution

found on the analytical raw data.

Reporting -Reporting limits (MDLs and MRLs) are adjusted based on variations in sample preparation amounts, analytical dilutions and Limits

percent solids, where applicable.


Electronic Electronic Signature added in accordance with TestAmerica's Electronic Reporting and Electronic Signatures Policy. Signature Application of electronic signature indicates that the report has been reviewed and approved for release by the laboratory.

Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

TestAmerica Portland

hall W. Smil

The results in this report apply to the samples analyzed in accordance with the chair of custody document. This analytical report shall not be reproduced except in full, without the written approval of the laboratory.





## Test/America

11720 North Creek Pkwy N Suite 400, Bothell, WA 98011-8244 425-420-9200 FAX 420-9210 1922 F. First Ave. Spokane, WA 99206-5302 509-924-9200 FAX 924-9290 9408 SW Nimbus Ave. Beaverton, OR 97008-7145 503-906-9200 FAX 906-9210 907-563-9200 FAX 906-9210 907-563-9200 FAX 906-9210

|                                  | , (                         | CHAIN  | OF C        | USTODY REPORT      |  |           | Work O    | rder #:         | PRD0021  | ટ           |
|----------------------------------|-----------------------------|--------|-------------|--------------------|--|-----------|-----------|-----------------|--|-------------|
|                                  | Boese > As                  |        |             | INVOICE TO. Ray Be | igath (char  | 8-        |           | TURNARO<br>in B | OUND REQUEST                                     |             |
| ADDRESS Z 5 1 45                 | Vymodel<br>Sic Porterior Ar | c 200  | 7           |                    |  | ,         | 7         | ] [5]           | norganic Analyses  4 3 2 1  Ivdrocarbon Analyses | < 1         |
| PHONE 513 170.798                | TAX 503 570-                | CS37   |             | P.O. NUMBER:       | (VAIIVE  |           | 3         |                 | 3 2 1 <  | ί           |
| PROJECT NAME THAN                |                             | 7      | T           |                    |  |           | STI       | ,               |  |             |
| PROJECT NUMBER: TCC              | •                           |        |             |                    | ) ANALYSES   |           |           |                 | pecify:<br>than standard may incur l             | Duch Change |
| SAMPLED BY: FOR                  | <u> </u>                    | *      | 1 12 3      |                    |  |           |           | T               |  |             |
| CLIENT SAMPLE<br>IDENTIFICATION  | SAMPLING<br>DATE:TIME       | 至五     | STEX        |                    |  |           | (W. S. O) | # OF<br>CONT.   | LOCATION<br>COMMENTS                             | WO ID       |
| NW@4.6                           | 4/1/08 1010                 |        |             |                    |  |           | 5         | i               |  | -           |
| NFLOOR@7'                        | 1020                        |        |             |                    |  |           |           | 1               |  |             |
| , 5We 4.61                       | /012                        | -  -   |             |                    |  |           |           | 11-1            |  | -           |
| , EW @ 4.6'                      | 1019                        | 5 X    | X           |                    |  | .,        | - -       | 41              |  | -           |
| SFLOOR CT'                       | 102                         | 2      |             |                    |  |           |           |                 |  |             |
| " WWG 4.6'                       | 1017                        | 7 X    | X           |                    |  |           |           |                 |  |             |
| , GTULK PILET                    | 1041                        | 5      |             |                    |  |           |           | 41-4            |  | -           |
| * STOLKPILEZ                     | 104                         | 5      |             |                    |  |           |           | +               |  |             |
| , NEWORG 7.5'                    | 121                         | VX     | X           |                    |  |           | 1         | V               |  | -           |
| 10                               |                             |        |             | DATE: 4100         | RECEIVED BY Lamie &  | 2 No. 1   |           |                 | DATE.  | TILE        |
| PRINT NAME: FRIVE CHAP           | MAN FIRM:                   | BBA    |             | TIME: 1502         | PRINT NAME: S. TV  | eland     | FIRM      | TAI             | TIME: /  | 5.02        |
| RELEASED BY:                     |                             |        |             | DATE:<br>TIME:     | RECEIVED BY: PRINT NAME:   |           | FIRM      |                 | DATE:<br>TIME:                                   |             |
| PRINT NAME.  ADDITIONAL REMARKS: | Wantify it c                | de fee | <del></del> | by NWTPH ,         | Distriction of the Control of the Co | appropri  | ate       | A               | TEMP:  FOOT PAGE                                 | E/OF7       |
| COC REV 09-2004                  | 3                           |        | 1           | -y 100 (11) V      | VICTIVAL DES   | All of or | '\        |                 | 3.8  | 1           |

# Testamerica ANALYTICAL TESTING CORPORATION

11"20 North Creek Pkwy N Suite 400, Bothell, WA 98011-8244 11922 E. First Ave, Spokane, WA 99206-5302 9405 SW Nimbus Ave, Beaverton, OR 97008-7145 425-420-9200 FAX 420-9210 509-924-9200 FAX 924-9290 503-906-9200 FAX 906-9210 907-503-9200 FAX 906-9210

2007 A. Levelman and Appear Rel St., Apr. Anchorage, AK 0080241119

Work Order #: P200028 CHAIN OF CUSTODY REPORT TURNAROUND REQUEST Bucse THENT. Rin Bergon - Cosung in Business Days \* ADDRESS 25195 St. Pertering for 207 Organic & Inorganic Analyses PHONE DIS -570 978 FRAN 570 570 0557 P.O. NUMBER PRESERVATIVE PROJECT NUMBER: 7002 15c. 0800 OTHER Specify REQUESTED ANALYSES Turnaround Requests less than standard may mow Rush Charges Benc SAMPLED BY LOCATION MATRIX SAMPLING CLIENT SAMPLE COMMENTS WOID CONT (W, S, O) DATE TIME IDENTIFICATION not field filtered TC-WATER (20D DATE TIME: PRINT NAME FIRM: RECEIVED BY: RELEASED BY DATE: TIME TIME: PRINT NAME PRINT NAME ADDITIONAL REMARKS NWTPH Methods

**TestAmerica Sample Receipt Checklist** Work Order No. PRONOZ8 Received by: Unpacked by: Logged-in by: Client: BBA Section 41 Project: Tillamook Creamary Date: 1-111 initials. Temperature out of range Initials: Not enough Ice No Ice ice Melted \*\*\* ESI Clients (see Section C) W/in 4 Hours Other Cooler Temperature (IR): C plastic glass NA (oil/air samples, ESI client) Temperature Blank: Custody Seals: (# ) Sample Status: Signature: Y N Dated: (If N circled, see NOD) Received from: General: TA Courier Container Type: Intact? N Senvoy #Cooler(s) UPS # Containers Match COC? none given #Box(s) Fed Ex IDs Match COC? N None ( #Other: X Client For Analyses Requested: TDP Coolant Type: Correct Type & Preservation? DHL ★ Gellce Adequate Volume? SDS Loose Ice · Mid-Valley Within Hold Time? N None GS/TA Volatiles/ Oil Quality: Packing Material: GS/Senvoy VOAs/ Syringes free of Headspace? NA Other: **Bubble Bags** TB on COC? (not provided) Ν NA Styrofoam Cubbies Metals None ( Other HNO3 Preserved? NA Dissolved Metals Filtered? NA ESI Clients Only: FED EX/ UPS Was the tracking paper keepable? NO Temperature Blank: not provided If circle? NO, what is the Tracking number?

PM Reviewed: Initial/Date)

Comments:

# APPENDIX E Push Probe and Monitoring Well Completion Logs

PAGE\_1 OF\_1

| PROBE NO.:    | P1                 |
|---------------|--------------------|
| PROJECT CODE: | TC02ISC.08UC       |
| CADD FILE:    | TÇ02I\$C.08UC      |
| PROJECT:      | TILLAMOOK CREAMERY |
| LOCATION:     | 2500 LATIMER ROAD  |
|               | TILLAMOOK, OR      |

TOTAL DEPTH: 20'

SURFACE ELEVATION: N/A

PROBING METHOD: MACRO CORE

PROBED BY: PACIFIC NORTHWEST DRILLING

LOGGED BY: ERIK CHAPMAN

DATE COMPLETED: 4/29/08

| DEPTH<br>(feet) | SAMPLE IDENTIFICATION AND LAB RESULTS | PID | H,O<br>LEVEL | LITHOLOGIC DESCRIPTION  | LITHOLOGY     | DEPTH<br>(feet) | PROBE<br>ABANDONMENT |
|-----------------|---------------------------------------|-----|--------------|---|---------------|-----------------|----------------------|
| F °             |                                       |     |              | - GRAVEL/ Soil Surface  |               | F°              |                      |
|                 | =                                     |     |              | -Clayey SILT (ML): dark brown, soft, dry  | <i>200000</i> | ŀ               |                      |
|                 | TC02-P1-3.5'                          | 0.0 |              | _ greyish—brown w/ brown mottled, wet   |               | -               |                      |
| 5               | TC02-P1-6'                            | 0.0 |              | grey w/ orange mottling, firm, slightly moist   |               | _ 5             |                      |
| -               |                                       |     |              |   |               | -               |                      |
|                 | TC02-P1-8.5'                          | 0.0 |              |   |               | -               |                      |
| 10              | TC02-P1-11'                           | 0.0 |              | ,   |               | <u> </u>        |                      |
| -               | TC02-P1-14'                           | 0.0 |              | - SAND (SM): greyish brown, fine-grained sand, trace silt, soft, moist  TSILT (ML): grey w/ orange mottling, firm, slightly | ¥ 77.         | -               |                      |
| 15              | TC02-P1-15.5'                         | 0.0 | ₩0           | moist to dry, wet @ 16.5'BLS  |               | — 15<br>-       |                      |
|                 |                                       | 0.0 |              | SAND (SIA), dade and Caraca data  |               | -               |                      |
| _ 20            |                                       | 0.0 |              | - SAND (SM): dark grey, fine-grained sand, firm, moist  |               | _ 20            |                      |
|                 |                                       | _   |              |   |               | -               |                      |
|                 |                                       |     |              |   | 8             |                 |                      |
| _ 25            |                                       |     |              |   |               | - 25            |                      |

| L | EQ | Q |
|---|----|---|
|   |    |   |

WD

Water Level in borehole during drilling (i.e. first encountered)

NOTES:



Bengeson-Boese + Associates, Inc.
Comprehensive Environmental Services

32986 Roberts Court Coburg, Oregon 97408 (541) 484-9484 25195 SW Parkway Ave., Suite 207 Wilsonville, Oregon 97070 (503) 570-9484

NOTE: CLASSIFICATION OF SOILS BASED ON THE UNITED SOILS CLASSIFICATION SYSTEM.

| PROBE NO .:   | P2                 |
|---------------|--------------------|
| PROJECT CODE: | TC02ISC.08UC       |
| CADD FILE:    | TC02ISC.08UC       |
| PROJECT:      | TILLAMOOK CREAMERY |
| LOCATION:     | 2500 LATIMER ROAD  |
|               | TILLAMOOK OR       |

 TOTAL DEPTH:
 20'

 SURFACE ELEVATION:
 N/A

 PROBING METHOD:
 MACRO CORE

 PROBED BY:
 PACIFIC NORTHWEST DRILLING

 LOGGED BY:
 ERIK CHAPMAN

 DATE COMPLETED:
 4/29/08

| DEPTH<br>(feet) | SAMPLE IDENTIFICATION AND LAB RESULTS | PID          | H,0<br>LEVEL | LITHOLOGIC DESCRIPTION   | LITHOLOGY | DEPTH<br>(feet) | PROBE<br>ABANDONMENT |
|-----------------|---------------------------------------|--------------|--------------|--|-----------|-----------------|----------------------|
| -<br>-          | *                                     |              |              | - SOIL SURFACE  - GRAVEL (GM): grey, fine grained, rounded (pea-gravel), moist to wet                                      |           | F °             |                      |
| -<br>-<br>- 5   | TC02-P2-4.5'                          | 405          |              | - Clayey SILT (ML): dark grey, moist, strong<br>hydrocarbon odor   |           | -<br>-<br>- 5   |                      |
| -<br> -<br> -   | TC02-P2-7'                            | 80.5<br>20.5 |              | - greyish brown/orange mottling, soft, slightly<br>moist,<br>- grey, firm  |           | -<br>-          |                      |
| <br>  10<br> -  | TC02-P2-9.5'                          | 12.9         |              | grey w/ orange mottling, soft, slightly moist  |           | -<br>- 10       |                      |
| -<br> -<br> -   | TC02-P2-12'                           | 0.0          | B            |  |           | -               |                      |
| — 15<br>-<br>-  | TC02-P2-15.5'                         | 12.5         | <b>*</b>     | - SILT (ML): greyish brown, saturated  |           | — 15<br>-       |                      |
| - 20            | TC02-P2-18'                           | 0.0          |              | <ul> <li>dry</li> <li>SILT (ML): grey w/ orange mottling, firm, slightly moist, black fine-grained sand in shoe</li> </ul> |           | -               |                      |
| -               |                                       | ×            |              |  |           | - 20<br>-<br>-  |                      |
| -<br>- 25       |                                       | *            |              |  |           | - 25            |                      |
| L               |                                       |              |              |  |           |                 |                      |

| And and a second | 4.5 | × |
|------------------|-----|---|

WD

Water Level in borehole during drilling (i.e. first encountered)

| NOTES: |  |  |
|--------|--|--|
|        |  |  |



Bergeson-Boese + Associates, Inc.
Comprehensive Environmental Services

32986 Roberts Court Coburg, Oregon 97408 (541) 484-9484 25195 SW Parkway Ave., Suite 207 Wilsonville, Oregon 97070 (503) 570-9484

PAGE\_1\_ OF\_1\_

| PROBE NO .:   | P3                 |
|---------------|--------------------|
| PROJECT CODE: | TC02ISC.08UC       |
| CADD FILE:    |                    |
| PROJECT:      | TILLAMOOK CREAMERY |
| LOCATION:     | 2500 LATIMER ROAD  |
|               | TILLAMOOK, OR      |

TOTAL DEPTH: 15'

SURFACE ELEVATION: N/A

PROBING METHOD: MACRO CORE

PROBED BY: PACIFIC NORTHWEST DRILLING

LOGGED BY: ERIK CHAPMAN

DATE COMPLETED: 4/29/08

| DEPTH<br>(feet)    | SAMPLE IDENTIFICATION AND LAB RESULTS                       | PID                             | H,0<br>LEVEL | LITHOLOGIC DESCRIPTION  LITHOLOGY  DEPTH (feet)  PROBE ABANDONMENT  |
|--------------------|---|---------------------------------|--------------|---|
| - 5<br>-<br>-<br>- | TC02-P3-3' TC02-P3-4.5' TC02-P3-6' TC02-P3-8' TC02-P3-10.5' | 0.0<br>0.0<br>0.0<br>0.0<br>0.0 |              | - ASPHALT - GRAVEL (GM): grey, fine-medium grained, rounded, dry - Cloyey SILT (ML): dark grey, trace clay, soft, moist - grey w/ brown mottling, slightly moist - becomes dry  - wet - Silty SAND (SP): greyish brown mottled w/ orange-reddish brown, soft, wet |

| LEGEN | D |
|-------|---|
|       |   |

WD

Water Level in borehole during drilling (i.e. first encountered)

| NOTES: |  |  |
|--------|--|--|
|        |  |  |



Bergeson-Bosse + Associates, Inc.

32986 Roberts Court Coburg, Oregon 97408 (541) 484-9484 25195 SW Parkway Ave., Suite 207 Wilsonville, Oregon 97070 (503) 570–9484

NOTE: CLASSIFICATION OF SOILS BASED ON THE UNITED SOILS CLASSIFICATION SYSTEM.

PAGE\_1\_ 0F\_1

| PROBE NO .:   | P4                 |
|---------------|--------------------|
| PROJECT CODE: | TÇ02ISC.08UC       |
| CADD FILE:    | TC02ISC.08UC       |
| PROJECT:      | TILLAMOOK CREAMERY |
| LOCATION:     | 2500 LATIMER ROAD  |
|               | TILLAMOOK OR       |

TOTAL DEPTH: 20'

SURFACE ELEVATION: N/A

PROBING METHOD: MACRO CORE

PROBED BY: PACIFIC NORTHWEST DRILLING

LOGGED BY: ERIK CHAPMAN

DATE COMPLETED: 4/29/08

| DEPTH<br>(feet) | SAMPLE IDENTIFICATION AND LAB RESULTS | PID | H,O<br>LEVEL | LITHOLOGIC DESCRIPTION   | LITHOLOGY | DEPTH<br>(feet) | PROBE<br>ABANDONMENT |
|-----------------|---------------------------------------|-----|--------------|--|-----------|-----------------|----------------------|
| F°              |                                       |     |              | - ASPHALT<br>- GRAVEL (GM): grey, med-coarse grained                                       |           | F°              |                      |
|                 | TC02-P4-3'                            | 0.0 | ₩D           | – Clayey SILT (ML): grey, soft, wet  |           |                 |                      |
|                 |                                       | 0.0 |              |  |           | -               |                      |
| - 5             | "                                     |     |              | – grey; soft, wet  | 2012-00   | <b>—</b> 5      |                      |
| -               | TC02-P4-6.5'                          | 0.0 |              | - grey w/ brown mottling, firm, slightly moist   |           |                 |                      |
|                 | TC02-P4-8.5'                          | 0.0 |              |  |           | -               |                      |
| <u> </u>        |                                       | 4   |              |  |           | 10              |                      |
|                 | TC02-P4-11.5'                         | 0.0 | <b>W</b>     | reddish brown, dry   |           |                 |                      |
| -               |                                       |     |              |  |           | -               |                      |
| 15              | TC02-P4-14.5'                         | 0.0 |              | <ul> <li>Silty SAND (SP): brown w/ grey mottling,<br/>fine—grained, soft, moist</li> </ul> |           | -<br>- 15       |                      |
|                 |                                       |     |              | — SILT (ML): grey, trace fine sand, soft, slightly   |           | _               |                      |
| -               |                                       |     |              | moist Sale, Cort, Signly   |           | -               |                      |
| 20              |                                       |     |              |  |           | - 20            |                      |
| -               | ine "                                 |     |              |  |           | - 20            |                      |
|                 | × ,,                                  |     |              | *  | ¥         | -               |                      |
| 1- 1            |                                       |     |              |  |           |                 |                      |
| _ 25            |                                       |     |              |  |           | - 25            |                      |

| <b>-</b> 0 | $\rightarrow$ |
|------------|---------------|
| _          |               |

WD

Water Level in borehole during drilling (i.e. first encountered)

| NOTES: |  |
|--------|--|
| -      |  |



Bergeson-Boese + Associates, Inc.

32986 Roberts Court Coburg, Oregon 97408 (541) 484-9484 25195 SW Parkway Ave., Suite 207 Wilsonville, Oregon 97070 (503) 570-9484

PAGE\_1 OF\_1

| PROBE NO .:   | P5                 |
|---------------|--------------------|
| PROJECT CODE: | TC02ISC.08UC       |
| CADD FILE:    | TC02ISC.08UC       |
| PROJECT:      | TILLAMOOK CREAMERY |
| LOCATION:     | 2500 LATIMER ROAD  |
|               | TILLAMOOK OR       |

TOTAL DEPTH: 20'

SURFACE ELEVATION: N/A

PROBING METHOD: MACRO CORE

PROBED BY: PACIFIC NORTHWEST DRILLING

LOGGED BY: ERIK CHAPMAN

DATE COMPLETED: 4/29/08

| DEPTH<br>(feet)    | SAMPLE IDENTIFICATION AND LAB RESULTS | PID | H,0<br>LEVEL | LITHOLOGIC DESCRIPTION  LITHOLOGY  DEPTH (feet)  PROBE ABANDONMEN                   |
|--------------------|---------------------------------------|-----|--------------|---|
| F 0                |                                       |     |              | - GRAVEL SURFACE silt, brown  |
|                    | w                                     | 0.0 |              | Clayey SILT (ML): grey w/ orange mottling, dry, soft, no sample due to low recovery |
| 5                  |                                       | 0.0 |              |   |
| F                  |                                       | 0.0 |              |   |
|                    | TC02-P5-8.5'                          | 0.0 |              |   |
| - 10  <sub>T</sub> | CO2-P5-10.5'                          | 0.0 |              | - 10  |
|                    |                                       |     |              |   |
| 15                 |                                       |     |              | Silty SAND (SP): brown, w/ grey mottling, fine-grained sand, slightly moist         |
|                    | CO2-P5-15.5'                          | 0.0 | <b>W</b> P   | soturoted 15  |
|                    |                                       |     |              |   |
| 20                 | ₩                                     |     |              |   |
|                    |                                       |     |              |   |
|                    |                                       |     |              |   |
| _ 25               |                                       | ži) |              | 25  |

| ш | -0 | ΞN | 9 |
|---|----|----|---|
|   |    |    |   |

WD

Water Level in borehole during drilling (i.e. first encountered)

| NOTES | : |      |  |
|-------|---|------|--|
|       |   |      |  |
|       | _ | <br> |  |



Bergeson-Boese + Associates, Inc.
Comprehensive Environmental Services

32986 Roberts Court Coburg, Oregon 97408 (541) 484-9484 25195 SW Porkwoy Ave., Suite 207 Wilsonville, Oregon 97070 (503) 570-9484

# APPENDIX F Historical Groundwater Monitoring and Sample Data Tables (LUST 29-00-0859)

### **GROUNDWATER MONITORING DATA - MONITORING WELLS**

Tillamook Co. Creamery Association 4185 Highway 101 North Tillamook, Oregon 97141 DEQ USTC No. 29-00-0859 DTW = Depth to water WTE = Water Table Elevation Where Shaded = Not Analyzed

Parameters: BTEX, EDB, EDC, MTBE, Lead, Related Volatile Aromatic Hydrocarbons

| Monitori | ng Well MW | -1   |       |      |       |         |       |          |     |     |     |            |             |            | T. T | 7                 |
|----------|------------|------|-------|------|-------|---------|-------|----------|-----|-----|-----|------------|-------------|------------|--|-------------------|
|          |            |      |       | ene  | ene   | benzene | les   | ıthalene |     |     | ш   | olved Lead | ropybenzene | opybenzene | -Trimethylbenzene                        | 5-Trimethybenzene |
| Date     | PVC Elev.  | DTW  | WTE   | Benz | Tolué | Ethylb  | Xyler | Naphtha  | EDB | EDC | MTB | Diss       | d-osi       | n-Pr       | 1,2,4                                    | 1,3,6             |
| 9/25/00  | 100.00     | 6,67 | 93.33 | ND   | ND    | ND      | ND    | ND       | ND  | ND  | ND  | ND         | ND          | ND         | ND                                       | ND                |
| 12/12/00 | 100.00     | 4.88 | 95.12 | ND   | ND    | ND      | ND    | ND       | NA  | NA  | NA  | NA         | NA          | NA         | NA                                       | NA                |
| 3/9/01   | 100.00     | 4.98 | 95.02 | ND   | ND    | ND      | ND    | ND       | NA  | NA  | NA  | NA         | NA          | NA         | NA                                       | NA                |
| 5/30/01  | 100.00     | 5.63 | 94.37 | ND   | ND    | ND      | ND    | ND       | NA  | NA  | NA  | NA         | NA          | NA         | NA                                       | NA                |
| 9/13/01  | 100.00     | 6.40 | 93.60 |      |       |         |       |          |     |     |     |            |             |            |  |                   |
| 12/5/01  | 100.00     | 1.92 | 98.08 |      |       |         |       |          |     |     |     |            |             |            |  |                   |

| Date     | PVC Elev. | DTW  | WTE   | Benzene | Toluene | Ethylbenzene | Xylenes | Naphthalene | ED8 | EDC | MTBE | Dissolved Lead | iso-Propybenzene | n-Propybenzene | 1,2,4-Trimethylbenzene | 1,3,5-Trimethybenzene |
|----------|-----------|------|-------|---------|---------|--------------|---------|-------------|-----|-----|------|----------------|------------------|----------------|------------------------|-----------------------|
| 9/25/00  | 99.40     | 6.75 | 92.65 | ND      | 1.6     | ND           | ND      | ND          | ND  | ND  | ND   | ND             | ND               | ND             | ND                     | ND                    |
| 12/12/00 | 99.40     | 4.79 | 94.61 | ND      | ND      | ND           | ND      | ND          | NA  | NA  | NA   | NA             | NA               | NA             | NA                     | NA                    |
| 3/9/01   | 99.40     | 4.81 | 94.59 | ND      | ND      | ND           | ND      | ND          | NA  | NA  | NA   | NA             | NA               | NA             | NA                     | NA                    |
| 5/30/01  | 99.40     | 5.43 | 93.97 | ND      | ND      | ND           | ND      | ND          | NA  | NA  | NA   | NA             | NA               | NA             | NA                     | NA                    |
| 9/13/01  | 99.40     | 6.35 | 93.05 |         |         |              |         |             |     |     |      |                |                  |                |                        |                       |
| 12/5/01  | 99.40     | 2,10 | 97.30 |         |         |              |         |             |     |     |      |                |                  |                |                        |                       |

|          |           |      |       |         |         |              |         |             |     |     |      | ס             | ene            | ле             | lbenzene             | benzene               |
|----------|-----------|------|-------|---------|---------|--------------|---------|-------------|-----|-----|------|---------------|----------------|----------------|----------------------|-----------------------|
| Date     | PVC Elev. | DTW  | WTE   | Benzene | Toluene | Ethylbenzene | Xylenes | Naphthalene | EDB | EDC | MTBE | Dissolved Lea | iso-Propybenze | n-Propybenzene | 1,2,4-Trimethylbenze | 1,3,5-Trimethybenzene |
| 9/25/00  | 99.91     | 6.79 | 93.12 | ND      | ND      | ND           | ND      | ND          | ND  | ND  | ND   | ND            | ND             | ND             | ND                   | ND                    |
| 12/12/00 | 99.91     | 4.45 | 95.46 | ND      | ND      | ND           | ND      | ND          | NA  | NA  | NA   | NA            | NA             | NA             | NA                   | NA                    |
| 3/9/01   | 99,91     | 4.68 | 95.23 | ND      | ND      | ND           | ND      | ND          | NA  | NA  | NA   | NA            | NA             | NA             | NA                   | NA                    |
| 5/30/01  | 99.91     | 5.32 | 94.59 |         |         |              |         |             |     |     |      |               |                |                |                      |                       |
| 9/13/01  | 99.91     | 6.06 | 93.85 |         |         |              |         |             |     |     |      |               |                |                |                      |                       |
| 12/5/01  | 99.91     | 2.32 | 97.59 |         |         |              |         |             |     |     |      |               |                |                |                      |                       |

| Monitori | ng Well MW | -4   |       |         |         |              |         |             |     |     |      |                |                 |                | ·                      |                       |
|----------|------------|------|-------|---------|---------|--------------|---------|-------------|-----|-----|------|----------------|-----------------|----------------|------------------------|-----------------------|
| Date     | PVC Elev.  | DTW  | WTE   | Benzene | Toluene | Ethylbenzene | Xylenes | Naphthalene | EDB | EDC | MTBE | Dissolved Lead | so-Propybenzene | n-Propybenzene | 1,2,4-Trimethylbenzene | 1,3,5-Trimethybenzene |
| 5/30/01  | 100.25     | 7:18 | 93.07 | 7.0     | ND 4    | 1.0          | ND      | ND          | ND  | 2.2 | ND   | NA             | 3.6             | 2.9            | ND                     | ND                    |
| 9/13/01  | 100.25     | 7.59 | 92.66 | 6.9     | ND      | ND           | 1.3     | ND          | ND  | ND  | ND   | NA             | 1.7             | ND             | 1.2                    | , ND                  |
| 12/5/01  | 100.25     | 2.48 | 97.77 | 5.7     | ND      | 5.6          | ND      | ND          | ND  | 2.0 | ND   | NA             | 3.1             | 3.8            | 1.3                    | ND                    |



www.bergeson-boese.com