

1  
2

# DRAFT FINAL BACKCHECK

## Site Inspection

### Quality Assurance Project Plan Addendum

#### Raymond F. Rees Training Center

#### Hermiston, Oregon

Perfluorooctanesulfonic Acid (PFOS) and  
Perfluorooctanoic Acid (PFOA) Impacted Sites  
ARNG Installations, Nationwide

August 2022

Prepared for:



Army National Guard Bureau  
111 S. George Mason Drive  
Arlington, VA 22204

UNCLASSIFIED



## 4 Table of Contents

1. Introduction
  - 5 1.1 Project Authorization
  - 6 1.2 SI Purpose
  - 7 1.3 QAPP Addendum Organization
- QAPP Worksheets #1 & #2: Title and Approval Page and QAPP Identifying Information  
QAPP Worksheets #3 & #5: Project Organization and QAPP Distribution  
QAPP Worksheets #4, #7 & #8: Personnel Qualifications and Sign-off Sheet  
QAPP Worksheet #6: Communication Pathways  
QAPP Worksheet #9: Technical Project Planning Session Summary  
QAPP Worksheet #10: Conceptual Site Model  
QAPP Worksheet #11: Project/Data Quality Objectives  
Final PQAPP Worksheet #12: Measurement Performance Criteria  
Final PQAPP Worksheet #13: Secondary Data Uses and Limitations  
QAPP Worksheet #14 & #16: Project Tasks and Schedule  
Final PQAPP Worksheet #15: Screening Limits and Laboratory-Specific Detection/  
Quantitation Limits  
QAPP Worksheet #17: Sampling Design and Rationale  
QAPP Worksheet #18: Sampling Locations and Methods  
Final PQAPP Worksheet #19 & #30: Sample Containers, Preservation, and Hold Times  
Final PQAPP Worksheet #20: Field Quality Control Summary  
Final PQAPP Worksheet #21: Field Standard Operating Procedures  
Final PQAPP Worksheet #22: Field Equipment Calibration, Maintenance, Testing, and  
Inspection  
Final PQAPP Worksheet #23: Analytical Standard Operating Procedures  
Final PQAPP Worksheet #24: Analytical Instrument Calibrations  
Final PQAPP Worksheet #25: Analytical Instrument and Equipment Maintenance, Testing  
and Inspection  
Final PQAPP Worksheet #26 & #27: Sample Handling, Custody, and Disposal  
Final PQAPP Worksheet #28: Analytical Quality Control and Corrective Actions  
Final PQAPP Worksheet #29: Project Documents and Records  
Final PQAPP Worksheet #31, #32 & #33: Assessments and Corrective Action  
Final PQAPP Worksheet #34: Data Verification and Validation Inputs  
Final PQAPP Worksheet #35: Data Verification Procedure  
Final PQAPP Worksheet #36: Data Validation Procedures  
Final PQAPP Worksheet #37: Data Usability Assessment
2. References

## 8 **Tables**

9	Table 1-1	Comparison of PQAPP to QAPP Addendum
10	Table 11-1	Groundwater Decision Rules
11	Table 11-2	Soil Decision Rules
12	Table 17-1	Site Inspection Sample Count
13	Table 17-2	Soil Sample Rationale and Target Depths for Borings
14	Table 17-3	Groundwater Sample Rationale and Proposed Screen Intervals

## 15 **Figures**

16	Figure 3-1	Project Organizational Chart
17	Figure 10-1	Facility Location
18	Figure 10-2	Groundwater Features
19	Figure 10-3	Surface Water Features
20	Figure 10-4	Areas of Interest
21	Figure 17-1	Proposed SI Sample Locations – AOI 1 and 2
22	Figure 17-2	Proposed SI Sample Locations – AOI 3

## 23 **Appendices**

24	Appendix A	Technical Project Planning Meeting Minutes (TPP1 and TPP2)
25	Appendix B	Standard Operating Procedures

## 26 Acronyms and Abbreviations

27	°C	degrees Celsius
28	°F	degrees Fahrenheit
29	AECOM	AECOM Technical Services, Inc.
30	AFFF	aqueous film forming foam
31	amsl	above mean sea level
32	AOI	Area of Interest
33	APP	Accident Prevention Plan
34	ARNG	Army National Guard
35	ASTM	American Society for Testing and Materials
36	bgs	below ground surface
37	BRAC	Base Realignment and Closure
38	CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
39	CFR	Code of Federal Regulations
40	CGA	Critical Groundwater Area
41	CoC	chain of custody
42	CPR	cardiopulmonary resuscitation
43	CSM	conceptual site model
44	DA	Department of the Army
45	DL	detection limit
46	DO	dissolved oxygen
47	DoD	Department of Defense
48	DQI	data quality indicators
49	DQO	data quality objectives
50	DUA	Data Usability Assessment
51	ELAP	Environmental Laboratory Accreditation Program
52	ERB	equipment rinsate blank
53	FRB	field reagent blank
54	FTA	fire training area
55	GCAL	Gulf Coast Analytical Laboratories, LLC
56	GPS	global positioning system
57	HAZWOPER	hazardous waste operations and emergency response
58	HDPE	high-density polyethylene
59	IDQTF	Intergovernmental Data Quality Task Force
60	IDW	investigation-derived waste
61	ISC	instrument sensitivity check
62	LC/MS/MS	liquid chromatography tandem mass spectrometry
63	LOD	limit of detection
64	LOQ	limit of quantitation
65	MAES	Multiple Award Environmental Services
66	MDL	method detection limit

67	MPC	measurement performance criteria
68	MRL	method reporting limit
69	MS/MSD	matrix spike/ matrix spike duplicate
70	NELAP	National Environmental Laboratory Accreditation Program
71	ng/L	nanograms per liter
72	NPDES	National Pollutant Discharge Elimination System
73	NTU	nephelometric turbidity units
74	OAR	Oregon Administrative Rules
75	OMD	Oregon Military Department
76	ONG	Oregon National Guard
77	ORARNG	Oregon Army National Guard
78	ORDEQ	Oregon Department of Environmental Quality
79	ORP	oxidation-reduction potential
80	OSD	Office of the Secretary of Defense
81	OSHA	Occupational Safety and Health Administration
82	OWRD	Oregon Water Resources Department
83	PA	Preliminary Assessment
84	PFAS	per- and polyfluoroalkyl substances
85	PFBS	perfluorobutanesulfonic acid
86	PFOA	perfluorooctanoic acid
87	PFOS	perfluorooctanesulfonic acid
88	PFHxA	perfluorohexanoic acid
89	PFUdA	perfluoroundecanoic acid
90	PID	photoionization detector
91	PPE	personal protective equipment
92	PQAPP	Programmatic UFP-QAPP
93	PVC	poly-vinyl chloride
94	PWS ID	Public Water Service Identification
95	QA	quality assurance
96	QAPP	Quality Assurance Project Plan
97	QC	quality control
98	QL	quantitation limit
99	QSM	Quality Systems Manual
100	RI	Remedial Investigation
101	RTC	Raymond F. Rees Training Center
102	RTI	Regional Training Institute
103	SDG	sample delivery group
104	SDT	sonic drilling technology
105	SI	Site Inspection
106	SL	screening level
107	SOP	standard operating procedure
108	SSHP	Site Safety and Health Plan

109	TCRA	Time Critical Removal Action
110	TO	Task Order
111	TOC	total organic carbon
112	TPP	Technical Project Planning
113	TSA	technical system audit
114	UCL	upper confidence limit
115	UCMR 3	Unregulated Contaminant Monitoring Rule 3
116	UFP	Uniform Federal Policy
117	UCD	Umatilla Chemical Depot
118	US	United States
119	USACE	United States Army Corps of Engineers
120	USCS	Unified Soil Classification System
121	USEPA	United States Environmental Protection Agency
122	USGS	United States Geological Survey
123	WWTP	wastewater treatment plant

124

125

THIS PAGE INTENTIONALLY BLANK

## 126 1. Introduction

### 127 1.1 Project Authorization

128 This is the Installation-Specific Addendum to the Army National Guard (ARNG) per- and  
129 polyfluoroalkyl substances (PFAS) Site Inspection (SI) Programmatic Uniform Federal Policy-  
130 Quality Assurance Project Plan (UFP-QAPP). This SI UFP-QAPP Addendum addresses specific  
131 SI activities to be completed at Raymond F. Rees Training Center (RTC) in Hermiston, Oregon.

132 The ARNG G9 is the lead agency in performing *Preliminary Assessments (PAs) and Site*  
133 *Inspections (SIs) for Perfluorooctanesulfonic acid (PFOS) and Perfluorooctanoic acid (PFOA)*  
134 *Impacted Sites at ARNG Facilities Nationwide*. This work is supported by the United States (US)  
135 Army Corps of Engineers (USACE) Baltimore District and their contractor AECOM Technical  
136 Services, Inc. (AECOM) under Contract Number W912DR-12-D-0014, Task Order (TO)  
137 W912DR17F0192, issued 11 August 2017. Programmatic, the ARNG is assessing the  
138 potential environmental impacts primarily from aqueous film forming foam (AFFF) and similar  
139 chemical releases suspected at their properties related to processes that used PFAS (e.g., fire  
140 training, firefighting, and metal plating).

141 The SI project elements will be performed by AECOM in accordance with the Comprehensive  
142 Environmental Response, Compensation, and Liability Act (CERCLA; US Environmental  
143 Protection Agency [USEPA], 1980), as amended, the National Oil and Hazardous Substances  
144 Pollution Contingency Plan (40 Code of Federal Regulations [CFR] Part 300; USEPA, 1994), and  
145 in compliance with US Department of the Army (DA) requirements and guidance for field  
146 investigations, including specific requirements for sampling for PFOA, PFOS,  
147 perfluorobutanesulfonic acid (PFBS), and the group of related compounds known in the industry  
148 as PFAS. The term PFAS will be used throughout this plan to encompass all PFAS being  
149 evaluated, including PFOA, PFOS, perfluorohexanesulfonic acid (PFHxS), perfluorononanoic  
150 acid (PFNA), and perfluorobutanesulfonic acid (PFBS), which are the key components of the  
151 suspected releases being evaluated, and the other 12 related compounds listed in the TO. This  
152 UFP-QAPP Addendum focuses on the SI phase of work specific to RTC (also referred to as the  
153 “facility”) in Hermiston, Oregon.

### 154 1.2 SI Purpose

155 The objective of this SI effort is to identify whether there has been a release to the environment  
156 from the Areas of Interest (AOIs) identified in the PA and determine the presence or absence of  
157 PFOA, PFOS, PFHxS, PFNA, and PFBS at or above screening levels (SLs) at the facility.

158 As stated in the *Federal Facilities Remedial Site Inspection Summary Guide* (USEPA, 2005), an  
159 SI has five goals:

- 160 1) Develop information to potentially eliminate a release from further consideration because  
161 it is determined that it poses no significant threat to human health or the environment.
- 162 2) Determine the potential need for a removal action (i.e., Time Critical Removal Action  
163 [TCRA]; applies to drinking water only).
- 164 3) Collect or develop data to evaluate the release.
- 165 4) Collect additional data to develop the conceptual site model (CSM) in preparation for an  
166 effective Remedial Investigation (RI).

167 5) Collect data to determine whether the release is more than likely the result of activities  
 168 associated with the Department of Defense (DoD).

169 In addition to the USEPA identified goals of an SI, the ARNG SI effort will also aim to evaluate  
 170 whether the concentrations can be attributed to on-facility or off-facility sources that were  
 171 identified within 4 miles of the installation as part of the PA (e.g., fire stations, major manufacturers,  
 172 other DoD facilities).

### 173 1.3 QAPP Addendum Organization

174 Elements of every ARNG PFAS SI are addressed in the SI Programmatic UFP-QAPP (PQAPP)  
 175 (AECOM, 2018). The PQAPP is comprehensive and is consistent with the USEPA's intent that  
 176 the UFP-QAPP be the primary planning document for an entire project (Intergovernmental Data  
 177 Quality Task Force [IDQTF], 2005a-c). This QAPP Addendum, in combination with the PQAPP  
 178 elements, meets the requirements set forth in the UFP for QAPPs (IDQTF, 2005a-c) and USEPA  
 179 *Requirements for Quality Assurance Project Plans* (USEPA, 2001).

180 This QAPP Addendum was prepared to include the detailed information specific to the SI at RTC.  
 181 For ease of review, material from the PQAPP is included in this deliverable alongside the RTC-  
 182 specific worksheets. **Table 1-1** below describes the components that are covered under the  
 183 PQAPP and those that are covered under this UFP-QAPP Addendum.

184 **Table 1-1: Comparison of PQAPP to QAPP Addendum**

QAPP Addendum Worksheets	Applicable Document
Worksheets #1 and #2- Title and Approval Page and QAPP Identifying Information	Programmatic/Site-Specific
Worksheets #3 and #5- Project Organization and QAPP Distribution	Programmatic/Site-Specific
Worksheets #4, #7, #8- Personnel Qualifications and Sign-off Sheet	Programmatic/Site-Specific
Worksheet #6- Communication Pathways	Programmatic/Site-Specific
Worksheet #9- Technical Project Planning Session Summary	Site-Specific
Worksheet #10- Conceptual Site Model	Site-Specific
Worksheet #11- Project/ Data Quality Objectives	Site-Specific
Worksheet #12- Measurement Performance Criteria	Programmatic
Worksheet #13- Secondary Data Uses and Limitations	Programmatic
Worksheets #14 and #16- Project Tasks and Schedule	Site-Specific
Worksheet #15- Screening Limits and Laboratory- Specific Detection/ Quantitation Limits	Programmatic
Worksheet #17- Sampling Design and Rationale	Site-Specific
Worksheet #18- Sampling Locations and Methods	Site-Specific
Worksheets #19 and #30- Sample Containers, Preservation and Hold Times	Programmatic

<b>QAPP Addendum Worksheets</b>	<b>Applicable Document</b>
Worksheet #20- Field Quality Control Summary	<b>Programmatic/Site-Specific</b>
Worksheet #21- Field Standard Operating Procedures	<b>Programmatic</b>
Worksheet #22- Field Equipment Calibration, Maintenance, Testing and Inspection	<b>Programmatic</b>
Worksheet #23- Analytical Standard Operating Procedures	<b>Programmatic</b>
Worksheet #24- Analytical Instrument Calibration	<b>Programmatic</b>
Worksheet #25- Analytical Instrument and Equipment Maintenance, Testing and Inspection	<b>Programmatic</b>
Worksheets #26 and #27- Sample Handling, Custody and Disposal	<b>Programmatic</b>
Worksheet #28- Analytical Quality Control and Corrective Actions	<b>Programmatic</b>
Worksheet #29- Project Documents and Records	<b>Programmatic</b>
Worksheets #31, #32 and #33- Assessments and Corrective Action	<b>Programmatic</b>
Worksheet #34- Data Verification and Validation Inputs	<b>Programmatic</b>
Worksheet #35- Data Verification Procedures	<b>Programmatic</b>
Worksheet #36- Data Validation Procedures	<b>Programmatic</b>
Worksheet #37- Data Usability Assessment	<b>Programmatic</b>

185

THIS PAGE INTENTIONALLY BLANK

186 **QAPP Worksheets #1 & #2: Title and Approval Page and**  
187 **QAPP Identifying Information**

188 **Site Name/Project Name:** Army National Guard/ Multiple Award Environmental Services (MAES)  
189 Delivery Order 00014/ Preliminary Assessments (PA) and Site Inspections (SI) for  
190 Perfluorooctanesulfonic Acid (PFOS) and Perfluorooctanoic Acid (PFOA) Impacted Sites, ARNG  
191 Installations, Nationwide

192  
193 **Installation:** Raymond F. Rees Training Center, Hermiston, Oregon

194  
195 **Contract Work Assignment Number:** USACE Contract No. W912DR-12-D-0014;  
196 Delivery Order No. W912DR17F0192

197 **Relevant Plans and Reports from Previous Investigations:** Relevant plans and reports from  
198 previous investigations are identified in the references cited in the introductory text that precedes  
199 these worksheets and in subsequent worksheets, as appropriate.

200

201  
202 Investigative Organization Project Manager \_\_\_\_\_  
203 Printed Name / Organization Signature / Date  
Claire Mitchell / AECOM Project Manager

204

205  
206 Investigative Organization Quality Manager \_\_\_\_\_  
207 Printed Name / Organization Signature / Date  
Sarah Gettier / AECOM Project QC Officer

208

209  
210 Army National Guard \_\_\_\_\_  
211 Printed Name / Organization Signature / Date  
David Connolly / ARNG Program Manager

212

213  
214 Oregon Army National Guard \_\_\_\_\_  
215 Printed Name / Organization Signature / Date  
James G. Arnold / Environmental Program Manager

216

217  
218 Contract Organization Project Manager \_\_\_\_\_  
219 Printed Name / Organization Signature / Date  
Timothy Peck / USACE, Baltimore District


220

THIS PAGE INTENTIONALLY BLANK

221 **QAPP Worksheets #3 & #5: Project Organization and**  
 222 **QAPP Distribution**

223 The organization chart in **Figure 3-1** identifies key project personnel, as well as lines of authority  
 224 and lines of communication among the ARNG, USACE, and prime contractor (AECOM). The  
 225 QAPP Addendum will be distributed to all parties noted in the figure below. This organization chart  
 226 is consistent with the PQAPP with the exception of the state regulatory personnel.

227 **Figure 3-1 Project Organizational Chart**



228

THIS PAGE INTENTIONALLY BLANK

## 229 QAPP Worksheets #4, #7 & #8: Personnel Qualifications and Sign-off Sheet

230 This worksheet contains a list of the key project personnel who are identified as performing the tasks that are defined in this QAPP  
 231 Addendum and includes the personnel's organization, project role, education/experience, and specialized training/certifications. The  
 232 personnel have signed and dated the worksheet to signify that they agree with the information in this QAPP Addendum and agree to  
 233 implement it.

Name	Organization	Project Role	Education/Experience	Specialized Training / Certifications	Signature/Date
Scott McClelland, PG	AECOM	MAES Program Manager	Education: BA, Geology MS, Geology  Experience: 30+ years; executing and managing environmental investigation and remediation projects including program management of USACE Baltimore contracts.	Professional Geologist, KY AECOM Certified PM	Signature available upon request.
Rosa Gwinn, PG, PhD	AECOM	ARNG Program Manager	Education: BA, Geology MS, Geology PhD, Geology  Experience: 33+ years; managed 4 ORA Phase II TOs of similar scope, complexity, and duration for USACE and ARNG; experience with PFAS investigations.	Professional Geologist, WA, UT AECOM Certified PM OSHA 40hr HAZWOPER OSHA 8hr Refresher AECOM PFAS Sampling Training	Signature available upon request.
Claire Mitchell, PE, PMP	AECOM	Project Manager	Education: BS, Civil Engineering  Experience: 10+ years of environmental engineering experience including task management for PFAS investigations for DoD clients.	Professional Engineer, MO PMP Certification AECOM Certified PM OSHA 40hr HAZWOPER OSHA 8hr Refresher First Aid/ CPR AECOM PFAS Sampling Training	Signature available upon request.

Name	Organization	Project Role	Education/Experience	Specialized Training / Certifications	Signature/Date
Laurie Stenberg, PG	AECOM	Senior Scientist	Education: BA, Geology  Experience: 27+ years; served as senior scientist for ORA Phase II TOs; experience with PFAS investigations.	Professional Geologist, PA AECOM Certified PM OSHA 40hr HAZWOPER OSHA 8hr Refresher AECOM PFAS Sampling Training	Signature available upon request.
Jacquelyn Harrington, CHMM	AECOM	Senior Scientist	Education: BA, Biology  Experience: 27+ years; served as senior scientist for ORA Phase II TOs; MMRP RIs, experience with PFAS investigations.	CHMM AECOM Certified PM OSHA 40hr HAZWOPER OSHA 8hr Refresher OSHA 8hr Supervisor First Aid/CPR AECOM PFAS Sampling Training	Signature available upon request.
Sarah Gettier	AECOM	QC Officer	Education: BS, Civil Engineering, MS Environmental Engineering  Experience: 15+ years direct experience developing QAPPs and other environmental planning documents as a technical leader.	OSHA 40hr HAZWOPER OSHA 8hr Supervisor OSHA 8hr Refresher First Aid/CPR AECOM PFAS Sampling Training	Signature available upon request.
Scott Dietz, CSP, STSC	AECOM	Health and Safety Officer	Education: BS, Safety Sciences  Experience: 23+ years; managing safety, health, and environment on construction, environmental, and remediation projects including government projects requiring compliance with the USACE Engineering Manual 385-1-1.	CSP STSC OSHA 40hr HAZWOPER OSHA 500 Trainer for OSHA for Construction Industry OSHA 510 OSHA Standards for the Construction Industry OSHA 30hr Construction OSHA 10hr Construction OSHA 8hr Refresher	Signature available upon request.

Name	Organization	Project Role	Education/Experience	Specialized Training / Certifications	Signature/Date
Anthony Palmieri, PG	AECOM	SI Senior Lead	Education: BS, Geology  Experience: 15+ years of managing and conducting environmental site investigations, including PFAS, for DoD clients.	Professional Geologist, OR, WA AECOM Certified PM 40hr HAZWOPER OSHA 8hr Refresher 8hr OSHA Supervisor 30hr OSHA Supervisor	Signature available upon request.
Justin Vetter, PG	AECOM	SI Task Manager	Education: BS, Geology MS, Geology  Experience: 9+ years; served as geologist for Phase IIs, RI/Fs, and cleanup actions, including federal projects and large-scale private sector projects and portfolios.	Licensed Geologist, WA OSHA 40hr HAZWOPER OSHA 8hr Refresher OSHA 8hr Supervisor EM-385-1-1 Certified AECOM PFAS Sampling Training	Signature available upon request.
Robert Kennedy	AECOM	Senior Chemist	Education: BA, Chemistry  Experience: 27+ years; served as senior scientist for ORA Phase II TOs; experience with PFAS investigations.	Auditing/Data Review training	Signature available upon request.
Naoum Tavantzis	AECOM	Project Chemist	Education: BA, Environmental Science Masters of Business Administration  Experience: 9+ years; project chemist for ORA Phase II TOs; PFAS investigations, data validation, laboratory coordination.	OSHA 40hr HAZWOPER OSHA 8hr Refresher OSHA 8hr Supervisor AECOM PFAS Sampling Training	Signature available upon request.
Michael Stankevich	AECOM	GIS Specialist	Education: BA, Environmental Studies  Experience: 9+ years; completed SDSFIE submittals for multiple ARNG installations.	ArcGIS Training	Signature available upon request.
Nicole Lancaster	AECOM	Data Management	Education: BS, Marine Biology, MS Chemistry  Experience: 10+ years, experience with data validation, data management, laboratory coordination, and field sampling.	OSHA 40hr HAZWOPER OSHA 8hr Refresher First Aid/CPR AECOM PFAS Sampling Training	Signature available upon request.

Name	Organization	Project Role	Education/Experience	Specialized Training / Certifications	Signature/Date
Gretchen Welshofer	AECOM	Regulatory Specialist	Education: BA, Communication MS, Environmental Science  Experience: 27+ years; performing human health risk assessments; expertise in evaluating potential risks and hazards to human health posed by PFAS at DoD facilities; developed technical approach document that helps facilities manage PFAS-affected environmental media and waste streams; expertise in evaluating contaminant fate and transport for validity of exposure pathways.	NA	Signature available upon request.
Sarah Stinger, PG	AECOM	Technical Quality	Education: BS, Geology MS, Geology  Experience: 33+ years; performing CERCLA investigations; served as task leader and in QA role for ORA Phase II TOs at multiple ARNG installations.	Professional Geologist, VA, PA, LA AECOM Certified PM OSHA 40hr HAZWOPER OSHA 8hr Refresher	Signature available upon request.
Joe Witte	AECOM	Project Coordinator	Education: BS, Environmental Science and Policy  Experience: 4+ years with 2 years direct experience working on ARNG and Army investigations under MMRP and ORA and developing QAPPs.	OSHA 40hr HAZWOPER OSHA 8hr Refresher First Aid/CPR AECOM PFAS Sampling Training	Signature available upon request.
Carolyn Dicharry	Pace Gulf Coast (Formerly GCAL)	Laboratory Project Manager	Education: BS, Geology, post-Baccalaureate in Education  Experience: 30 years in the environmental lab industry – 15 years experience in Quality Assurance; 7 years experience as a Project Manager/client services; 2 years in Data Validation; 2 years as Safety Manager and Waste Coordinator; 8 years in Asbestos laboratory	NA	Signature available upon request.

Name	Organization	Project Role	Education/Experience	Specialized Training / Certifications	Signature/Date
Jacqueline Bendolph	Pace Gulf Coast	Laboratory Quality Manager	Education: BS, Chemistry Experience: 20+ years, organic analysis and sample preparation management.	NA	Signature available upon request.

234 **Notes:**

- 235 AECOM = AECOM Technical Services, Inc.
- 236 ARNG = Army National Guard
- 237 BA = Bachelor of Arts
- 238 BS = Bachelor of Science
- 239 CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act
- 240 CHMM = Certified Hazardous Materials Manager
- 241 CPR = cardiopulmonary resuscitation
- 242 CSP = Certified Safety Professional
- 243 DoD = Department of Defense
- 244 GCAL = Gulf Coast Analytical Laboratories, LLC.
- 245 GIS = Geographic Information System
- 246 HAZWOPER = Hazardous Waste Operations and Emergency Response
- 247 hr = hour
- 248 ITRC= Interstate Technology and Regulatory Council
- 249 KY = Kentucky
- 250 LA = Louisiana
- 251 MAES = Multiple Award Environmental Services
- 252 MC = munitions constituents
- 253 MMRP = Military Munitions Response Program
- 254 MO = Missouri
- 255 MS = Master of Science
- 256 NA = not applicable
- 257 NH = New Hampshire
- 258 OR = Oregon
- 282

- 259 ORA = Operational Range Assessment
- 260 OSHA = Occupational Safety and Health Administration
- 261 PA = Pennsylvania
- 262 PE = Professional Engineer
- 263 PFAS = per- and polyfluoroalkyl substances
- 264 PG = Professional Geologist
- 265 PhD = Doctor of Philosophy
- 266 PM = Project Manager
- 267 PMP = Project Management Professional
- 268 QA = quality assurance
- 269 QAPP = Quality Assurance Project Plan
- 270 QC = quality control
- 271 QSM = Quality Systems Manual
- 272 RI = Remedial Investigation
- 273 SDSFIE = Spatial Data Standards for Facilities Infrastructure and Environment
- 274 SI = Site Inspection
- 275 STSC = Safety Trained Supervisor Construction
- 276 TNI = The NELAC Institute
- 277 TO = Task Order
- 278 USACE = United States Army Corps of Engineers
- 279 UT = Utah
- 280 VA = Virginia
- 281 WA = Washington

THIS PAGE INTENTIONALLY BLANK

## 283 QAPP Worksheet #6: Communication Pathways

284 **Worksheet #6** documents the issues (communication drivers) that trigger the need to communicate with other project personnel or  
 285 stakeholders. The purpose of **Worksheet #6** is to ensure there are procedures in place for providing the appropriate notifications and  
 286 generating the appropriate documentation when handling important communications, including those involving regulatory interfaces,  
 287 unexpected events, emergencies, non-conformances, and stop-work orders.

Communication Driver	Organization	Name	Contact Information	Procedure (Timing, Pathway, Documentation)
Program Manager decisions and modification	USACE, Baltimore District Project Manager	Tim Peck, PG, PMP	410-962-3416 <a href="mailto:timothy.j.peck@usace.army.mil">timothy.j.peck@usace.army.mil</a>	Initiate award of work and options. Track project progress through monthly reporting and daily field reporting. Stop work for quality or performance concerns.
	USACE, Omaha District Project Manager	Steve Gragert, CHMM	402-995-2743 <a href="mailto:steve.p.gragert@usace.army.mil">steve.p.gragert@usace.army.mil</a>	
	USACE, Sacramento District Project Manager	James Lukasko	916-557-5392 <a href="mailto:james.j.lukasko@usace.army.mil">james.j.lukasko@usace.army.mil</a>	
	USACE, Seattle District Project Manager	Briana Niestrom	206-764-3498 <a href="mailto:Briana.C.Niestrom@usace.army.mil">Briana.C.Niestrom@usace.army.mil</a>	
	USACE, Louisville District Project Manager	Steve Kvaal, PMP	502-315-6316 <a href="mailto:Steven.Kvaal@usace.army.mil">Steven.Kvaal@usace.army.mil</a>	
	USACE, Alaska District Project Manager	Andrea Beausang	907-753-2557 <a href="mailto:Andrea.L.Beausang@usace.army.mil">Andrea.L.Beausang@usace.army.mil</a>	
	USACE, Jacksonville District Project Manager	Jennifer Tyler	561-379-2854 <a href="mailto:Jennifer.L.Tyler@usace.army.mil">Jennifer.L.Tyler@usace.army.mil</a>	

Communication Driver	Organization	Name	Contact Information	Procedure (Timing, Pathway, Documentation)
Program Technical Review	ARNG Project Managers	Bonnie Packer, PhD Pamela Hess Joe Davis Rob Halla Amanda Sullivan, MS Jennifer Li	703-607-7977 <a href="mailto:bonnie.m.packer.ctr@army.mil">bonnie.m.packer.ctr@army.mil</a> 208-880-9734 <a href="mailto:pamela.s.hess.mil@army.mil">pamela.s.hess.mil@army.mil</a> 615-791-1139 <a href="mailto:joe.b.davis36.ctr@army.mil">joe.b.davis36.ctr@army.mil</a> 703-607-7995 <a href="mailto:Walter.r.hall2.civ@army.mil">Walter.r.hall2.civ@army.mil</a> 304-642-6000 <a href="mailto:Amanda.d.sullivan7.ctr@army.mil">Amanda.d.sullivan7.ctr@army.mil</a> 301-717-6939 <a href="mailto:jennifer.j.li2.ctr@army.mil">jennifer.j.li2.ctr@army.mil</a>	The AECOM PM will obtain ARNG technical review and concurrence of the QAPP and project documents and any field modifications/QAPP changes as necessary. All approved modifications will be included in QAPP revisions (prior to field work). ARNG technical review and comments will be incorporated into the QAPP and project documents and a record of ARNG comments saved in project files for documentation.
Installation interface	ORARNG	Kelly Toynton, PE	503-559-2775 <a href="mailto:kelly.a.toynton.nfg@army.mil">kelly.a.toynton.nfg@army.mil</a>	Communicate project scope/schedule and coordinate logistics between project team and installation personnel on an as-needed basis, documented via phone records and emails.
Regulatory agency interface (Oregon Department of Environmental Quality)				Communicate technical approaches and decisions directly to regulatory agencies' representative(s) on an as-needed basis, documented via phone records and emails.
Community/ media interface				Communicate information directly to communities or media on an as-needed basis.

Communication Driver	Organization	Name	Contact Information	Procedure (Timing, Pathway, Documentation)
Manage all project phases Field progress reports Field modifications/QAPP changes	AECOM Project Manager	Claire Mitchell, PE, PMP	703-682-9098 <a href="mailto:claire.mitchell@aecom.com">claire.mitchell@aecom.com</a>	All materials and information about the project will be forwarded from the AECOM PM to ARNG/ USACE. Any field or laboratory changes will be coordinated with Briana Niestrom (USACE), Joe Davis (ARNG), and Kelly Toynton (ORARNG). The AECOM PM will obtain ARNG/ USACE approval/ concurrence for field modifications/ QAPP changes as necessary. All approved modifications will be included in QAPP revisions (prior to field work) or field change request forms (during field work), and resolution/ corrective action identified.
	AECOM SI Senior Lead	Anthony Palmieri, PG	206-438-2417 <a href="mailto:anthony.palmieri@aecom.com">anthony.palmieri@aecom.com</a>	Support AECOM PM in implementing SI tasks/procedures. Disseminate programmatic information from PM to SI Task Managers. Serve as lead verifier for SI documents.
	AECOM SI Task Manager	Justin Vetter, PG	206-403-4230 <a href="mailto:justin.vetter@aecom.com">justin.vetter@aecom.com</a>	Responsible for overseeing preparation of SI QAPP and SI Report. Oversee daily activities and site-related communications. Communicate directly with SH&E manager.
	AECOM QC Officer	Sarah Gettier	301-944-0159 <a href="mailto:sarah.gettier@aecom.com">sarah.gettier@aecom.com</a>	Oversee/conduct quality audits to assure field program performed in accordance with approved protocols. Support AECOM PM, Technical Task Manager, and Team Leaders to assure quality reviews are completed on project deliverables, including consistency and conformance with applicable regulatory and DoD guidance and with industry practices. Work with Project Chemist to resolve performance problems with contracted analytical laboratory.
Analytical laboratory modifications and performance problems	AECOM Project Chemist / Data Validator	Naoum Tavantzis	301-267-8761 <a href="mailto:naoum.tavantzis@aecom.com">naoum.tavantzis@aecom.com</a>	Notify AECOM PM and QC Officer in a timely manner of performance problems encountered by the contracted analytical laboratory. PM will secure approval for modifications to the QAPP as necessary from ARNG/ USACE. All approved modifications will be included in Nonconformance and Corrective Action Report.

Communication Driver	Organization	Name	Contact Information	Procedure (Timing, Pathway, Documentation)
Data verification issues (e.g., incomplete records) and data validation issues (e.g., non-compliance with procedures)	AECOM Project Chemist / Data Validator	Naoum Tavantzis	301-267-8761 <a href="mailto:naoum.tavantzis@aecom.com">naoum.tavantzis@aecom.com</a>	Verify/validate all analytical chemistry sample results from analytical laboratories with criteria developed in this QAPP and deliver to the PM and the Project QA Managers.
Data review corrective actions	AECOM Project Chemist / Data Validator	Naoum Tavantzis	301-267-8761 <a href="mailto:naoum.tavantzis@aecom.com">naoum.tavantzis@aecom.com</a>	Notify Laboratory PMs to identify resolution/corrective actions.
Sample receipt variances	Pace Gulf Coast	Carolyn Dicharry	225-769-4900 <a href="mailto:carolyn.dicharry@pacelabs.com">carolyn.dicharry@pacelabs.com</a>	Report all project non-conformances and problems to the AECOM Project Chemist.
Laboratory QC variances				Report all project non-conformances and problems to the AECOM Project Chemist.
Analytical corrective actions				Report all project non-conformances and problems to the AECOM Project Chemist.
Laboratory modifications and performance problems				Report all project non-conformances and problems to the Pace Gulf Coast PM. Pace Gulf Coast PM will report to AECOM Project Chemist.

- 288 **Notes:**  
 289 AECOM = AECOM Technical Services, Inc.  
 290 ARNG = Army National Guard  
 291 DoD = Department of Defense  
 292 PM = Project Manager  
 293 ORARNG = Oregon Army National Guard  
 294 QA = quality assurance  
 295 QAPP = Quality Assurance Project Plan  
 296 QC = quality control  
 297 SH&E = Safety, Health, and Environment  
 298 SI = Site Inspection  
 299 USACE = United States Army Corps of Engineers  
 300

## 301 QAPP Worksheet #9: Technical Project Planning Session 302 Summary

303 This worksheet serves as a record of future Technical Project Planning (TPP) sessions. The intent  
304 is to provide a concise record of participants, key decisions or agreements reached, and action  
305 items. Minutes will be approved by all participants prior to being implemented into the QAPP  
306 Addendum (TPP Meeting Minutes, **Appendix A**).

307 AECOM will implement the TPP process as listed in Engineer Manual 200-1-2 (USACE, 2016)  
308 including facility meetings in a professional and organized manner to obtain consensus on specific  
309 Data Quality Objectives (DQOs) for SI work. Three meetings will be held (in person and/ or  
310 teleconference) per the Performance Work Statement as described below:

- 311 • TPP Meeting 1 - Discuss DQOs (pre-work plan) and CSM
- 312 • TPP Meeting 2 - Finalize work plan technical approach
- 313 • TPP Meeting 3 - Verify all data gaps have been filled and finalize SI Report

314

315

THIS PAGE INTENTIONALLY BLANK

## 316 QAPP Worksheet #10: Conceptual Site Model

317 The information presented in this section was gathered during the PA at RTC. The PA process  
318 included the following tasks:

- 319 • Reviewed data resources to obtain information relevant to suspected PFAS releases;
- 320 • Conducted a site visit on 1 and 2 October 2018;
- 321 • Interviewed current RTC personnel, including Oregon ARNG (ORARNG) and Oregon  
322 Military Department (OMD) personnel during the site visit, ORARNG environmental  
323 managers, operations staff, the OMD Environmental Manager, OMD Cultural Resources  
324 Manager, OMD Wildland Fire Manager, OMD RTC Training Site Manager (former State  
325 Aviation Officer), and OMD Real Estate/Property Manager;
- 326 • Completed visual site inspections at known or suspected PFAS release locations and  
327 documented with photographs;
- 328 • Developed CSM(s) to outline the potential release and pathway of PFAS for the AOIs and  
329 the ARNG facility.

330 The findings of the PA are summarized in this worksheet. Additional details about RTC can be  
331 found in the PA Report (AECOM, 2020).

### 332 Facility Location and Description

333 RTC is located in Morrow and Umatilla Counties, approximately one mile northwest of the  
334 Interstate 82 and Interstate 84 intersection in the City of Hermiston, Oregon, and approximately  
335 eight miles southwest of the City of Umatilla (**Figure 10-1**). The installation encompasses 7,500  
336 acres, including a 170-acre cantonment area used to support the Oregon National Guard's (ONG)  
337 mission of military training (the cantonment area encompasses 170 acres) (State of Oregon,  
338 2021; ONG, 2018). RTC is situated in the southeastern corner of the former Umatilla Chemical  
339 Depot (UCD), which comprises 19,729 acres and spans west into Morrow County (ONG, 2018).

340 The ORARNG has operated an enclave within the UCD since the 1980s for training and  
341 administrative purposes. The fenced-in UCD was formerly an Army Ordnance Depot in operation  
342 from 1941 to 2011, designated as a military munitions and supply depot for World War II,  
343 developed with ammunition storage igloos, warehouses, administrative buildings and barracks,  
344 and has miles of railroad (ONG, 2018). In 1962, the purpose of the UCD changed to receiving,  
345 storing, issuing, and maintaining chemical munitions, resulting in a name change to Umatilla Army  
346 Depot. In 1988, the Base Realignment and Closure (BRAC) Commission listed the UCD for  
347 realignment. From 1990 to 1994, the facility reorganized in preparation for eventual closure,  
348 shipping all conventional ammunition and supplies to other installations. The UCD, at one time,  
349 stored 12 percent (%) of the nation's stockpile of chemical weapons, but no chemical weapons  
350 were used, manufactured, or tested at the UCD.

351 In 1996, the Umatilla Chemical Agent Disposal Facility was constructed to demilitarize chemical  
352 weapons stored at the UCD. In 2005, the UCD was placed on the BRAC list again. In 2011,  
353 chemical weapon incineration was completed, and the incineration plant was demolished. In  
354 2012, the UCD was closed and transferred to inactive operational status in accordance with the  
355 Defense Base Closure and Realignment Act of 1990, Public Law 101-510, as amended, and the  
356 National Defense Authorization Act for Fiscal Year 2012, Public Law 112-81 (Doyle, 2018). The  
357 UCD was reassigned to the US Army Installation Management Command for management. The  
358 US Army Garrison Commander, Joint Base Lewis-McChord, assumed command authority for the

359 UCD and property accountability pending disposal of excess property. Since the UCD's official  
360 closure in 2012, a BRAC-contracted caretaker oversees the UCD pending disposal of multiple  
361 parcels to new owners (planned for commercial and public development and designated wildlife  
362 habitat).

363 In December 2017, the Adjutant General of Oregon and the USACE signed over 7,500 acres of  
364 the former UCD's 19,729 acres to ORARNG to develop Camp Umatilla Oregon, an installation  
365 accommodating weekend and annual training requirements in addition to military units from other  
366 services supporting the ORANRG's federal and state missions in achieving the Army's mission.  
367 Camp Umatilla includes areas for live-fire weapons training, maneuver training, and  
368 classroom/simulations training for units up to battalion size. Camp Umatilla is also home to the  
369 249th Regional Training Institute (RTI) (ONG, 2018).

## 370 Facility Environmental Setting

371 RTC is located in north central Oregon and is situated on the southern edge of the Columbia  
372 Plateau, which extends north into Washington State (approximately three miles to the north of the  
373 facility). The Oregon portion of the plateau is made up entirely of lowlands, extending from the  
374 western Cascade Mountains to the southeastern Blue Mountains. With a generally flat to gently  
375 rolling topography, permeable soil, and minimal precipitation in the region, little to no stormwater  
376 runoff occurs on RTC. The surface elevation at the geographic center of RTC is 570 feet above  
377 mean sea level (amsl); however, the elevation ranges from 400 feet amsl in the north to 677 feet  
378 amsl in the south (ONG, 2018).

379 The prominent surface feature at RTC is the Coyote Coulee, a valley that cuts across the facility.  
380 Land use in the vicinity of RTC is almost exclusively zoned agricultural, with rural-residential areas  
381 located to the northwest, in the City of Irrigon, and east, in the City of Hermiston (USACE, 2013).

## 382 Geology

383 During late Miocene and early Pliocene times (between 14 and 16 million years ago), a fissure  
384 volcanic eruption lead to a series of flood basalts that engulfed the Pacific Northwest, forming a  
385 large igneous province called the Columbia River Basalt Group. The rock group consists of five  
386 major basalt flows, including the Steens Basalt, Imnaha Basalt, Grande Ronde Basalt, Wanapum  
387 Basalt, and Saddle Mountains Basalt. As the molten rock came to the surface, the Earth's crust  
388 gradually sank into the space left by the rising lava, forming the down-warped bedrock surface of  
389 the Dalles-Umatilla Syncline. RTC is near the base of the south flanks of this broad syncline. The  
390 underlying basalt is composed of layers of separate basaltic lava flows, each of which is as much  
391 as 100 feet thick (Whitehead, 1994).

392 The crust subsidence produced a large plateau, slightly depressed lava plain known as the  
393 Columbia Plateau, which covers more than 60,000 square miles. The northwesterly advancing  
394 lava forced the Columbia River into its present course. The Oregon portion of the plateau is made  
395 up entirely of lowlands, extending from the eastern slopes of the Cascade Mountains to the  
396 southern Blue Mountains.

397 These basalts are overlain by as much as 200 feet of Pleistocene alluvial gravel deposits. These  
398 surface deposits are known as the Ordnance Gravels and are comprised of permeable silts,  
399 sands, and gravels, with some cobbles to the west of Coyote Coulee. Much coarser permeable  
400 deposits containing considerable quantities of boulders occur along the east wall of the Coulee  
401 and toward the east side of RTC (USACE, 2013).

402 Soils at RTC consist of very deep, excessively drained sandy loam and coarse sand (**Figure 10-**  
403 **2**). Soil series include Burbank loamy fine sand, Quincy fine sand, and Quincy loamy fine sand.

## 404 [Hydrogeology](#)

405 The Columbia Plateau Basaltic Aquifer system is a regional groundwater resource that occupies  
406 about 50,600 square miles and extends across a small part of northern Idaho, northeastern  
407 Oregon, and a large part of southeastern Washington. The aquifer system is a layered series of  
408 fractured basalt formations of the Columbia River Basalt Group, separated by confining units and  
409 unconsolidated deposits of loose material, all underlain by pre-Miocene rocks (Whitehead, 1994).

410 The groundwater occurs beneath RTC in a number of distinct hydrogeologic units, starting with a  
411 near-surface unconsolidated-deposit aquifer overlying a series of confined basalt aquifers: Saddle  
412 Mountain Basalt, confining unit, Wanapum Basalt, confining unit, Grand Ronde Basalt, and pre-  
413 Miocene rocks (USACE, 2013). Additionally, there is a highly productive permeable unconfined  
414 aquifer to the south of RTC that consists of alluvial deposits and the weathered surface of the  
415 Elephant Mountain Member, basaltic flow of the Saddle Mountain Basalt group. This unit is  
416 overlain by approximately 20 to 125 feet of unsaturated alluvial sand and gravel. Based on a  
417 review of nearby well logs and other available information, depth to groundwater beneath RTC  
418 ranges from approximately 60 to 100 feet below ground surface (bgs) (ambient depth to  
419 groundwater ranges from approximately 50 to 120 feet bgs from the unsaturated alluvial sand and  
420 gravel overlying the unconfined aquifer) (OWRD, 2022; USACE, 2013). Groundwater flow  
421 beneath RTC exhibits seasonal variation due to groundwater extraction for irrigation and recharge  
422 from agricultural canals in the vicinity. In the summer and fall, groundwater flow direction is  
423 generally to the east and south, while in the winter and early spring, groundwater flow direction is  
424 generally to the northwest, towards the Columbia River (USACE, 2013) (**Figure 10-2**).

425 RTC is situated within the Oregon Water Resources Department (OWRD) Ordnance Gravel  
426 Critical Groundwater Area (CGA) and the Ordnance Basalt CGA, both water allocation restrictions  
427 due to overdraft since the 1950s and 1970s, respectively (IRZ Consulting, 2009; OWRD, 2018b).  
428 The Ordnance Gravel CGA within Morrow and Umatilla Counties protects an overlying shallow  
429 sand and gravel aquifer and comprises approximately 82 square miles (OWRD, 2018b). The  
430 Ordnance Basalt CGA, which is situated within Morrow and Umatilla Counties and is centered on  
431 the former Umatilla Ordnance Depot, protects the underlying Columbia River Basalt aquifer and  
432 comprises approximately 175 square miles (OWRD, 2018b). Groundwater levels within the  
433 Ordnance Gravel and Basalt CGAs declined during groundwater development in the 1950s and  
434 1970s, respectively, but have been relatively stable as of recent (OWRD, 2018b). In 2009, the  
435 OWRD, working in conjunction with other state agencies and local planning groups, proposed  
436 increasing water availability within the Ordnance Gravel and Basalt CGAs through the Umatilla  
437 Basin Aquifer Recharge Project that would involve pumping surface water from the Columbia  
438 River and storing it in the CGA aquifer for use during seasonal higher water demand (IRZ  
439 Consulting, LLC, 2009).

440 RTC drinking water is supplied by two groundwater wells withdrawing water from a confined basalt  
441 aquifer at depths ranging from 679 feet bgs to 709 feet bgs (USACE, 2013) (**Figure 10-2**). The  
442 drinking water system serving the UCD Administration Area (Public Water Service Identification  
443 [PWS ID] OR4101136) serves at least 25 residential connections and a population of 124  
444 (USACE, 2013). The drinking water system serving the northern portion of the UCD (PWS ID  
445 OR4194664) serves up to 10 residential connections and a population of 662 (USACE, 2013). As  
446 of 2018, however, the two domestic groundwater wells were not in use (ONG, 2018). The pumping  
447 capacity of these drinking water wells range from 30 to 1,000 gallons per minute, with  
448 approximately 20% of the total capacity of the wells being used for domestic water, and the  
449 remainder used for fire protection (US Fish and Wildlife Service, 2007). According to OMD, plans  
450 have been established to utilize three on-site wells and re-drill two additional wells in the  
451 immediate future for additional drinking water.

452 A total of 120 groundwater monitoring wells have been installed at the facility to-date  
453 (**Figure 10-2**) (USACE, 2013). Groundwater monitoring well data suggest groundwater flow  
454 direction beneath the facility is northward, toward the Columbia River; however, irrigation pumping  
455 of the shallow alluvial aquifer causes groundwater in the south and central portions of facility to  
456 flow in a southern direction during the summer and fall. Historical disposal practices at the  
457 Explosives Washout Lagoons resulted in dissolved-phase explosives constituents in groundwater,  
458 which is currently being remediated by a groundwater pump and treat system (**Figure 10-2**).  
459 Groundwater flow direction north of the cantonment area is locally affected in the vicinity of  
460 treatment system extraction wells and in the vicinity of the treated effluent infiltration field. In  
461 general, groundwater within an extraction well's radius of influence flows radially towards  
462 extraction and flows radially outward from the infiltration field.

463 The alluvial and most shallow basalt aquifers are the main sources of domestic water in the region,  
464 with many irrigation and municipal wells are located more than 500 feet bgs (US Geological  
465 Survey [USGS], 2016). Three municipal water supply systems withdraw groundwater for drinking  
466 water in the vicinity of RTC and include the City of Hermiston (to the east), City of Umatilla (to the  
467 northeast), and City of Irrigon (to the north) (OWRD, 2018a). The City of Hermiston obtains its  
468 drinking water supply from groundwater (shallow and deep wells; deep wells withdraw water from  
469 the Columbia River Basalt aquifer) and surface water (sourced the Lake Walulla segment of the  
470 Columbia River) (City of Hermiston, 2020). The City of Umatilla obtains its drinking water supply  
471 from groundwater (four deep basalt wells) located within the city limits, approximately 6 miles to  
472 the northwest and hydrologically downgradient of RTC (Umatilla, 2019; Umatilla, 2008). The City  
473 of Irrigon obtains its drinking water supply from two groundwater wells located along the Columbia  
474 River, located to the north of RTC (City of Irrigon, 2018). Approximately 1,500 wells are located  
475 within a 4-mile radius of RTC and are mostly used for domestic and irrigation purposes (**Figure**  
476 **10-2**) (USACE, 2013). The Columbia River is a major source of potable and irrigation water in the  
477 region, and is also used for recreation, fishing, and the generation of hydroelectric power. The  
478 Umatilla River, a tributary to the Columbia River, is principally used for irrigation (USACE, 2013).

479 The snowmelt water from the Blue Mountains of Eastern Oregon contributes to the recharge of  
480 deep basalt aquifers underlying the Columbia River Plateau. Overall, recharge is slow due to low  
481 annual precipitation rates in the region, and recharge areas are small relative to the expanse of  
482 the Columbia Plateau. Historically, surface water withdrawals from the Columbia River have been  
483 greater than recharge in many areas, and restrictions have been placed on groundwater in some  
484 parts of this aquifer system as previously described.

485 The Unregulated Contaminant Monitoring Rule (UCMR) sampling program was an addition to the  
486 1996 Safe Drinking Water Act, which requires USEPA issue a new list of no more than 30  
487 unregulated contaminants to be monitored by public water systems every five years (USEPA,  
488 2020). PFAS were added as part of the UCMR 3 list in 2012 (USEPA, 2016a). The UCMR 3  
489 dataset was evaluated to determine which public water systems were sampled for PFAS within a  
490 20-mile radius of the facility. Based on this rule, public drinking water for the cities of Hermiston  
491 and Boardman was sampled in 2014 and 2015, and analytical results for the six PFAS compounds  
492 sampled were non-detect. No other public water system was sampled within 20 miles of the facility  
493 (USEPA, 2017a). PFAS analyses performed in 2014 and 2015 had method detection limits (DLs)  
494 that were higher than currently achievable.

495 Drinking water from water wells at RTC were sampled and analyzed for selected PFAS, including  
496 PFOS, PFOA, PFBS, PFHxS, and PFNA, in 2016 and 2021 and are summarized as follows:

- 497 • October 2016 drinking water samples: Three water wells were sampled on 24 October 2016.  
498 Samples were analyzed by EPA 537. An unvalidated laboratory analytical report, reporting  
499 23 PFAS compounds including PFOS, PFOA, PFHxS, PFNA, and PFBS, indicated that

500 PFOA and PFHxS were detected in all three samples, but at concentrations below the  
501 screening levels presented in the OSD memorandum “Investigating Per- and Polyfluoroalkyl  
502 Substances within the Department of Defense Cleanup Program,” July 6, 2022 (Assistant  
503 Secretary of Defense, 2022).

504 • August 2019 drinking water samples: Two water wells were sampled on 22 August 2019.  
505 Samples were analyzed by EPA 537 Version 1.1. An unvalidated laboratory analytical report  
506 for four water samples and one field duplicate indicates the 14 reported PFAS, including  
507 PFOS, PFOA, PFHxS, PFNA, and PFBS, were not detected above LOQs ranging from 1.7  
508 ng/L to 1.9 ng/L. All LOQs were below screening levels presented in the OSD memorandum  
509 “Investigating Per- and Polyfluoroalkyl Substances within the Department of Defense  
510 Cleanup Program,” July 06, 2022 (Assistant Secretary of Defense, 2022).

511 • December 2021 drinking water samples: Two water wells were sampled on 14 December  
512 2021. Samples were analyzed by EPA 537.1 Version 1.0. An unvalidated laboratory  
513 analytical, reporting 18 PFAS compounds including PFOS, PFOA, PFHxS, PFNA, and  
514 PFBS, indicated that PFOS was detected in one sample, but at a concentration below the  
515 screening levels presented in the OSD memorandum “Investigating Per- and Polyfluoroalkyl  
516 Substances within the Department of Defense Cleanup Program,” July 6, 2022 (Assistant  
517 Secretary of Defense, 2022). All other results were not detected above LOQs ranging from  
518 1.4 ng/L to 1.5 ng/L.

## 519 Hydrology

520 Surface waters infiltrate into permeable soils and may run off onto lower surrounding lands;  
521 therefore, no standing surface water is found at RTC. The nearest surface water features are the  
522 Umatilla River, located approximately 2.5 miles to the east, and the Columbia River, located  
523 approximately 3.5 miles to the north of RTC (**Figure 10-3**).

524 The Umatilla River is an 89-mile tributary of the Columbia River, with headwaters in the Blue  
525 Mountains. Draining a basin of 2,450 square miles, the Umatilla River enters the Columbia River  
526 in the City of Umatilla, approximately 4.5 miles to the northeast of RTC. The Columbia River is  
527 the largest river in the Pacific Northwest. With a drainage area of 258,000 square miles and a  
528 length of 1,243 miles, the Columbia River extends into seven US states and a Canadian province  
529 (British Columbia). Beginning in the Rocky Mountains of British Columbia, Canada, the Columbia  
530 River flows northwest and then south into Washington State, then turns west forming the border  
531 between Washington and Oregon, ultimately discharging into the Pacific Ocean further west.

532 Multiple canal systems surround RTC, including the West Extension Irrigation Canal to the north,  
533 High Line Canal to the south, and Westland Canals F, A, and I to the east. These canals remove  
534 water from the Umatilla River for irrigation of the local agriculture.

535 The central part of RTC lacks well-defined drainage patterns. Minimal stormwater runoff is  
536 generated at RTC; stormwater generally flows into the numerous shallow depressions found in  
537 the flat and gently rolling topography characterized within the region. The most significant  
538 depressions are located at the base of the west-facing bluff of Coyote Coulee, which creates a  
539 natural divide along a portion of the boundary between Patterson Slough – Lake Umatilla  
540 Watershed and the Umatilla River Watershed (**Figure 10-3**). Drainage from several buildings  
541 located at the top of the bluff discharges into these depressions. Surface runoff in the area east  
542 of Coyote Coulee is toward the southern boundary into a shallow, elongated depression running  
543 parallel to the Union Pacific Railroad and Interstate 84 (USACE, 2013).

544 RTC handles and treats all wastewater produced within the facility; a sewage treatment plant,  
545 septic tanks, and drain field systems are located at the facility. RTC operates the wastewater

546 systems in accordance with a National Pollutant Discharge Elimination System (NPDES) permit  
547 and two water pollution control permits issued by the Oregon Department of Environmental  
548 Quality (ORDEQ) (USACE, 2013). Domestic wastewater is run through an oil water separator and  
549 routed to the sewage treatment plant at the south-central part of the facility.

## 550 Climate

551 The climate at RTC is characterized as a dry continental (Canestorp, 2007). Temperatures are  
552 moderated year-round by the Pacific Ocean, with seasonal temperatures at RTC averaging 75  
553 degrees Fahrenheit (°F) in the summer and 35°F in the winter. High temperatures can reach  
554 100°F when air from the Pacific is hindered by predominating stagnant, high-pressure systems in  
555 the north or east in the summer or early fall. The resulting dry and hot southerly air allows for  
556 increased risk of wildfires in the region. Wind in the area tends to be channeled along the  
557 Columbia River valley, in conjunction with a prevailing westerly wind, resulting in a prevailing west-  
558 southwest wind at RTC.

559 Average annual precipitation in the region is 8.85 inches, 60% of which occurs between November  
560 and March. Annual snowfall is approximately 10 inches, with the majority falling between  
561 December and March. Although summer precipitation is unusual, when it does occur, it is usually  
562 in the form of thunderstorms, which can sometimes cause flash flooding.

## 563 Current and Future Land Use

564 During a BRAC meeting to reassess the land space and training needs of the former UCD, a plan  
565 was developed to divide the installation into four parcels: one parcel would be converted into a  
566 wildlife conservation refuge; the second parcel would become an industrial zone to aid in the  
567 economic growth of the area; the third parcel would be taken over by the Oregon Department of  
568 Transportation; and the fourth parcel would be used by the ORARNG as a premier training facility,  
569 known as Camp Umatilla Oregon (now RTC). The OMD invested \$2 million in infrastructure  
570 improvements to the 1940s era installation (Ingersoll, 2018).

571 RTC is currently used for weekend and annual training requirements for the ONG and other  
572 military branches. RTC is home to the ORARNG's 1st Infantry Training Battalion of the 249th  
573 Regional Training Institute and the only certified Army infantry training academy west of the  
574 Mississippi River in the continental US (Koester, 2016).

575 OMD intends to invest in facility improvements including sewer line repairs, a new water  
576 distribution system, road realignments, security fencing, administration and office space  
577 enhancements, new classrooms, as well as barracks for more than 320 soldiers and dining facility  
578 improvements (Ingersoll, 2018). After these improvements, OMD intends to build an infantry  
579 training schoolhouse (McDowell, 2018). RTC is anticipated to remain used for military training  
580 purposes in the future.

## 581 Areas of Interest and Conceptual Site Models

582 PFAS-containing materials were potentially released to soil and groundwater within the boundary  
583 of RTC through fire training exercises and stormwater conveyance. Three AOIs were identified  
584 based on preliminary data and assumed groundwater flow directions. These AOIs are described  
585 below and presented on **Figure 10-4**.

586 In general, the potential routes of exposure to PFAS are ingestion and inhalation. Human  
587 exposure via the dermal contact pathway may occur, and current risk practice suggests it is an  
588 insignificant pathway compared to ingestion; however, exposure data for dermal pathways are  
589 sparse and continue to be the subject of toxicological study.

## 590 AOI 1 Former Fire Training Areas

591 AOI 1 includes the two Former Fire Training Areas (FTAs) within the cantonment area at RTC.  
592 The FTAs, designated FTA 01 and Burn Pit, are both locations where activities occurred that  
593 involved potential PFAS-containing materials. Interviews with facility personnel confirmed AFFF  
594 may have been used at the former FTAs, which are located approximately 300 feet apart from  
595 one another. Based on close proximity and similar historical use, the two FTAs were grouped into  
596 a single AOI (AOI 1).

597 FTA 01 was an area designated for fire training and nozzle practice; however, interviewees could  
598 not confirm whether the foam used during these trainings contained PFAS. It is estimated that the  
599 FTA was used for training occurred between 2003 and 2008; however, the exact duration and  
600 time period are unknown.

601 The Burn Pit area was formerly used regularly throughout the year to conduct controlled burns of  
602 wood and other organic debris. Interviewees recall foam being used during the burns to suppress  
603 flames; however, they could not confirm if the foam used during the burns contained PFAS.

604 Ground-disturbing activities to surface soil at AOI 1 could result in site worker, construction worker,  
605 and trespasser exposure to potential PFAS contamination via ingestion of surface soil or  
606 inhalation of soil particles (dust). Ground-disturbing activities to subsurface soil could result in site  
607 and construction worker exposure. Therefore, the inhalation and ingestion pathways for these  
608 receptors are considered potentially complete for AOI 1.

609 PFAS are water soluble and can migrate readily from soil to the groundwater, which is estimated  
610 to be 60 to 100 feet bgs (USACE, 2013). Because potential PFAS releases to surface soil at AOI  
611 1 have occurred, PFAS may migrate from surface soil to groundwater via leaching. As shown on  
612 **Figure 10-2**, because drinking water wells are located within the facility boundary (a domestic  
613 well is located approximately 1,000 feet to the northwest and hydrologically downgradient of AOI  
614 1), an irrigation well is located outside the facility boundary (approximately 2,000 feet south of AOI  
615 1), and given seasonal variation affecting groundwater flow direction, the ingestion exposure  
616 pathway for groundwater to site workers, construction workers, and off-facility receptors is  
617 considered potentially complete. No surface water features flow through AOI 1; therefore, surface  
618 water and sediment exposure pathways are incomplete.

## 619 AOI 2 Fire Station

620 AOI 2 is the Fire Station, which was constructed in 1941 (ORNG, 2018), within the cantonment  
621 area of RTC known to store PFAS-containing materials. During the site visit on 2018, one 5-gallon  
622 bucket of concentrated AFFF was observed at the Fire Station. AFFF-capable firetrucks were  
623 previously located at RTC, and the AFFF tanks on the firetrucks were refilled using 5-gallon  
624 buckets at the Fire Station. Allegedly, there was no designated staging area for refilling AFFF into  
625 the firetrucks. Additionally, firetrucks were washed outside the Fire Station. The exact location is  
626 unknown; however, the activity likely occurred in the paved area east of the Fire Station or  
627 adjacent to a water spigot northeast of the Fire Station. The time period in which AFFF was stored  
628 or used at the Fire Station is unknown; however, given the history of AFFF use by the military,  
629 AFFF use at the Fire Station dates back to at least 1969 (Interstate Technology and Regulatory  
630 Council, 2020). A stormwater conveyance line is located east of Fire Station with catch basins  
631 southeast and southwest of the Fire Station building. The Fire Station and a floor drain within the  
632 firetruck bay are connected to the sanitary sewer which routes domestic wastewater to the  
633 wastewater treatment plant (WWTP) located approximately one mile to the west of the Fire Station  
634 (OMD, 2018). Stormwater conveyance lines discharge to a ditch near the WWTP.

635 Ground-disturbing activities to surface soil at AOI 2 could result in site worker, construction worker,  
636 and trespasser exposure to potential PFAS contamination via ingestion of surface soil or  
637 inhalation of soil particles (dust). Ground-disturbing activities to subsurface soil could result in site  
638 and construction worker exposure. Therefore, the inhalation and ingestion pathways for these  
639 receptors are considered potentially complete for AOI 2.


640 Because potential PFAS releases to surface soil at AOI 2 have occurred, PFAS may migrate from  
641 the surface soil to the groundwater via leaching. PFAS are water soluble and can migrate readily  
642 from soil to the groundwater, which is estimated to be 60 to 100 feet bgs (USACE, 2013). As  
643 shown on **Figure 10-2**, because drinking water wells are located within the facility boundary (a  
644 domestic well is located approximately 900 feet to the northwest and hydrologically cross-gradient  
645 of AOI 2), and an irrigation well is located outside the facility boundary (approximately 2,000 feet  
646 south of AOI 2), and given seasonal variation affecting groundwater flow direction, the ingestion  
647 exposure pathway for groundwater to site workers, construction workers, and off-facility receptors  
648 is considered potentially complete. No surface water features flow through AOI 2; therefore,  
649 surface water and sediment exposure pathways are incomplete.

### 650 [AOI 3 Wastewater Treatment Plant](#)


651 AOI 3 is the former WWTP west of the RTC cantonment area. RTC managed wastewater via  
652 septic systems, leach fields, and the WWTP in accordance with NPDES and two Water Pollution  
653 Control Facility permits issued by the ORDEQ (USACE, 2013). Domestic wastewater generated  
654 in the cantonment area and all steam cleaning wastewater generated throughout the facility was  
655 formerly discharged into the underground sanitary sewer piping routed to the WWTP (USACE,  
656 2013; OMD, 2018). Steam-cleaning wastewater was pre-treated through an oil/water separator  
657 prior to being routed to the WWTP. The WWTP infrastructure included an Imhoff tank, a standby  
658 Imhoff tank, a sludge drying bed, and a tile field percolation system (AMEC, 2012). Prior to the  
659 WWTP's decommissioning, treated wastewater discharged to the tile field where it dissipated by  
660 evapotranspiration and controlled seepage in accordance with discharge permits. Additionally, the  
661 stormwater conveyance system servicing the cantonment area discharged to an open ditch near  
662 the WWTP (USACE, 2013).

663 Ground-disturbing activities to surface soil at AOI 3 could result in site worker, construction worker,  
664 and trespasser exposure to potential PFAS contamination via ingestion of surface soil or  
665 inhalation of soil particles (dust). Ground-disturbing activities to subsurface soil could result in site  
666 and construction worker exposure. Therefore, the inhalation and ingestion pathways for these  
667 receptors are considered potentially complete for AOI 3.

668 Because potential PFAS releases to surface soil at AOI 3 have occurred, PFAS may migrate from  
669 the surface soil to the groundwater via leaching. PFAS are water soluble and can migrate readily  
670 from soil to the groundwater, which is estimated to be 60 to 100 feet bgs (USACE, 2013). As  
671 shown on **Figure 10-2**, because drinking water wells are located within the facility boundary (a  
672 domestic well is located approximately 1 mile to the east and hydrologically cross-gradient of AOI  
673 3), an irrigation well is located outside the facility boundary (approximately 2,500 feet southeast  
674 of AOI 3), and groundwater flow direction seasonal variations, the ingestion exposure pathway  
675 for groundwater to site workers, construction workers, and off-facility receptors is considered  
676 potentially complete. No surface water features flow through AOI 3; therefore, surface water and  
677 sediment exposure pathways are incomplete.




CLIENT	ARNG			
NOTES	Site Inspection for PFAS at Raymond F. Rees Training Center, OR			
REVISED	3/31/2022	GIS BY	MS	3/31/2022
SCALE	1:316,800	CHK BY	JH	3/31/2022
Base Map: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI,	PM	CM	3/31/2022	



<b>Facility Location</b>	
<b>AECOM</b> 12420 Milestone Center Drive Germantown, MD 20876	<b>Figure 10-1</b>

C:\Users\stankevichm\OneDrive - AECOM Directory\ARNG\_PFAS\_GIS\_60552172\MXD\OR\Camp\_Umatilla\SI\_Figures\SI\_QAPP\Fig\_10-1\_Camp\_Umatilla\_Facility\_Location.mxd




Treatment System	Summer/Fall Inferred Groundwater Flow Direction	<b>Wells</b>
Pump and Treat system approximated radius of influence (extraction and infiltration)	Winter/Spring Inferred Groundwater Flow Direction	Domestic Well
Facility Boundary	<b>Geology</b>	Commercial Well
Umatilla Chemical Depot	Qal - Alluvial	Industrial Well
Water Body	Qgs - Glaciofluvial, Lacustrine, and Pediment Sedimentary Deposits	Irrigation Well
Wetland	Ts - Tuffaceous sedimentary rocks, undifferentiated	Livestock Well
River/Stream		Municipal/Community Well
Canal/Ditch		Monitoring/Observation Well
Pipeline		Other/Unknown Well

CLIENT	ARNG			
NOTES	Site Inspection for PFAS at Raymond F. Rees Training Center, OR			
REVISED	3/31/2022	GIS BY	MS	3/31/2022
SCALE	1:126,720	CHK BY	JH	3/31/2022
Base Map: Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS,	PM	CM	3/31/2022	




<b>Groundwater Features</b>	
<b>AECOM</b>	<b>Figure 10-2</b>
12420 Milestone Center Drive Germantown, MD 20876	

C:\Users\stankevichm\OneDrive - AECOM Directory\ARNG\_PFAS\_GIS\_60552172\MXD\OR\Camp\_Umatilla\SI\_Figures\SI\_QAPP\Fig\_10-2\_Camp\_Umatilla\_Groundwater.mxd




**Legend**

- Facility Boundary
- Umatilla Chemical Depot
- ▶ Surface Water Flow Direction



CLIENT	ARNG			
NOTES	Site Inspection for PFAS at Raymond F. Rees Training Center, OR			
REVISED	3/31/2022	GIS BY	MS	3/31/2022
SCALE	1:126,720	CHK BY	JH	3/31/2022
Base Map: Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS,	PM	CM	3/31/2022	




**Surface Water Features**

12420 Milestone Center Drive  
Germantown, MD 20876

**Figure 10-3**

C:\Users\stankevichm\OneDrive - AECOM Directory\ARNG\_PFAS\_GIS\_60552172\MXD\OR\Camp\_Umatilla\SI\_Figures\SI\_QAPP\Fig\_10-3\_Camp\_Umatilla\_Surface\_water.mxd



**Legend**

- Area of Interest
- Potential PFAS Release
- No Suspected Release
- Facility Boundary
- Umatilla Chemical Depot
- Water Body
- Canal/Ditch
- Surface Water Flow Direction
- Summer/Fall Inferred Groundwater Flow Direction
- Winter/Spring Inferred Groundwater Flow Direction

**Wells**

- Domestic Well
- Commercial Well
- Industrial Well
- Irrigation Well
- Livestock Well
- Municipal/Community Well
- Monitoring/Observation Well
- Other/Unknown Well

CLIENT	ARNG			
PROJECT	Site Inspection for PFAS at Raymond F. Rees Training Center, OR			
REVISED	3/31/2022	GIS BY	MS	3/31/2022
SCALE	1:24,000	CHK BY	JH	3/31/2022
Base Map: Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community		PM	CM	3/31/2022

N

TITLE

**Areas of Interest**

12420 Milestone Center Drive  
Germantown, MD 20876

**Figure 10-4**

## 682 QAPP Worksheet #11: Project/Data Quality Objectives

683 DQOs specify the level of data required to support the decision-making process for a project. Specific DQOs have been established  
684 for each facility and are described in this UFP-QAPP Addendum. These DQOs follow the USEPA's seven-step iterative process for  
685 DQO development. DQOs are influenced by the ongoing project planning discussions with stakeholders and will be updated if new  
686 consensus decisions materialize.

### 687 1. State the Problem

688 The presence of PFAS, which may pose a risk to human health or the environment, in environmental media at the facility is  
689 currently unknown. PFAS are classified as emerging environmental contaminants that are garnering increasing regulatory interest  
690 due to their potential risks to human health and the environment. The regulatory framework for managing PFAS at both the federal  
691 and state level continues to evolve. The DoD has adopted a policy to retain facilities in the CERCLA process based on risk-based  
692 SLs for soil and groundwater, as described in a memorandum from the Office of the Secretary of Defense (OSD) dated 6 July  
693 2022 (Assistant Secretary of Defense, 2022). The ARNG program under which this SI will be performed follows this DoD policy.  
694 Should the maximum concentration for sampled media exceed the SLs established in the OSD memorandum, the AOI will proceed  
695 to the next phase under CERCLA. The SLs established in the OSD memorandum apply to six compounds: PFOS, PFOA, PFBS,  
696 PFHxS, PFNA, and hexafluoropropylene oxide dimer acid (HFPO-DA). The SLs are presented in **Worksheet #15** of this QAPP  
697 Addendum. Of the six PFAS compounds presented in the 6 July 2022 OSD memorandum, HFPO-DA (commonly referred to as  
698 GenX) is not included as an analyte for this SI. HFPO-DA has primarily been used as a replacement for PFOA in the manufacturing  
699 of fluoropolymers, so it is not likely to have been released at the vast majority of DoD properties. However, ARNG will add HFPO-  
700 DA to the list of constituents sampled during the next phase of CERCLA if warranted.

701 The following quotes from the DA policy documents form the basis for this project (DA, 2016; DA, 2018):

- 702 • “The Army will research and identify locations where PFOS and/or PFOA containing products, such as AFFF, are known or  
703 suspected to have been used. Installations shall coordinate with installation/facility fire response or training offices to identify AFFF  
704 use or storage locations. The Army will consider fire training areas, AFFF storage locations, hangars/buildings with AFFF  
705 suppression systems, fire equipment maintenance areas, and areas where emergency response operations required AFFF use  
706 as possible source areas. In addition, metal plating operations, which used certain PFOS-containing mist suppressants, shall be  
707 considered possible source areas.”
- 708 • “Based on a review of site records...determine whether a CERCLA PA is appropriate for identifying PFOS/PFOA release sites. If  
709 the PA determines a PFOS/PFOA release may have occurred, a CERCLA SI shall be conducted to determine presence/absence  
710 of contamination.”
- 711 • “Identify sites where perfluorinated compounds are known or suspected to have been released, with the priority being those sites  
712 within 20 miles of the public systems that tested above USEPA Health Advisory levels.” (USEPA, 2016a, 2016b).

713 **2. Identify the Goals of the Study**

714 The goals of the SI include the following:

- 715 1. Determine the presence or absence of PFOA, PFOS, PFBS, PFHxS, and PFNA at or above SLs at RTC.
- 716 2. Develop information to potentially eliminate a release from further consideration because it is determined that it poses no  
717 significant threat to human health or the environment.
- 718 3. Determine the potential need for a TCRA (applies to drinking water only). The primary actions that will be considered include  
719 provision of alternative water supplies or wellhead treatment.
- 720 4. Collect or develop data to evaluate the release.
- 721 5. Collect data to better characterize the release for more effective and rapid initiation of an RI, if determined necessary.
- 722 6. If PFOA, PFOS, PFBS, PFHxS, and PFNA are determined to be present, aim to evaluate whether the concentrations can be  
723 attributed to on-facility or off-facility sources that were identified within 4 miles of the installation as part of the PA (e.g., fire  
724 stations, major manufacturers, other DoD facilities).

725 **3. Identify Information Inputs**

726 Primary information inputs include:

- 727 • The PA Report for Camp Umatilla (now RTC);
- 728 • Analytical data collected during other environmental sampling efforts at RTC;
- 729 • Groundwater, surface water, soil, and/or sediment (if applicable) sample data collected in accordance with this QAPP Addendum;  
730 and
- 731 • Field data collected including groundwater elevation and water quality parameters measured using a multi-parameter water quality  
732 meter.

733 **4. Define the Boundaries of the Study**

734 The scope of the SI is horizontally bounded by the facility limits of RTC. Off-facility sampling is not included in the scope of this SI;  
735 however, if future off-facility sampling is required, the proper stakeholders will be notified, and necessary rights of entry will be  
736 obtained by ARNG with the property owner(s). Although historical data indicates groundwater may be encountered between 60 to  
737 100 feet bgs, recent drought conditions in the region could result greater depths to groundwater. For planning purposes, an average  
738 depth to groundwater of 150 feet bgs is assumed for the AOCs. The scope of the SI is vertically bounded as follows: groundwater  
739 (150 feet bgs), subsurface soil from sonic drilling technology (SDT) borings (15 feet bgs and 150 feet bgs) and surface soil (0 to 2

740 feet bgs). The temporal boundaries of the study are limited by seasonal conditions; the field work for the scope will be performed  
741 Summer/Fall 2022.

742 **5. Develop the Analytic Approach**

743 Samples will be analyzed by a DoD Environmental Laboratory Accreditation Program (ELAP) and NELAP certified laboratory [i.e.,  
744 Pace Gulf Coast (formerly Gulf Coast Analytical Laboratories, LLC [GCAL])]. Data will be compared to SLs (**Worksheet #15**), and  
745 decision rules as defined in the PQAPP will be applied concerning actions to be taken based on any SL exceedances. Decision  
746 rules have been developed for groundwater and soil that will apply to all data collected. These rules will govern response actions  
747 based on the results of the SI sampling effort.

748 The decision rules described in the tables at the end of this section (**Tables 11-1** and **11-2**) identify actions based on the following:

749 Groundwater:

- 750 1. Is there a human receptor within 4 miles of the facility?
- 751 2. What is the concentration of PFOA, PFOS, PFBS, PFHxS, and PFNA at the potential source area?
- 752 3. What is the concentration of PFOA, PFOS, PFBS, PFHxS, and PFNA at the boundary?
- 753 4. What does the CSM suggest in terms of source, pathway, and receptor?

754 Soil:

- 755 1. What is the concentration of PFOA, PFOS, PFBS, PFHxS, and PFNA in shallow surface soil (0-2 feet bgs)?
- 756 2. What is the concentration of PFOA, PFOS, PFBS, PFHxS, and PFNA in soil (i.e., capillary fringe) (60-95 feet bgs)?
- 757 3. What does the CSM suggest in terms of source, pathway, and receptor?

758 Soil and groundwater samples will be collected from potential source areas identified in **Worksheet #10**. Based on hydrogeologic  
759 information and recent drought conditions, groundwater is expected to be encountered at approximately 150 feet bgs. The regional  
760 aquifer is significantly deeper (greater than 500 feet bgs) and will not be subject to drilling during this investigation. Proposed SI  
761 sample locations and depths are defined in **Worksheet #17**.

762 **6. Specify Performance/Acceptance Criteria**

763 See **Worksheet #37**.

764 **7. Develop the Detailed Plan for Obtaining Data**

765 See **Worksheet #17** and **#18**.

766

THIS PAGE INTENTIONALLY BLANK

767

**Table 11-1: Groundwater Decision Rules**

Scenario	PFAS Concentration Range	Response (Off-facility human receptor within 4 miles)	Response (No off-facility human receptor within 4 miles)
Scenario 1	ND	No further action required during SI phase.	No further action required during SI phase.
Scenario 2	> ND (any positive detection)  and  < SLs	1.) Assess CSM including: - Data reliability and bias - Migration via groundwater flow (i.e., groundwater flow towards potential receptors) - Flow to surface water bodies, drinking water intakes - Distance from boundary to receptor - Aquifer where drinking water well(s) are screened - Estimated timeframe of release(s)  2.) No further action during SI Phase at this time. ARNG may consider need for additional evaluation in the future for groundwater.	1.) Assess CSM as described.  2.) No further action during SI Phase at this time. ARNG may consider need for additional evaluation in the future for groundwater.
Scenario 3	> SLs	1.) Assess CSM as described above and: - Potential off-facility alternative PFAS sources  2.) If exceedance of SLs is near facility boundary and the assessment of the CSM implies unacceptable risk to human health caused by a PFAS release attributable to ARNG activities, ARNG may initiate off-facility sampling protocol.  3.) Proceed to RI.	1.) Assess CSM as described.  2.) Proceed to RI.

- 768 **Notes:**  
 769 < = less than  
 770 > = greater than  
 771 ARNG = Army National Guard  
 772 CSM = conceptual site model  
 773 ND = non-detect  
 774 PFAS = per- and polyfluoroalkyl substances  
 775 RI = Remedial Investigation  
 776 SI = Site Inspection  
 777 SL = screening level

778

**Table 11-2: Soil Decision Rules**

Scenario	PFAS Concentration Range	Response
Scenario 1	ND	No further action during SI Phase.
Scenario 2	> ND (any positive detection) and < SLs	15.) Assess CSM including: Potential for particulate runoff (i.e., transport via surface water) Nearby receptors and land use (residential or industrial/commercial worker) at the source location (i.e., potential for incidental ingestion) Depth to groundwater; distance to nearby surface water body Comparison of soil concentrations to groundwater concentrations at the source or nearby surface water body - Data reliability and bias  2.) No further action for soil during SI Phase at this time. ARNG may consider need for additional evaluation in the future.
Scenario 3	> SLs	1.) Assess CSM as above and: Comparison of soil concentrations to groundwater concentrations at the source and downgradient at the boundary 2.) Proceed to RI.

779  
 780  
 781  
 782  
 783  
 784  
 785  
 786  
 787  
 788

**Notes:**  
 < = less than  
 > = greater than  
 ARNG = Army National Guard  
 CSM = conceptual site model  
 ND = non-detect  
 PFAS = per- and polyfluoroalkyl substances  
 RI = Remedial Investigation  
 SI = Site Inspection  
 SL = screening level

## 789 Final PQAPP Worksheet #12: Measurement Performance Criteria

**Matrix** Groundwater/ Potable Wells  
**Analytical Group** PFAS  
**Concentration** Low

Data Quality Indicators	Measurement Performance Criteria	QC Sample and/or Activity Used to Assess Measurement Performance	QC Sample Assesses Error for S, A or Both (S&A)
Accuracy/Bias	LCS/LCSD and MS/MSD shall be spiked with all analytes. Analyte recovery limits per Worksheet #15	LCS/LCSD, MS/MSD	A
Precision	Laboratory duplicates analysis should have an RPD < 30%	LCS/LCSD, MS/MSD	A
Precision	Values > 5X LOQ: RPD must be ≤ 30% Values ≤ 5X LOQ: Absolute difference ≤ 2x the LOQ	Field Duplicates	S
Accuracy/Contamination	No analytes detected > ½ LOQ or > 1/10 the amount measured in any sample or 1/10 the regulatory limit, whichever is greater	Method Blank, Field Reagent Blanks, Equipment Rinsate Blanks	A
Sensitivity	Detection limits ≤ to acceptance criteria Instrument Sensitivity Check concentrations must be within ±30% of their true values.	Detection Limits, Instrument Sensitivity Check	A
Completeness	Completeness criteria will be considered met if 100% of all planned sample data (as requested on CoC in lab reports and EDD; including requested reanalyses) are collected	Reported Sample Data	S & A
Comparability	Based on accuracy and media comparison	Use of standardized SOPs in field and laboratory	S & A
Comparability	Serial dilution preparation (allowed due to known high concentrations of PFAS, notation of 'foamed' on CoC is considered documented approval)	Field shake test	S & A
Representativeness	Samples met conditions per Worksheet #19/30	Laboratory Receipt Checklist, Cooler Temperature Blank	S

- 790 **Notes:**  
 791 % = percent  
 792 A = analytical  
 793 CoC = chain of custody  
 794 EDD = electronic data deliverable  
 795 LCS/LCSD = laboratory control spike/ laboratory control spike duplicate  
 796 LOQ = limit of quantitation  
 797 MS/MSD = matrix spike/ matrix spike duplicate
- < = less than  
 > = greater than  
 ≤ = less than or equal to  
 QC = quality control  
 RPD = relative percent difference  
 S = sampling  
 SOP = standard operating procedure

**Matrix** Soil and Sediment  
**Analytical Group** PFAS  
**Concentration** Low

Data Quality Indicators	Measurement Performance Criteria	QC Sample and/or Activity Used to Assess Measurement Performance	QC Sample Assesses Error for Sampling (S), Analytical (A) or Both (S&A)
Accuracy/Bias	LCS/LCSD and MS/MSD shall be spiked with all analytes. Analyte recovery limits per Worksheet #15	LCS, LCSD, MS, MSD	A
Precision	Laboratory duplicates analysis should have a RPD < 30%	LCS/LCSD, MS/MSD	A
Precision	Values > 5X LOQ: RPD must be ≤ 30% Values ≤ 5X LOQ: Absolute difference ≤ 2x the LOQ	Field Duplicates	S
Accuracy/ Contamination	No analytes detected > ½ LOQ or > 1/10 the amount measured in any sample or 1/10 the regulatory limit, whichever is greater	Method Blank, Field Reagent Blanks, Equipment Rinsate Blanks	A
Sensitivity	Detection limits ≤ to acceptance criteria Instrument Sensitivity Check concentrations must be within ±30% of their true values.	Detection Limits, Instrument Sensitivity Check	A
Completeness	Completeness criteria will be considered met if 100% of all planned sample data (as requested on CoC in lab reports and EDD; including requested reanalyses) are collected	Reported Sample Data	S & A
Comparability	Based on accuracy and media comparison	Use of standardized SOPs in field and laboratory	S & A
Representativeness	Samples met conditions per Worksheet #19/30	Laboratory Receipt Checklist, Cooler Temperature Blank	S

- 798 **Notes:**
- 799 < = less than
- 800 > = greater than
- 801 ≤ = less than or equal to
- 802 A = analytical
- 803 CoC = chain of custody
- 804 EDD = electronic data deliverable
- 805 LCS/LCSD = laboratory control spike/ laboratory control spike duplicate
- 806 LOQ = limit of quantitation
- 807 MS/MSD = matrix spike/ matrix spike duplicate
- 808 QC = quality control
- 809 RPD = relative percent difference
- 810 S = sampling
- 811 SOP = standard operating procedure

## 812 Final PQAPP Worksheet #13: Secondary Data Uses and Limitations

813 Secondary data sources, uses, and limitations are tabulated below. Original source documents were reviewed for uncertainty discussions  
 814 that may identify additional or more suitable data limitations.

Data Type	Source	Data Uses Relative to Current Project	Factors Affecting Reliability of Data and Limitations on Data Use
Meteorological	National Weather Service	Estimates of seasonal fluctuations in precipitation.	Meteorological data is generally for a regional area. Actual site conditions may vary.
Topographic	USGS	Inferred surface water based on local topography at each site. Groundwater flow maps will ultimately rely upon groundwater measurements from monitoring wells.	Topography of some sites may have been altered by building or grading activities.
Soil and groundwater chemistry, groundwater monitoring data, and data gaps identification	Historical site reports	Applicable to the evaluation of historical site conditions in soil and groundwater to supplement data being collected under this delivery order.	The data may not represent current conditions because of the age of some of the data. Reliability of second- or third-party data quality.
Historical site records (i.e., material inventories)	Purchase records, site inventories, onsite records, safety data sheets	Applicable to the evaluation of potential constituents of concern and source areas.	Records may be incomplete or inaccurate.
Periodicals (i.e., news articles)	Local newspapers, magazines or other periodicals	Applicable to the evaluation of the use of potential constituents of concern at off-facility locations or mutual use/ aid agreements with local fire department or other entities.	Records may be incomplete or inaccurate.

815 **Notes:**  
 816 USGS = United States Geological Survey

817

THIS PAGE INTENTIONALLY BLANK

## 818 QAPP Worksheet #14 & #16: Project Tasks and Schedule

819 The following table describes the main tasks and schedule for the SI:

Task	Start Date	End Date
<b>Pre-mobilization</b>	July 2022	July 2022
<b>Mobilization</b>	July 2022*	July 2022*
<b>Field Work</b>	July 2022*	July 2022*
<b>Demobilization</b>	August 2022*	August 2022*
<b>Data Review/Validation</b>	September 2022	September 2022
<b>Reporting</b>	October 2022	February 2023

820 Notes:  
821 \* Weather permitting

822

THIS PAGE INTENTIONALLY BLANK

823 **Final PQAPP Worksheet #15: Screening Limits and Laboratory-Specific**  
 824 **Detection/Quantitation Limits**

825 **Matrix: Groundwater/ Potable Wells**

826 **Analyte Group: PFAS**

827 **Method: PFAS by LC/MS/MS compliant with QSM 5.3 Table B-15**

Analyte	CAS Number	Laboratory Control Spike Lower Control Limit (%)	Laboratory Control Spike Upper Control Limit (%)	Achievable Laboratory Limits		
				DL (ng/L)	LOD (ng/L)	LOQ (ng/L)
Perfluorooctanesulfonic acid (PFOS)	1763-23-1	65	140	0.81	4.0	10
Perfluoroheptanoic acid (PFHpA)	375-85-9	72	130	0.48	4.0	10
Perfluorohexanesulfonic acid (PFHxS)	355-46-4	68	131	0.95	4.0	10
Perfluorononanoic acid (PFNA)	375-95-1	69	130	0.78	4.0	10
Perfluorooctanoic acid (PFOA)	335-67-1	71	133	0.95	4.0	10
Perfluorobutanesulfonic acid (PFBS)	375-73-5	72	130	0.81	4.0	10
Perfluorobutanoic acid (PFBA)	375-22-4	73	129	0.90	4.0	10
Perfluoropentanoic acid (PFPeA)	2706-90-3	72	129	0.85	4.0	10
N-ethyl perfluorooctanesulfonamidoacetic acid (NEtFOSAA)	2991-50-6	61	135	0.97	8.0	10
N-methyl perfluorooctanesulfonamidoacetic acid (NMeFOSAA)	2355-31-9	65	136	0.91	8.0	10
Perfluorodecanoic acid (PFDA)	335-76-2	71	129	0.86	4.0	10
Perfluorotetradecanoic acid (PFTeDA)	376-06-7	71	132	0.98	4.0	10
Perfluorododecanoic acid (PFDoA)	307-55-1	72	134	0.88	4.0	10
Perfluorohexanoic acid (PFHxA)	307-24-4	72	129	0.99	4.0	10
Perfluorotridecanoic acid (PFTrDA)	72629-94-8	65	144	0.99	4.0	10
Perfluoroundecanoic acid (PFUdA)	2058-94-8	69	133	0.95	4.0	10
6:2 Fluorotelomer sulfonic acid (6:2 FTS)	27619-97-2	64	140	0.94	4.0	10
8:2 Fluorotelomer sulfonic acid (8:2 FTS)	39108-34-4	67	138	0.90	4.0	10

828 **Notes:**

829 % = percent

830 CAS = Chemical Abstracts Service

831 DL = detection limit

832 LC/MS/MS = liquid chromatography tandem mass spectrometry

833 LOD = limit of detection

834 LOQ = limit of quantitation

835 ng/L = nanograms per liter

836 PFAS = per- and polyfluoroalkyl substances

837 QSM = Quality Systems Manual

838 USEPA = United States Environmental Protection Agency

839 **Matrix: Soil/Sediment**  
 840 **Analyte Group: PFAS**  
 841 **Method: PFAS by LC/MS/MS compliant with QSM 5.3 Table B-15**

Analyte	CAS Number	Laboratory Control Spike Lower Control Limit (%)	Laboratory Control Spike Upper Control Limit (%)	Achievable Laboratory Limits		
				DL (µg/kg)	LOD (µg/kg)	LOQ (µg/kg)
Perfluorooctanesulfonic acid (PFOS)	1763-23-1	68	136	0.194	0.40	1.0
Perfluoroheptanoic acid (PFHpA)	375-85-9	71	131	0.078	0.40	1.0
Perfluorohexanesulfonic acid (PFHxS)	355-46-4	67	130	0.122	0.40	1.0
Perfluorononanoic acid (PFNA)	375-95-1	72	129	0.062	0.40	1.0
Perfluorooctanoic acid (PFOA)	335-67-1	69	133	0.059	0.40	1.0
Perfluorobutanesulfonic acid (PFBS)	375-73-5	72	128	0.071	0.40	1.0
Perfluorobutanoic acid (PFBA)	375-22-4	71	135	0.046	0.40	1.0
Perfluoropentanoic acid (PFPeA)	2706-90-3	69	132	0.054	0.40	1.0
N-ethyl perfluorooctanesulfonamidoacetic acid (NEtFOSAA)	2991-50-6	61	139	0.097	0.40	1.0
N-methyl perfluorooctanesulfonamidoacetic acid (NMeFOSAA)	2355-31-9	63	144	0.196	0.40	1.0
Perfluorodecanoic acid (PFDA)	335-76-2	69	133	0.041	0.40	1.0
Perfluorotetradecanoic acid (PFTeDA)	376-06-7	69	133	0.119	0.40	1.0
Perfluorododecanoic acid (PFDoA)	307-55-1	69	135	0.101	0.40	1.0
Perfluorohexanoic acid (PFHxA)	307-24-4	70	132	0.043	0.40	1.0
Perfluorotridecanoic acid (PFTrDA)	72629-94-8	66	139	0.119	0.40	1.0
Perfluoroundecanoic acid (PFUdA)	2058-94-8	64	136	0.011	0.40	1.0
6:2 Fluorotelomer sulfonic acid (6:2 FTS)	27619-97-2	64	140	0.066	0.40	1.0
8:2 Fluorotelomer sulfonic acid (8:2 FTS)	39108-34-4	65	137	0.122	0.40	1.0

842 **Notes:**  
 843 % = percent  
 844 µg/kg = micrograms per kilogram  
 845 CAS = Chemical Abstracts Service  
 846 DL = detection limit  
 847 LC/MS/MS = liquid chromatography with tandem mass spectrometry  
 848 LOD = limit of detection  
 849 LOQ = limit of quantitation  
 850 PFAS = per- and polyfluoroalkyl substances  
 851 QSM = Quality Systems Manual  
 852 USEPA = United States Environmental Protection Agency

853 **Matrix: Soil**  
 854 **Analyte Group: Wet Chemistry**

Analyte	Method	Laboratory Control Spike Lower Control Limit (%)	Laboratory Control Spike Upper Control Limit (%)	Achievable Laboratory Limits		
				DL (mg/kg)	LOD (mg/kg)	LOQ (mg/kg)
Total Organic Carbon	9060A	90	110	150	200	250

855 **Notes:**  
 856 % = percent  
 857 DL = detection limit  
 858 LOD = limit of detection  
 859 LOQ = limit of quantitation  
 860 mg/kg = milligrams per kilogram  
 861 NA = not applicable

862 **SLs for Soil and Groundwater**

863 The DoD has adopted a policy to retain facilities in the CERCLA process based on conservative SLs for soil and groundwater, as  
 864 described in a memorandum from the OSD dated 6 July 2022 (Assistant Secretary of Defense, 2022). The ARNG program under which  
 865 this SI will be performed follows this DoD policy and should the maximum concentration for sampled media exceed the SLs established  
 866 in the OSD memorandum, the AOI will proceed to the next phase under CERCLA. The SLs established in the OSD memorandum apply  
 867 to six compounds: PFOA, PFOS, PFBS, PFHxS, PFNA, and HFPO-DA.

Analyte	CAS Number	Residential (Soil) (µg/kg) <sup>a,b,c</sup> 0-2 feet bgs	Industrial/ Commercial Composite Worker (Soil) (µg/kg) <sup>a,b,c</sup> 2 -15 feet bgs	Tap Water (Groundwater) (ng/L) <sup>a,c</sup>
Perfluorooctanesulfonic acid (PFOS)	1763-23-1	13	160	4
Perfluoroheptanoic acid (PFHpA)	375-85-9	-	-	-
Perfluorohexanesulfonic acid (PFHxS)	355-46-4	130	1,600	39
Perfluorononanoic acid (PFNA)	375-95-1	19	250	6
Perfluorooctanoic acid (PFOA)	335-67-1	19	250	6
Perfluorobutanesulfonic acid (PFBS)	375-73-5	1,900	25,000	601
Perfluorobutanoic acid (PFBA)	375-22-4	-	-	-
Perfluoropentanoic acid (PFPeA)	2706-90-3	-	-	-
N-ethyl perfluorooctanesulfonamidoacetic acid	2991-50-6	-	-	-
N-methyl perfluorooctanesulfonamidoacetic acid	2355-31-9	-	-	-
Perfluorodecanoic acid (PFDA)	335-76-2	-	-	-
Perfluorotetradecanoic acid (PFTeDA)	376-06-7	-	-	-
Perfluorododecanoic acid (PFDoA)	307-55-1	-	-	-
Perfluorohexanoic acid (PFHxA)	307-24-4	-	-	-
Perfluorotridecanoic acid (PFTTrDA)	72629-94-8	-	-	-
Perfluoroundecanoic acid (PFUdA)	2058-94-8	-	-	-
6:2 Fluorotelomer sulfonic acid (6:2 FTS)	27619-97-2	-	-	-
8:2 Fluorotelomer sulfonic acid (8:2 FTS)	39108-34-4	-	-	-

868

869

**Notes:**

870

a.) Assistant Secretary of Defense, 2022. Risk Based Screening Levels in Groundwater and Soil using USEPA's Regional Screening Level Calculator. Hazard Quotient (HQ) = 0.1. 6 July 2022.

871

b.) The SLs for soil are based on incidental ingestion of soil applied to the soil intervals reasonably anticipated to be encountered; surface soil (0 to 2 feet bgs for the residential scenario) and subsurface soil (2 to 15 feet bgs for the industrial/commercial worker scenario).

872

873

c.) Of the six PFAS compounds presented in the 6 July 2022 OSD memorandum, HFPO-DA (commonly referred to as GenX) was not included as an analyte for this SI. However, ARNG will add HFPO-DA to the list of constituents sampled during the next phase of CERCLA if warranted.

874

875

876

µg/kg = micrograms per kilogram

877

bgs = below ground surface

878

CAS = Chemical Abstracts Service

879

ng/L = nanograms per liter

880

OSD = Office of the Secretary of Defense

881

SL = screening level

882

883

884

THIS PAGE INTENTIONALLY BLANK

## 885 QAPP Worksheet #17: Sampling Design and Rationale

886 **Worksheet #17a-f** describes the sampling design, basis for its selection, and field investigation  
887 details. Field activities will be completed per the Standard Operating Procedures (SOPs) in  
888 **Appendix B**.

889 The objective of the SI is to identify whether there has been a release to soil and groundwater (if  
890 present) at each AOI and determine the presence or absence of PFOA, PFOS, PFBS, PFHxS,  
891 and PFNA at or above SLs. As discussed in **Worksheet #10**, three AOIs were identified at RTC.  
892 Regional groundwater flow at RTC is generally to the northwest; however, seasonal variation  
893 exists: in the summer and fall, groundwater flow direction is generally to the east and south, while  
894 in the winter and early spring, groundwater flow direction is generally to the northwest towards  
895 the Columbia River.

896 • AOI 1: Sometime between 2003 and 2008 (exact time period is unknown), AFFF was used  
897 at former FTA 01 and a Burn Pit located approximately 100 yards from one another. FTA  
898 01 was designated for fire training and nozzle practice, and the Burn Pit was used regularly  
899 throughout the year for controlled burns of wood and other organic debris. Interviewees  
900 recall foam being used during the burns to suppress flames; however, it could not be  
901 confirmed if the foam used during the burns contained PFAS.

902 • AOI 2: Since approximately 1969, AFFF was stored at the Fire Station in 5-gallon buckets.  
903 AFFF tanks on firetrucks at the Fire Station were manually refilled with concentrated AFFF  
904 from 5-gallon buckets in a non-designated location. Firetrucks were also washed outside  
905 the Fire Station. The exact locations are unknown but are likely to have occurred in front  
906 (east) of the Fire Station or near a water spigot northeast of the Fire Station.

907 • AOI 3: Since 1941 and prior to its decommissioning, the WWTP had handled domestic  
908 wastewater from the cantonment area and steam cleaning wastewater generated  
909 throughout the facility (AMEC, 2012). Steam-cleaning wastewater was treated through an  
910 oil/water separator prior to being routed to the WWTP via underground sanitary sewer. The  
911 WWTP infrastructure included an Imhoff tank, a standby Imhoff tank, a sludge drying bed,  
912 and a tile field percolation system (AMEC, 2012). Treated wastewater was discharged to  
913 the tile field, where it dissipated by evapotranspiration and controlled seepage. PFAS-  
914 containing wastewater discharged to the WWTP has not been confirmed; however, potential  
915 PFAS-containing liquids were likely discharged into floor drains and sinks connected to the  
916 sanitary sewer piping routed to the WWTP (AMEC, 2012). Additionally, the stormwater  
917 conveyance system service the cantonment area discharged to an open ditch adjacent to  
918 the WWTP. Potential AFFF releases at the Fire Station could have been captured as  
919 domestic wastewater or stormwater and discharged to the tile field or ditch.

920 Environmental media samples will be collected from the AOIs in accordance with the applicable  
921 CSM, as summarized in **Table 17-1**. Permanent monitoring wells will be installed at and within  
922 the vicinity where PFAS were potentially released.

923 In instances where deviations from this sampling design and rationale are made due to  
924 unforeseen conditions, a Field Change Request Form will be generated to document the change  
925 and request feedback from the AECOM Task and Project Managers, USACE, and ARNG.

926 **Sampling Tasks**

927 The field program will include tasks as detailed in the following Worksheet elements:

- 928 • **Worksheet #17a** – Mobilization
- 929 • **Worksheet #17b** – Sonic Drilling Boring Installation and Soil Sampling
- 930 • **Worksheet #17c** – Permanent Groundwater Monitoring Well Installation and Groundwater
- 931 Sampling
- 932 • **Worksheet #17d** – Synoptic Water Level Measurements
- 933 • **Worksheet #17e** – Surveying
- 934 • **Worksheet #17f** – Investigation-Derived Waste Management

935 **Table 17-1: Site Inspection Sample Count**

AOI	Potential PFAS Release Area	# of SDT Boring Locations	# of HA Boring Locations	Approximate Depth (feet bgs)	Groundwater Samples	Soil Samples	Surface Water/Sediment
1	Former FTAs	3	25	150 (2 locations) 15 (1 location)	2	72	0
2	Fire Station	3	1	150 (2 locations) 15 (1 location)	2	10	0
3	Former WWTP	4	12	150 (4 locations)	4	38	0
<b>Total (not including QC)</b>		10	38	--	8	120	0

936 **Notes:**

- 937 1) All samples will be analyzed for PFAS.
- 938 2) One soil sample per AOI will be analyzed for pH and TOC from a location in the source area. Grain size analysis will be performed in up to
- 939 one soil sample per AOI where extensive horizontal and vertical clay units are identified by the field geologist, if these conditions are
- 940 encountered in the field.

- 941 AOI = area of interest
- 942 bgs = below ground surface
- 943 HA = hand auger
- 944 PFAS = per- and polyfluoroalkyl substances
- 945 QC = quality control
- 946 SDT = sonic drilling technology
- 947 WWTP = wastewater treatment plant

948 **QAPP Worksheet #17a**  
 949 **Sampling Design and Rationale**  
 950 **Mobilization**

951 **Site Preparation**

952 The site preparation activities for the SI field investigation operations include mobilization of field  
 953 team personnel and equipment. No vegetation clearance is planned during field investigation  
 954 activities.

955 **PFAS Site Water Supply Sampling and Sampling Equipment Acceptability**

956 A sample from the potable water source (i.e., decontamination water) will be collected prior to  
 957 mobilization to confirm that it is acceptable for use for during field activities (i.e., equipment  
 958 decontamination). The water source is acceptable for use if the detected concentration is less  
 959 than 1/5 the SL. If the decontamination water has concentrations greater than 1/5 the SL, the  
 960 project team will determine whether the water is acceptable for its intended use based on site-  
 961 specific factors (i.e., drilling methodology, relevant sample media). If the water is deemed  
 962 unacceptable, water will be brought onsite from another source confirmed to be PFAS-free  
 963 through sampling. Quality control (QC) samples will not be collected for the decontamination  
 964 water sample.

965 All materials being purchased or rented for field work will be confirmed as acceptable for use in  
 966 the PFAS sampling environment. A summary of acceptability of materials for use in the PFAS  
 967 sampling environment is provided in SOP 3-41 (**Appendix B**). As an additional layer of control,  
 968 prior to the start of field work each day, a PFAS Sampling Checklist will be completed (SOP 3-41,  
 969 **Appendix B**). The checklist will serve as a reminder to each field team member regarding the  
 970 allowable materials within the sampling environment. An example of the checklist is provided  
 971 below.

972 **Example PFAS Daily Sampling Checklist**

Team Members		
Yes	No	Description
		Has AECOM PFAS Sampling guidance been reviewed by all team members? Comments:
		Has AECOM field sampling staff received needed training certification? Comments:
		Was a briefing held for field sampling staff? Comments:
		Were additional PFAS sampling instructions given to field sampling staff? Comments:
		Have personal clothing and PPE requirements been followed by all field sampling staff? Comments:
		Were lotions and sunscreen used for field sampling staff? Comment:
Sample Collection		
		Has a PFAS-free water source been identified? Comment: Source of PFAS-free water:
		Have all sampling items, parts and equipment been inspected to be free of PFAS? Comment:
		Has sampling location sequence been communicated to avoid cross-contaminations? Comment:
		Have drilling fluids been evaluated and shown to be free of PFAS? Comment:
		Use of PFAS-free decontamination solution? Brand name of decontamination solution:
		Have all field logs, notebooks, pens, labels been inspected, and do they meet AECOM PFAS sampling guidance requirements? Comment:
		Have all sample shipping materials (ice, Ziploc® bags) been inspected, and do they meet AECOM PFAS sampling guidance requirements? Comment:
		Have all blanks arrived at the site and will they be collected to verify cross-contamination? Comment:
Document Control		
		Have all variances from sampling guidance been documented? Comment:
Other Comments:		

973  
 974 **Personnel Qualifications**

975 All personnel mobilized to the facility will meet applicable Occupational Safety and Health  
 976 Administration (OSHA) training requirements including hazardous waste operations and  
 977 emergency response (HAZWOPER) training and medical surveillance requirements as specified  
 978 in the Accident Prevention Plan (APP) and Site Safety and Health Plan (SSHP). Personnel will be  
 979 required to complete the DoD's *Operations Security Awareness for Military Members, DoD*

980 *Employees, and Contractors and Level 1 Antiterrorism Awareness Training.* Additionally, all  
981 AECOM employees that will be performing field work will take an internal PFAS sampling  
982 guidance training.

### 983 Permits and Notifications

984 Utility clearance will be conducted by a private utility locator under the supervision of the AECOM  
985 field team using ground penetrating radar or electromagnetic methods with support from  
986 ORARNG (e.g., utility maps, GIS layers, site knowledge, etc.). A minimum of two weeks to  
987 coordinate the clearance will be required. AECOM or its drilling subcontractor will contact Oregon  
988 811, the local one-call utility location system. AECOM and the drilling subcontractor will participate  
989 in an RTC orientation prior to initiating work, if required. The determination of the orientation  
990 requirement will be made after final intrusive investigation locations are determined. AECOM will  
991 also contact the ARNG Environmental Manager at least five business days prior to the scheduled  
992 start of the field activities. A site walk will be scheduled with the appropriate ARNG personnel to  
993 mark out locations of the subsurface utilities. As a precaution, the first 5 feet of each boring will  
994 be pre-cleared using hand tools (e.g., post-hole diggers, augers, etc.) or air knifing methods. All  
995 field work will be coordinated with the ARNG Environmental Manager and/or his/her designee.

### 996 Health and Safety Requirements

997 Health and safety requirements for SI field activities are provided in the APP. Field personnel will  
998 wear PFAS-free Level D personal protective equipment (PPE). Detailed Activity Hazard Analyses  
999 identifying the physical, chemical, and biological hazards that may be encountered at the facility  
1000 and the associated mitigation methods are presented in the SSHP.

1001 All onsite personnel who may be exposed to hazardous conditions will be required to meet training  
1002 requirements identified in Federal Regulation 29 CFR 1910.120 (HAZWOPER). At least two  
1003 personnel trained in first aid and cardiopulmonary resuscitation (CPR) will be onsite during field  
1004 activities. Training certificates for personnel (HAZWOPER 40-hour training; current HAZWOPER  
1005 8-hour refresher training; and first aid/CPR) will be maintained onsite by the Site Supervisor.

1006 Personnel and visitors who enter the facility will be required to review the APP and SSHP and  
1007 sign the acknowledgement form. Site workers will be required to sign the daily tailgate safety  
1008 meeting form and fill out daily Activity Hazard Analysis forms. Safety issues that arise during  
1009 implementation of field activities will be addressed during tailgate safety meetings held daily  
1010 before the workday and will be documented in the daily tailgate safety meeting form.

1011 All site workers will adhere to current DoD COVID-19 guidance.

### 1012 **QAPP Worksheet #17b** 1013 **Sampling Design and Rationale** 1014 ***Sonic Drilling Boring Installation and Soil Sampling***

1015 Soil samples will be collected via hand auger and SDT (SOP 3-21). Hand augers will be used to  
1016 collect surface soil samples. Borings will be advanced using SDT at locations designated for  
1017 subsurface soil sample collection; however, hand augers will be used to clear the top 5 feet of the  
1018 boring, in accordance with AECOM utility clearance protocols, and collect surface soil samples. A  
1019 Terra Sonic Tsi 150cc or similar will be used to collect continuous soil cores to the target depth,  
1020 anticipated to utilize a 7-inch diameter core barrel with an 8-inch diameter override casing. All  
1021 drilling materials will be PFAS-free.

1022 Due to the geology and recent drought conditions at the facility, depth to groundwater at the facility  
1023 is not currently known, but it is expected that groundwater will be encountered at up to

1024 approximately 150 feet bgs at AOIs 1 through 3. Therefore, it may not be possible to target  
 1025 subsurface soil sample intervals based on depth to the groundwater table, and a combination of  
 1026 hand augers and SDT will be used to collect up to three soil samples per boring as follows:

- 1027 • one surface soil sample (0 to 2 feet bgs – hand auger) – see further discussion below  
 1028 regarding depth intervals.
- 1029 • If the boring is intended to be advanced to up to approximately 150 feet bgs and to be  
 1030 completed as a monitoring well, one subsurface soil sample approximately 2 feet above the  
 1031 groundwater table (capillary fringe) or the bottom of the boring. If the boring is intended to  
 1032 be advanced to approximately 15 feet bgs and not be completed as a monitoring well, one  
 1033 subsurface sample at the approximate mid-point between the surface and the bottom of the  
 1034 boring (SDT).
- 1035 • one subsurface soil sample from 13 to 15 feet bgs (SDT).

1036 The surface soil samples will be collected using a hand auger during utility preclearance (SOP 3-  
 1037 17). Surface soil samples will be sampled at either a single-depth interval or a multi-depth interval.  
 1038 Samples from monitoring well and boring locations and selected surface soil sampling locations  
 1039 will be collected from a single-depth interval, from approximately 0 to 2 feet bgs. The remaining  
 1040 surface soil samples will be collected from a multi-depth interval, from approximately 0 to 6 inches  
 1041 bgs, 6 to 12 inches bgs, and 12 to 24 inches bgs.

1042 The proposed sample locations are shown on **Figures 17-1** and **17-2** and described in  
 1043 **Worksheet #18**. The soil sample rationale and target depths are provided in **Table 17-2** below.  
 1044 Borings advanced up to 150 feet bgs will be converted into permanent groundwater monitoring  
 1045 wells, as described in **Worksheet #17c**.

**Table 17-2: Soil Sample Rationale and Target Depths for Borings**

Area of Interest	Number of Sampling Locations	Sample Collection Method	Target Depth (feet bgs)	Rationale
AOI 1	3	SDT	15 and 150	Surface and subsurface soil samples will be collected within the vicinity of each identified potential release area within AOI 1: the Burn Pit and FTA 01. Documented use of an unknown foam to control and suppress fires at the Burn Pit provides the highest probability for encountering PFAS, if PFAS-containing foam was used in AOI 1.  Due to the anticipated depth to groundwater, subsurface soil samples (capillary fringe) will be collected from only three locations: one boring within the Burn Pit area and two borings within the FTA 01. The boring within the Burn Pit area will be completed to up to approximately 150 feet bgs to collect surface soil (hand auger), subsurface soil (15 feet bgs), and subsurface soil (capillary fringe) samples. One boring within FTA 01 will be completed as described above, and the other will be completed to 15 feet bgs to collect surface soil (hand auger) and subsurface soil (SDT) samples.
	8 19	Hand Auger, single-depth Hand Auger, multi-depth	2	

Area of Interest	Number of Sampling Locations	Sample Collection Method	Target Depth (feet bgs)	Rationale
AOI 1 (cont.)	8 19	Hand Auger, single-depth Hand Auger, multi-depth	2	A hand auger will be used to collect a single-depth interval surface soil sample at each SDT boring location prior to hand clearing, or immediately adjacent to the SDT boring. A total of two additional single-depth interval and seven multi-depth interval surface soil sample locations will be collected within the Burn Pit. A total of four additional single-depth interval and twelve multi-depth interval surface soil sample locations will be collected within FTA 01.
AOI 2	3	SDT	15 and 150	<p>Surface and subsurface soil samples will be collected within the vicinity of the identified potential release area within AOI 2: the Fire Barn. The grassy area north of the Fire Station driveway is the most likely location where a potential AFFF release not captured by a floor drain or stormwater catch basin would infiltrate into soil and migrate to groundwater.</p> <p>Due to the anticipated depth to groundwater, subsurface soil samples (capillary fringe) will be collected from only three locations: one boring north of the Fire Station driveway, one boring adjacent to a water spigot northeast of the Fire Station, and one boring approximately between AOI 1 and AOI 2 to address potential seasonal variability of groundwater flow direction. The boring adjacent to the water spigot will be completed to 15 feet bgs to collect surface soil (hand auger) and subsurface soil (SDT) samples. The remaining two borings will be completed to approximately 150 feet bgs to collect surface soil (hand auger), subsurface soil (15 feet bgs), subsurface soil (capillary fringe) samples.</p> <p>A hand auger will be used to collect a single-depth interval surface soil sample at each SDT boring locations prior to hand clearing, or immediately adjacent to the SDT boring. A total of one additional single-depth interval surface soil sample location will be collected within the vicinity between the Fire Station and the water spigot.</p>
	4	Hand Auger, single-depth	2	

Area of Interest	Number of Sampling Locations	Sample Collection Method	Target Depth (feet bgs)	Rationale
AOI 3	3	SDT	150	Surface and subsurface soil samples will be collected within the vicinity of each identified potential release area within AOI 3: the former WWTP. Potential PFAS-containing material conveyed to the former WWTP via the sanitary sewer pipes was discharged as treated wastewater beneath the ground surface. Based on season groundwater pumping and assumed groundwater direction(s), subsurface soil samples will be collected from four locations: two within the footprint of the tile field, one adjacent to the nearby plant building, and one adjacent to the stormwater infiltration ditch. Subsurface soil samples (15 feet bgs and capillary fringe) will be collected at each boring location.
	9 7	Hand Auger, single-depth Hand Auger, multi-depth	2	A hand auger will be used to collect a single-depth interval surface soil sample at each boring location prior to hand clearing, or immediately adjacent to the SDT boring. A total of five additional single-depth interval samples will be collected within the tile field, as well as six multi-depth interval surface soil sample locations within the tile field and at the nearby plant building, and one multi-depth interval sample at the stormwater infiltration ditch.

- 1047 **Notes:**
- 1048 AOI = area of interest
- 1049 bgs = below ground surface
- 1050 SDT = sonic drilling technology
- 1051 WWTP = wastewater treatment plant

1052 The soil cores will be continuously logged for lithological descriptions by a field geologist using  
 1053 the Unified Soil Classification System (USCS) per SOP 3-16. A photoionization detector (PID) will  
 1054 be used to screen the breathing zone during boring activities. Observations and measurements  
 1055 will be recorded on field forms and in a non-treated field logbook. Photographs of the boring cores  
 1056 will also be taken. At a minimum, depth interval, recovery thickness, PID concentrations, moisture,  
 1057 relative density, color (using a Munsell soil color chart), and texture (using the USCS) will be  
 1058 recorded. Additional observations to be recorded may include groundwater or perched water  
 1059 depth, organic material, or cultural debris. If a continuous, competent clay is observed in a boring  
 1060 with a thickness in excess of 3 feet, measures will be taken to avoid completely penetrating this  
 1061 potential confining unit.

1062 It is anticipated that all borings will be advanced in areas without surface cover; however, if a  
 1063 boring is required in asphalt, locations not completed as a monitoring well will be abandoned by  
 1064 backfilling with bentonite chips to approximately 6 inches bgs, and the remainder of the borehole  
 1065 will be patched with an asphalt cold patch. Borings into concrete will be avoided, if possible;  
 1066 however, if borings are advanced into concrete, locations not completed as a monitoring well will  
 1067 be abandoned by backfilling with bentonite chips to approximately 6 inches bgs, and the  
 1068 remainder of the borehole will be filled with concrete to provide as flush a surface as possible.  
 1069 The surface at each location will be restored to match the surrounding area.

1070 QC samples will be collected in accordance with **Worksheet #20**. Field duplicate samples will be  
1071 collected at a rate of 10% and analyzed for the same parameters as the accompanying samples.  
1072 Matrix spikes/ matrix spike duplicates (MS/MSDs) will be collected at the rate of 5% and analyzed  
1073 for the same parameters as the accompanying samples. One Field Reagent Blank (FRB) will be  
1074 collected per sampling event and will be analyzed for PFAS. For non-dedicated sampling  
1075 equipment, decontamination will be completed after each use (i.e., downhole tool and hand auger  
1076 decontaminated between intervals sampled for laboratory analysis), and associated equipment  
1077 rinsate blanks (ERBs) will be collected at a rate of one per twenty samples. ERBs will be analyzed  
1078 for the same analytes as the associated samples. A temperature blank will be placed in each  
1079 cooler to ensure that samples are preserved at or below 6 degrees Celsius (°C) during shipment.

1080 Each sample will be collected into laboratory-supplied bottleware and submitted to the laboratory  
1081 for analysis of selected parameters. Samples will be analyzed for PFAS by liquid chromatography  
1082 tandem mass spectrometry (LC/MS/MS) compliant with Quality Systems Manual (QSM) 5.3 Table  
1083 B-15. Additionally, one soil sample per AOI from a location in the source area will be analyzed for  
1084 total organic carbon (TOC) (USEPA Method 9060A) and pH (USEPA Method 9045D). Additionally,  
1085 up to one soil sample per AOI will be submitted for grain size analysis with sieve and hydrometer  
1086 (American Society for Testing and Materials [ASTM] D-422) (i.e., clay content). The grain size  
1087 analysis will be performed where extensive horizontal and vertical clay units are identified by the  
1088 field geologist if these conditions are encountered in the field. Sample containers will be PFAS-  
1089 free. The laboratory method DLs for these analytes are presented in **Worksheet #15**. Samples  
1090 will be packaged on ice and transported daily via overnight commercial carrier under standard  
1091 chain of custody (CoC) procedures to the laboratory (see SOP 3-04).

1092 **QAPP Worksheet #17c**  
1093 **Sampling Design and Rationale**  
1094 ***Permanent Groundwater Monitoring Well Installation and Groundwater Sampling***

1095 As discussed in **Worksheet #17b**, boreholes for permanent monitoring wells will be created using  
1096 a Terra Sonic TSi 150cc (or equivalent). Once the borehole has been advanced to the specified  
1097 depth, if groundwater is encountered, a well will be installed according to *SOP 3-12, Monitoring*  
1098 *Well Installation (Appendix B)*. The well will be constructed of either 2-inch or 4-inch diameter,  
1099 flush-threaded Schedule 40 or Schedule 80 PVC that will have a sand trap at the bottom with an  
1100 estimated 10 to 20 feet of 0.010 slot well screen and blank well casing to ground surface and  
1101 sealed with a lockable compression cap. Diameter of borehole will be a minimum of 2 inches  
1102 greater than the outside diameter of the well screen. The filter pack within the annular space  
1103 around the screen will consist of 2/12 Monterrey sand and will be placed at least 1 foot above the  
1104 top of the well screen. A well seal consisting of hydrated bentonite chips or bentonite grout will be  
1105 installed above the sand pack. The screened interval of each well will target the top of the  
1106 groundwater table. Surface completion will include installation of flush mount well vaults or stickup  
1107 well casings, depending on anticipated traffic or likeliness of standing water. Bollards may be  
1108 installed around well monuments requiring additional protection from surface activities. Wells will  
1109 be installed, completed, and developed accordance with Oregon Administrative Rules (OAR)  
1110 Chapter 690 Division 240.

1111 The proposed sample locations are shown on **Figures 17-1** and **17-2** and are described in  
1112 **Worksheet #18**. Based on a review of nearby well logs and other available information, depth to  
1113 groundwater beneath RTC ranges from approximately 60 to 100 feet bgs (OWRD, 2022; USACE,  
1114 2013), with a maximum investigation depth of approximately 150 feet bgs. The target screen  
1115 intervals and further rationale for the sampling locations are described in **Table 17-3** below.

1116 **Table 17-3: Groundwater Sample Rationale and Proposed Screen Intervals**

Area of Interest	# of Permanent Wells	Target Screen Interval	Rationale
AOI 1	2	Top of groundwater table (up to an est. 150 feet bgs)	One monitoring well proposed at the Burn Pit and one monitoring well proposed at FTA 01. No additional wells proposed due the anticipated depth to groundwater.
AOI 2	2	Top of groundwater table (up to an est. 150 feet bgs)	One monitoring well proposed adjacent to the Fire Station and one monitoring well proposed within the vicinity between AOI 1 and AOI 2. No additional wells proposed due to the anticipated depth to groundwater.
AOI 3	4	Top of groundwater table (up to an est. 150 feet bgs)	Two monitoring wells proposed within the tile field of the former WWTP, one adjacent to the plant building, and one adjacent to the stormwater infiltration ditch.

1117 **Notes:**  
 1118 AOI = area of interest  
 1119 bgs = below ground surface

1120 Once the borehole for each permanent groundwater monitoring well has been advanced to the  
 1121 desired depth, a monitoring well will be installed as described above. Prior to sampling, each  
 1122 newly installed permanent monitoring well will be developed to establish a hydraulic connection  
 1123 between the well and the surrounding saturated formation. Standard methods for monitoring well  
 1124 development are described in SOP 3-13 (**Appendix B**). The goals of this well development are  
 1125 to settle the filter pack and to remove accumulated sediment/suspended solids that may enter the  
 1126 well during installation. Well development will be performed a minimum of 24 hours after well  
 1127 construction to allow time for the bentonite or grout seal to cure. Development will be performed  
 1128 by first using a surge block followed by a bailer (PVC or stainless steel) or pneumatic pump to  
 1129 remove sediments from the well and surrounding filter pack. Multiple iterations of surging and  
 1130 bailing may be required, dependent on the aquifer characteristics.

1131 Once the bailed water is visually free of sediment, development will continue using high-flow  
 1132 pumping techniques (greater than 0.5 liter per minute) until the water quality parameters  
 1133 (temperature, pH, specific conductance, oxidation-reduction potential [ORP], and turbidity)  
 1134 stabilize to within 10% of the previous reading for three consecutive measurements, or until five  
 1135 borehole volumes (well casing plus annular space) have been removed. Dissolved oxygen (DO)  
 1136 readings may be recorded but will not be used as development completion criteria. Water quality  
 1137 instruments will be calibrated in accordance with SOP 3-24 (**Appendix B**).

1138 Monitoring wells may be screened in silty material, water quality parameters, and notably, turbidity  
 1139 may not stabilize using high-flow pumping techniques. If water quality parameters do not stabilize  
 1140 to within 10% after five well volumes, low-flow pumping techniques (less than 0.5 liter per minute)  
 1141 will be performed for an additional well volume to better document groundwater conditions  
 1142 encountered during low-flow groundwater sampling. If necessary, well development water will be  
 1143 contained in labeled DOT-approved containers and managed as described in **Worksheet #17f**.

1144 The following information will be recorded during the development of each permanent well:

- 1145 • Date, time, personnel, and well designation;
- 1146 • Static groundwater levels;
- 1147 • Volume of water in well prior to development;
- 1148 • Volume of water removed;

- 1149 • Water Quality Parameters;
- 1150 • Observations of water characteristics (e.g., color, odor, turbidity); and
- 1151 • Description of development technique.

1152 A low-flow groundwater sample will be collected at each well using a peristaltic pump with tubing  
1153 that has been determined to be PFAS-free (i.e. high-density polyethylene [HDPE] or other PFAS-  
1154 free material). If the peristaltic pump cannot generate enough hydraulic lift to bring the  
1155 groundwater to the surface, groundwater samples will be collected at each well using a bladder  
1156 pump with a bladder and tubing that have been determined to be PFAS-free (i.e., HDPE or other  
1157 PFAS-free material). Groundwater samples will be collected using a PFAS-free 1.75-inch Geotech  
1158 Bladder pump or other sampling device. Alternatively, a PFAS-free bailer may be used to collect  
1159 groundwater samples at locations at which the use of a pump is impractical.

1160 Prior to sample collection, turbidity and other water quality parameters (e.g., temperature, specific  
1161 conductance, pH, dissolved oxygen [DO], and oxidation-reduction potential [ORP]) will be  
1162 measured and recorded on the field sampling form every 5 minutes until the above measurements  
1163 have stabilized. Water quality parameters will be measured using a water quality meter and flow-  
1164 through cell (see *SOP 3-14: Monitoring Well Sampling* and *SOP 3-24: Water Quality Parameter*  
1165 *Testing* for more details). In addition, a subsample of each groundwater sample will be collected  
1166 in a separate container and undergo a shaker test to identify if there is any foaming. If foaming is  
1167 observed, the observation will be noted on the CoC to notify the laboratory of potentially high  
1168 PFAS concentrations in the sample prior to analysis. Any non-dedicated sampling materials will  
1169 be decontaminated between wells.

1170 Each sample will be collected into laboratory-supplied bottleware and submitted to the laboratory  
1171 for analysis of selected parameters (PFAS by LC/MS/MS compliant with QSM 5.3 Table B-15)  
1172 (DoD, 2019a) as per SOP 3-41. The laboratory method DLs for these analytes are presented in  
1173 **Worksheet #15**. QC samples will be collected in accordance with **Worksheet #20**. For non-  
1174 dedicated sampling equipment, decontamination will be completed after each use (i.e., bladder  
1175 pump decontaminated between temporary well locations), and associated ERBs will be collected  
1176 at a rate of one per twenty samples. ERBs will be collected at a rate of one per twenty samples  
1177 and will be analyzed for the same analytes as the associated samples. A temperature blank will  
1178 be placed in each cooler to ensure that samples are preserved at or below 6 °C during shipment.  
1179 Sample containers will be PFAS-free, and the aqueous samples will not be filtered. Samples will be  
1180 packaged on ice and transported daily via overnight commercial carrier under standard CoC  
1181 procedures to the laboratory (SOP 3-04).

1182 **QAPP Worksheet #17d**  
1183 **Sampling Design and Rationale**  
1184 ***Synoptic Water Level Measurements***

1185 Groundwater levels will be used to monitor site-wide groundwater elevations and assess  
1186 groundwater flow. Synoptic water level elevation measurements will be collected from the newly-  
1187 installed monitoring wells (as shown on **Worksheet #18**). The wells will be surveyed, and the  
1188 water level measurement will be taken from the survey mark on the northern side of the well  
1189 casing.

1190  
1191  
1192

**QAPP Worksheet #17e**  
**Sampling Design and Rationale**  
**Surveying**

1193 A small notch will be cut on the northern side of the well casing which will be surveyed by a state-  
1194 licensed surveyor (see SOP 3-07). The top of casing and ground surface elevation will be  
1195 surveyed for each newly installed well. Survey data will be collected in the applicable Universal  
1196 Transverse Mercator zone projection with WGS84 datum (horizontal) and North American Vertical  
1197 Datum 1988 (vertical).

1198  
1199  
1200

**QAPP Worksheet #17f**  
**Sampling Design and Rationale**  
**Investigation-Derived Waste Management**

1201 Currently, the disposal of PFAS investigation-derived waste (IDW) is not regulated. As such, the  
1202 IDW will be managed as follows:

1203 Non-hazardous solid IDW (i.e., soil cuttings) generated during SI activities will be containerized  
1204 in properly labeled 55-gallon drums (see SOP 3-05). This IDW will not be sampled and will assume  
1205 the PFAS characteristics of the associated soil samples collected from that source location. The  
1206 IDW will be stored at a location designated by the RTC Environmental Manager and ORARNG.  
1207 ARNG will manage disposal of the solid IDW and will coordinate with ORDEQ to ensure proper  
1208 disposal in accordance with Oregon Administrative Rules (OAR) Chapter 340 and the Army  
1209 Guidance for Addressing Releases of PFAS, Q18 (DA, 2018).

1210 Liquid IDW generated during SI activities (i.e., purged groundwater and decontamination fluids)  
1211 will be containerized in 55-gallon drums (see SOP 3-05). The liquid IDW will not be sampled and  
1212 will assume the PFAS characteristics of the associated groundwater samples collected from that  
1213 source location. The containerized IDW will be temporarily stored onsite at a location designated  
1214 by the RTC Environmental Manager and ORARNG until the analytical results for the associated  
1215 groundwater samples are available. Liquid IDW drums will only be filled 75% full to account for  
1216 freeze/thaw cycles. ARNG will manage and dispose of the liquid IDW under a separate contract  
1217 in accordance with *SOP No. 042A for Treating Liquid Investigation-Derived Material (Purge water,*  
1218 *drilling water, and decontamination fluids)* (EA Engineering, Science, and Technology, Inc., 2021).  
1219 ARNG will further coordinate with the ORDEQ to ensure proper disposal is in accordance with  
1220 OAR Chapter 340 and the Army Guidance for Addressing Releases of PFAS, Q18 (DA, 2018).

1221 AECOM will collect global positioning system (GPS) points (i.e., polygons) around the location  
1222 where the IDW drums are stored.



1223 Other solids such as spent PPE, plastic sheeting, tubing, rope, unused monitoring well  
1224 construction materials, and other environmental media generated during the field activities will be  
1225 disposed of at a licensed solid waste landfill.

1226

1227

THIS PAGE INTENTIONALLY BLANK

1228



**Legend**

- Proposed Monitoring Well
- Proposed Soil Boring
- Proposed surface soil sample – single-depth interval
- Proposed surface soil sample – multi-depth interval
- Area of Interest
- Potential PFAS Release

CLIENT	ARNG			
PROJECT	Site Inspection for PFAS at Raymond F. Rees Training Center, OR			
REVISED	7/12/2022	GIS BY	MS	7/12/2022
SCALE	1:960	CHK BY	JH	7/12/2022
Base Map: Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community	PM	CM	7/12/2022	




**Proposed SI Sample Locations - AOI 1 and AOI 2**

12420 Milestone Center Drive  
 Germantown, MD 20876


**Figure 17-1**

C:\Users\stankevichm\OneDrive - AECOM\Directory\ARNG\_PFAS\_GIS\_60552172\MXDs\OR\Camp\_Umatilla\SI\_Figures\SI\_QAPP\Fig\_17-2\_Camp\_Umatilla\_Proposed\_SI\_Samples\_AOI1\_AOI2.mxd




**Legend**

- ◆ Proposed Monitoring Well
- ☒ Proposed surface soil sample – single-depth interval
- ☒ Proposed surface soil sample – multi-depth interval
- Area of Interest
- Facility Boundary



CLIENT	ARNG			
PROJECT	Site Inspection for PFAS at Raymond F. Rees Training Center, OR			
REVISED	7/12/2022	GIS BY	MS	7/12/2022
SCALE	1:2,640	CHK BY	JH	7/12/2022
Base Map: Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community		PM	CM	7/12/2022



**Proposed SI Sample Locations - AOI 3**

12420 Milestone Center Drive  
Germantown, MD 20876

**Figure 17-2**

## 1231 QAPP Worksheet #18: Sampling Locations and Methods

1232 The table below describes the samples that will be collected during the SI. Sampling SOPs can be found in **Appendix B**.

AOI	Location Identifier	Sample Identifier	Matrix	Depth	Type (Sampling Tool)	Analyte/Analytical Group	Sampling SOP
<b>Soil Samples</b>							
<b>All</b>	AOI01-01	AOI01-01-SB-[Start Depth]-[End Depth]	Surface Soil, Single-Depth Interval	0-2 ft bgs	Hand Auger	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)	3-21
	AOI01-04	AOI01-04-SB-[Start Depth]-[End Depth]					
	AOI01-09	AOI01-09-SB-[Start Depth]-[End Depth]					
	AOI01-11	AOI01-11-SB-[Start Depth]-[End Depth]					
	AOI01-14	AOI01-14-SB-[Start Depth]-[End Depth]					
	AOI01-19	AOI01-19-SB-[Start Depth]-[End Depth]					
	AOI01-21	AOI01-21-SB-[Start Depth]-[End Depth]					
	AOI01-23	AOI01-23-SB-[Start Depth]-[End Depth]					
	AOI01-28	AOI01-28-SB-[Start Depth]-[End Depth]					
	AOI02-01	AOI02-01-SB-[Start Depth]-[End Depth]					
	AOI02-02	AOI02-02-SB-[Start Depth]-[End Depth]					
	AOI02-03	AOI02-03-SB-[Start Depth]-[End Depth]					
	AOI02-04	AOI02-04-SB-[Start Depth]-[End Depth]					
	AOI03-01	AOI03-01-SB-[Start Depth]-[End Depth]					
	AOI03-02	AOI03-02-SB-[Start Depth]-[End Depth]					
	AOI03-03	AOI03-03-SB-[Start Depth]-[End Depth]					
	AOI03-04	AOI03-04-SB-[Start Depth]-[End Depth]					
	AOI03-08	AOI03-08-SB-[Start Depth]-[End Depth]					
	AOI03-09	AOI03-09-SB-[Start Depth]-[End Depth]					
	AOI03-13	AOI03-13-SB-[Start Depth]-[End Depth]					
	AOI03-14	AOI03-14-SB-[Start Depth]-[End Depth]					
AOI03-15	AOI03-15-SB-[Start Depth]-[End Depth]						
<b>All</b>	AOI01-02	AOI01-02-SB-[Start Depth]-[End Depth]	Surface Soil, Multi-Depth Interval	0-6 in bgs 6-12 in bgs 12-24 in bgs	Hand Auger	(see above)	3-21
		AOI01-02-SB-[Start Depth]-[End Depth]					
	AOI01-03	AOI01-03-SB-[Start Depth]-[End Depth]					
		AOI01-03-SB-[Start Depth]-[End Depth]					
	AOI01-05	AOI01-05-SB-[Start Depth]-[End Depth]					
		AOI01-05-SB-[Start Depth]-[End Depth]					

AOI	Location Identifier	Sample Identifier	Matrix	Depth	Type (Sampling Tool)	Analyte/Analytical Group	Sampling SOP
	AOI01-06	AOI01-06-SB-[Start Depth]-[End Depth]					
	AOI01-07	AOI01-06-SB-[Start Depth]-[End Depth] AOI01-07-SB-[Start Depth]-[End Depth]					
	AOI01-08	AOI01-07-SB-[Start Depth]-[End Depth] AOI01-08-SB-[Start Depth]-[End Depth]					
	AOI01-10	AOI01-08-SB-[Start Depth]-[End Depth] AOI01-10-SB-[Start Depth]-[End Depth]					
	AOI01-12	AOI01-10-SB-[Start Depth]-[End Depth] AOI01-12-SB-[Start Depth]-[End Depth]					
	AOI01-13	AOI01-12-SB-[Start Depth]-[End Depth] AOI01-13-SB-[Start Depth]-[End Depth]					
	AOI01-15	AOI01-13-SB-[Start Depth]-[End Depth] AOI01-15-SB-[Start Depth]-[End Depth]	(see above)	(see above)	(see above)	(see above)	(see above)
	AOI01-16	AOI01-15-SB-[Start Depth]-[End Depth] AOI01-16-SB-[Start Depth]-[End Depth]					
	AOI01-17	AOI01-16-SB-[Start Depth]-[End Depth] AOI01-17-SB-[Start Depth]-[End Depth]					
	AOI01-18	AOI01-17-SB-[Start Depth]-[End Depth] AOI01-18-SB-[Start Depth]-[End Depth]					
	AOI01-20	AOI01-18-SB-[Start Depth]-[End Depth] AOI01-20-SB-[Start Depth]-[End Depth]					
	AOI01-22	AOI01-20-SB-[Start Depth]-[End Depth] AOI01-22-SB-[Start Depth]-[End Depth]					
	AOI01-24	AOI01-22-SB-[Start Depth]-[End Depth] AOI01-24-SB-[Start Depth]-[End Depth]					
		AOI01-24-SB-[Start Depth]-[End Depth]					

AOI	Location Identifier	Sample Identifier	Matrix	Depth	Type (Sampling Tool)	Analyte/Analytical Group	Sampling SOP
	AOI01-25	AOI01-25-SB-[Start Depth]-[End Depth]					
	AOI01-26	AOI01-26-SB-[Start Depth]-[End Depth]					
	AOI01-27	AOI01-27-SB-[Start Depth]-[End Depth]					
	AOI03-05	AOI03-05-SB-[Start Depth]-[End Depth]					
	AOI03-06	AOI03-06-SB-[Start Depth]-[End Depth]	(see above)	(see above)	(see above)	(see above)	(see above)
	AOI03-07	AOI03-07-SB-[Start Depth]-[End Depth]					
	AOI03-10	AOI03-10-SB-[Start Depth]-[End Depth]					
	AOI03-11	AOI03-11-SB-[Start Depth]-[End Depth]					
	AOI03-12	AOI03-12-SB-[Start Depth]-[End Depth]					
	AOI03-16	AOI03-16-SB-[Start Depth]-[End Depth]					
<b>All</b>	AOI01-01 AOI01-11 AOI01-28  AOI02-01 AOI02-02 AOI02-03  AOI03-01	AOI01-01-SB-[Start Depth]-[End Depth] AOI01-11-SB-[Start Depth]-[End Depth] AOI01-28-SB-[Start Depth]-[End Depth]  AOI02-01-SB-[Start Depth]-[End Depth] AOI02-02-SB-[Start Depth]-[End Depth] AOI02-03-SB-[Start Depth]-[End Depth]  AOI03-01-SB-[Start Depth]-[End Depth]	Subsurface Soil	Mid-point or 13-15 ft bgs	Sonic Drilling Sampling System	(see above)	3-21

AOI	Location Identifier	Sample Identifier	Matrix	Depth	Type (Sampling Tool)	Analyte/Analytical Group	Sampling SOP
	AOI03-02 AOI03-03 AOI03-04	AOI03-02-SB-[Start Depth]-[End Depth] AOI03-03-SB-[Start Depth]-[End Depth] AOI03-04-SB-[Start Depth]-[End Depth]					
<b>All</b>	AOI01-01 AOI01-11 AOI01-28  AOI02-01 AOI02-02 AOI02-03  AOI03-01 AOI03-02 AOI03-03 AOI03-04	AOI01-01-SB-[Start Depth]-[End Depth] AOI01-11-SB-[Start Depth]-[End Depth] AOI01-28-SB-[Start Depth]-[End Depth]  AOI02-01-SB-[Start Depth]-[End Depth] AOI02-02-SB-[Start Depth]-[End Depth] AOI02-03-SB-[Start Depth]-[End Depth]  AOI03-01-SB-[Start Depth]-[End Depth] AOI03-02-SB-[Start Depth]-[End Depth] AOI03-03-SB-[Start Depth]-[End Depth] AOI03-04-SB-[Start Depth]-[End Depth]	Subsurface Soil	Above groundwater table or bottom of boring	(see above)	(see above)	3-21
<b>Groundwater Samples</b>							
<b>All</b>	AOI01-01 AOI01-28  AOI02-02 AOI02-03  AOI03-01 AOI03-02 AOI03-03 AOI03-04	AOI01-01-GW AOI01-28-GW  AOI02-02-GW AOI02-03-GW  AOI03-01-GW AOI03-02-GW AOI03-03-GW AOI03-04-GW	Groundwater	Mid-screen	Bladder pump	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)	3-14
<b>QA/QC Samples</b>							
<b>All</b>	AOI01-01*	AOI01-01-SB-Depth-D* AOI01-01-SB-Depth-MS* AOI01-01-SB-Depth-MSD*	Solid (Soil)	TBD	Hand Auger; Sonic Drilling Sampling System	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)  Limited Sample Selection (one sample per AOI): TOC (USEPA Method 9060A) pH (USEPA Method 9045D)	3-21, 3-22

AOI	Location Identifier	Sample Identifier	Matrix	Depth	Type (Sampling Tool)	Analyte/Analytical Group	Sampling SOP
All	AOI01-1*	AOI01-01-GW-D* AOI01-01-GW-MS* AOI01-01-GW-MSD*	Aqueous (Groundwater)	Mid-screen	Bladder pump	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)	3-14
NA	NA	CU-FRB-01	Water Quality	NA	NA (Pour laboratory-supplied PFAS-free water)	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)	3-10
NA	NA	CU-ERB-01 CU-ERB-02 CU-ERB-03 CU-ERB-04	Water Quality	NA	NA (Pour laboratory-supplied PFAS-free water)	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)	3-10
NA	NA	CU-DECON-01 CU-DECON-02	Decontamination Water Source	NA	NA (collect from tap or hose)	PFAS (LC/MS/MS compliant with QSM 5.3 Table B-15)	3-10

1233  
1234  
1235  
1236  
1237  
1238  
1239  
1240  
1241  
1242  
1243  
1244  
1245  
1246  
1247  
1248  
1249  
1250  
1251  
1252  
1253  
1254  
1255  
1256  
1257

**Notes:**

\* Locations of field quality control samples (duplicates and MS/ MSDs) will be selected in the field at the rates specified in **Worksheet #20** of this SI QAPP Addendum. The location and sample identifiers listed in **Worksheet #18** are included as examples only.

- |   |   |
|---|---|
| AOI = area of interest                                    | TBD = to be determined                                |
| ASTM = American Society for Testing and Materials         | TOC = total organic carbon                            |
| bgs = below ground surface                                | USEPA = United States Environmental Protection Agency |
| D = duplicate   |   |
| ERB = equipment rinsate blank                             |   |
| FRB = field reagent blank                                 |   |
| ft = feet   |   |
| GW = groundwater  |   |
| in = inches   |   |
| LC/MS/MS = liquid chromatography tandem mass spectrometry |   |
| MS = matrix spike   |   |
| MSD = matrix spike duplicate                              |   |
| NA = not applicable                                       |   |
| PFAS = per- and polyfluoroalkyl substances                |   |
| PW = potable water  |   |
| QA = quality assurance                                    |   |
| QC = quality control                                      |   |
| QSM = Quality Systems Manual                              |   |
| SB = soil boring  |   |
| SOP = standard operating procedure                        |   |

1258

1259

THIS PAGE INTENTIONALLY BLANK

1260

## Final PQAPP Worksheet #19 & #30: Sample Containers, Preservation, and Hold Times

1261

**Laboratory:** Pace Gulf Coast  
 7979 Innovation Park Dr.  
 Baton Rouge, Louisiana 70820  
 (225) 769-4900

**List any required accreditations/certifications:** DoD/ELAP; applicable state certification

**Back-up Laboratory:** NA

**Sample Delivery Method:** FedEx

Analyte/ Analyte Group	Matrix	Method/SOP	Accreditation Expiration Date	Container(s) (number, size & type per sample)	Preservation	Preparation Holding Time	Analytical Holding Time	Data Package Turnaround
PFAS	Aqueous	QSM 5.3 Table B-15/ SOP LCMS-011 (BRTO-0111)	ELAP-01/31/2023 NELAP-6/30/2023	HDPE w/ HDPE screw cap 2 x 125 mL	Cool, 0-6°C	14 days from collection to extraction	28 days from extraction to analysis	28 days
PFAS	Solid	QSM 5.3 Table B-15/ SOP LCMS-011 (BRTO-0111)	ELAP-01/31/2023 NELAP-6/30/2023	HDPE w/ HDPE screw cap 1 x 250 mL	Cool, 0-6°C	28 days from collection to extraction	28 days from extraction to analysis	28 days
Total Organic Carbon	Solid	USEPA 9060A, SM 5310 B- 2011/WL-057	ELAP-01/31/2023 NELAP-6/30/2023	Polyethylene, Glass 1 x 2oz	Cool, 0-6°C	30 days to extraction	7 days from extraction to analysis	28 days
pH	Solid	USEPA 9045D/EXT- 032	ELAP-01/31/2023 NELAP-6/30/2023	Polyethylene, Glass 1 x 2oz	None	NA	Immediate	28 days
Grain Size	Solid	ASTM D422/ CA-551	02/01/2022	Polyethylene, Glass 1 x 8oz	Cool, 0-6°C	None	None	28 days

1262

**Notes:**

1263

1.) TOC and pH are important for evaluating transport through the soil medium.

1264

°C = degrees Celsius

1265

ASTM = American Society for Testing and Materials

1266

DoD = Department of Defense

1267

ELAP = Environmental Laboratory Accreditation

1268

Program

1269

HDPE = high-density polyethylene

1270

LCMS = liquid chromatography/ mass spectrometry

1271

mL = milliliter

1272

NA = not applicable

1273

NELAP = National Environmental Laboratory

1274

Accreditation Program

1275

oz = ounce

1276

PFAS = per- and polyfluoroalkyl substances

1277

QSM = Quality Systems Manual

1278

SOP = standard operating procedure

1279

USEPA = United States Environmental Protection

1280

Agency

1281

1282

THIS PAGE INTENTIONALLY BLANK

1283 **Final PQAPP Worksheet #20: Field Quality Control Summary**

Matrix	Analytical Group	Field Samples	Field Duplicates	Matrix Spikes	Matrix Spike Duplicates	Field Reagent Blanks	Equipment Rinsate Blanks*	Total Samples
Groundwater	PFAS	8	1	1	1	1	1	12
Soil	PFAS	120	12	6	6	1	1**	146
	pH, TOC	3	1	1	0	0	0	5
	Grain Size	3	0	0	0	0	0	3
Decontamination Water	PFAS	2	0	0	0	0	0	2

- 1284 **Notes:**
- 1285 \*Applies only if use of non-dedicated sampling equipment is necessary
- 1286 \*\* Equipment rinsate blanks for solid matrices are aqueous samples
- 1287 PFAS = per- and polyfluoroalkyl substances
- 1288 TOC = total organic carbon
- 1289

Measurement Performance Criteria Table — Field Quality Control Samples				
QC Sample	Analytical Group	Frequency	Data Quality Indicators	MPC
<b>Matrix: Aqueous (Groundwater/ Potable Wells)</b>				
Field Duplicate	PFAS	One per 10 field samples	Precision	Values > 5X LOQ: RPD must be ≤30% Values ≤ 5X LOQ: Absolute difference ≤ 2x the LOQ
Matrix Spike/Matrix Spike Duplicate	PFAS	One per 20 field samples <sup>1</sup>	Bias/Accuracy/Precision (lab)	RPD ≤ 30%; Refer to Worksheet #28 for recovery criteria
Equipment Rinsate Blank	PFAS	One per 20 field samples per type of reusable equipment used <sup>2</sup>	Accuracy/ Bias	No target analytes ≥ ½ LOQ, unless target analytes in field samples are > 10x those in rinsate blank. Laboratory-certified PFAS-free water will be used to collect ERBs.
Reagent Blank	PFAS	One per sampling event <sup>3</sup>	Accuracy/ Bias	No target analytes ≥ ½ LOQ, unless target analytes in field samples are > 10x those in rinsate blank
Cooler Temperature Blank	PFAS	One per cooler	Representativeness	Temperature must be above freezing and ≤ 6 °C
<b>Matrix: Solid (Soil)</b>				
Field Duplicate	PFAS, TOC	One per 10 field samples	Precision	Values > 5X LOQ: RPD must be ≤30% Values ≤ 5X LOQ: Absolute difference ≤ 2x the LOQ
Matrix Spike/Matrix Spike Duplicate	PFAS, TOC	One per 20 field samples <sup>1</sup>	Bias/Accuracy/Precision (lab)	RPD ≤ 30%; Refer to Worksheet #28 for recovery criteria
Reagent Blank	PFAS	One per sampling event <sup>3</sup>	Accuracy/ Bias	No target analytes ≥ ½ LOQ, unless target analytes in field samples are > 10x those in rinsate blank
Equipment Rinsate Blank	PFAS	One per 20 field samples per type of reusable equipment used <sup>2</sup>	Accuracy/ Bias	No target analytes ≥ ½ LOQ, unless target analytes in field samples are > 10x those in rinsate blank
Cooler Temperature Blank	PFAS	One per cooler	Representativeness	Temperature must be above freezing and ≤ 6°C

1290

- 1291 **Notes:**  
1292 1.) Analyzed more frequently than one per twenty samples or per sample delivery group.  
1293 2.) Only for re-usable equipment, not for disposable equipment/ supplies.  
1294 3.) Regardless of matrix.
- 1295 % = percent  
1296  $\leq$  = less than or equal to  
1297  $\geq$  = greater than or equal to  
1298 °C = degrees Celsius  
1299 FRB = field reagent blank  
1300 LOQ = limit of quantitation  
1301 MPC = measurement performance criteria  
1302 PFAS = per- and polyfluoroalkyl substances  
1303 QC = quality control  
1304 RPD = relative percent difference  
1305 TOC = total organic carbon

1306

THIS PAGE INTENTIONALLY BLANK

## 1307 Final PQAPP Worksheet #21: Field Standard Operating Procedures

1308 A summary of SOPs is provided in the table below, which can be found in **Appendix B**. All field staff will be trained through AECOM's  
 1309 internal PFAS Sampling Training prior to performing any sampling activities. A summary of the acceptability of certain materials for use  
 1310 in the PFAS sampling environment and a PFAS sampling checklist to be completed daily is provided in SOP 3-41.

Reference Number	Title, Revision Date, and/or Number	Originating Organization	Modified for Project Work?	Comments
3-01	<i>Utility Clearance</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-02	<i>Logbooks</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-03	<i>Recordkeeping, Sample Labeling and Chain of Custody</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-04	<i>Sample Handling, Storage, and Shipping</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-05	<i>Investigation-Derived Waste Management</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-06	<i>Equipment Decontamination</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-07	<i>Land Surveying</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-09	<i>Geophysics</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-12	<i>Monitoring Well Installation</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-13	<i>Monitoring Well Development</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-14	<i>Monitoring Well Sampling</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-15	<i>Monitoring Well and Borehole Abandonment</i>	AECOM	N	See SOP for detailed procedures

Reference Number	Title, Revision Date, and/or Number	Originating Organization	Modified for Project Work?	Comments
3-16	<i>Soil and Rock Classification</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-20	<i>Operation and Calibration of Photoionization Detector</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-21	<i>Surface and Subsurface Soil Sampling Procedures</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-22	<i>Sediment Sampling</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-24	<i>Water Quality Parameter Testing for Groundwater Sampling</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-33	<i>Subsurface Soil Sampling by Split Spoon</i>	AECOM	Y	Modified for PFAS sampling See SOP for detailed procedures
3-41	<i>Per- and Polyfluoroalkyl Substance Field Sampling Protocol</i>	AECOM	Y	See SOP for detailed procedures

- 1311 **Notes:**
- 1312 AECOM = AECOM Technical Services, Inc.
- 1313 N = no
- 1314 NA = not applicable
- 1315 PFAS = per- and polyfluoroalkyl substances
- 1316 SOP = standard operating procedure
- 1317 Y = yes

1318 **Final PQAPP Worksheet #22: Field Equipment Calibration, Maintenance,**  
1319 **Testing, and Inspection**

Field Equipment	Calibration Activity	Maintenance Activity	SOP Reference	Testing Activity	Inspection Activity	Title or Position of Responsible Person	Frequency	Calibration Acceptance Criteria	Corrective Action
<b>Horiba U-52 Water Quality Standards</b> (pH, ORP, DO, Conductivity, Temperature, Turbidity)	Calibrate with standard solutions	Per page 8 of SOP 3-24	SOP 3-24	Operational equipment check and calibration	Visually inspect for cleanliness and obvious defects (broken/missing parts)	Field Technician Lead	Prior to use	pH: $\pm 0.01$ pH units Conductivity: $\pm 0.01$ $\mu\text{S}/\text{cm}$ Turbidity: $\pm 0.01$ NTU DO: $\pm 0.01$ mg/L Temp: $\pm 0.01$ $^{\circ}\text{C}$	Minor: Repair Major: Replace instrument
<b>MiniRAE 2000 (PID)</b>	Calibrate with fresh air and isobutylene calibration gas	Per page 4 of SOP 3-20	SOP 3-20	Operational equipment check and calibration	Visually inspect for cleanliness and obvious defects (broken/missing parts)	Field Technician Lead	Prior to use	0-99 ppm $\pm 0.1$ ppm 100-1,999 ppm $\pm 1.0$ ppm 2,000-10,000 ppm $\pm 10$ ppm	Minor: Repair Major: Replace instrument
<b>QED MP10 Controller</b> (Bladder Pump Controller Box)	NA	--	SOP 3-14	Operational equipment check	Visually inspect for cleanliness and obvious defects (broken/missing parts)	Field Technician Lead	Prior to use	NA	Minor: Repair Major: Replace instrument
<b>QED SamplePro</b> (Stainless Steel Submersible Bladder Pump)	NA	Per page 7 of SOP 3-14	SOP 3-14	Operational equipment check	Visually inspect for cleanliness and obvious defects (broken/missing parts)	Field Technician Lead	Prior to use	NA	Minor: Repair Major: Replace instrument

1320

Field Equipment	Calibration Activity	Maintenance Activity	SOP Reference	Testing Activity	Inspection Activity	Title or Position of Responsible Person	Frequency	Calibration Acceptance Criteria	Corrective Action
<b>Solinst 101</b> (Water Level Meter)	NA	Per page 5 of SOP 3-14	SOP 3-14	Operational equipment check	Visually inspect for cleanliness and obvious defects (broken/missing parts)	Field Technician Lead	Prior to use	NA	Minor: Repair Major: Replace instrument
<b>Geotech GeoPump</b> (Peristaltic Pump)	NA	NA	SOP 3-14	Operational equipment check	Visually inspect for cleanliness and obvious defects (broken/missing parts)	Field Technician Lead	Prior to use	NA	Minor: Repair Major: Replace instrument

- 1321 **Notes:**
- 1322 °C = degrees Celsius
- 1323 DO = dissolved oxygen
- 1324 mg/L = milligrams per liter
- 1325 NA = not applicable
- 1326 NTU = nephelometric turbidity unit
- 1327 ORP = oxidation-reduction potential
- 1328 PID = photoionization detector
- 1329 ppm = parts per million
- 1330 SOP = standard operating procedure
- 1331 Temp = temperature
- 1332 µS/cm = micro Siemens per centimeter
- 1333

1334

## Final PQAPP Worksheet #23: Analytical Standard Operating Procedures

Lab SOP Number	Title, Revision Date, and / or Number	Definitive or Screening Data	Matrix and Analytical Group	Instrument	Organization Performing Analysis	Modified for Project Work? (Y/N)
ENV-SOP-BRTO-0111	<i>PFAS in NPW/SCM by LC-MS/MS with Isotopic Dilution (QSM Table B-15 Compliant) and SPE/DIA Extraction (LCMS-011) (28 Mar 2020)</i>	Definitive	Water/PFAS	Agilent 6460 Triple Quad LC/MS/MS	Pace Gulf Coast	N
			Solid/PFAS			
ENV-SOP-BTRO-0044	<i>TOC in Solids and Wastes by Combustion Analyzer (WL-057) (27 Feb 2020)</i>	Definitive	Solid/TOC	Shimadzu TOC-V CSH or TOC-V CPH analyzer	Pace Gulf Coast	N
ENV-SOP-BTRO-0037	<i>pH and ORP in Waters, Solids and Wastes by Meter (EXT-032), 1 September 2020, Revision 1</i>	Definitive	Solid/pH	Orion 720A pH Meter, Combination Electrode	Pace Gulf Coast	N
CA-551	<i>Grain Size Analysis, 06/20, Revision 3.</i>	Definitive	Solid/Grain Size	Sieve	Katahdin Analytical Services, Inc.	N

1335  
 1336  
 1337  
 1338  
 1339  
 1340  
 1341  
 1342  
 1343

**Notes:**

- LCMS = liquid chromatography/ mass spectrometry
- LC/MS/MS = liquid chromatography tandem mass spectrometry
- N = no
- PFAA = perfluorinated alkyl acids
- PFAS = per- and polyfluoroalkyl substances
- SOP = standard operating procedure
- TOC = total organic carbon
- Y = yes

1344

THIS PAGE INTENTIONALLY BLANK

1345 **Final PQAPP Worksheet #24: Analytical Instrument Calibrations**

Instrument/Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
LC/MS/MS	Calibration Standards	NA	Prior to sample analysis	For analytes which have both linear and branched isomers and have standards available containing both linear and branched isomers, the analytes are calibrated and quantitated using a single continuous baseline to integrate all identifiable isomers.	NA	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Tune Check	NA	When the masses fall outside of the $\pm 0.5$ amu of the true value (as determined by the product ion formulas).	Mass assignments of tuning standard within 0.5 amu of true value.	Retune instrument and verify. If the tuning will not meet acceptance criteria, an instrument mass calibration must be performed and the tune check repeated.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)

Instrument/Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
LC/MS/MS	Minimum five-point initial calibration for all analytes (ICAL)	5.0 – 100 ppb on column	Initial calibration prior to sample analysis	<p>The isotopically labeled analog of an analyte (Extracted Internal Standard Analyte) must be used for quantitation if commercially available (Isotope Dilution Quantitation). Commercial PFAS standards available as salts are acceptable providing the measured mass is corrected to the neutral acid concentration. Results shall be reported as the neutral acid with appropriate CAS number. If a labeled analog is not commercially available, the Extracted Internal Standard Analyte with the closest retention time or chemical similarity to the analyte must be used for quantitation. (Internal Standard Quantitation) Analytes must be within 70-130% of their true value for each calibration standard.</p> <p>ICAL must meet one of the two options below:                      Option 1: The RSD of the RFs for all analytes must be <math>\leq 20\%</math>.                      Option 2: Linear or nonlinear calibrations must have <math>r_2 \geq 0.99</math> for each analyte.</p>	Repeat calibration if criterion is not met	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Second source calibration verification	50 ppb on column	Once after each initial calibration	All analytes must calculate to be within 70-130% of true value and extracted internal standard must calculate to be within 50-150% of true value.	Remake standard, recalibrate if necessary	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Retention Time Windows	NA	Prior to sample analysis	Established with the first CCV of the day or the average of the ICAL on days when calibration is performed. See Table 3 of LCMS-011 for RT Windows.	Perform maintenance on pump or column. Recalibrate, if necessary, to re-establish retention times.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)

Instrument/Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
LC/MS/MS	Tune check	Agilent ESI-L Low Concentration Tuning Mix	Daily, prior to sample analysis, only once per analytical batch. No time constraints.	Manufacturer recommended criteria which include delta and FWHM tolerance checks of 6 m/z's over the spectrum of the detector.	Retune instrument and repeat check tune. Maintenance may be required.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	LOD/LOQ verification	Various, see Table 3 of LCMS-010	Quarterly	LOD meets method qualitative requirements or is at least 3x higher than noise; LOQ is recovered within LCS criteria.	Perform instrument maintenance and repeat failed LOD or LOQ study passing two consecutive tests or perform new DL study.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	ICV	NA	Once after each ICAL, analysis of a second source standard prior to sample analysis.	Analyte concentrations must be within $\pm 30\%$ of their true value.	Correct problem, rerun ICV. If problem persists, repeat ICAL.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	CCV	5 ppb and 50 ppb on column	Prior to sample analysis, after every 10 field samples, and at the end of the analytical sequence.	Concentration of analytes must range from the LOQ to the mid-level calibration concentration.  Analyte concentrations must be within $\pm 30\%$ of their true value.	Immediately analyze two additional consecutive CCVs. If both pass, samples may be reported without reanalysis. If either fails, or if two consecutive CCVs cannot be run, perform corrective action(s) and repeat CCV and all associated samples since last successful CCV. Alternately, recalibrate if necessary; then reanalyze all associated samples since the last acceptable CCV.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)

Instrument/Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
LC/MS/MS	Mass Spectral Acquisition Rate	NA	Each analyte, Extracted Internal Standard (EIS) Analyte.	<p>Calibrate the mass scale of the MS with calibration compounds and procedures described by the manufacturer.</p> <p>Mass calibration range must bracket the ion masses of interest. The most recent mass calibration must be used for every acquisition in an analytical run.</p> <p>Mass calibration must be verified to be <math>\pm 0.5</math> amu of the true value, by acquiring a full scan continuum mass spectrum of a PFAS stock standard.</p>	NA	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Calibration, Calibration Verification, and Spiking Standards	5 ppb and 50 ppb on column	<p>Instrument must have a valid mass calibration prior to any sample analysis. Mass calibration is verified after each mass calibration, prior to initial calibration (ICAL).</p>	<p>Standards containing both branched and linear isomers must be used when commercially available. PFAS method analytes may consist of both branched and linear isomers, but quantitative standards that contain the linear and branched isomers do not exist for all method analytes.</p> <p>For PFAS that do not have a quantitative branched and linear standard, identify the branched isomers by analyzing a qualitative standard that includes both linear and branched isomers and determine retention times, transitions and transition ion ratios. Quantitate samples by integrating the total response (i.e., accounting for peaks that are identified as linear and branched isomers) and relying on the initial calibration that uses the linear isomer quantitative standard.</p>	NA	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)

Instrument/Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
LC/MS/MS	ISC	NA	Prior to analysis and at least once every 12 hours.	Analyte concentrations must be at LOQ; concentrations must be within $\pm 30\%$ of their true values.	Correct problem, rerun ISC. If problem persists, repeat ICAL.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Instrument Blanks	NA	Immediately following the highest standard analyzed and daily prior to sample analysis.	Concentration of each analyte must be $\leq \frac{1}{2}$ the LOQ. Instrument Blank must contain EIS to enable quantitation of contamination.	If acceptance criteria are not met after the highest calibration standard, calibration must be performed using a lower concentration for the highest standard until acceptance criteria is met. If sample concentrations exceed the highest allowed standard and the sample(s) following exceed this acceptance criteria ( $>1/2$ LOQ), they must be reanalyzed.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Retention Time Window	NA	Once per ICAL and at the beginning of the analytical sequence.	Position shall be set using the midpoint standard of the ICAL curve when ICAL is performed. On days when ICAL is not performed, the initial CCV is used.	NA	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)
LC/MS/MS	Retention Time (RT Window Width	NA	Every field sample, standard, blank, and QC sample	RT of each analyte and EIS analyte must fall within 0.4 minutes of the predicted retention times from the daily calibration verification or, on days when ICAL is performed, from the midpoint standard of the ICAL. Analytes must elute within 0.1 minutes of the associated EIS. This criterion applies only to analyte and labeled analog pairs.	Correct problem and reanalyze samples.	Analyst, Supervisor, QA Manager	LCMS-011 (BRTO-0111)

Instrument/ Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
LC/MS/MS	Ion Transitions (Precursor →Product)	NA	Every field sample, standard, blank, and QC sample	In order to avoid biasing results high due to known interferences for some transitions, the following transitions must be used for the quantification of the following analytes: PFOA: 413 → 369 PFOS: 499 → 80 PFHxS: 399 → 80 PFBS: 299 → 80 4:2 FTS: 327 → 307 6:2 FTS: 427 → 407 8:2 FTS: 527 → 507 NEtFOSAA: 584 → 419 NMeFOSAA: 570 → 419 If these transitions are not used, the reason must be technically justified and documented (e.g., alternate transition was used due to observed interferences).	NA	NA	LCMS-011 (BRTO-0111)
Shimadzu TOC-V CSH or TOC-V CPH	ICAL	Various	Analyzed and evaluated before any result can be quantitated.	The correlation coefficient must be 0.995 or greater	Correct problem; recalibrate instrument, new calibration verified	Analyst, Supervisor, QA Manager	WL-057 (BRTO-0044)
Shimadzu TOC-V CSH or TOC-V CPH	ICV	10,000 µg & 20,000 µg	Immediately following the ICAL	±10% (90-110% of true value)	Instrument maintenance, reanalysis of ICV or initial calibration or re-preparation of the standards	Analyst, Supervisor, QA Manager	WL-057 (BRTO-0044)

Instrument/ Equipment	Calibration Procedure	Calibration Range	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person(s) Responsible for CA	SOP Reference
Shimadzu TOC-V CSH or TOC-V CPH	CCV	10,000 µg	Each day that an ICAL is not performed a CCV must be performed before sample analysis. Also analyze every 10 samples ant at the end of analytical batch	±10 % (90-110% of true value)	Instrument maintenance, reanalysis of ICV or initial calibration or re-preparation of the standards	Analyst, Supervisor, QA Manager	WL-057 (BRTO-0044)
Shimadzu TOC-V CSH or TOC-V CPH	CCB	<250 mg/kg	Analyzed after every 10 samples or more frequently and at the end of analytical batch	Concentration must be less than the LOQ	Correct problem; recalibrate instrument	Analyst, Supervisor, QA Manager	WL-057 (BRTO-0044)
Orion 720 pH Meter	Calibrate meter	1.00-13.00	Daily before use	92-108%	Recalibrate meter	Analyst, Supervisor QA Manager	EXT-032
Orion 720 pH Meter	QC Check Buffer	8.00	Immediately after calibration and with every 20 samples	0.05 pH units of the true value	Recalibrate meter	Analyst, Supervisor, QA Manager	EXT-032

- 1346 **Notes:**  
 1347 % = percent  
 1348 µg = micrograms  
 1349 amu = atomic mass unit  
 1350 CCB = continuing calibration blank  
 1351 CCV = continuing calibration verification  
 1352 DL = detection limit  
 1353 ESI = electrospray ionization  
 1354 ICAL = initial calibration

1355	ICV = independent calibration verification
1356	ISC = instrument sensitivity check
1357	LCMS = liquid chromatography/ mass spectrometry
1358	LC/MS/MS = liquid chromatography tandem mass spectrometry
1359	LCS = laboratory control spike
1360	LOD = limit of detection
1361	LOQ = limit of quantitation
1362	mg/kg = milligram per kilogram
1363	NA = not applicable
1364	OSD = Office of the Secretary of Defense
1365	PFOA = perfluorooctanoic acid
1366	PFOS = perfluorooctanesulfonic acid
1367	ppb = parts per billion
1368	QA = quality assurance
1369	QC = quality control
1370	RSD = relative standard deviation
1371	SOP = standard operating procedure
1372	SL = screening level
1373	S/N = signal to noise
1374	

1375 **Final PQAPP Worksheet #25: Analytical Instrument and Equipment**  
 1376 **Maintenance, Testing and Inspection**

Instrument/ Equipment	Maintenance Activity	Testing Activity	Inspection Activity	Frequency	Acceptance Criteria	Corrective Action	Responsible Person	SOP Reference
LC/MS/MS	Clean ESI Chamber	NA	NA	Weekly or as needed	NA	NA	Analyst	LCMS-011 (BRTO-0111)
LC/MS/MS	Backflush Analytical Column and Hold Column for Solvent Cleaning	NA	Peak Asymmetry	As needed	NA	NA	Analyst	LCMS-011 (BRTO-0111)
Shimadzu TOC-V CSH or TOC-V CPH	Change injection needle, change catalyst	TOC	Monitor instrument performance via Continuing Calibration Verification	As needed or replace as necessary, loss of sensitivity or failing resolutions, erratic response	No maintenance is required as long as instrument QC meets criteria	Perform instrument maintenance, clean injection needle, change catalyst	Analyst, Supervisor, QA Manager	WL-057 (BRTO-0044)

- 1377 **Notes:**  
 1378 ESI = electrospray ionization  
 1379 LCMS = liquid chromatography/ mass spectrometry  
 1380 LC/MS/MS = liquid chromatography tandem mass spectrometry  
 1381 NA = not applicable  
 1382 QC = quality control  
 1383 SOP = standard operating procedure  
 1384 TOC = total organic carbon

1385

THIS PAGE INTENTIONALLY BLANK

## 1386 Final PQAPP Worksheet #26 & #27: Sample Handling, Custody, and Disposal

1387 **Sampling Organization:** AECOM

1388 **Laboratory:** Pace Gulf Coast

1389 **Method of sample delivery (shipper/carrier):** FedEx

1390 **Number of days from reporting until sample disposal:** 60 Days

Activity	Organization and title or position of person responsible for the activity	SOP reference
Sample labeling	AECOM	SOP 3-03 <i>Recordkeeping, Sample Labeling and Chain of Custody</i>
CoC form completion	AECOM	
Packaging	AECOM	SOP 3-04 <i>Sample Handling, Storage, and Shipping</i>
Shipping coordination	AECOM	
Sample receipt, inspection, & log-in	Pace Gulf Coast	SAD-001 <i>Sample Receiving and LIMS Log-In</i>
Sample custody and storage	Pace Gulf Coast	SAD-002 <i>Sample Chain of Custody and Sample Integrity</i>
Sample disposal	Pace Gulf Coast	GEN-009 <i>Waste Collection, Storage, Disposal</i>

1391 **Notes:**

1392 AECOM = AECOM Technical Services, Inc.

1393 CoC = chain of custody

1394 GEN = Quality Control Standard Operating Procedure

1395 LIMS = Laboratory Information Management System

1396 SAD = Sample Administration Standard Operating Procedure

1397 SOP = Standard Operating Procedure

1398

THIS PAGE INTENTIONALLY BLANK

1399

## Final PQAPP Worksheet #28: Analytical Quality Control and Corrective Actions

1400

**Matrix:** Soil & Aqueous

1401

**Analytical Group:** PFAS

1402

**Analytical Method:** PFAS by LC/MS/MS compliant with QSM 5.3 Table B-15

1403

**SOP Reference:** LCMS-011 (BRTO-0111)

1404

**Certification Status:** DoD/ELAP Certification

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
Aqueous Sample Preparation	Each sample and associated batch QC samples.	Solid Phase Extraction (SPE) must be used unless samples are known to contain high PFAS concentrations e.g., Aqueous Film Forming Foam (AFFF). Inline SPE is acceptable.  Entire sample plus bottle rinsate must be extracted using SPE. Known high PFAS concentration samples require serial dilution be performed in duplicate. Documented project approval is needed for samples prepared by serial dilution as opposed to SPE.	NA	Analyst, Supervisor, QA Manager	As per Table B-15
Solid Sample Preparation	Each sample and associated batch QC samples.	Entire sample received by the laboratory must be homogenized prior to subsampling.	NA	NA	As per Table B-15
Sample Cleanup Procedure	Each sample and associated batch QC samples. Not applicable to AFFF and AFFF Mixture Samples	ENVI-Carb™ or equivalent must be used on each sample and batch QC sample	NA	NA	As per Table B-15

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
Method Blank	One per preparatory batch, maximum of 20 samples	No analytes detected > ½ LOQ or > 1/10th the amount measured in any sample or 1/10th the regulatory limit, whichever is greater.	Correct problem. If required, re-extract and reanalyze MB and all QC samples and field samples processed with the contaminated blank. Samples may be reextracted and analyzed outside of hold times, as necessary for corrective action associated with QC failure. Apply B-flag to all results for the specific analyte(s) in all samples in the associated preparatory batch.	Analyst, Supervisor, QA Manager	As per Table B-15
LCS	One per preparatory batch, maximum of 20 samples	Blank spiked with all analytes at a concentration ≥ LOQ and ≤ the mid-level calibration concentration.  As Per Worksheet #15 and Table C-44 and 45 of QSM 5.3	Correct problem, then re- extract and reanalyze the LCS and all samples in the associated preparatory batch for failed analytes if sufficient sample material is available. Samples may be reextracted and analyzed outside of hold times, as necessary for corrective action associated with QC failure.	Analyst, Supervisor, QA Manager	As per Table B-15
Matrix Spike	One per preparatory batch. Not required for aqueous samples prepared by serial dilution instead of SPE.	Sample spiked with all analytes at a concentration ≥ LOQ and ≤ the mid-level calibration concentration.  All targets spiked and within the QC limits included in Worksheet #15.	Evaluate the data to determine if the failed criteria are due to sample matrix or laboratory error. Re-prep if sufficient sample is available when lab error is suspected, otherwise, qualify data with narrative.	Analyst, Supervisor, QA Manager	As per Table B-15

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
MSD or MD	For MSD: One per preparatory batch. For MD: Each aqueous sample prepared by serial dilution instead of SPE.	For MSD: Sample spiked with all analytes at a concentration $\geq$ LOQ and $\leq$ the mid-level calibration concentration. For MSD: All targets spiked and within the QC limits included in Worksheet #15. RPD $\leq$ 30% (between MS and MSD or sample and MD).	The data shall be evaluated to determine the source of difference. For Sample/MD: RPD criteria only apply to analytes whose concentration in the sample is greater than or equal to the LOQ. The MD is a second aliquot of the field sample that has been prepared by serial dilution.	Analyst, Supervisor, QA Manager	As per Table B-15
Extracted Internal Standards	Every field sample, standard, blank, and QC sample.	Added to solid sample prior to extraction. Added to aqueous samples, into the original container, prior to extraction. For aqueous samples prepared by serial dilution instead of SPE, added to final dilution of samples prior to analysis. EIS Analyte recoveries must be within 50% to 150% of ICAL midpoint standard area or area measured in the initial CCV on days when an ICAL is not performed.	If recoveries are acceptable for QC samples, but not field samples, the field samples must be re-prepped and reanalyzed (greater dilution may be needed). If recoveries are unacceptable for QC samples, correct problem, and reanalyze all associated failed field samples.	Analyst, Supervisor, QA Manager	As per Table B-15
Instrument Internal Standard Analytes (Used for quantitation of drinking water results)	Every field sample, standard, blank, and QC sample.	Added to aliquot of sample dilutions, QC samples, and standards just prior to analysis. Peak areas must be within -50% to +50% of the area measured in the ICAL midpoint standard. On days when ICAL is not performed, the peak areas must be within -50% to +50% of the peak area measured in daily initial CCV.	If peak areas are unacceptable, analyze a second aliquot of the extract or sample if enough extract remains. If there is not enough extract, reanalyze the first aliquot. If second analysis meets acceptance criteria, report the second analysis. If it fails, either analysis may be reported with the appropriate flags.	Analyst, Supervisor, QA Manager	As per Table B-15

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
Post Spike Sample	Only applies to aqueous samples prepared by serial dilution instead of SPE that have reported value of "<LOQ" for analyte(s).	Spike aliquot(s) of sample at the final dilution(s) reported for sample with all analytes that have reported value of "<LOQ" in the final dilution. The spike must be at the LOQ concentration to be reported with the sample (the "<LOQ" value). When analyte concentrations are calculated as "<LOQ", the spike must recover within 70-130% of its true value.	When analyte concentrations are calculated as "<LOQ", and the spike recovery does not meet the 70-130% acceptance criteria, the sample, sample duplicate, and post spike sample must be reanalyzed at consecutively higher dilutions until the criteria is met.	Analyst, Supervisor, QA Manager	As per Table B-15

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
Sample PFAS Identification	All analytes detected in a sample.	The chemical derivation of the ion transitions must be documented. A minimum of two ion transitions (Precursor → quant ion and precursor → confirmation ion) and the ion transitions ratio per analyte are required for confirmation. Exception is made for analytes where two transitions do not exist (PFBA and PFPeA). Documentation of the primary and confirmation transitions and the ion ratio is required. In-house acceptance criteria for evaluation of ion ratios must be used and must not exceed 50-150%. Signal to Noise Ratio (S/N) must be ≥ 10 for all ions used for quantification and must be ≥ 3 for all ions used for confirmation. Quant ion and confirmation ion must be present and must maximize simultaneously (±2 seconds).	NA	Analyst, Supervisor, QA Manager	As per Table B-15

- 1405 **Notes:**  
 1406 % = percent  
 1407 < = less than  
 1408 > = greater than  
 1409 ≤ = less than or equal to  
 1410 ≥ = greater than or equal to  
 1411 AFFF = aqueous film forming foam  
 1412 CCV = continuing calibration verification  
 1427

- 1413 ICAL = initial calibration  
 1414 LC/MS/MS = liquid chromatography tandem  
 mass spectrometry  
 1415  
 1416 LCS = laboratory control spike  
 1417 LOD = limit of detection  
 1418 LOQ = limit of quantitation  
 1419 MD = matrix duplicate

- 1420 MS/MSD = matrix spike/matrix spike duplicate  
 1421 NA = not applicable  
 1422 QA = quality assurance  
 1423 QC = quality control  
 1424 RPD = relative percent difference  
 1425 SOP = standard operating procedure  
 1426 SPE = solid phase extraction

- 1428 **Matrix:** Soil
- 1429 **Analytical Group:** Total Organic Carbon
- 1430 **Analytical Method:** USEPA 9060A
- 1431 **SOP Reference:** BRTO-0044
- 1432 **Certification Status:** DoD/ELAP Certification

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
Method Blank	One per preparatory batch, maximum of 20 samples	Concentration shall not be > 1/2 the LOQ or 1/10 the amount of sample	The source of contamination should be investigated and samples should be reanalyzed. If, additional sample is not available, report with narrative.	Analyst, Supervisor, QA Manager	As per method
LCS	One per preparatory batch, maximum of 20 samples	90-110%	If LCS fails to meet lab criteria, the source of inaccuracy should be investigated and samples reanalyzed. If additional sample is not available, report in a narrative.	Analyst, Supervisor, QA Manager	As per method
MS	One pair per batch (assuming sufficient volume exists) or as specified by client request.	80-120%	If recovery is outside control limits and a lab error suspected, repeat the MS determination. If the LCS is within control limits and the matrix interference is indicated, analyze a post digestion spike and report results with a narrative.	Analyst, Supervisor, QA Manager	As per method
Duplicate/ MSD	One pair per batch (assuming sufficient volume exists) or as specified by client request.	RPD should be ≤20	Investigate the source of the precision error. A source of precision error in the duplicate /MSD may be the homogenous nature of the sample. If lab error is suspected, repeat analysis. If matrix issue is indicated, report with a narrative.	Analyst, Supervisor, QA Manager	As per method

- 1433 **Notes:**
- 1434 % = percent
- 1435 < = less than
- 1436 ≤ = less than or equal to
- 1437 DoD = Department of Defense
- 1438 ELAP = Environmental Laboratory Accreditation Program
- 1439 LCS = laboratory control spike
- 1446

- 1440 LOQ = limit of quantitation
- 1441 MS/MSD = matrix spike/matrix spike duplicate
- 1442 QA = quality assurance
- 1443 QC = quality control
- 1444 RPD = relative percent difference
- 1445 SOP = standard operating procedure

- 1447 **Matrix:** Soil
- 1448 **Analytical Group:** pH
- 1449 **Analytical Method:** USEPA 9045D
- 1450 **SOP Reference:** EXT-032
- 1451 **Certification Status:** DoD/ELAP Certification

QC Sample	Frequency/ Number	Method/SOP Acceptance Limits	Corrective Action	Person(s) Responsible	Measurement Performance Criteria
QC Check Buffer	Before sample analysis, after every 20 samples and at the end of analysis	Within $\pm 0.05$ pH of true value	Do not analyze samples without a daily LCS that meets criteria.	Analyst, Supervisor, QA Manager	As per method
Duplicate	One per batch, maximum of 20 samples	Within 0.1 pH unit	Repeat if sample volume allows or narrate results.	Analyst, Supervisor, QA Manage	As per method

- 1452 **Notes:**
- 1453 % = percent
- 1454 DoD = Department of Defense
- 1455 ELAP = Environmental Laboratory Accreditation Program
- 1456 LCS = laboratory control spike
- 1457 QA = quality assurance
- 1458 QC = quality control
- 1459 SOP = standard operating procedure
- 1460

1461

THIS PAGE INTENTIONALLY BLANK

1462 **Final PQAPP Worksheet #29: Project Documents and Records**

Sample Collection Documents and Records	Onsite Analysis Documents and Records	Offsite Analysis Documents and Records	Data Assessment Documents and Records	Other
Field Logbook	Field Logbook	Sample receipt, custody, and tracking records	Field sampling audit records	NA
CoC Records	Field Sampling Forms	Sample prep logs	Laboratory audit records	
Air Bills	Equipment Inspection Forms	Equipment calibration logs	Data validation reports	
Custody Seals	Boring Logs	Run logs	Data usability assessment reports	
Corrective Action Forms	Corrective Action Forms	Equipment maintenance test, and inspection logs	Corrective Action Forms	
Field Sampling Forms	Daily Tailgate SH&E Sign In Sheet	Corrective Action Forms	Field Change Request Form	
Sample location and depth data	APP/SSHP Acknowledgement	Reported analytical results		
Field equipment calibration logs	Dig Permits	Data package completeness checklists		
		Sample disposal records		
		Extraction/cleanup records		
		Raw data		
		EQulS™		
		ROE Agreements		
		Photographic Logs		

- 1463 **Notes:**
- 1464 APP/SSHP = Accident Prevention Plan/ Site Safety and Health Plan
- 1465 CoC = chain of custody
- 1466 EQulS = Environmental Quality Information System
- 1467 SH&E = Safety, Health, and Environment
- 1468 NA = not applicable
- 1469 ROE = right of entry

1470

THIS PAGE INTENTIONALLY BLANK

1471 **Final PQAPP Worksheet #31, #32 & #33: Assessments and Corrective Action**

1472 This worksheet is used to document responsibilities for conducting project assessments, responding to assessment findings, and  
 1473 implementing corrective action. Appropriately scheduled assessments allow management to implement corrective action in a timely  
 1474 manner, thereby correcting non-conformances and minimizing their impact on DQOs/Project Quality Objectives.

1475 **Assessments:**

Assessment Type	Frequency	Internal or External	Organization Performing Assessment	Person(s) Responsible for Performing Assessment	Person(s) Responsible for Responding to Assessment Findings	Person(s) Responsible for Identifying and Implementing Corrective Action	Person(s) Responsible for Monitoring Effectiveness of Corrective Action
Project Manager Review	Monthly (for field efforts that are longer than one month)	Internal	AECOM	Project Manager/ AECOM	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	Project Manager/ AECOM
Review of CoC forms	Daily	Internal	AECOM	Project Chemist/ AECOM	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	Project Chemist/ AECOM
Laboratory Data Assessment (validation)	Once	Internal	AECOM	Data Validator	Project Chemist/ AECOM	Data Validator	Project Chemist/ AECOM
Daily Quality Control Audits	Daily	Internal	AECOM	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	QA Officer/ AECOM
Field TSAs	Daily	Internal	AECOM	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	QA Officer/ AECOM
Field Performance Audits	Weekly	Internal	AECOM	Project Manager/ AECOM or representative	Field Sampling Team Leader/ AECOM	Field Sampling Team Leader/ AECOM	Project Manager/ AECOM

1476

1477 **Assessment Response and Corrective Action:**

Assessment Type	Nature of Deficiencies Documentation	Individual(s) Notified of Findings	Timeframe of Notification	Nature of Corrective Action Response Documentation	Individual(s) Receiving Corrective Action Response	Timeframe for Response
Field Sampling Audit	Email	Field Sampling Team Leader/AECOM Project Manager	Immediate	Daily QC Report/ Email	Project Quality Manager/ Project Manager	24 hours after notification
Project Manager Review	Email	Field Sampling Team Leader/ AECOM	Immediate	Daily QC Report/ Email	AECOM Project Manager	24 hours after notification
Review of CoC forms	Email	Field Sampling Team Leader/AECOM Project Manager	Immediate	Daily QC Report/ Email	Project Chemist	24 hours after notification
Laboratory Data Assessment (validation)	Written Audit Report	Laboratory QA Manager; AECOM Project Chemist	Within 24 hours after audit	Email	Data Validator	Up to 1 week after notification
Daily Quality Control Audits	Email/ Daily QC Report	Field Sampling Team Leader/AECOM Project Manager	Immediate	Daily QC Report/ Email	AECOM Project Manager	24 hours after notification
Field TSAs	Email/ Daily QC Report	Field Sampling Team Leader/AECOM Project Manager	Immediate	Daily QC Report/ Email	AECOM Project Manager	24 hours after notification
Field Performance Audits	Email	Field Sampling Team Leader	Immediate	Daily QC Report/ Email	AECOM Project Manager	24 hours after notification

1478

1479 **Laboratory Assessments: Pace Gulf Coast**

Assessment Type	Responsible Party & Organization	Number/Frequency	Estimated Dates	Assessment Deliverable	Deliverable Due Date
DoD/ELAP Accreditation	PJLA	Every Two Years	NA	Certification	NA
PT samples	Laboratory QAM	Accreditation	Per Accrediting Authority	Per Accrediting Authority	Per Accrediting Authority
Data Review	Naoum Tavantzis, AECOM	Once	45 days after receipt of data	Validation Report	45 days after receipt of data
External Laboratory Audit	PJLA	Bi-annually	NA	Written Audit Report	NA
Internal Laboratory Audit	Pace Gulf Coast	Annually	NA	Written Audit Report	NA

- 1480 **Notes:**
- 1481 AECOM = AECOM Technical Services, Inc.
- 1482 CoC = chain of custody
- 1483 DoD = Department of Defense
- 1484 ELAP = Environmental Laboratory Accreditation Program
- 1485 NA = not applicable
- 1486 PJLA = Perry Johnson Laboratories Accreditation
- 1487 PT = proficiency testing
- 1488 QA = quality assurance
- 1489 QAM = Quality Assurance Manager
- 1490 QC = quality control
- 1491 TSA = technical system audit
- 1492

1493

1494

THIS PAGE INTENTIONALLY BLANK

1495  
 1496

## Final PQAPP Worksheet #34: Data Verification and Validation Inputs

Item	Description	Verification (Completeness)	Validation (Conformance to Specifications)
<b>Planning Documents/Records</b>			
1	Approved QAPP	X	
2	Contract	X	
4	Field SOPs	X	
5	Laboratory SOPs	X	
<b>Field Records</b>			
6	Field logbooks	X	
7	Equipment calibration records	X	
8	CoC Forms	X	X
9	Sampling diagrams/surveys	X	
10	Drilling logs	X	
11	Relevant correspondence	X	
12	Change orders/deviations	X	
13	Field audit reports	X	
14	Field change request forms	X	
<b>Analytical Data Package</b>			
16	Cover sheet (laboratory identifying information)	X	X
17	Case narrative	X	X
18	Internal laboratory CoC	X	X
19	Sample receipt records	X	X
20	Sample chronology (i.e., dates and times of receipt, preparation, and analysis)	X	X
21	Communication records	X	
22	LOD/LOQ establishment and verification	X	
23	Standards traceability	X	
24	Instrument calibration records	X	X
25	Definition of laboratory qualifiers	X	
26	Results reporting forms	X	X
27	QC sample results	X	X
28	Corrective action reports	X	X
29	Raw data	X	X
30	Electronic data deliverable	X	X

- 1497 **Notes:**  
 1498 CoC = chain of custody  
 1499 LOD = limit of detection  
 1500 LOQ = limit of quantitation  
 1501 QAPP = Quality Assurance Project Plan  
 1502 QC = quality control  
 1503 SOP = standard operating procedure

1504

THIS PAGE INTENTIONALLY BLANK

## 1505 Final PQAPP Worksheet #35: Data Verification Procedure

1506 This worksheet documents procedures that will be used to verify project data. The procedures apply to both field and laboratory records.  
 1507 Data verification is a completeness check to confirm that all required activities were conducted, all specified records are present, and  
 1508 the contents of the records are complete. As illustrated in the following example, verification often is performed at more than one step  
 1509 by more than one person.

Records Reviewed	Requirement Documents	Process Description	Responsible Person, Organization
CoC forms and shipping forms	CoC, Shipping Documents	CoC forms and shipping documentation will be reviewed internally upon their completion and verified against the packed sample coolers they represent. The shipper's signature on the CoC should be initialed by the reviewer, a copy of the CoC retained in the facility file, and the original and remaining copies taped inside the cooler for shipment.	Appropriate Field Sampling Team Leaders for the individual medias
Review of field logbooks	Field Logbooks	Review for completeness and accuracy.	Appropriate field Sampling Team Leaders
Field sampling TSAs	TSA Reports	Assessment of field sampling process prior to start of, or as close to the start of sampling as possible.	QA Manager or designee
Fixed laboratory analytical data review	Laboratory Data Package	Data controls are compared to this QAPP and DoD QSM v 5.3 (PFAS by LC/MS/MS compliant with QSM 5.3 Table B-15) in a Three-Tiered process using a minimum 100% peer review.	PM or QA Manager
Fixed laboratory TSAs	Laboratory Data Package	ELAP audit and internal quality audits.	QA Manager
Fixed laboratory data verification	Data Validation Reports	100% data verification/validation for water and soil.	AECOM Project Chemist
Fixed laboratory data validation	Data Validation Reports	Calculate and assess laboratory DQIs.	QA Manager, or designee

- 1510 **Notes:**  
 1511 AECOM = AECOM Technical Services, Inc.  
 1512 CoC = chain of custody  
 1513 DoD = Department of Defense  
 1514 DQI = data quality indicator  
 1515 ELAP = Environmental Laboratory Accreditation Program  
 1516 PFAS = per- and polyfluoroalkyl substances  
 1517 PM = Project Manager  
 1518 QA = quality assurance  
 1519 QAPP = Quality Assurance Project Plan  
 1520 QSM = Quality Systems Manual  
 1521 TSA = technical system audit  
 1522 USEPA = United States Environmental Protection Agency

1523

THIS PAGE INTENTIONALLY BLANK

1524 **Final PQAPP Worksheet #36: Data Validation Procedures**

1525 **Data Validator: AECOM**

Analytical Group/Method	All Analytical Data
Analytical specifications	WS#24, WS #28 & Laboratory SOPs
Measurement performance criteria	WS #12, WS#15, and WS#28
Percent of data packages to be validated	100%
Percent of raw data reviewed	100%
Percent of results to be recalculated	0%
Validation procedure and qualification	National Functional Guidelines for Organic Superfund Data Review, January 2017 (USEPA, 2017b); Department of Defense General Data Validation Guidelines, November 2019 (DoD, 2019b); Data Validation Guidelines Module 3: Data Validation Procedure for Per- and Polyfluoroalkyl Substances Analysis by QSM Table B-15 (DoD, 2020).
Validation code	S2bVEM/S2bVM
Electronic validation program/version	AECOM EarthSoft EQuIS™ Automated Validation Assistant

- 1526 **Notes:**
- 1527 % = percent
- 1528 AECOM = AECOM Technical Services, Inc.
- 1529 DoD = Department of Defense
- 1530 EQuIS = Environmental Quality Information System
- 1531 SOP = standard operating procedure
- 1532 USEPA = United States Environmental Protection Agency
- 1533 WS = worksheet

1534

THIS PAGE INTENTIONALLY BLANK

## 1535 Final PQAPP Worksheet #37: Data Usability Assessment

1536 The Data Usability Assessment (DUA) is an evaluation at the conclusion of data collection activities that uses the results of both data  
 1537 verification and validation in the context of the overall project decisions or objectives. Using both quantitative and qualitative methods,  
 1538 the assessment will determine whether project execution and the resulting data the DQOs established in **Worksheet #11** were  
 1539 achieved. Both sampling and analytical activities will be considered with the ultimate goal to assess whether the final, qualified results  
 1540 support the decisions to be made with the data.

1541 The following personnel are responsible for participating in the DUA:

- 1542 • AECOM Project Manager: Claire Mitchell
- 1543 • AECOM Project Chemist: Naoum Tavantzis
- 1544 • AECOM SI Task Manager: Justin Vetter

1545 The DUA will be documented as a discussion within the SI report and refer to the Data Validation Report that will appear in an appendix  
 1546 of the SI Report. The SI Report and DUA will be reviewed by the USACE. The Data Validation Report will follow the procedures given  
 1547 in **Worksheet #36**.

1548 The following steps summarize the processes used to determine whether the collected data are of the right type, quality, and quantity  
 1549 to support the environmental decision-making for ARNG related to PFAS contamination at certain installations and describe how data  
 1550 quality issues will be addressed and how limitations on the use of the data will be handled.  
 1551

<p><b>Step 1</b></p>	<p><b>Review the project’s objectives and sampling design.</b></p> <p>The key components established in the DQOs (<b>Worksheet #11</b>) will be reviewed to ensure that they are still applicable. Also, the sampling design and how it was implemented in the field will be reviewed for consistency with the stated objectives. For example, this step in the DUA will:</p> <ul style="list-style-type: none"> <li>• Reevaluate whether comparison criteria (i.e., SL; <b>Worksheet #15</b>) were updated since PQAPP generation and if laboratory quantitation limits (QLs) were sensitive enough for those changes (e.g., QLs remain lower than new criteria). It is important to note several states are in various stages of developing or finalizing limits for PFAS chemicals for different media; therefore, it is critical that SLs are regularly evaluated over the course of the project to ensure the SLs remain current. Additionally, project data must meet the measurement performance criteria (MPC) for sensitivity and project QLs specified in <b>Worksheets #15 &amp; 28</b>.</li> <li>• Discuss the limitations and impact on the use of project data if validation reports indicate that project specific sensitivity goals or QLs were not achieved for a specific sampling or laboratory group, dataset or sample delivery group (SDG), matrix, analytical group, or concentration level.</li> </ul>
<p><b>Step 2</b></p>	<p><b>Review the data verification and data validation outputs</b></p> <p>Available Quality Assurance (QA) reports, including both field and laboratory generated forms, will be reviewed for deviations from planned activities identified in Step 1 (e.g., number and locations of samples, holding time exceedances, damaged samples, non-compliant proficiency testing sample results, and SOP deviations) and determine their impacts on the data usability. Validated data will be summarized and/or compiled to identify patterns, trends, and anomalies as they relate to the Data Quality Indicators (DQIs) precision, accuracy/bias,</p>

	<p>representativeness, comparability, completeness, and sensitivity. Descriptions of each DQI and examples of how each may be incorporated into the usability report follow.</p>
<p><b>Step 2 (cont.)</b></p>	<p><b>Precision</b>                  Precision is the degree to which a set of observations or measurements of the same property, obtained under similar conditions, conform to themselves. Precision is usually expressed as standard deviation, variance, percent difference, or range, in either absolute or relative terms. Quality Control (QC) measures for precision include field duplicates, laboratory duplicates, MSDs, analytical replicates, and surrogates. To meet the needs of the data users, SI project data must meet the MPC for precision specified in <b>Worksheet #12</b> of this QAPP.                  Precision errors may be the result of one or more of the following: PFAS cross-contamination, field instrument variation, analytical measurement variation, poor sampling technique, sample transport problems, or spatial variation (heterogeneous sample matrices). To identify the cause of imprecision, the field sampling design rationale and sampling techniques will be evaluated by the reviewer, and both field and analytical duplicate/replicate sample results will be compared. For example, if poor precision is indicated in both the field and analytical duplicates/replicates, then the laboratory may be the source of error. If poor precision is limited to the field duplicate/replicate results, then the sampling technique, PFAS contamination, field instrument variation, sample transport, medium inhomogeneity, or spatial variability may be the source of error. If data validation reports indicate that analytical imprecision exists for a particular dataset or SDG, then the impact of that imprecision on usability will be discussed in the usability report.</p> <p><b>Accuracy/Bias</b>                  Accuracy is the degree of agreement between an observed value and an accepted reference value. Accuracy includes a combination of random error (precision) and systematic error (bias) due to sampling and analytical operations. Examples of QC measures for accuracy include Matrix Spikes, Laboratory Control Samples, and ERBs. A measurement is accurate when the reported value does not differ from the true value or known concentration of the spike or standard. To meet the needs of the data users, project data must meet the MPC for accuracy/bias specified in <b>Worksheet #12</b> of this QAPP.                  The usability report for each installation will:</p> <ul style="list-style-type: none"> <li>• Discuss and compare data on contamination and accuracy/bias (when bias is observable) for each matrix, analytical group, and concentration level.</li> <li>• Describe the limitations on the use of project data if extensive contamination, inaccuracy, or bias exists, or when inaccuracy is limited to a specific sampling or laboratory group, dataset or SDG, matrix, or concentration level.</li> <li>• Discuss the impact of any qualitative and quantitative trends in bias on the sample data.</li> </ul> <p><b>Representativeness</b>                  Representativeness is the measure of the degree to which data accurately and precisely represent a characteristic of a population, a parameter variation at a sampling point, a process condition, or an environmental condition, and it is achieved through a well-designed sampling program and by using standardized sampling strategies, techniques, and analytical procedures. To meet the needs of the data users, project data must meet the MPC for sample representativeness specified in <b>Worksheet #12</b> of this QAPP. <b>Worksheet #28 &amp; 35</b> discusses how the QA/QC activities (e.g., review of sampling design and SOPs, field sampling Technical System Audits (TSAs), and analysis audits) and QC sample data will be reviewed to assess sample representativeness. For example, if field duplicate precision checks indicate potential spatial variability, additional scoping meetings and subsequent resampling may be needed to collect data that are more representative of a nonhomogeneous site.                  The usability report for each installation will:</p>

	<ul style="list-style-type: none"> <li>• Discuss the impact of field duplicate imprecision on site representativeness. For example, when data variability is high among field duplicate datasets (i.e., high relative standard deviation), calculation of the 95% upper confidence limit (UCL) of the population mean is more likely to overestimate the true mean and therefore achieve better statistical coverage.</li> <li>• Discuss the impact of laboratory and field sampling methods on sampling results and how they reflect site conditions.</li> </ul>
<b>Step 2 (cont.)</b>	<ul style="list-style-type: none"> <li>• Discuss the effect of site heterogeneity on sampling results in light of sampling methods used.</li> <li>• Describe the limitations on the use of project data when sampling results are non-representative for all data or for a specific sampling, group, dataset or SDG, matrix, analytical group, or concentration level.</li> </ul>
	<p><b>Comparability</b></p> <p>Comparability is the degree to which different methods, datasets, and decisions agree or can be represented as similar. Comparability describes the confidence (expressed qualitatively or quantitatively) that two datasets can contribute to a common analysis and interpolation. The SI results will be used as benchmarks for determining comparability for data collected during any future sampling events at the various installations using the same or similar sampling and analytical SOPs. At this time, data will not be compared to other datasets or data using different sampling or analytical SOPs.</p> <p>To ensure future comparability of data generated for the installations, standard sample collection procedures and approved analytical methods will be used. Sample analyses will be performed by the laboratory using approved methods and procedures. Comparability criteria will be considered met for the project if, based on data reviewed, the sample collection and analytical procedures (such as use of alternate preparation if indicated by a positive field shake test) are determined to have been followed or defined to show that variations did not affect the values reported. Deviations to sampling scope will be documented in sampling nonconformance reports which may contain some of the discussion of comparability. The usability reports will describe the limitations on the use of project data when project-required data comparability is not achieved for the overall project or is limited to a specific sampling or laboratory group, dataset or SDG, matrix, analytical group, or concentration level.</p>
	<p><b>Completeness</b></p> <p>Completeness is a measure of the amount of valid data obtained from a measurement system compared with the amount that was expected to be obtained under correct, normal circumstances. To meet the needs of the data users, project data must meet the MPC for data completeness. Completeness criteria will be considered met if 100% of all planned sample data are collected. As applicable, the usability report may also:</p> <ul style="list-style-type: none"> <li>• Describe how the amount of valid data will be determined as a percentage of the number of valid measurements for each matrix, analytical group, and concentration level.</li> <li>• Describe how critical data were assessed for completeness when certain sample locations or analytes and matrices are more critical than others in making project decisions.</li> <li>• Evaluate the impact of missing information. Ensure that enough information was obtained for the data to be usable to meet the DQOs (<b>Worksheet #11</b>).</li> </ul>
	<p><b>Sensitivity</b></p> <p>Sensitivity is the capability of a test method or instrument to discriminate between measurement responses representing different levels (e.g., concentrations) of a variable of interest. Examples of QC measures for determining sensitivity include laboratory fortified blanks, a DL study, Limit of Detection (LOD)/Limit of Quantitation (LOQ) Verifications, and Instrument Sensitivity Checks (ISC). To meet the needs of the data users, project data must meet the MPC for sensitivity and project QLs specified in <b>Worksheets #15 &amp; 28</b> of this QAPP. If appropriate, the usability report may also:</p>

	<ul style="list-style-type: none"> <li>• Discuss and compare sensitivity and DL/LOD/LOQ from the datasets collected for the project for each matrix, analytical group, and concentration level.</li> <li>• Discuss the impact of a lack of sensitivity or higher DL/LOD/LOQ on data usability, if validation reports indicate that sensitivity goals or DL/LOD/LOQ goals were not achieved.</li> </ul>
<b>Step 2 (cont.)</b>	<ul style="list-style-type: none"> <li>• Describe the limitations on the use of project data when sampling results are non-representative for all data or for a specific sampling, group, dataset or SDG, matrix, analytical group, or concentration level.</li> </ul>
<b>Step 3</b>	<p><b>Verify the assumptions of the selected statistical method</b></p> <p>The use of statistical methods for data assessment for this project will be limited to estimating a 95% UCL (or mean as appropriate for the analyte) for the assessment of risks.</p>
<b>Step 4</b>	<p><b>Implement the statistical method</b></p> <p>Where statistical methods are used, the underlying assumptions will be assessed during the DUA. The consequences of selecting the incorrect alternative will be discussed, and uncertainty tolerances will be considered.</p>
<b>Step 5</b>	<p><b>Document data usability and draw conclusions</b></p> <p>The DUA will determine and document whether the data can be used as intended given any deviations and corrective actions that may have occurred. Limitations on data use will be considered and discussed as appropriate, and the performance of the sampling design assessed. Conclusions will be drawn taking any data limitations into consideration and documented in the SI report.</p>

1552

## 1553 2. References

- 1554 AECOM. 2018. *Final Site Inspection Programmatic Uniform Federal Policy-Quality Assurance*  
1555 *Project Plan, Perfluorooctane Sulfonic Acid (PFOS) and Perfluorooctanoic Acid (PFOA)*  
1556 *Impacted Sites ARNG Installations, Nationwide Contract No. W912DR-12-D-*  
1557 *0014/W912DR17F0192*. 9 March.
- 1558 AECOM. 2020. *Final Preliminary Assessment Report, Camp Umatilla, Hermiston, Oregon*. May.
- 1559 AMEC. 2012. *Revised Environmental Condition of Property Environmental Baseline Survey*  
1560 *Report*. 7,421-Acre Oregon Military Department Parcel, Umatilla Chemical Depot, Umatilla  
1561 and Morrow Counties, Oregon. September.
- 1562 Assistant Secretary of Defense. 2022. *Investigation Per- and Polyfluoroalkyl Substances within*  
1563 *the Department of Defense Cleanup Program*. United States Department of Defense. 6 July.
- 1564 Canestorp, K.M. 2007. *Integrated Natural Resources Management Plan. October 2007 through*  
1565 *September 2012*. Colorado Fish and Wildlife Assistance Office, U.S. Fish and Wildlife Service.
- 1566 City of Hermiston. 2020. *2020 Water Quality Report*. Available at  
1567 [https://www.hermiston.or.us/sites/default/files/fileattachments/public\\_works/page/4751/2020](https://www.hermiston.or.us/sites/default/files/fileattachments/public_works/page/4751/2020_water_quality_report.pdf)  
1568 [water\\_quality\\_report.pdf](https://www.hermiston.or.us/sites/default/files/fileattachments/public_works/page/4751/2020_water_quality_report.pdf). Accessed March 9, 2021.
- 1569 City of Irrigon. 2018. *Drinking Water Report 2017 Sampling Results*. Available at  
1570 [https://ci.irrigon.or.us/wp-content/uploads/2018/05/Irrigon-2018-Annual-Drinking-Water-](https://ci.irrigon.or.us/wp-content/uploads/2018/05/Irrigon-2018-Annual-Drinking-Water-Sampling-Report.pdf)  
1571 [Sampling-Report.pdf](https://ci.irrigon.or.us/wp-content/uploads/2018/05/Irrigon-2018-Annual-Drinking-Water-Sampling-Report.pdf). Accessed March 12, 2021.
- 1572 City of Umatilla. 2008. *Water System Master Plan*. Available at [https://www.umatilla-](https://www.umatilla-city.org/sites/default/files/fileattachments/public_works/page/1211/2008_water_system_master_plan.pdf)  
1573 [city.org/sites/default/files/fileattachments/public\\_works/page/1211/2008](https://www.umatilla-city.org/sites/default/files/fileattachments/public_works/page/1211/2008_water_system_master_plan.pdf) [water system mast](https://www.umatilla-city.org/sites/default/files/fileattachments/public_works/page/1211/2008_water_system_master_plan.pdf)  
1574 [er\\_plan.pdf](https://www.umatilla-city.org/sites/default/files/fileattachments/public_works/page/1211/2008_water_system_master_plan.pdf). Accessed March 12, 2021.
- 1575 City of Umatilla. 2019. *Annual Water Quality Report Reporting Year 2019*. Available at. Accessed  
1576 March 12, 2021.
- 1577 DA. 2016. *Army Guidance to Address Perfluorooctane Sulfonate (PFOS) and Perfluorooctanoic*  
1578 *Acid (PFOA) Contamination*. August.
- 1579 DA. 2018. *Army Guidance for Addressing Releases of Per- and Polyfluoroalkyl Substances*.  
1580 4 September.
- 1581 DoD. 2019a. *Department of Defense (DoD), Department of Energy (DOE) Consolidated Quality*  
1582 *Systems Manual (QSM) for Environmental Laboratories, Version 5.3*.
- 1583 DoD. 2019b. *General Data Validation Guidelines. Environmental Data Quality Workgroup*. 4  
1584 November.
- 1585 DoD. 2020. *Data Validation Guidelines Module 3: Data Validation Procedure for Per- and*  
1586 *Polyfluoroalkyl Substances Analysis by QSM Table B-15*. 1 May.
- 1587 Doyle, Susan Badger (Doyle). 2018. *Umatilla Army Depot*. Oregon Historical Society. Available at  
1588 [https://www.oregonencyclopedia.org/articles/umatilla\\_army\\_depot/#.YEfvH2hKiiN](https://www.oregonencyclopedia.org/articles/umatilla_army_depot/#.YEfvH2hKiiN). Accessed  
1589 December 2018.

- 1590 EA Engineering, Science, and Technology, Inc. 2021. *Standard Operating Procedure No. 042A*  
1591 *for Treating Liquid Investigation-Derived Material (Purge water, drilling water, and*  
1592 *decontamination fluids)*. Revision 1. March.
- 1593 IDQTF. 2005a. *Uniform Federal Policy for Quality Assurance Project Plans; Evaluating,*  
1594 *Assessing, and Documenting Environmental Data Collection and Use Programs, Evaluating,*  
1595 *Assessing, and Documenting Environmental Data Collection and Use Programs, Part 1: UFP-*  
1596 *QAPP Manual.* USEPA Publication Numbers: EPA-505-B-04-900A; DoD Publication  
1597 Numbers: DTIC ADA 427785. Final, Version 1. March.
- 1598 IDQTF. 2005b. *Uniform Federal Policy for Quality Assurance Project Plans (UFP-QAPP);*  
1599 *Evaluating, Assessing, and Documenting Environmental Data Collection and Use Programs.*  
1600 *Part 2: FP-QAPP Workbook.* Version 1. USEPA: EPA-505-B-04-900C and DoD: DTIC ADA  
1601 427486.
- 1602 IDQTF. 2005c. *Uniform Federal Policy for Quality Assurance Project Plans (UFP-QAPP);*  
1603 *Evaluating, Assessing, and Documenting Environmental Data Collection and Use Programs.*  
1604 *Part 2B: Quality Assurance/Quality Control Compendium: Minimum QA/QC Activities.* EPA-  
1605 505-B-04-900B and DoD: DTIC ADA 426957.
- 1606 Ingersoll, Christopher. 2018. *Big changes for Camp Umatilla.* Oregon National Guard Public  
1607 Affairs Office. Defense Visual Information Distribution Service. January 11, 2018.
- 1608 IRZ Consulting, LLC. 2009. *Umatilla Basin Regional Aquifer Recovery Assessment.* June 2009.
- 1609 Interstate Technology Regulatory Council (ITRC). 2020. *Per- and Polyfluoroalkyl Substances*  
1610 *(PFAS).* Technical/Regulatory Guidance. April.
- 1611 Koester, Jonathan. 2016. *Oregon Training Center Helps Soldiers Transition to Infantry.* The United  
1612 States Army. November 9, 2016.
- 1613 McDowell, Jade. 2018. *Oregon Military Department upgrades Camp Umatilla.* Associated Press.  
1614 The Washington Times. February 5, 2018.
- 1615 Oregon Military Department (OMD). 2018. *Figure 2. Camp Umatilla SPCC 2018 Site Plan*  
1616 *Cantonment.* December 19.
- 1617 Oregon National Guard (ONG). 2018. *Final Environmental Assessment for Expanded Operations*  
1618 *at the Oregon Army National Guard's Camp Umatilla Oregon (CUO).* August 30.
- 1619 Oregon Water Resources Department (OWRD). 2018. *Oregon Drinking Water Protection*  
1620 *Program.* Available at  
1621 <https://hdcgxc2.deq.state.or.us/HVR291/index.html?viewer=drinkingwater>. Accessed  
1622 December.
- 1623 OWRD. 2018b. *Agenda Item A, March 15, 2018, Water Resources Commission Meeting, Review*  
1624 *of Conditions in Critical Groundwater Areas.*
- 1625 OWRD. 2022. *Oregon Water Resources Department Well Report Query.* Available at  
1626 [https://apps.wrd.state.or.us/apps/gw/well\\_log/Default.aspx](https://apps.wrd.state.or.us/apps/gw/well_log/Default.aspx). Accessed July 7.
- 1627 State of Oregon. 2021. *Camp Umatilla.* Available at  
1628 <https://www.oregon.gov/omd/programs/Pages/Camp-Umatilla.aspx>. Accessed March 9.
- 1629 United States Army Corps of Engineers (USACE). 2013. *U.S Army BRAC 2013 - Environmental*  
1630 *Condition of Property Report, Umatilla Chemical Depot - Oregon.* September 2013.

- 1631 USACE. 2016. *Technical Project Planning Process, EM-200-1-2*. 26 February.
- 1632 USEPA. 1980. *Comprehensive Environmental Response, Compensation, and Liability Act*  
1633 *(CERCLA)*.
- 1634 USEPA. 1994. *National Oil and Hazardous Substances Pollution Contingency Plan (Final Rule)*.  
1635 40 CFR Part 300; 59 Federal Register 47384. September.
- 1636 USEPA. 2001. *EPA Requirements for Quality Assurance Project Plans*. EPA QA/R-5. EPA/240/B-  
1637 01/003.
- 1638 USEPA. 2005. *Federal Facilities Remedial Site Inspection Summary Guide*.
- 1639 USEPA. 2014. *Management of Investigation Derived Waste*. SESD Operating Procedure.  
1640 SESDPROC-202-R3. July.
- 1641 USEPA. 2016a. *Third Unregulated Contaminant Monitoring Rule*. Available at  
1642 <https://www.epa.gov/dwucmr/third-unregulated-contaminant-monitoring-rule>. Accessed  
1643 March 9.
- 1644 USEPA. 2016b. *Drinking Water Health Advisory for Perfluorooctanoic Acid (PFOA)*. Office of  
1645 Water (4304T). Health and Ecological Criteria Division, Washington, DC 20460. EPA  
1646 Document Number: 822-R-16-005. May.
- 1647 USEPA. 2016c. *Drinking Water Health Advisory for Perfluorooctane Sulfonate (PFOS)*. Office of  
1648 Water (4304T). Health and Ecological Criteria Division, Washington, DC 20460. EPA  
1649 Document Number: 822-R-16-004. May.
- 1650 USEPA. 2017a. *UCMR 3 (2013-2015) Occurrence Data by State. Occurrence Data for the*  
1651 *Unregulated Contaminant Monitoring Rule*. Accessed 9 July 2019 at [https://www.epa.gov/](https://www.epa.gov/dwucmr/occurrence-data-unregulated-contaminant-monitoring-rule)  
1652 [dwucmr/occurrence-data-unregulated-contaminant-monitoring-rule](https://www.epa.gov/dwucmr/occurrence-data-unregulated-contaminant-monitoring-rule). January.
- 1653 USEPA. 2017b. *National Functional Guidelines for Organic Superfund Data Review*. OLEM  
1654 9355.0-136, EPA-540-R-2017-002. Office of Superfund Remediation and Technology  
1655 Innovation. January.
- 1656 USEPA. 2020. *Learn About the Unregulated Contaminant Monitoring Rule*. Available at  
1657 <https://www.epa.gov/dwucmr/learn-about-unregulated-contaminant-monitoring-rule>.  
1658 Accessed March 9.
- 1659 USEPA. 2021. *Technical Fact Sheet: Toxicity Assessment for PFBS*.  
1660 <https://www.epa.gov/pfas/learn-about-human-health-toxicity-assessment-pfbs>. 8 April.
- 1661 United States Fish and Wildlife Service (USFWS). 2007. *Integrated Natural Resources*  
1662 *Management Plan*. October 2007.
- 1663 United States Geological Survey (USGS). 2016. *Umatilla Basin Ground-Water Study*. Available  
1664 at [https://or.water.usgs.gov/proj/umatilla\\_gw/background.html](https://or.water.usgs.gov/proj/umatilla_gw/background.html). Accessed March 12, 2021.
- 1665 Whitehead, R.L. 1994. *Ground Water Atlas of the United States: Segment 7, Idaho, Oregon,*  
1666 *Washington*. HA 730-H. United States Geological Survey. Available at  
1667 <https://pubs.usgs.gov/ha/730h/report.pdf>.

THIS PAGE INTENTIONALLY BLANK

1668 **Appendix A – Technical Project Planning Meeting Minutes**  
1669 **(TPP1 and TPP2)**

1670

THIS PAGE INTENTIONALLY BLANK

1671

## Appendix B – Standard Operating Procedures

1672

THIS PAGE INTENTIONALLY BLANK

1673

1674

SOPs available upon request.

1675

1676

THIS PAGE INTENTIONALLY BLANK